

Key No. 20033 - SH-75, ELKHORN RD TO RIVER ST, KETCHUM
Blaine County

Item No	Description	QTY	Unit
104-005A	PARTNERING	25,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	37,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	25,000.00	CA
110-005A	TRAINING	1,000.00	HR
201-005A	CLEARING & GRUBBING	5.30	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	175.00	EACH
202-010A	SELECTIVE REMOVAL OF STUMPS	100.00	EACH
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
203-006A	REMOVAL OF SIGN	58.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	58,596.00	SY
203-025A	REMOVAL OF CATCH BASIN	22.00	EACH
203-035A	REMOVAL OF CONCRETE CULVERT (MONOLITHIC)	1.00	EACH
203-055A	REMOVAL OF CONCRETE PAVEMENT	232.00	SY
203-060A	REMOVAL OF CONCRETE SIDEWALK	2,396.00	SY
203-070A	REMOVAL OF CURB & GUTTER	9,332.00	FT
203-075A	REMOVAL OF FENCE	3,247.00	FT
203-080A	REMOVAL OF GUARDRAIL	217.00	FT
203-080B	REMOVAL OF BARRIER	408.00	FT
203-085A	REMOVAL OF GUTTER	231.00	FT
203-095A	REMOVAL OF MANHOLE	10.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS (ROCK DITCH)	516.00	FT
203-123B	REMOVAL OF MISCELLANEOUS ITEMS (PIPE)	3,572.00	FT
203-123C	REMOVAL OF MISCELLANEOUS ITEMS (BLOCK WALL)	166.00	FT
203-130A	REMOVAL OF PAVEMENT MARKINGS	45,000.00	FT
205-005A	EXCAVATION	36,900.00	CY
205-040A	GRANULAR BORROW	22.00	CY
205-060A	WATER FOR DUST ABATEMENT	6,220.00	MG
205-095A	SOFT SPOT REPAIR	10,000.00	CA
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	245.00	CY
210-015A	COMPACTING BACKFILL	22.00	CY
212-011A	FIBER WATTLE	1,858.00	FT
212-020A	SILT FENCE	4,315.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	16.00	EACH
212-095A	INLET PROTECTION (FILTER)	120.00	EACH
212-105A	WATER AND POLLUTION	10,000.00	CA
212-110A	WATER POLLUTION CONTROL MANAGER	1.00	LS
213-005A	TOPSOIL (12")	5,174.00	CY
215-005A	GEOSYNTH REINFORCED ABUTMENT BACKFILL	413.00	CY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	5,000.00	CA
303-022A	3/4" AGGREGATE TYPE B FOR BASE	61,860.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	7,160.00	GAL
405-240A	MISCELLANEOUS PAVEMENT	790.00	SY
405-245A	APPROACH	1.00	EACH
405-410A	SUPERPAVE HMA PAVEMENT CLASS SP-T	760.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	22,310.00	TON

502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	139.70	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	155.40	CY
502-465A	PRESTRESSED SLAB (48" WIDTH X 26" DEPTH)	468.00	FT
502-515A	THERMAL CONTROL PLAN	1.00	LS
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	20,017.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	12,493.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	18,635.00	LB
504-035A	PEDESTRIAN / BICYCLE RAILING	253.00	FT
504-050A	3-TUBE CURB MOUNT RAIL	653.50	FT
507-005A	ELASTOMERIC BEARINGS PLAIN (48"x6"x0.75" GRADE 4)	16.00	EA
551-005A	PREPARED & PLACED PPC OVERLAY	318.60	SY
551-010A	FURNISHED PPC OVERLAY MATERIAL	7.70	CY
560-005A	DEWATERING FOUNDATION	2.00	LS
574-005A	ANTI-GRAFFITI COATING	8,530.00	SF
575-005A	TEXTURED CONCRETE SURFACE	120.00	SY
584-005A	TEMPORARY SHORING	1.00	LS
584-005B	TEMPORARY SHORING (WALL2) (APPROX 875 SF)	1.00	LS
584-005C	TEMPORARY SHORING (SLOPE 4) (APPROX 312 SF)	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
586-005B	UTILITY CONDUIT (IPC)	1.00	LS
602-045A	24" PIPE CULVERT	94.00	FT
604-035A	18" IRRIGATION PIPE	58.00	FT
604-045A	24" IRRIGATION PIPE	104.00	FT
605-025A	12" STORM SEWER PIPE	2,835.00	FT
605-035A	18" STORM SEWER PIPE	8,458.00	FT
605-045A	24" STORM SEWER PIPE	385.00	FT
605-465A	MANHOLE TYPE C	42.00	EACH
605-467A	MANHOLE TYPE D	5.00	EACH
605-470A	SEDIMENT & OIL TRAP MANHOLE	6.00	EACH
605-500A	CATCH BASIN TYPE 1	75.00	EACH
605-510A	CATCH BASIN TYPE 2	7.00	EACH
605-630A	INLET TYPE 8	3.00	EACH
605-635A	ADJUST MANHOLE COVERS	20.00	EACH
605-640A	ADJUST VALVE COVERS	27.00	EACH
608-035A	18" APRON FOR PIPE	6.00	EACH
608-045A	24" APRON FOR PIPE	1.00	EACH
609-025A	MINOR STRUCTURES (24" HEADWALL)	2.00	EACH
609-025B	MINOR STRUCTURES (5'x5' BOX)	1.00	EACH
610-045A	FENCE TYPE 5 B	138.00	FT
610-300A	TEMPORARY FENCE (LIVESTOCK)	300.00	FT
614-015A	SIDEWALK	3,592.00	SY
614-020A	DRIVEWAY (OFFSET SIDEWALK MOD)	731.00	SY
614-020B	DRIVEWAY (DIPPED SIDEWALK MOD)	141.00	SY
614-020C	DRIVEWAY (ROLLED CURB)	298.00	SY
614-025A	CURB RAMP (PARALLEL)	133.00	SY
614-025B	CURB RAMP (PERPENDICULAR)	177.00	SY
615-259A	CURB TYPE 4	11.00	FT
615-331A	GUTTER TYPE 1 (MOD)	142.00	FT
615-492A	CURB & GUTTER TYPE 2	16,302.00	FT

615-494A	CURB & GUTTER TYPE 4	3,923.00	FT
616-010A	SIGN TYPE B-1	360.00	SF
616-040G	STEEL SIGN POST TYPE B-2	174.00	FT
616-040k	STEEL SIGN POST TYPE E-2	332.00	FT
616-080A	REINSTALL SIGN FACE	5.00	EACH
616-090A	SPECIAL INSTALL SIGN	15.00	EACH
616-100A	SIGN BRACES	136.00	LB
617-005A	DELINEATOR TYPE 1	69.00	EACH
617-010A	DELINEATOR TYPE 2	8.00	EACH
617-070A	MILEPOST TY 2	4.00	EACH
619-010A	ILLUMINATION TYPE 2 (CONVENTIONAL)	1.00	LS
620-020A	PLANTING TREE (SEEDLING or CONTAINER)	53.00	EACH
620-025A	PLANTING SHRUB (BARE-ROOT or CONTAINER)	34.00	EACH
621-005A	SEED BED PREPARATION	3.55	ACRE
621-010A	SEEDING (DRYLAND)	3.49	ACRE
621-010B	SEEDING (RIPARIAN)	0.06	ACRE
621-015A	MULCHING	7.10	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	7.10	ACRE
621-035A	FERTILIZING	3.49	ACRE
624-005A	LOOSE RIPRAP	407.00	CY
624-005A	LOOSE RIPRAP (CLASS VII)	234.00	CY
624-005B	LOOSE RIPRAP (D50=9")	20.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	2,260.00	SF
626-035A	BARRICADE TYPE 2	5.00	EACH
626-040A	BARRICADE TYPE 3	9.00	EACH
626-050A	DRUMS	600.00	EACH
626-076B	ARROW BOARD TYPE C	600.00	DAY
626-092A	TEMPORARY PAVEMENT MARKING TAPE	10,260.00	FT
626-093A	TEMP PAV MARKING - WATERBORNE	256,500.00	FT
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	1,280.00	HR
626-112B	FLOOD LIGHTS	50.00	DAY
626-115A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	600.00	DAY
626-116A	TEMPORARY CONCRETE BARRIER	1,130.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	1,180.00	FT
626-118A	TEMPORARY CRASH CUSHION	4.00	EACH
626-120A	FLAGGER CONTROL	960.00	HR
626-121A	R&R TEMP CRASH CUSHION	5.00	EACH
630-005A	T,W,S,A PAVEMENT MARKINGS - WATERBORNE	1,662.00	SF
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	2,060.00	SF
630-025A	LONG PAV MKG - WATERBORNE	89,590.00	FT
640-005A	DRAINAGE GEOTEXTILE	200.00	SY
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	718.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE (TY III)	25,320.00	SY
645-010A	C3 FIELD LAB - AGG, SOILS, SP 3 & SP 5	1.00	LS
656-010A	SIGNAL HOUSING	31.00	EACH
656-015A	INTERSECTION PREEMPTION DETECTION SYSTEM	2.00	EACH
656-020C	INT DETECTION SYSTEM - VIDEO	2.00	EACH
656-025C	ELECTRICAL SERVICE PEDESTAL TYPE 3	2.00	EACH
656-030A	INTERSECTION SIGNAL STRUCTURE (SH-75 AND ELKHORN)	1.00	EACH

656-030B	INTERSECTION SIGNAL STRUCTURE (SH-75 AND SERENADE)	1.00	EACH
656-035A	INTERSECTION PEDESTRIAN SYSTEM (SH-75 AND ELKHORN)	1.00	EACH
656-035B	INTERSECTION PEDESTRIAN SYSTEM (SH-75 AND SERENADE)	1.00	EACH
656-040A	SIGNAL CABINET	2.00	EACH
656-045A	SIGNAL CONTROLLER	2.00	EACH
656-050A	PED & TRAFF CNTL SIG HEAD FRANG POLES	8.00	EACH
656-065A	COMB CAB & SVS PEDESTAL FOUNDATION	2.00	EACH
656-070A	ADDITIONAL ELECTRICAL ITEMS (SH-75 AND ELKHORN)	1.00	LS
656-070B	ADDITIONAL ELECTRICAL ITEMS (SH-75 AND SERENADE)	1.00	LS
657-015A	RRFB, AC POWERED	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	30,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-15A	RETAINING WALL (LARGE GRAVITY CONCRETE BLOCK)	6,730.00	SF
S501-15B	RETAINING WALL (CAST IN PLACE)	280.00	SF
S501-15C	RETAINING WALL (SMALL GRAVITY CONCRETE BLOCK)	225.00	SF
S501-15F	SOLDIER PILE WALL	1,080.00	SF
S501-17A	MSE RETAINING WALL	1,843.00	SF
S501-25A	SP BRIDGE VIBRATION MONITORING	1.00	LS
S501-30A	SP BRIDGE DRILLED SHAFT (3FT DIAMETER)	320.00	FT
S501-30B	SP BRIDGE MOMENT SLAB (TRAIL CREEK BRIDGE)	290.00	FT
S501-30C	SP BRIDGE MOMENT SLAB (OVER RET WALLS)	242.00	FT
S501-35B	SP BRIDGE REINFORCED STEEPENED SOIL SLOPE	843.00	SY
S501-40A	SP BRIDGE LOW DENSITY CELLULAR CONCRETE FILL	130.00	CY
S501-45A	SP BRIDGE STAINLESS STEEL REINFORCEMENT	1,957.00	LB
S900-50A	CONTINGENCY AMOUNT DRILLED SHAFT REMOVAL OF OBSTRUCTIONS	40,000.00	CA
S901-05A	SP REMOVE KETCHUM ROCK SIGN	1.00	EACH
S901-05B	SP HIGH FLOW BYPASS MANHOLE	3.00	EACH
S901-05C	SP 3' WOOD GATE	1.00	EACH
S901-05D	SP 15' WOOD GATE	1.00	EACH
S901-05E	SP DRYWELL	2.00	EACH
S901-05F	SP REMOVE AND RESET SKI AREA SIGN	2.00	EACH
S901-05G	SP REMOVE AND RESET TRAIL SIGN	1.00	EACH
S901-05H	SP DITCH INLET	3.00	EACH
S901-05I	SP REMOTE NETWORK SYSTEM	2.00	EACH
S901-05J	SP JUNCTION BOX (FUTURE LIGHTING)	9.00	EACH
S901-05K	SP JUNCTION BOX (ITS)	22.00	EACH
S901-05L	SP SPLICE VAULT	2.00	EACH
S901-05M	SP 24" HEADGATE	2.00	EACH
S904-05A	SP REMOVAL OF SIGNAL	1.00	LS
S904-05B	SP TEMPORARY SIGNAL	1.00	LS
S904-05C	SP TURBIDITY MONITORING	1.00	LS
S904-05D	SP SLOPE SPRINKLER SYSTEM	1.00	LS
S911-05A	SP ORANGE SAFETY FENCE	1,200.00	FT
S911-05B	SP REMOVE AND RESET WHITE RAIL FENCE AND GA TES	292.00	FT
S911-05C	SP REMOVE DECORATIVE WALL	209.00	FT
S911-05E	SP REMOVE CONDO WALL (PARTIAL)	7.00	FT
S911-05F	SP WOOD RAIL FENCE	361.00	FT

S911-05G	SP 6' WOOD FENCE	13.00	FT
S911-05H	SP REMOVE AND RESET WOOD RAIL FENCE	31.00	FT
S911-05I	SP INSTALL 2" CONDUIT (FUTURE LIGHTING)	4,010.00	FT
S911-05J	SP INSTALL 4" CONDUIT (ITS)	1,992.00	FT
S911-05K	SP INSTALL 3" CONDUIT (FUTURE IRRIGATION)	255.00	FT
S912-05A	SP LANDSCAPE AND IRRIGATION REPAIR	8,523.00	SY
S912-05B	SP REMOVE AND RESET BRICK PAVERS	87.00	SY
S912-05C	SP THICKENED SIDEWALK FOR RAILING	229.00	SY
S912-05D	SP THICKENED SIDEWALK FOR CIP WALL	108.00	SY
S912-05E	SP GRASS GRID	183.00	SY
S913-05A	SP MODULAR DETENTION SYSTEM	1,097.00	CY
S916-05A	SP TRAFFIC CONTROL SUPERVISOR	360.00	DAY
S916-05B	SP UTILITY COORDINATOR	280.00	DAY
Z629-05A	MOBILIZATION	1.00	LS