

Key No. 20681 - SH-21, SOUTH FORK PAYETTE BR (LOWMAN)
Boise County

Item No	Description	QTY	Unit
104-005A	PARTNERING	32,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	15,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	2,500.00	CA
110-005A	TRAINING	1,397.00	HR
201-005A	CLEARING & GRUBBING	1.10	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	38.00	EACH
203-006A	REMOVAL OF SIGN	16.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	8,650.00	SY
203-020A	REMOVAL OF BRIDGE - FULL	1.00	EACH
203-080A	REMOVAL OF GUARDRAIL	380.00	FT
203-090A	REMOVAL OF INLET	1.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS (18" CMP)	566.00	FT
205-005A	EXCAVATION	2,984.00	CY
205-040A	GRANULAR BORROW	71.00	CY
205-095A	SOFT SPOT REPAIR	10,000.00	CA
209-005A	SMALL DITCH	1,036.00	FT
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	168.00	CY
210-010A	STRUCTURE EXCAVATION SCHEDULE NO. 2	125.00	CY
210-015A	COMPACTING BACKFILL	171.00	CY
212-011A	FIBER WATTLE	2,220.00	FT
212-020A	SILT FENCE	785.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	1.00	EACH
212-095A	INLET PROTECTION	1.00	EACH
212-105A	WATER AND POLLUTION	10,000.00	CA
213-010A	TOPSOIL	762.00	SY
303-022A	3/4" AGGREGATE TYPE B FOR BASE	3,647.00	TON
307-010A	OPEN-GRADED BASE CLASS I	100.00	TON
405-245A	APPROACH	2.00	EACH
405-410A	SUPERPAVE HMA PAVEMENT CLASS SP-T	450.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	1,708.00	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	159.10	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	32.00	CY
502-435A	APPROACH SLAB	188.00	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	35,730.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	3,604.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	340.00	LB
504-005A	STEEL BRIDGE (Approx Weight = 332,091 LB)	1.00	LS
504-050A	3-TUBE CURB MOUNT RAIL	584.00	FT
505-045A	PROVIDE & DRIVE STEEL H PILE (14 X 117)	540.00	FT
505-205C	PROVIDE & INSTALL PILE SHOES OR TIPS	12.00	EACH
507-005A	ELASTOMERIC BEARINGS PLAIN (0.5"x6"x16")	12.00	EA
507-010A	ELASTOMERIC BEARINGS LAMINATED (3"x13"x15")	12.00	EA
511-005A	CONCRETE WATERPROOF SYSTEM (Type C)	143.00	SY
520-005A	PREDRILLING FOR PILING IN SOIL (30" Dia.)	180.00	FT
520-010A	PREDRILLING FOR PILING IN ROCK (30" Dia.)	173.00	FT

551-005A	PREPARED & PLACED PPC OVERLAY	1,196.50	SY
551-010A	FURNISHED PPC OVERLAY MATERIAL	29.10	CY
560-005A	DEWATERING FOUNDATION	1.00	LS
566-005A	COMPRESSION EXPANSION JOINT (2.5")	73.30	FT
576-005A	(GFRP) REINFORCEMENT	333.40	FT
584-005A	TEMPORARY SHORING	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
602-035A	18" PIPE CULVERT	54.00	FT
605-035A	18" STORM SEWER PIPE	523.00	FT
605-615A	INLET TYPE 3	1.00	EACH
608-035A	18" APRON FOR PIPE	2.00	EACH
612-005A	W-BEAM GUARDRAIL	1,469.50	FT
612-050A	GUARDRAIL TERMINAL	6.00	EACH
612-120A	GUARDRAIL TRANSITION, LOW SPEED	4.00	EACH
616-010A	SIGNS TY B	119.30	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	85.00	LB
616-055A	BRKAWY WOOD SIGN POST TY D	0.28	MFBM
617-005A	DELINEATOR TY 1	17.00	EACH
617-045A	DELINEATOR TY 9	60.00	EACH
621-010A	SEEDING	0.81	ACRE
621-035A	FERTILIZING	0.81	ACRE
621-070A	HYDRA APPLIED EROSION CONTROL PROD	0.81	SY
621-080A	TURF REINFORCED MAT	762.00	SY
624-005A	LOOSE RIPRAP (D50=12")	508.00	CY
624-005B	LOOSE RIPRAP (D50=0.5')	271.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	529.00	SF
626-040A	BARRICADE TY 3	4.00	EACH
626-050A	DRUMS	70.00	EACH
626-093A	TEMP PAV MARKING - WATERBORNE	2,812.00	FT
626-100B	MISC TEMPORARY TRAF CONT ITEMS	25,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	1,200.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	1,365.00	DAY
626-116A	TEMP CONCRETE BARRIER	1,050.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	525.00	FT
626-118A	TEMP CRASH CUSHION SACRIFICIAL - WATER FILLED	2.00	EACH
626-120A	FLAGGER CONTROL	300.00	HR
626-130B	TEMPORARY TRAFFIC CONTROL SIGNAL	920.00	DAY
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	75.00	EACH
630-005A	T,W,S,A PAVEMENT MARKINGS - WATERBORNE	180.00	SF
630-025A	LONG PAV MKG - WATERBORNE	14,400.00	FT
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	1,780.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	8,930.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	15,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-20A	SP BRIDGE DRILLED SHAFT - CROSS HOLE LOG (CSL) TES T	4.00	EACH
S501-25A	SP BRIDGE SEWER UTILITY	1.00	LS
S501-30A	SP BRIDGE DRILLED SHAFT - CROSS HOLE LOG (CSL) ACC ESS TUBES	1,199.00	FT

S501-30B	SP BRIDGE DRILLED SHAFT - PERMANENT CASING (4.92' x 1" WALL)	159.80	FT
S501-40A	SP BRIDGE UHPC (ULTRA-HIGH PERFORMANCE CONCRETE)	56.00	CY
S501-40B	SP BRIDGE DRILLED SHAFT - SOIL EXCAVATION INCLUDING HAUL	25.00	CY
S501-40C	SP BRIDGE DRILLED SHAFT - ROCK EXCAVATION INCLUDING HAUL	81.00	CY
S501-40D	SP BRIDGE DRILLED SHAFT - SELF-CONSOLIDATING CONCRETE CLASS 40A	130.00	CY
S501-45A	SP BRIDGE DRILLED SHAFT - METAL REINFORCEMENT	30,920.00	LB
S501-51A	SP BRIDGE FULL-DEPTH DECK PANELS	8,960.80	SF
S900-50A	CONTINGENCY AMOUNT ASBESTOS TESTING, REMOVAL, AND DISPOSAL	15,000.00	CA
S900-50B	CONTINGENCY AMOUNT DRILLED SHAFT - REMOVAL OF OBSTRUCTIONS	50,000.00	CA
S900-50C	CONTINGENCY AMOUNT DIRECTED SIGNAL TIMING MONITOR	50,000.00	CA
S901-05A	SP INSTALLATION OF WILLOW CUTTINGS OR PLANTINGS	70.00	EACH
S904-05A	SP TURBIDITY MONITORING	1.00	LS
S915-05A	SP REINFORCED SOIL SLOPE	7,650.00	SF
Z629-05A	MOBILIZATION	1.00	LS