University of Kentucky
Procurement Services

INVITATION FOR BIDS

CCK-2563.30-16-25
CTC + AAC BP08 Fit-Out Group 1
ADDENDUM #1
12/05/2024

IMPORTANT: BID AND ADDENDUM MUST BE RECEIVED BY: 01/16/2025 @ 3:00 P.M. LEXINGTON, KY TIME

Bidder must acknowledge receipt of this, and any addendum as stated in the Invitation for Bids.

ITEM #1: Revisions & Modifications to the Original Bid Documents

- Please refer to and incorporate into your bid the enclosed additional information from the project team.

OFFICIAL APPROVAL
UNIVERSITY OF KENTUCKY

12/05/2024

Ken Scott

Ken Scott / (859) 257-9102

SIGNATURE

_____

_____
Typed or Printed Name

University of Kentucky
Procurement Services
322 Peterson Service Building
Lexington, KY 40506-0005

An Equal Opportunity University

CHAMPLIN
ARCHITECTURE

Addendum 1

Client	University of Kentucky Healthcare	Date	12/5/24
Project	UK Cancer Center + AAC BP-08 Fitout (Group 1)	UK Project #	2563.3
	Addendum #1 UK-2563.30-16-25	Champlin Project #	514-5350

This addendum provides information to clarify or adjust construction items which may affect any or all trade contractors. The original documents for the referenced project are amended as noted in this addendum and made part of said documents and shall govern the work covered by the Form of Proposal. All work to be in strict accordance with the terms, stipulations and conditions of contract documents.

SUMMARY OF ATTACHMENTS

PART A - DRAWINGS:

None.

PART B SPECIFICATIONS

Table of Contents APPENDIX
- Deleted Medical Equipment Excel Report
- Added Medical Equipment Reports (PDF with embedded Cut Sheet Links). PDF contains Bookmarks organized by level and specialty (e.g. Pharmacy, Breast Imaging, Rad-Onc Treatment).

PART C – RESPONSES TO BIDDER QUESTIONS:

None.

PART D – ADDITIONAL EXHIBITS

None

PART E – SKETCHES

None.

PART F – UPDATED BID FORMS

None.

End of Addendum

TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS
012300 Alternates
014339.10 Integrated Interior Mockups
017419 Construction Waste Management and Disposal
017419A Construction Waste Management Tracking Worksheet
017900 UK Design and Construction Standards Demonstration and Training
018113.20 Sustainable Design Requirements – LEED V4.1 BD+C: New Construction and Major Renovation
018113.20A New Construction Checklist
018113.20B LEED Product Data Sheet
019113 Building Systems Commissioning

DIVISION 02 - EXISTING CONDITIONS
Not Used

DIVISION 03 – CONCRETE
030513 Concrete Sealers

DIVISION 04 – MASONRY
044313.16 Adhered Stone Masonry Veneer (Interior)

DIVISION 05 – METALS
055813 Column Covers
055819 Heating/Cooling Unit Covers
057313 Glazed Decorative Metal Railings
057500 Decorative Formed Metal

DIVISION 06 - WOOD, PLASTICS AND COMPOSITES
060660 Plastic Fabrications
061053 Miscellaneous Rough Carpentry
062023 Interior Finish Carpentry
064116 Plastic-Laminate-Faced Architectural Cabinets

DIVISION 07 - THERMAL AND MOISTURE PROTECTION
072100 Thermal Insulation
078100 Applied Fire Protection
078123 Intumescent Fire Protection
078413 Penetration Firestopping
078443 Joint Firestopping
079200 Joint Sealants
079513.13 Interior Expansion Joint Cover Assemblies

DIVISION 08 – OPENINGS
081113 Hollow Metal Doors and Frames
081416 Flush Wood Doors
081713 Integrated Metal Door Opening Assemblies
083113 Access Doors and Frames
083313 Coiling Counter Doors
083323.10 Overhead Coiling Doors - Fire Rated
083343 Overhead Coiling Smoke Curtains

083400 Special Function Doors
083450 Neutron/Radiation Shielding Sliding Doors
083451 Neutron/Radiation Shielding Swinging Doors
083513 Accordion Folding Fire Doors
084113 Aluminum-Framed Entrances and Storefronts – Interior
084126 All-Glass Entrances and Storefronts
084243 Intensive Care Unit/Critical Care Unit (ICU/CCU) Entrances
084418 Glazed Steel Curtain Wall-Fireframes Curtain Wall Series
085100 Steel Windows
087100 Door Hardware
087113 Power Door Operators
088005 Glazing - Interior
088113 Decorative Glass Glazing
088300 Mirrors
088813 Fire-Rated Glazing

DIVISION 09 - FINISHES
092116.23 Gypsum Board Shaft Wall Assemblies
092216 Non-Structural Metal Framing
092900 Gypsum Board
093013 Ceramic Tiling
095113 Acoustical Panel Ceilings
095133 Acoustical Metal Pan Ceilings
095426 Suspended Wood Ceilings
096513 Resilient Base and Accessories
096516 Resilient Sheet Flooring
096519 Resilient Tile Flooring
096536 Static-Controlled Resilient Flooring
096623 Resinous Matrix Terrazzo Flooring
096723 Resinous Flooring
096813 Tile Carpeting
097200 Wallcoverings
097216.16 Rigid-Sheet Vinyl Wall Coverings
097700 Fiberglass-Reinforced Wall Panels
097713 Site-Fabricated Stretched Fabric Wall Systems
097773 Metal Louver Wall Systems
098316 Acoustical Plaster Ceilings
098433 Sound-Absorbing Wall Units
098453 Sound Barrier Mullion Trim Cap
099114 Exterior Painting
099124 Interior Painting
099300 Staining and Transparent Finishing
099600 High-Performance Coatings

DIVISION 10 – SPECIALTIES
101100 Visual Display Units
101210 Display Wall System
102113.19 Plastic Toilet Compartments
102123 Cubicle Curtains and Track
102233 Accordion Folding Partitions
102239 Folding Panel Partitions
102600 Wall and Door Protection
102800 Toilet, Bath, and Laundry Accessories
104413 Fire Protection Cabinets
104416 Fire Extinguishers

104513 Photoluminescent Egress Path Markings
105113 Metal Lockers
105123 Plastic-Laminate-Clad Lockers
105129 Phenolic Lockers
105600 Shelving and Closet Hardware

DIVISION 11 – EQUIPMENT
114000 Foodservice Equipment

DIVISION 12 – FURNISHINGS
122200 Curtains and Drapes
122413 Roller Window Shades
123570 Healthcare Casework
123616 Metal Countertops
123623.13 Plastic-Laminate-Clad Countertops
123661.16 Solid-Surfacing Countertops
123661.19 Quartz Agglomerate Countertops

DIVISION 13 - SPECIAL CONSTRUCTION
134900 Radiation Protection
134901.01 MRI, RF Shielded Enclosure

DIVISION 14 - CONVEYING EQUIPMENT
149200 Pneumatic Tube Systems

DIVISION 20 - MECHANICAL
200100 General Provisions
200200 Scope of the Mechanical Work
200300 Shop Drawings, Descriptive Literature, Maintenance Manuals, Parts Lists, Special Keys and Tools
200500 Coordination Among Trades, Systems Interfacing and Connection of Equipment Furnished by Others
201100 Sleeving, Cutting, Patching and Repairing
201200 Excavation, Trenching, Backfilling and Grading
201300 Pipe, Pipe Fittings, and Pipe Support
201310 Welding
202100 Valves and Cocks
202110 Access to Valves, Equipment, Filters, Etc.
202200 Insulation
202300 Thermometers and Others, Monitoring Instruments
202400 Identifications, Tags, Charts, Etc.
202500 Hangers, Clamps, Attachments, Etc.
202600 Mechanical/Electrical Vibration Controls and Seismic Restraints
203100 Testing, Balancing, Lubrication and Adjustments

DIVISION 21 – FIRE SUPPRESSION
210100 Fire Protection System

DIVISION 22 – PLUMBING
220100 Plumbing Specialties
220200 Plumbing Fixtures, Fittings and Trim
220500 Compressed Air System
220600 Medical Gas Piping Systems
226700 Reverse Osmosis Water Treatment System

DIVISION 23 – HEATING VENTILATING AND AIR CONDITIONING

230100 Pumps
230200 HVAC Equipment and Hydronic Specialties
230300 Condensate Drainage System (For Cooling Equipment)
230500 Common Work Results for HVAC, Refrigerant Management
230800 Commissioning of HVAC
231100 Registers, Grilles, Diffusers and Louvers
231110 Integrated Ceiling System
231200 Sheet Metal and Flexible Duct
232500 HVAC Water Treatment
233423 HVAC Power Ventilators
233600 Air Terminal Units
235700 Heat Exchangers for HVAC
236426 Rotary-Screw Water Chillers
238123 Computer-Room Air-Conditioners
238216 Air Coils
238219 Fan Coil Units
238414 Electric Resistive Humidifiers

DIVISION 26 – ELECTRICAL

260000 General Electrical Requirements
260513.16 Medium-Voltage, Single-and-Multi-Conductor Cables
260516 Owner-Furnished Equipment
260519 Low-Voltage Electrical Power Conductors and Cables
260526 Grounding and Bonding for Electrical Systems
260529 Hangers and Supports for Electrical Systems
260533 Raceway and Boxes for Electrical Systems
260533.13 Surface Raceway System
260543.10 Underground Ducts and Raceways for Electrical Systems
260543.13 Excavation and Backfill
260553 Electrical Systems Identification
260573 Power System Studies
260593 Electrical Systems Firestopping
260812 Power Distribution Acceptance Tests
260813 Power Distribution Acceptance Test Tables
260923 Lighting Control Devices
260943 Network Lighting Controls
261116 Secondary Unit Substations
261216 Dry-Type, Medium-Voltage Transformers
261316 Medium-Voltage Fusible Interrupter Switchgear
262200 Low-Voltage Transformers
262300 Low-Voltage Switchgear
262313 Paralleling Low-Voltage Switchgear
262413 Switchboards
262416.13 Lighting and Appliance Panelboards
262416.16 Distribution Panelboards
262416.19 Isolation Panelboards
262500 Enclosed Bus Assemblies
262550 Generator Docking Station
262713 Electrical Metering
262726 Wiring Devices
262813 Fuses

262816 Enclosed Switches and Circuit Breakers
262913 Enclosed Controllers
263213 Diesel Engine Generators
263623 Automatic Transfer Switches
264113 Lightning Protection for Structures
264300 Surge Protective Devices (SPD)
265100 Lighting Systems

DIVISION 27 – TELECOMMUNICATIONS
270501 General Provisions Telecommunications
270503 Shop Drawings, Literature, Manuals, Parts Lists, and Special Tools
270508 Coordination Among Trades, Systems Interfacing and Connection of Equipment Furnished by Others
270526 Grounding and Bonding for Communications Systems
270536 Cable Trays for Communications Systems
270553 Identification for Communication Systems
271100 Communications Equipment Room Fittings
271500 Communications Horizontal Cabling
275223 Nurse Call System

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY
281643 Perimeter Security Safety
282300 Video Surveillance
283113 Fire Detection and Alarm Systems

DIVISION 33 – UTILITIES
330000 General Mechanical Site Requirements
330524 Mechanical Site Utility Valves
330529 Mechanical Site Utility Supporting Devices
330530 Steam Concrete Structures
330531 Cast-In-Place Concrete
330532 Mechanical Site Utilities Waterproofing
330553 Mechanical Site Utility Identification
330700 Mechanical Site Utility Systems Insulation
332120 Mechanical Site Utility Piping Specialties
332124 Mechanical Site Utility Sump Pumps
335110 Mechanical Site Utility Pipe and Pipe Fittings

APPENDIX
Shielding Calculation Report Linear Accelerators dated 2/6/2024 ..... 1 thru 20
Shielding Calculation Report HDR Vault dated 6/9/2023 ..... 1 thru 4
Radiation Shielding Design Report (PET/CT, SPECT/CT, Hot Lab) dated Revised 7/30/2024 ..... 1 thru 8
Radiation Shielding Design Report (X-ray Imaging Rooms, Etc.) ..... 1 thru 12
Medical Equipment Narrative ..... 1 thru 4
Equipment Responsibility Matrix ..... 1 thru 6
Medical Equipment Budget Summary ..... 1 thru 2
Medical Equipment Reports (Cut Sheet Links) ..... 1 thru 1998
~~*Medical Equipment Excel Report*~~
Medical Equipment Site Specific Drawings

END OF TABLE OF CONTENTS

TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS
012300 Alternates
014339.10 Integrated Interior Mockups
017419 Construction Waste Management and Disposal
017419A Construction Waste Management Tracking Worksheet
017900 UK Design and Construction Standards Demonstration and Training
018113.20 Sustainable Design Requirements – LEED V4.1 BD+C: New Construction and Major Renovation
018113.20A New Construction Checklist
018113.20B LEED Product Data Sheet
019113 Building Systems Commissioning

DIVISION 02 - EXISTING CONDITIONS
Not Used

DIVISION 03 – CONCRETE
030513 Concrete Sealers

DIVISION 04 – MASONRY
044313.16 Adhered Stone Masonry Veneer (Interior)

DIVISION 05 – METALS
055813 Column Covers
055819 Heating/Cooling Unit Covers
057313 Glazed Decorative Metal Railings
057500 Decorative Formed Metal

DIVISION 06 - WOOD, PLASTICS AND COMPOSITES
060660 Plastic Fabrications
061053 Miscellaneous Rough Carpentry
062023 Interior Finish Carpentry
064116 Plastic-Laminate-Faced Architectural Cabinets

DIVISION 07 - THERMAL AND MOISTURE PROTECTION
072100 Thermal Insulation
078100 Applied Fire Protection
078123 Intumescent Fire Protection
078413 Penetration Firestopping
078443 Joint Firestopping
079200 Joint Sealants
079513.13 Interior Expansion Joint Cover Assemblies

DIVISION 08 – OPENINGS
081113 Hollow Metal Doors and Frames
081416 Flush Wood Doors
081713 Integrated Metal Door Opening Assemblies
083113 Access Doors and Frames
083313 Coiling Counter Doors
083323.10 Overhead Coiling Doors - Fire Rated
083343 Overhead Coiling Smoke Curtains

083400 Special Function Doors
083450 Neutron/Radiation Shielding Sliding Doors
083451 Neutron/Radiation Shielding Swinging Doors
083513 Accordion Folding Fire Doors
084113 Aluminum-Framed Entrances and Storefronts – Interior
084126 All-Glass Entrances and Storefronts
084243 Intensive Care Unit/Critical Care Unit (ICU/CCU) Entrances
084418 Glazed Steel Curtain Wall-Fireframes Curtain Wall Series
085100 Steel Windows
087100 Door Hardware
087113 Power Door Operators
088005 Glazing - Interior
088113 Decorative Glass Glazing
088300 Mirrors
088813 Fire-Rated Glazing

DIVISION 09 - FINISHES
092116.23 Gypsum Board Shaft Wall Assemblies
092216 Non-Structural Metal Framing
092900 Gypsum Board
093013 Ceramic Tiling
095113 Acoustical Panel Ceilings
095133 Acoustical Metal Pan Ceilings
095426 Suspended Wood Ceilings
096513 Resilient Base and Accessories
096516 Resilient Sheet Flooring
096519 Resilient Tile Flooring
096536 Static-Controlled Resilient Flooring
096623 Resinous Matrix Terrazzo Flooring
096723 Resinous Flooring
096813 Tile Carpeting
097200 Wallcoverings
097216.16 Rigid-Sheet Vinyl Wall Coverings
097700 Fiberglass-Reinforced Wall Panels
097713 Site-Fabricated Stretched Fabric Wall Systems
097773 Metal Louver Wall Systems
098316 Acoustical Plaster Ceilings
098433 Sound-Absorbing Wall Units
098453 Sound Barrier Mullion Trim Cap
099114 Exterior Painting
099124 Interior Painting
099300 Staining and Transparent Finishing
099600 High-Performance Coatings

DIVISION 10 – SPECIALTIES
101100 Visual Display Units
101210 Display Wall System
102113.19 Plastic Toilet Compartments
102123 Cubicle Curtains and Track
102233 Accordion Folding Partitions
102239 Folding Panel Partitions
102600 Wall and Door Protection
102800 Toilet, Bath, and Laundry Accessories
104413 Fire Protection Cabinets
104416 Fire Extinguishers

104513 Photoluminescent Egress Path Markings
105113 Metal Lockers
105123 Plastic-Laminate-Clad Lockers
105129 Phenolic Lockers
105600 Shelving and Closet Hardware

DIVISION 11 – EQUIPMENT
114000 Foodservice Equipment

DIVISION 12 – FURNISHINGS
122200 Curtains and Drapes
122413 Roller Window Shades
123570 Healthcare Casework
123616 Metal Countertops
123623.13 Plastic-Laminate-Clad Countertops
123661.16 Solid-Surfacing Countertops
123661.19 Quartz Agglomerate Countertops

DIVISION 13 - SPECIAL CONSTRUCTION
134900 Radiation Protection
134901.01 MRI, RF Shielded Enclosure

DIVISION 14 - CONVEYING EQUIPMENT
149200 Pneumatic Tube Systems

DIVISION 20 - MECHANICAL
200100 General Provisions
200200 Scope of the Mechanical Work
200300 Shop Drawings, Descriptive Literature, Maintenance Manuals, Parts Lists, Special Keys and Tools
200500 Coordination Among Trades, Systems Interfacing and Connection of Equipment Furnished by Others
201100 Sleeving, Cutting, Patching and Repairing
201200 Excavation, Trenching, Backfilling and Grading
201300 Pipe, Pipe Fittings, and Pipe Support
201310 Welding
202100 Valves and Cocks
202110 Access to Valves, Equipment, Filters, Etc.
202200 Insulation
202300 Thermometers and Others, Monitoring Instruments
202400 Identifications, Tags, Charts, Etc.
202500 Hangers, Clamps, Attachments, Etc.
202600 Mechanical/Electrical Vibration Controls and Seismic Restraints
203100 Testing, Balancing, Lubrication and Adjustments

DIVISION 21 – FIRE SUPPRESSION
210100 Fire Protection System

DIVISION 22 – PLUMBING
220100 Plumbing Specialties
220200 Plumbing Fixtures, Fittings and Trim
220500 Compressed Air System
220600 Medical Gas Piping Systems
226700 Reverse Osmosis Water Treatment System

DIVISION 23 – HEATING VENTILATING AND AIR CONDITIONING

230100 Pumps
230200 HVAC Equipment and Hydronic Specialties
230300 Condensate Drainage System (For Cooling Equipment)
230500 Common Work Results for HVAC, Refrigerant Management
230800 Commissioning of HVAC
231100 Registers, Grilles, Diffusers and Louvers
231110 Integrated Ceiling System
231200 Sheet Metal and Flexible Duct
232500 HVAC Water Treatment
233423 HVAC Power Ventilators
233600 Air Terminal Units
235700 Heat Exchangers for HVAC
236426 Rotary-Screw Water Chillers
238123 Computer-Room Air-Conditioners
238216 Air Coils
238219 Fan Coil Units
238414 Electric Resistive Humidifiers

DIVISION 26 – ELECTRICAL

260000 General Electrical Requirements
260513.16 Medium-Voltage, Single-and-Multi-Conductor Cables
260516 Owner-Furnished Equipment
260519 Low-Voltage Electrical Power Conductors and Cables
260526 Grounding and Bonding for Electrical Systems
260529 Hangers and Supports for Electrical Systems
260533 Raceway and Boxes for Electrical Systems
260533.13 Surface Raceway System
260543.10 Underground Ducts and Raceways for Electrical Systems
260543.13 Excavation and Backfill
260553 Electrical Systems Identification
260573 Power System Studies
260593 Electrical Systems Firestopping
260812 Power Distribution Acceptance Tests
260813 Power Distribution Acceptance Test Tables
260923 Lighting Control Devices
260943 Network Lighting Controls
261116 Secondary Unit Substations
261216 Dry-Type, Medium-Voltage Transformers
261316 Medium-Voltage Fusible Interrupter Switchgear
262200 Low-Voltage Transformers
262300 Low-Voltage Switchgear
262313 Paralleling Low-Voltage Switchgear
262413 Switchboards
262416.13 Lighting and Appliance Panelboards
262416.16 Distribution Panelboards
262416.19 Isolation Panelboards
262500 Enclosed Bus Assemblies
262550 Generator Docking Station
262713 Electrical Metering
262726 Wiring Devices
262813 Fuses

262816 Enclosed Switches and Circuit Breakers
262913 Enclosed Controllers
263213 Diesel Engine Generators
263623 Automatic Transfer Switches
264113 Lightning Protection for Structures
264300 Surge Protective Devices (SPD)
265100 Lighting Systems

DIVISION 27 – TELECOMMUNICATIONS
270501 General Provisions Telecommunications
270503 Shop Drawings, Literature, Manuals, Parts Lists, and Special Tools
270508 Coordination Among Trades, Systems Interfacing and Connection of Equipment Furnished by Others
270526 Grounding and Bonding for Communications Systems
270536 Cable Trays for Communications Systems
270553 Identification for Communication Systems
271100 Communications Equipment Room Fittings
271500 Communications Horizontal Cabling
275223 Nurse Call System

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY
281643 Perimeter Security Safety
282300 Video Surveillance
283113 Fire Detection and Alarm Systems

DIVISION 33 – UTILITIES
330000 General Mechanical Site Requirements
330524 Mechanical Site Utility Valves
330529 Mechanical Site Utility Supporting Devices
330530 Steam Concrete Structures
330531 Cast-In-Place Concrete
330532 Mechanical Site Utilities Waterproofing
330553 Mechanical Site Utility Identification
330700 Mechanical Site Utility Systems Insulation
332120 Mechanical Site Utility Piping Specialties
332124 Mechanical Site Utility Sump Pumps
335110 Mechanical Site Utility Pipe and Pipe Fittings

APPENDIX
Shielding Calculation Report Linear Accelerators dated 2/6/2024 ..... 1 thru 20
Shielding Calculation Report HDR Vault dated 6/9/2023 ..... 1 thru 4
Radiation Shielding Design Report (PET/CT, SPECT/CT, Hot Lab) dated Revised 7/30/2024 ..... 1 thru 8
Radiation Shielding Design Report (X-ray Imaging Rooms, Etc.) ..... 1 thru 12
Medical Equipment Narrative ..... 1 thru 4
Equipment Responsibility Matrix ..... 1 thru 6
Medical Equipment Budget Summary ..... 1 thru 2
Medical Equipment Reports (Cut Sheet Links) ..... 1 thru 1998
~~*Medical Equipment Excel Report*~~
Medical Equipment Site Specific Drawings

END OF TABLE OF CONTENTS

Room: Break Room
Room #: B005D

Department: Materials Management / Dock

Coffee Brewer

AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Break Room **Department: Materials Management / Dock**

Room #: B005D

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Freezer, Commercial

AE #: FRCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Summit Appliance Div / Felix Storch	SCFF237		Floor	OF/VI	Project

The SCFF237 is a 23 cu.ft commercial all-freezer with a complete stainless steel cabinet. View Cutsheet 209340

Alt for Frigidaire Ref/Frzr

W x D x H: 27.5 x 31 x 83.8 in.
Electrical: 115V 60Hz 8A **Weight:** 273 lbs.
Elect Notes: NEMA 15-5P

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser. View Cutsheet 142083

W x D x H: 21 x 24 x 36 in. **Clearance:** Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase **Weight:** 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90º hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Room: Break Room **Department:** Materials Management / Dock

Room #: B005D

Ice Maker / Water Dispenser, Component — AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series

No Cutsheet 211856

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator.

View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required

View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Room: Break Room **Department:** Materials Management / Dock

Room #: B005D

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Request from Mark Filburn to monitor temperature for all staff breakroom refrigerators.

Network: Wired

Refrigerator, Double Door Glass — AE #: REDD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Summit Appliance Div / Felix Storch	SCR49SSG		Floor	OF/VI	Project

49 cu.ft. commercial reach-in refrigerator in complete stainless steel with glass doors. View Cutsheet 210283

Model confirmed with user group

W x D x H: 55.3 x 31 x 83.8 in.
Electrical: 115V 60Hz 7.5A **Weight:** 441 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling w/ Lid/Sign — AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Med Gas Room **Department: Materials Management / Dock**

Room #: C000N1

Room Notes: This is not a manifold room. Room intended to hold E cylinders for building. Vendor to bring in and swap used tanks from floors. Full and used cylinders need to be separated.

Cabinet, Medical Gas Tank

AE #: CMGT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	E.L.S. Products Corp	MG121		Floor	OF/OI	Project

Lockable oxygen storage cabinet, holds 21-24 D and/or E cylinders. With self latch standard door. Optional casters add 4" to height and 30 pounds to weight

View Cutsheet 209279

Need to store at least 50 full tanks and empty tanks. (3) cabinets intended for 3 each. This model confirmed.

W x D x H: 44 x 18 x 43 in.

Weight: 265 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Casters-Factory Installed (2 Rigid, 2 Swivel)	CA18	1	6

Room: Radioactive Delivery Holding

Department: Materials Management / Dock

Room #: C000N3

Room Notes: Assumes no medical equipment required for this space.

Room: Mail Room

Department: Materials Management / Dock

Room #: C000W2

Cart, Mail

AE #: CMAL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Uline	H-1200		Floor	OF/OI	Project

2 removable baskets for sorting and loading. File capacity – 80-100 letter or legal-size folders. 10" semi-pneumatic rear wheels. Recommended for heavy loads or longer distances. Hanging file folders available. View Cutsheet 171305

W x D x H: 23 x 30 x 38 in.

Cart, Utility

AE #: CAUT-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	MW605		Floor	OF/VI	Project

Two-shelf chrome wire utility cart with handles and 36"x18" shelves. Ships disassembled in one carton. Load capacity 375 lbs. Four 4" resilient rubber wheels. View Cutsheet 209185

W x D x H: 36 x 18 x 38 in.

Weight: 40 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling Can/ Bottle

AE #: WRCB-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	Project

Green slim jim recycling with venting channels; 23 gallon View Cutsheet 124391

W x D x H: 11 x 22 x 30 in.

Room: Lockers

Department: Materials Management / Dock

Room #: C000W7

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Dock **Department:** Materials Management / Dock

Room #: C001

Cart, Flatbed

AE #: CAFL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	59UZ31		Floor	OF/OI	Project

Magliner aluminum deck platform truck with 2000 lb. load capacity and 12.5"H deck. Ribbed deck surface. Removable raised end handle. Casters 8" thermoplastic solid rubber: (2) rigid and (2) swivel. View Cutsheet 208882

Quantity and specs per Carl Jackson

W x D x H: 30 x 60 x 39 in.

Cart, Supply, 4ft

AE #: CASU-74

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Quantum Storage Systems	WR74-2448P / 74UP		Floor	OF/OI	Project

Stationary steel wire shelving 48"W x 24"D x 74"H with 4 shelves for wet and dry environments, starter configuration. Green epoxy coating contains antimicrobial additive that prevents growth of mold, mildew, and bacteria. Load capacity 800 lbs. per shelf / 3200 lbs. total. Assemble without tools. View Cutsheet 208938

W x D x H: 48 x 24 x 74 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Caster Kit, 5",		1	4

Cart, Utility

AE #: CAUT-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	MW605		Floor	OF/VI	Project

Two-shelf chrome wire utility cart with handles and 36"x18" shelves. Ships disassembled in one carton. Load capacity 375 lbs. Four 4" resilient rubber wheels. View Cutsheet 209185

W x D x H: 36 x 18 x 38 in.

Weight: 40 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. One dispenser needed by each door.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Clean Dock **Department:** Materials Management / Dock

Room #: C001

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Pallet Jack — AE #: PAJA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Crown	SP 3230		Floor	OF/OI	Project

Walkie electric pallet truck; load capacity 4500 lbs. Lift height 9.25". Fork length 47.6". Travel speed empty 3.7 mph / loaded 3.5 mph. View Cutsheet 208883

W x D x H: 27.9 x 70.9 x 47.5 in.
Electrical: 115V 60Hz **Weight:** 715 lbs.

Pallet Jack — AE #: PAJA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Crown	PTH-50-27-48		Floor	OF/OI	Project

Manual pallet jack with 48" fork length. Maximum lift height up to 7.95". Maximum load capacity up to 5000 lbs. Depth and height estimated based on 48" fork length. 7" articulating wheels. Reinforced handle with ergonomic contoured design. View Cutsheet 208943

W x D x H: 27 x 56 x 48 in.
Weight: 160 lbs.

Refrigerator Freezer, Upright — AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant. View Cutsheet 208926

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Room: Clean Dock

Department: Materials Management / Dock

Room #: C001

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office

Department: Materials Management / Dock

Room #: C001A

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Office, Shared

Department: Materials Management / Dock

Room #: C001B

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Gen Storage

Department: Materials Management / Dock

Room #: C002

Cart, Biohazard Container

AE #: CABC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Stericycle			Floor	OF/VI	Project

Custom Shelving Cart to hold Stericycle Biohazard Containers/Boxes

View Cutsheet 209276

Clean sharps containers for distribution to floors as needed

W x D x H: 48 x 24 x 69 in.

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

Spare crash carts to exchange with used carts.

W x D x H: 45 x 22.6 x 72 in.

Cart, Supply

AE #: CASU-69

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
8	Intermetro Industries	SUPER ERECTA	A566BC/A2460BR	Floor	OF/VI	Project

Adjustable super erecta chrome plated wire stem caster cart with 5 shelves, (4) posts; 5" casters (2 swivel, 2 brake). 60"w x 24"d x 69"h.

View Cutsheet 62298

Solid bottom shelf

W x D x H: 60 x 24 x 69 in.

Cart, Supply

AE #: CASU-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
16	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Super erecta model with chrome finish to include (3) wire shelves, (1) solid bottom shelf, (2) braking casters, (2) swivel casters, and (4) 63" posts

View Cutsheet 160459

W x D x H: 48 x 24 x 68 in.

Room: Gen Storage **Department: Materials Management / Dock**

Room #: C002

Cart, Supply — AE #: CASU-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	2424FS		Floor	OF/VI	Project

Standard type 304 solid stainless steel shelves with (2) revolving and (2) braking caster wheels. View Cutsheet 167384

W x D x H: 24 x 24 x 68 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Multi-Tier Shelving		1	1

Container, Pharmacy Waste - Black — AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
60	Stericycle	H18B		Floor	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid View Cutsheet 209270

Clean replacement bins for distribution to floors as needed. Can stack.

W x D x H: 12.5 x 17.3 x 24 in.

Container, Pharmacy Waste - Blue — AE #: COPW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	Brute 32-Gallon Round Container	FG263200BLUE	Floor	OF/VI	Service Agreement

Round lidded blue container for pharmaceutic waste, 30-gallon capacity. Diameter with handle is 25"(additional 1.54" on each side) View Cutsheet 209271

Clean replacement drums for non-hazardous pharmacy waste.

W x D x H: 21.9 x 21.9 x 27.8 in. **Clearance:** Left 1.54 in.; Right 1.54 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
32 Gallon Lid	FG263100BLUE	1	2

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. One dispenser needed by each door.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Gen Storage

Department: Materials Management / Dock

Room #: C002

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height

View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Soiled Dock **Department: Materials Management / Dock**

Room #: C003

Room Notes: Radiation monitors specified by RSO Bryan Lemieux

Monitor, Radiation

AE #: MORA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	375P-336	48-3285	Wall	OF/CI/VI	Project

Screening tool features (2) large wall mounted plastic scintillation detectors; digital controller includes battery back-up; programmable alarms; networkable. Check source: domestic CS137. View Cutsheet 170311

To be placed outside of Regulated Medical Waste room in entry way to Soiled Dock.

Network: Wired **Network Notes:** Refer to cut sheet for further information

Electrical: 120V 60Hz 10W
Elect Notes: **see manufacturer cutsheet for additional information**
Struct Notes: **see manufacturer cutsheet for additional information**

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Ethernet hardware kit	4396-579	1	1
Mains Relay +3 Pin	4396-202	1	1

Monitor, Radiation

AE #: MORA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	375P-336	48-3285	Wall	OF/CI/VI	Project

Screening tool features (2) large wall mounted plastic scintillation detectors; digital controller includes battery back-up; programmable alarms; networkable. Check source: domestic CS137. View Cutsheet 170311

To be placed outside of Pharmaceutical Waste room in entry way to Soiled Dock.

Network: Wired **Network Notes:** Refer to cut sheet for further information

Electrical: 120V 60Hz 10W
Elect Notes: **see manufacturer cutsheet for additional information**
Struct Notes: **see manufacturer cutsheet for additional information**

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Ethernet hardware kit	4396-579	1	1
Mains Relay +3 Pin	4396-202	1	1
Webpage and Service Software	1370-077	1	1

Room: Soiled Linen

Department: Materials Management / Dock

Room #: C003C

Room Notes: Linen vendor Logans will pick up from this area. No medical equipment needed for this area.

Room: Radioactive Waste **Department:** Materials Management / Dock

Room #: C005

Room Notes: Room managed by Radiation Safety (Bryan Lemieux)

Bin, Plastic

AE #: BIPL-15

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
52	Quantum Storage Systems	SNT300BL		Shelf	OF/OI	Project

Plastic blue bin without lid. Storage capacity 27.7 gallons. Stackable. Load capacity 100 lbs. View Cutsheet 209470

Quantity to be 4 for every shelving unit. Adjust quantity when shelving unit layout determined.

W x D x H: 19.5 x 29.5 x 15 in.

Cabinet, Lead Lined, Waste & Storage

AE #: CLLW-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nuclear Shields, B.V.	S0009		Floor	OF/CI	Project

Mobile lead shielded waste bin. Stainless steel interior and exterior. Lead thickness 12.5mm. Two methods to open cabinet to minimize handling times. View Cutsheet 210485

W x D x H: 21.7 x 21.3 x 31.9 in.

Weight: 573.2 lbs.

Cabinet, Storage

AE #: CAST-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Global Industrial	T9F237635GY		Floor	OF/OI	Project

Steel storage cabinet with recessed locking handle, gray. Assembles with (4) screws. Four shelves with capacity up to 185 lbs. Shelves adjust in 1.25" View Cutsheet 209472

increments. 3-point locking system. Comes with (2) keys.

W x D x H: 36 x 18 x 72 in.

Cart, Soiled Linen

AE #: CASL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	460800BLUE		Floor	OF/OI	Project

Cube truck, 8 cubic foot 300 lbs. capacity, color blue. No lid required. View Cutsheet 210498

W x D x H: 38 x 26 x 28.1 in.

Weight: 36 lbs.

Room: Radioactive Waste **Department:** Materials Management / Dock

Room #: C005

Room Notes: Room managed by Radiation Safety (Bryan Lemieux)

Cart, Therapy

AE #: CATH-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG409500BLA		Floor	OF/OI	Project

Enclosed cart with 2 shelves and 300 lbs. maximum load capacity. Color black. Includes (4) swivel casters. View Cutsheet 209471

W x D x H: 40.6 x 20.8 x 37.8 in.

Cart, Utility

AE #: CAUT-46

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1066BE		Floor	OF/OI	Project

Tough structural foam won't rust, chip or dent. Two 2-5/8" deep trays are 18 7/8" apart. Non-marking 5" casters: 2 swivel, 2 rigid View Cutsheet 159705

W x D x H: 26 x 46 x 33 in.

Chamber, Ion

AE #: CHIO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	9DP	48-3742	Cabinet	OF/OI	Project

Pressurized ion chamber. Range: background to 50 mSv/h (5 R/hr.). Shows exposure rate and either integrated exposure or peak exposure rate. View Cutsheet 210230

Rechargeable batteries; Audio and visual alarms. Data logging. USB connectivity. Free firmware updates through website.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Check Source, 10 uCi	01-5231	1	1

Check Source

AE #: CHSO-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	01-5196		Shelf	OF/OI	Project

Check source 1.0 uCi Cesium View Cutsheet 209475

W x D x H: 1 x 1 x 0.13 in.

Room: Radioactive Waste **Department:** Materials Management / Dock

Room #: C005

Room Notes: Room managed by Radiation Safety (Bryan Lemieux)

Check Source — AE #: CHSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Spectrum Techniques	Sr-90		Cabinet	OF/OI	Project

Disk source for Sr-90 designed for use as reference source. Size 0.125 x 1.0". View Cutsheet 209461

W x D x H: N/A x 0.13 x 1 in.

Detector, Gamma — AE #: DEGA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	44-172	47-3543	Cabinet	OF/OI	Project

Beta and low energy gamma detector. View Cutsheet 209462

W x D x H: 2 x 2 x 7 in.

Weight: 1 lbs.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Sani Wipe — AE #: DISW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Professional Disposables International	P010901		Wall	OF/CI	Supply Agreement

Sani-Bracket 3-in-1; for use with Sani-Cloth canisters View Cutsheet 146438

For purple and orange top wipes

W x D x H: 6 x 6 x 8.25 in.

Room: Radioactive Waste **Department:** Materials Management / Dock

Room #: C005

Room Notes: Room managed by Radiation Safety (Bryan Lemieux)

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Freezer, Chest

AE #: FRCH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Summit Appliance Div / Felix Storch	SCFM82		Floor	OF/VI	Project

7 cu ft manual defrost chest freezer. Commercially approved for use in foodservice establishments. Static cooling system. Seamless interior liner for simple clean up. Storage basket. Stainless steel corner protectors. White exterior. 100% cfc free. View Cutsheet 162308

Due to room size, Kimyli approved this model.

W x D x H: 37 x 23.5 x 33 in.
Electrical: 115V 60Hz 5A **Weight:** 100 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Ladder, Step

AE #: LADS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	6DHF0		Floor	OF/OI	Project

Folding Step: 2 Steps, 18 3/4 in Top Step Ht, 18 1/2 in Bottom Wd, 330 lb Load Capacity View Cutsheet 206472

Approved by Kimyli Lemieux via email 11/30/2023

W x D x H: 18.5 x 21 x 30 in.

Room: Radioactive Waste **Department:** Materials Management / Dock

Room #: C005

Room Notes: Room managed by Radiation Safety (Bryan Lemieux)

Lockbox

AE #: LOCK-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	18556		Wall	OF/CI	Project

Locking wall box with dial combination lock and pre-drilled mounting holes. View Cutsheet 210238

For holding check sources

W x D x H: 11 x 2.88 x 3.25 in.

Meter, Survey

AE #: MESU-26

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ludlum Measurements, Inc.	26-3	48-4232	Countertop	OF/OI	Project

High-range frisker features standard 15.51 cm2 GM pancake detector, loud audible click output, and large auto-ranging LCD display with LCD backlighting. Water resistant housing. Used to frisk people and objects. Three modes of operation available: Rate, Max, and Count. View Cutsheet 209460

W x D x H: 2.7 x 10.7 x 1.8 in.

Weight: 1 lbs.

Elect Notes: Uses (2) standard AA batteries.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Dose energy compensation filter w/tether	4519-041-02	1	2
Sample Holder for M-26	47-3948	1	2

Probe, Pancake

AE #: PRPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	44-9DOSE	47-3789	Cabinet	OF/OI	Project

For monitoring alpha, beta, and gamma radiation on personnel, objects, and surfaces. Model includes optional ambient dose filter. View Cutsheet 209463

W x D x H: 2.7 x 10.7 x 1.8 in.

Weight: 1 lbs.

Room: Radioactive Waste **Department:** Materials Management / Dock

Room #: C005

Room Notes: Room managed by Radiation Safety (Bryan Lemieux)

Ratemeter / Scaler, Digital

AE #: RASD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	2241-3i	48-3358	Cabinet	OF/OI	Project

General purpose digital ratemeter with built-in scaler. Auto ranging. Internal GM detector 10R/hr. View Cutsheet 209487

W x D x H: 3.5 x 8.5 x 6.5 in.

Weight: 3.5 lbs.

Elect Notes: Powered by (2) "D" cell batteries.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Probe Clips		1	1

Shelving

AE #: SHEL-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
13	Grainger	39K764		Floor	OF/OI	Project

Medium-duty standalone stationary steel shelving unit with 6 solid shelves. Color gray. Load capacity per shelf 800 lbs. / whole unit capacity 4,800 lbs. View Cutsheet 209469

Shelves adjustable in 1.5" increments.

W x D x H: 36 x 18 x 84 in.

Shield, Radiation

AE #: SHRA-54

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Atlantic Nuclear	16A-054		Floor	OF/OI	Project

For Radiation Therapy personnel. Fixed height shield has a 1" thick lead sheet which will reduce the dose from a cesium source by over 90%. Shield is mounted on a base with (4) 5" diameter swivel locking ball bearing casters. View Cutsheet 209468

W x D x H: 36 x 18 x 54 in.

Weight: 500 lbs.

Table, Work

AE #: TAWO-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	MWTS2436FS		Floor	OF/VI	Project

Space saver mobile stainless steel work table with solid bottom shelf, 600 lb load rating. View Cutsheet 207729

W x D x H: 36 x 24 x 34 in.

Weight: 64 lbs.

Room: Radioactive Waste **Department:** Materials Management / Dock

Room #: C005

Room Notes: Room managed by Radiation Safety (Bryan Lemieux)

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle

AE #: WARE-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Uline	H-3689BLU		Floor	OF/OI	Project

Round plastic 55-gallon blue waste receptacle with built-in handles. Nestable when empty. View Cutsheet 209473

For decayed (non-radioactive) waste

W x D x H: 26 x 26 x 33 in.

Weight: 18 lbs.

Room: Private Work

Department: Rad-Onc Clinic

Room #: A009C, A009E

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Conf / Team Work

Department: Rad-Onc Clinic

Room #: A009D

Waste Receptacle, Recycling Combination

AE #: WARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Max-R	P-RO-STT10D		Floor	OF/OI	Project

10-gallon Top Load Waste & Recycling Bins.

View Cutsheet 209397

W x D x H: 28 x 15 x 30 in.

Room: On-Stage Team Work Area **Department:** Rad-Onc Clinic

Room #: A009F

Room Notes: Space for 6 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room (GYN) / MR Prep

Department: Rad-Onc Clinic

Room #: A009G

Room Notes: Same MEQ as Bari-Gyn

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam Room (GYN) / MR Prep

Department: Rad-Onc Clinic

Room #: A009G

Room Notes: Same MEQ as Bari-Gyn

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Exam Room (GYN) / MR Prep **Department:** Rad-Onc Clinic

Room #: A009G

Room Notes: Same MEQ as Bari-Gyn

Light, Exam/ Treatment

AE #: LIET-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	GS300	44400	Floor	OF/OI	Project

LED exam light on mobile stand; features 20,000 lux and touchless controls. Ideal for primary care facilities, emergency rooms, outpatient facilities and dermatology; 5-year limited warranty View Cutsheet 122496

W x D x H: 20.9 x 20.9 x 58.7 in.
Electrical: 120V 60Hz 0.35A **Weight:** 12.75 lbs.

Light, Speculum

AE #: LISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	80010		Countertop	OF/OI	Project

Complete kleenspec cordless illumination system with charging station with us style ac plug. Associated disposables: kleenspec disposable vaginal specula. View Cutsheet 161569

W x D x H: 3.1 x 9.3 x 6.4 in.
Electrical: 120V 60Hz 0.2A **Weight:** 1.1 lbs.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: Exam Room (GYN) / MR Prep **Department:** Rad-Onc Clinic

Room #: A009G

Room Notes: Same MEQ as Bari-Gyn

Table, Exam, Power

AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.***

View Cutsheet 209180

Wide table top preferred by department.

W x D x H: 32 x 76 x 37 in.

Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room - GYN

Department: Rad-Onc Clinic

Room #: A009J, A009K, A009L

Room Notes: Same MEQ as Bari-Gyn

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam Room - GYN **Department:** Rad-Onc Clinic

Room #: A009J, A009K, A009L

Room Notes: Same MEQ as Bari-Gyn

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Exam Room - GYN **Department:** Rad-Onc Clinic

Room #: A009J, A009K, A009L

Room Notes: Same MEQ as Bari-Gyn

Light, Exam/ Treatment

AE #: LIET-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	GS300	44400	Floor	OF/OI	Project

LED exam light on mobile stand; features 20,000 lux and touchless controls. Ideal for primary care facilities, emergency rooms, outpatient facilities and dermatology; 5-year limited warranty View Cutsheet 122496

W x D x H: 20.9 x 20.9 x 58.7 in.
Electrical: 120V 60Hz 0.35A **Weight:** 12.75 lbs.

Light, Speculum

AE #: LISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	80010		Countertop	OF/OI	Project

Complete kleenspec cordless illumination system with charging station with us style ac plug. Associated disposables: kleenspec disposable vaginal specula. View Cutsheet 161569

W x D x H: 3.1 x 9.3 x 6.4 in.
Electrical: 120V 60Hz 0.2A **Weight:** 1.1 lbs.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: Exam Room - GYN **Department:** Rad-Onc Clinic

Room #: A009J, A009K, A009L

Room Notes: Same MEQ as Bari-Gyn

Table, Exam, Power

AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.***

View Cutsheet 209180

Wide table top preferred by department.

W x D x H: 32 x 76 x 37 in.

Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Greeter

Department: Rad-Onc Clinic

Room #: B000W1

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Consult

Department: Rad-Onc Clinic

Room #: B001A, B001C

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Toilet (Patient)

Department: Rad-Onc Clinic

Room #: B001B, B001Z

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Rad-Onc Clinic

Room #: B001B, B001Z

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department:** Rad-Onc Clinic

Room #: B001D, B001E, B001F, B001G, B001H, B001J, B001T, B001V, B001X

Room Notes: General Exam (2), Status Check (5)

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam Room **Department:** Rad-Onc Clinic

Room #: B001D, B001E, B001F, B001G, B001H, B001J, B001T, B001V, B001X

Room Notes: General Exam (2), Status Check (5)

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Light, Speculum

AE #: LISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	80010		Countertop	OF/OI	Project

Complete kleenspec cordless illumination system with charging station with us style ac plug. Associated disposables: kleenspec disposable vaginal specula. View Cutsheet 161569

W x D x H: 3.1 x 9.3 x 6.4 in.

Electrical: 120V 60Hz 0.2A **Weight:** 1.1 lbs.

Room: Exam Room **Department:** Rad-Onc Clinic

Room #: B001D, B001E, B001F, B001G, B001H, B001J, B001T, B001V, B001X

Room Notes: General Exam (2), Status Check (5)

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Height / Weight **Department:** Rad-Onc Clinic

Room #: B001E1, B001Y1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Room: Alcove, Height / Weight

Department: Rad-Onc Clinic

Room #: B001E1, B001Y1

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16"

View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: On-Stage Team Work Area **Department:** Rad-Onc Clinic

Room #: B001K

Room Notes: Space for 6 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Physician Work **Department:** Rad-Onc Clinic

Room #: B001L

Room Notes: Space for 4 - 8 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office, Shared

Department: Rad-Onc Clinic

Room #: B001M, B001N

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Office, Private

Department: Rad-Onc Clinic

Room #: B001P

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Radio-Pharm (RPT) **Department:** Rad-Onc Clinic

Room #: B001Q

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Chair, Blood Draw Bariatric — AE #: CBDB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Market Lab Inc.	ML40133		Floor	OF/OI	Project

Xl padded blood drawing chair; 35" seat width w. 2" padding; 700 lb. Weight capacity; adjustable height armrests; flip-up armrest. View Cutsheet 163844

W x D x H: 46 x 29 x 36 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Radio-Pharm (RPT) **Department:** Rad-Onc Clinic

Room #: B001Q

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Radio-Pharm (RPT) **Department:** Rad-Onc Clinic

Room #: B001Q

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Hot-Patient) **Department:** Rad-Onc Clinic

Room #: B001Q1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Hot-Patient) **Department:** Rad-Onc Clinic

Room #: B001Q1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Mobile Equipment **Department:** Rad-Onc Clinic

Room #: B001Q2

Lifter, Patient

AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor. View Cutsheet 208837

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Room: Radio-Pharm Prep **Department:** Rad-Onc Clinic

Room #: B001R

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Radio-Pharm Prep **Department:** Rad-Onc Clinic

Room #: B001R

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, View Cutsheet 162444

stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended.

W x D x H: 28 x 76 x 37 in.

Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Room: Radio-Pharm Prep

Department: Rad-Onc Clinic

Room #: B001R

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supply / Linen **Department:** Rad-Onc Clinic

Room #: B001S

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system — No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Scope — AE #: CASC-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Innerspace Corp / Stanley	SEB1927SGLW		Wall	OF/CI	Project

Wall Mounted Scope Cabinet. Hinged Door. AireCore with Brushed Aluminum. View Cutsheet 208684

W x D x H: 26.8 x 19.3 x 48 in.

Electrical: 120V 60Hz

Cabinet, Warming — AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.

Network: Wired

Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Cart, Cylinder, Medical Gas — AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Room: Clean Supply / Linen **Department:** Rad-Onc Clinic

Room #: B001S

Cart, Linen — AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Scope — AE #: CASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	CLEANASCOPE CART	103631	Floor	OF/OI	Project

10-tray cart transport cart system with 10 trays for endoscopes; minimizes direct handling and contact with airborne contaminants; uses green (clean) and red (contaminated) covers View Cutsheet 159789

W x D x H: 20.5 x 22.4 x 56.5 in.

Cart, Supply, 36x24x67 — AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility — AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Room: Clean Supply / Linen

Department: Rad-Onc Clinic

Room #: B001S

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Room: Mobile Equipment **Department:** Rad-Onc Clinic

Room #: B001S1

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration.

View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	5

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor.

View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff.

View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Room: Mobile Equipment **Department:** Rad-Onc Clinic

Room #: B001S1

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Copy/Work

Department: Rad-Onc Clinic

Room #: B001S2

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room - ENT **Department: Rad-Onc Clinic**

Room #: B001U, B001W, B001Y

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/OI	Project

No Cutsheet 10789

Cabinet, Exam/ Treatment, E.N.T. AE #: CAET-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	TC100C		Floor	OF/VI	Project

Sit-down height ENT treatment cabinet. Countertop height 33.5"H with 15"H backwall w/stainless steel shelf, (2) countertop recessed cordless instrument handle charger wells, right hand hose location, (2) application bottles, backwall mouonted glass bead mirror warmer, left side endoscope cold storage tubes (confirm size and mounting), and 4-port LED light source. View Cutsheet 208941

Review cut sheet and confirm options.Per CME quote 406078-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 35.5 x 21 x 48.5 in.
Electrical: 115V 60Hz 7.5A

Cabinet, Storage AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Room: Exam Room - ENT **Department:** Rad-Onc Clinic

Room #: B001U, B001W, B001Y

Cart, Video Procedure

AE #: CAVP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	WM-NP3/OEV-262H		Floor	OF/VI	Project

Mobile workstation (K10035366) with 27" high definition LCD monitor (OEV-262H) View Cutsheet 171517

To include the Visera Elite II OTV-S200 all-in-one video processor / light source and ImageStream nCare device and connectivity / licenses. Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

W x D x H: 26.2 x 26.6 x 81.6 in.
Network: Wired
Electrical: 120V 60Hz 15A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Ent Scope Hanger	MAJ-2145	2	2
Lcd Monitor Arm	MAJ-2216	1	1
Mountng Adaptor For Flat Panel	FLP-0002-17C	1	1
Nurses Control Arm	MAJ-2167	1	1
Sliding Keyboard	MAJ-2146	1	1
Videoscope Cable Evis Exera Ii	MAJ-1430	1	1
Visera Elite Keyboard	MAJ-1921	1	1

Chair, Procedure, Bariatric

AE #: CHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	830		Floor	OF/VI	Project

Power procedure chair. ADA compliant. Standard, swivel, or mobile base options. Foot and hand controls. Programable positioning. Oval articulating headrest. 725 lb. weight capacity. If power outlet is planned in floor, 3 ft. power cord (accessory) is needed. View Cutsheet 170372

Per CME quote 406079-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 25 x 73 x 39 in.
Electrical: 120V 60Hz 7A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Accessory rails		1	1
Exam light		1	1
Power Cord, 3 ft.	130-1905	1	1
Rectangular head rest		1	1

Room: Exam Room - ENT

Department: Rad-Onc Clinic

Room #: B001U, B001W, B001Y

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room - ENT **Department:** Rad-Onc Clinic

Room #: B001U, B001W, B001Y

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Cart	OF/OI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Ophthalmoscope

AE #: OPHT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	11720-L		Cart	OF/OI	Project

3.5v coaxial ophthalmoscope. Long-lasting LED illumination. Works with all Welch Allyn 3.5v power sources. View Cutsheet 205877

W x D x H: 1.77 x 2.95 x 3.15 in.

Otoscope

AE #: OTOS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Hillrom Company, Inc.	250-2		Cart	OF/OI	Project

Diagnostic 3.5V LED otoscope. Wide-angle viewing lens. Works with all Welch Allyn 3.5V power sources. Includes a port for pneumatic otoscopy. View Cutsheet 208578

Room: Exam Room - ENT **Department:** Rad-Onc Clinic

Room #: B001U, B001W, B001Y

Rechargeable Handle

AE #: REHA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Hillrom Company, Inc.	719-3		Cart	OF/OI	Project

Lithium Ion Plus Power handle with integrated USB-C charger. Also compatible with Welch Allyn Universal Desk Charger 719-DSK and 71140 chargers. View Cutsheet 206571

W x D x H: 1.18 x 1.18 x 5.51 in.

Weight: 0.31 lbs.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Hold **Department:** Rad-Onc Clinic

Room #: B007E

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Scope

AE #: CASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	CLEANASCOPE CART	103631	Floor	OF/OI	Project

10-tray cart transport cart system with 10 trays for endoscopes; minimizes direct handling and contact with airborne contaminants; uses green (clean) and red (contaminated) covers View Cutsheet 159789

W x D x H: 20.5 x 22.4 x 56.5 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.*** View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Room: Soiled Hold

Department: Rad-Onc Clinic

Room #: B007E

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Soiled Hold

Department: Rad-Onc Clinic

Room #: B007E

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Linac Control-Planning

Department: Rad-Onc Treatment

Room #: A0003.1

Room Notes: Gamma Knife Planning. (2) GK PCs, (1) PACs, (1) workstation

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight **Department:** Rad-Onc Treatment

Room #: A000N2

Room Notes: WC scale on clinic end. This will be smaller alcove with Stand-on scale

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug. View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz

Weight: 61 lbs.

Room: Alcove, Height / Weight **Department:** Rad-Onc Treatment

Room #: A000N2

Room Notes: WC scale on clinic end. This will be smaller alcove with Stand-on scale

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Treatment Planning Room **Department:** Rad-Onc Treatment

Room #: A000S1

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Alcove, Linac Positioning Blocks & Linen **Department:** Rad-Onc Treatment

Room #: A000S2

Cabinet, Warming — AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Cart, Utility — AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Alcove, Linac Positioning Blocks & Linen **Department:** Rad-Onc Treatment

Room #: A000S2

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Alcove, Linac Positioning Blocks & Linen **Department:** Rad-Onc Treatment

Room #: A000S2

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Ultrasound System

AE #: ULSY-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	B K Medical	BK3000		Floor	OF/VI	Project

High resolution ultrasound system dedicated to urology. Advanced imaging modes include elastography and contrast imaging. Two hours of plug freee imaging. View Cutsheet 170167

W x D x H: 26.4 x 33.5 x 64.6 in.
Network: Networked
Electrical: 115V 60Hz

Wheelchair, MRI

AE #: WHMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Staxi Corporation	MRI		Floor	OF/VI	Project

MRI Wheelchair, 600lb weight capacity. Non removable foot rests. Five inch casters. View Cutsheet 204144

W x D x H: 31 x 33 x 41 in.

Room: Prep / Recovery (Head Frame Room) **Department:** Rad-Onc Treatment

Room #: A000S3, A000S9

Room Notes: Room used for putting on head frames. Will only accommodate one patient at a time.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. hand sanitizers requested outside doors to room

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Prep / Recovery (Head Frame Room) **Department: Rad-Onc Treatment**

Room #: A000S3, A000S9

Room Notes: Room used for putting on head frames. Will only accommodate one patient at a time.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz
Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component — AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Prep / Recovery (Head Frame Room) **Department:** Rad-Onc Treatment

Room #: A000S3, A000S9

Room Notes: Room used for putting on head frames. Will only accommodate one patient at a time.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.
Weight: 25 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Crash Cart & Stretcher

Department: Rad-Onc Treatment

Room #: A000S5

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Alcove, Crash Cart & Stretcher **Department:** Rad-Onc Treatment

Room #: A000S5

Stretcher, Non-Ferrous, Bariatric

AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety. View Cutsheet 210322

MR conditional to 3T. Optional IV pole available.

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Toilet (Staff)

Department: Rad-Onc Treatment

Room #: A000S6, A008G

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: InPt Holding Bay **Department: Rad-Onc Treatment**

Room #: A000S7

Room Notes: 3 Pt Bays

Allowance, Installation

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring			Monitor	OF/VI	Project

No Cutsheet 92570

To cover project management and installation services; covers all floors except level 2.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208701

Room: InPt Holding Bay **Department:** Rad-Onc Treatment

Room #: A000S7

Room Notes: 3 Pt Bays

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Physiological — AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Philips Medical Systems - Monitoring	MX450		Stand	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle.

View Cutsheet 146867

Assumes monitors will use patients' X3 from inpatient units.

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Patient Lift, Ceiling Mount — AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Lift to run horizontally across all 3 bays

Supplemental Info

Electrical: 115V 60Hz 2.5A

Room: InPt Holding Bay **Department:** Rad-Onc Treatment

Room #: A000S7

Room Notes: 3 Pt Bays

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: InPt Holding Bay **Department:** Rad-Onc Treatment

Room #: A000S7

Room Notes: 3 Pt Bays

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stretcher, Non-Ferrous, Bariatric

AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety. View Cutsheet 210322

MR conditional to 3T. Optional IV pole available.

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Thermometer, Electronic, Oral

AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Room: InPt Holding Bay **Department:** Rad-Onc Treatment

Room #: A000S7

Room Notes: 3 Pt Bays

Waste Container, Biohazard

AE #: WACB-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883564		Floor	OF/OI	Project

Slim jim step-on container with 8-gallon capacity. Quiet controlled lid closure. Color: Red

View Cutsheet 151080

W x D x H: 16.7 x 10.6 x 21.1 in.

Weight: 6 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Nurse Work Area **Department: Rad-Onc Treatment**

Room #: A000S8

Room Notes: Across from InPt Holding Bay

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Cabinet, Warming — AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.
HVAC Notes: 1604 BTU/hr

Drug Dispensing Unit — AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

Per Katie Plahn email 9/14/2023

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Room: Nurse Work Area **Department:** Rad-Onc Treatment

Room #: A000S8

Room Notes: Across from InPt Holding Bay

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Pyxis, Undercounter — AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit. View Cutsheet 170325

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Container — AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Dressing Room (ADA)

Department: Rad-Onc Treatment

Room #: A000W1

Room Notes: Located in CT/MR. Hamper & Linen cabinet in ADA Subwait

Room: Sub-Wait (ADA)

Department: Rad-Onc Treatment

Room #: A000W2

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Toilet (Patient)

Department: Rad-Onc Treatment

Room #: A000W3, A006E, A006E1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Rad-Onc Treatment

Room #: A000W3, A006E, A006E1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Dressing Room

Department: Rad-Onc Treatment

Room #: A000W5

Room Notes: Located in CT/MR. Assumes no medical equipment

Room: Sub-Wait

Department: Rad-Onc Treatment

Room #: A000W6

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Linac Vault 1 - Halcyon

Department: Rad-Onc Treatment

Room #: A001A

Allowance, De-Installation/Installation

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems				OF/VI	Project

Allowance for relocation of existing radiation therapy system

No Cutsheet 210951

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/VI	Project

No Cutsheet 10789

For Linac positioning system - VisionRT, AlignRT

Barometer

AE #: BARO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	CB-800		Handheld	OF/OI	Project

The Model DB-800 is a portable digital barometer possessing a combination of handheld calculator size, graphic LCD display, high accuracy, and wide choice of units, making it ideal as a portable pressure reference.

View Cutsheet 208491

W x D x H: 3.5 x 1.4 x 7.5 in.

Weight: 1.1 lbs.

Elect Notes: Battery operated

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Room: Linac Vault 1 - Halcyon

Department: Rad-Onc Treatment

Room #: A001A

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Linac Vault 1 - Halcyon

Department: Rad-Onc Treatment

Room #: A001A

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Linac Vault 1 - Halcyon **Department:** Rad-Onc Treatment

Room #: A001A

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Monitor, Radiation

AE #: MORA-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	7008 RT		Wall	OF/CI/VI	Project

The Model 7008 RT is a wall-mounted radiation monitor designed to meet the specific needs of radiation therapy. It is designed to operate continuously View Cutsheet 209586 from an AC power line. In the event of power failure, the built-in, continuously trickle charged NiMH battery automatically switches in to begin supplying power immediately,

Include remote alarm unit - see accessories, plan for 75' cable to connect the two monitors If unable to obtain this model, replace with Ludlum 375/2 model**

W x D x H: 4.5 x 2.7 x 7.6 in.
Electrical: 208V 60Hz **Weight:** 1.5 lbs.
Elect Notes: AC power with back up battery. Power: 95–230 VAC, 50/60 Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Remote Alarm Unit	7008 R	1	1

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Room: Linac Vault 1 - Halcyon

Department: Rad-Onc Treatment

Room #: A001A

Radiation Therapy System

AE #: RTSY-01E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	Halcyon		Floor/Ceiling	EX/VI/CI	Existing

Halcyon achieves high quality care through 100% image-guided IMRT and RapidArc radiotherapy treatments. Patient imaging dose can be optimized by using the automatic mAs detection feature for kV CBCT image acquisition. With Halcyon, there is the potential to achieve less dosage to organs at risk and more dose conformity to the target with the MLC stacked-and staggered technology. The dual-layered MLC makes it possible to deliver IMRT and RapidArc treatments faster and more efficiently than before.

View Cutsheet 209957

Confirmed existing to relocate. Relocation allowance noted separately.

Supplemental Info

Network: Wired
Electrical: 480V 60Hz 3-Phase
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Linac Vault 1 - Halcyon

Department: Rad-Onc Treatment

Room #: A001A

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Linac Control

Department: Rad-Onc Treatment

Room #: A001, A002, A004, A005

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled

View Cutsheet 100085

resin will not rust and resists chips and dents

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Linac Vault 2 - Truebeam

Department: Rad-Onc Treatment

Room #: A002A

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/VI	Project

No Cutsheet 10789

For Linac positioning system - VisionRT, AlignRT

Barometer

AE #: BARO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	CB-800		Handheld	OF/OI	Project

The Model DB-800 is a portable digital barometer possessing a combination of handheld calculator size, graphic LCD display, high accuracy, and wide choice of units, making it ideal as a portable pressure reference.

View Cutsheet 208491

W x D x H: 3.5 x 1.4 x 7.5 in.

Weight: 1.1 lbs.

Elect Notes: Battery operated

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Room: Linac Vault 2 - Truebeam

Department: Rad-Onc Treatment

Room #: A002A

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Linac Vault 2 - Truebeam

Department: Rad-Onc Treatment

Room #: A002A

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Linac Vault 2 - Truebeam

Department: Rad-Onc Treatment

Room #: A002A

Monitor, Radiation

AE #: MORA-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	7008 RT		Wall	OF/CI/VI	Project

The Model 7008 RT is a wall-mounted radiation monitor designed to meet the specific needs of radiation therapy. It is designed to operate continuously from an AC power line. In the event of power failure, the built-in, continuously trickle charged NiMH battery automatically switches in to begin supplying power immediately,

View Cutsheet 209586

Include remote alarm unit - see accessories, plan for 75' cable to connect the two monitors If unable to obtain this model, replace with Ludlum 375/2 model**

W x D x H: 4.5 x 2.7 x 7.6 in.
Electrical: 208V 60Hz **Weight:** 1.5 lbs.
Elect Notes: AC power with back up battery. Power: 95–230 VAC, 50/60 Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Remote Alarm Unit	7008 R	1	1

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Radiation Therapy, Accelerator

AE #: RATA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	Truebeam	120 MLC	Floor/Ceiling	OF/CI/VI	Project

View Cutsheet 207157

Supplemental Info

Network: Wired
Electrical: 480V 60Hz 80A
Plumb Notes: Requires facility chilled water. Refer to manufacturer's site planning information.

Room: Linac Vault 2 - Truebeam

Department: Rad-Onc Treatment

Room #: A002A

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Linac Control (Gamma Knife) **Department:** Rad-Onc Treatment

Room #: A003

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled View Cutsheet 100085

resin will not rust and resists chips and dents

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Linac Vault 3 - Gamma Knife **Department:** Rad-Onc Treatment

Room #: A003A

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/VI	Project

No Cutsheet 10789

For Linac positioning system - VisionRT, AlignRT

Barometer

AE #: BARO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	CB-800		Handheld	OF/OI	Project

The Model DB-800 is a portable digital barometer possessing a combination of handheld calculator size, graphic LCD display, high accuracy, and wide choice of units, making it ideal as a portable pressure reference.

View Cutsheet 208491

W x D x H: 3.5 x 1.4 x 7.5 in.

Weight: 1.1 lbs.

Elect Notes: Battery operated

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Room: Linac Vault 3 - Gamma Knife **Department:** Rad-Onc Treatment

Room #: A003A

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Linac Vault 3 - Gamma Knife

Department: Rad-Onc Treatment

Room #: A003A

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Linac Vault 3 - Gamma Knife **Department:** Rad-Onc Treatment

Room #: A003A

Monitor, Radiation

AE #: MORA-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	7008 RT		Wall	OF/CI/VI	Project

The Model 7008 RT is a wall-mounted radiation monitor designed to meet the specific needs of radiation therapy. It is designed to operate continuously from an AC power line. In the event of power failure, the built-in, continuously trickle charged NiMH battery automatically switches in to begin supplying power immediately,

View Cutsheet 209586

Include remote alarm unit - see accessories, plan for 75' cable to connect the two monitors If unable to obtain this model, replace with Ludlum 375/2 model**

W x D x H: 4.5 x 2.7 x 7.6 in.
Electrical: 208V 60Hz **Weight:** 1.5 lbs.
Elect Notes: AC power with back up battery. Power: 95–230 VAC, 50/60 Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Remote Alarm Unit	7008 R	1	1

Monitor, Radiation

AE #: RAMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	Remote Monitoring System		Wall	OF/CI	Project

Specifications to be determined.

No Cutsheet 212998

Per Elekta, this is OF/OI (or CI). Need more information from Bryan Lemieux.

Network: Wired
Electrical: 120V 60Hz
Elect Notes: Emergency power required

Room: Linac Vault 3 - Gamma Knife **Department:** Rad-Onc Treatment

Room #: A003A

Monitor, Radiation/ Contamination

AE #: MORA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fluke Biomedical / Radiation Management Services	PRIME ALERT 10	05-433	Wall	OF/CI/VI	Project

Teletherapy radiation monitor w/ battery pack; monitor emits alarm when radiation level exceeds preset value selected by front panel switch; pair of bright red lamps on monitor's face flash on and off until safe conditions are restored; activated by scatter radiation; flashing green operation indicator light continuously monitors background radiation; self-stick wall mount bracket and ac adaptor/power converter included. Price includes remote alarm and back up battery pack.

View Cutsheet 11887

Price includes Prime Alert Remote and Backup Battery pack

W x D x H: 3.5 x 1.5 x 6 in.
Electrical: 120V 60Hz 1A **Weight:** 2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Primalarm Remote Alarm (3.5"W.1.5"D.6"H)	05-434	1	1
Primapack Ii Backup Battery Pack (4.5"W.2.8"D.6"H)	05-441	1	1

Oven, Drying

AE #: OVDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Qfix	Rapid Heat RT-2075-110		Countertop	OF/OI	Project

Dry air heating solution for thermoplastic masks and custom bolus. Two non-stick sliding racks and 7.5cm digital display

View Cutsheet 207393

Model and mounting location confirmed with Megan Gilmore 10/22/24

W x D x H: 32 x 30 x 19.1 in.
Electrical: 110V 60Hz **Weight:** 12 lbs.

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Room: Linac Vault 3 - Gamma Knife **Department:** Rad-Onc Treatment

Room #: A003A

Radiation Therapy System, Gamma Knife

AE #: RTGK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Elekta, Inc.	Esprit		Floor	OF/CI/VI	Project

Leksell Gamma Knife. Guaranteed accuracy1 of 0.3 mm. Dose delivered to the healthy brain tissue is 2–4x lower than other technologies. 2–21x lower extracranial dose than other technologies

View Cutsheet 210200

Supplemental Info

Network: Wired
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Linac Vault 3 - Gamma Knife

Department: Rad-Onc Treatment

Room #: A003A

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Linac Vault 4 - Edge **Department:** Rad-Onc Treatment

Room #: A004A

Allowance, De-Installation/Installation

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems				OF/VI	Project

Allowance for relocation of existing radiation therapy system

No Cutsheet 210951

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/OI	Project

No Cutsheet 10789

For all Physics devices needed throughout Linac Vaults, combined total

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/VI	Project

No Cutsheet 10789

For Linac positioning system - VisionRT, AlignRT

Barometer

AE #: BARO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	CB-800		Handheld	OF/OI	Project

The Model DB-800 is a portable digital barometer possessing a combination of handheld calculator size, graphic LCD display, high accuracy, and wide choice of units, making it ideal as a portable pressure reference.

View Cutsheet 208491

W x D x H: 3.5 x 1.4 x 7.5 in.

Weight: 1.1 lbs.

Elect Notes: Battery operated

Room: Linac Vault 4 - Edge

Department: Rad-Onc Treatment

Room #: A004A

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Linac Vault 4 - Edge

Department: Rad-Onc Treatment

Room #: A004A

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Room: Linac Vault 4 - Edge **Department:** Rad-Onc Treatment

Room #: A004A

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Monitor, Radiation

AE #: MORA-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	7008 RT		Wall	OF/CI/VI	Project

The Model 7008 RT is a wall-mounted radiation monitor designed to meet the specific needs of radiation therapy. It is designed to operate continuously View Cutsheet 209586

from an AC power line. In the event of power failure, the built-in, continuously trickle charged NiMH battery automatically switches in to begin supplying power immediately,

Include remote alarm unit - see accessories, plan for 75' cable to connect the two monitors If unable to obtain this model, replace with Ludlum 375/2 model**

W x D x H: 4.5 x 2.7 x 7.6 in.
Electrical: 208V 60Hz **Weight:** 1.5 lbs.
Elect Notes: AC power with back up battery. Power: 95–230 VAC, 50/60 Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Remote Alarm Unit	7008 R	1	1

Room: Linac Vault 4 - Edge

Department: Rad-Onc Treatment

Room #: A004A

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Radiation Therapy System, Radiosurgery

AE #: RTSR-01E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	Edge		Ceiling/Floor/Wall	EX/VI/CI	Existing

Dedicated Full-Body Radiosurgery Platform. Supports HyperArc® high-definition radiotherapy and RapidArc® radiotherapy technology.

View Cutsheet 209959

Confirmed existing to relocate. Relocation allowance noted separately.

Supplemental Info

Network: Wired
Electrical: 480V 60Hz 3-Phase
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Linac Vault 4 - Edge

Department: Rad-Onc Treatment

Room #: A004A

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Linac Vault 5 - Truebeam

Department: Rad-Onc Treatment

Room #: A005A

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/VI	Project

No Cutsheet 10789

For Linac positioning system - VisionRT, AlignRT.

Barometer

AE #: BARO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	CB-800		Handheld	OF/OI	Project

The Model DB-800 is a portable digital barometer possessing a combination of handheld calculator size, graphic LCD display, high accuracy, and wide choice of units, making it ideal as a portable pressure reference.

View Cutsheet 208491

W x D x H: 3.5 x 1.4 x 7.5 in.

Weight: 1.1 lbs.

Elect Notes: Battery operated

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Room: Linac Vault 5 - Truebeam

Department: Rad-Onc Treatment

Room #: A005A

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Linac Vault 5 - Truebeam

Department: Rad-Onc Treatment

Room #: A005A

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Linac Vault 5 - Truebeam **Department:** Rad-Onc Treatment

Room #: A005A

Monitor, Radiation — AE #: MORA-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	7008 RT		Wall	OF/CI/VI	Project

The Model 7008 RT is a wall-mounted radiation monitor designed to meet the specific needs of radiation therapy. It is designed to operate continuously from an AC power line. In the event of power failure, the built-in, continuously trickle charged NiMH battery automatically switches in to begin supplying power immediately,

View Cutsheet 209586

Include remote alarm unit - see accessories, plan for 75' cable to connect the two monitors If unable to obtain this model, replace with Ludlum 375/2 model**

W x D x H: 4.5 x 2.7 x 7.6 in.
Electrical: 208V 60Hz **Weight:** 1.5 lbs.
Elect Notes: AC power with back up battery. Power: 95–230 VAC, 50/60 Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Remote Alarm Unit	7008 R	1	1

Patient Lift, Ceiling Mount — AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Radiation Therapy, Accelerator — AE #: RATA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	Truebeam	120 MLC	Floor/Ceiling	OF/CI/VI	Project

View Cutsheet 207157

Supplemental Info

Network: Wired
Electrical: 480V 60Hz 80A
Plumb Notes: Requires facility chilled water. Refer to manufacturer's site planning information.

Room: Linac Vault 5 - Truebeam

Department: Rad-Onc Treatment

Room #: A005A

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room - Status Check, Inpt **Department:** Rad-Onc Treatment

Room #: A006A

Room Notes: No need for Pt monitoring in this room. Will bring in mobile VSM PRN

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room - Status Check, Inpt

Department: Rad-Onc Treatment

Room #: A006A

Room Notes: No need for Pt monitoring in this room. Will bring in mobile VSM PRN

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes.

View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Room: Exam Room - Status Check, Inpt **Department:** Rad-Onc Treatment

Room #: A006A

Room Notes: No need for Pt monitoring in this room. Will bring in mobile VSM PRN

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Light, Speculum — AE #: LISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	80010		Countertop	OF/OI	Project

Complete kleenspec cordless illumination system with charging station with us style ac plug. Associated disposables: kleenspec disposable vaginal specula. View Cutsheet 161569

W x D x H: 3.1 x 9.3 x 6.4 in.
Electrical: 120V 60Hz 0.2A **Weight:** 1.1 lbs.

Ophthalmoscope/ Otoscope — AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Room: Exam Room - Status Check, Inpt **Department:** Rad-Onc Treatment

Room #: A006A

Room Notes: No need for Pt monitoring in this room. Will bring in mobile VSM PRN

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Aneroid, Wall Mount

AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Exam Room - Status Check, Inpt **Department:** Rad-Onc Treatment

Room #: A006A

Room Notes: No need for Pt monitoring in this room. Will bring in mobile VSM PRN

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Stretcher, Non-Ferrous, Bariatric

AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety. View Cutsheet 210322

MR conditional to 3T. Optional IV pole available.

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Table, Mobile

AE #: TAMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Universal Medical	207166-FG		Floor	OF/OI	Project

The non-powered Kidney Cart is an ultra-lightweight mobile documentation cart with a generous-sized kidney shaped work surface. Its compact profile View Cutsheet 208554

and 3" casters allow you to move easily through care settings and tight spaces. Height adjustable; 32.5-48.5".

W x D x H: 28 x 18 x 48.5 in.

Room: Exam Room - Status Check, Inpt

Department: Rad-Onc Treatment

Room #: A006A

Room Notes: No need for Pt monitoring in this room. Will bring in mobile VSM PRN

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department:** Rad-Onc Treatment

Room #: A006B

Room Notes: Changed to general exam room per the MR Sim Zone discussion

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam Room **Department:** Rad-Onc Treatment

Room #: A006B

Room Notes: Changed to general exam room per the MR Sim Zone discussion

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Light, Speculum

AE #: LISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	80010		Countertop	OF/OI	Project

Complete kleenspec cordless illumination system with charging station with us style ac plug. Associated disposables: kleenspec disposable vaginal specula. View Cutsheet 161569

W x D x H: 3.1 x 9.3 x 6.4 in.

Electrical: 120V 60Hz 0.2A **Weight:** 1.1 lbs.

Room: Exam Room **Department:** Rad-Onc Treatment

Room #: A006B

Room Notes: Changed to general exam room per the MR Sim Zone discussion

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Hold

Department: Rad-Onc Treatment

Room #: A006C

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Room: Soiled Hold

Department: Rad-Onc Treatment

Room #: A006C

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Hold

Department: Rad-Onc Treatment

Room #: A006C

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supplies / Linen

Department: Rad-Onc Treatment

Room #: A006D

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system

No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired
Network Notes: One data outlet needed per wall
Electrical: 120V 60Hz

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available.

View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Electrical: 120V 60Hz 7.5A
Weight: 437 lbs.
HVAC Notes: 1604 BTU/hr

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position.

View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.
Weight: 6 lbs.

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures.

View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Room: Clean Supplies / Linen

Department: Rad-Onc Treatment

Room #: A006D

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Room: Office, Private

Department: Rad-Onc Treatment

Room #: A006F

Room Notes: *Megan and Dave

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Patient Prep Bay **Department:** Rad-Onc Treatment

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure

View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	6

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available.

View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.

Network: Wired

Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Patient Prep Bay **Department:** Rad-Onc Treatment

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Detector, Ferromagnetic

AE #: DEFE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	Ultra		Wall	OF/CI/VI	Project

The most advanced, efficient, and flexible ferromagnetic threat detection system—versatile enough to implement in a huge variety of places and spaces so you can keep your people, property, and sensitive information safe. Can be wall-mounted, or used with the portable, freestanding base. Width is for the floor base. Wall mounted width is 4.9"

View Cutsheet 209310

On wall from corridor to MRI Zone 3

W x D x H: 17.4 x 6.3 x 72.3 in.
Network: Wired
Electrical: 120V 60Hz 1.3A **Weight:** 46 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Patient Prep Bay **Department:** Rad-Onc Treatment

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

Per Katie Plahn email 9/14/2023

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Patient Prep Bay **Department: Rad-Onc Treatment**

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Monitor, Physiological — AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.

Network: Wired **Network Notes:** Required two data ports

Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Room: Patient Prep Bay **Department:** Rad-Onc Treatment

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available View Cutsheet 172960

Lift to run horizontally across all 3 bays Supplemental Info

Electrical: 115V 60Hz 2.5A

Room: Patient Prep Bay **Department:** Rad-Onc Treatment

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Pump, I.V., Non-Ferrous

AE #: PINF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	CONTINUUM MRIP		Stand	OF/OI	Project

Continuum mr i.v. System compatible with scanners up to and including 1.5t; allows placement of pump next to scanner bore; standard configuration includes dual channel pump with flow rate to 1200ml/hr; integrated 20-60ml syringe holder; bolus function with bolus weight and duration options; anti-bolus feature prevents delivery of false bolus after a downstream occlusion is detected

View Cutsheet 76044

W x D x H: 3.5 x 1.6 x 4.5 in.
Electrical: 120V 60Hz 0.12A
Elect Notes: Battery operated; charger included

Rack, Apron

AE #: RAAP-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf X-Ray Corporation	Deca-Rack, Free Standing	16411	Floor	OF/OI	Project

Prolong the life of your aprons and skirts by hanging them properly! Holds up to 10 pairs of aprons and skirts on pivot arms—plus gloves with the optional Glove-Rack Kit. Measures 54” H x 51” W x 26” D. Max rack depth is 26”. Shipping Weight: 125 lbs. 16411

View Cutsheet 209194

W x D x H: 51 x 26 x 54 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	8705-1251-900		Wall	OF/OI	Project

Push to set suction regulator

View Cutsheet 208749

W x D x H: 2.8 x 4.8 x 6.5 in.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: Patient Prep Bay **Department:** Rad-Onc Treatment

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Stand, IV, MRI — AE #: STIM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Blickman Inc	7792MR-2	0537792002	Floor	OF/OI	Project

5 Leg MR compatible IV stand with a stainless steel pole and stand at a 24" diameter. Height adjusts from 74" to 110". Comes with 2 removable hooks View Cutsheet 208728

W x D x H: 24 x 24 x 110 in.

Stretcher, Non-Ferrous, Bariatric — AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety. View Cutsheet 210322

MR conditional to 3T. Optional IV pole available.

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Room: Patient Prep Bay **Department:** Rad-Onc Treatment

Room #: A006G

Room Notes: 3 Pt bays. Zone 2. MR Sim, HDR, Brachy Prep

Thermometer, Electronic, Oral

AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius

View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Waste Container, Biohazard

AE #: WACB-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883564		Floor	OF/OI	Project

Slim jim step-on container with 8-gallon capacity. Quiet controlled lid closure. Color: Red

View Cutsheet 151080

W x D x H: 16.7 x 10.6 x 21.1 in.

Weight: 6 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

By sink for paper towel disposal

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Alcove, Nourishment

Department: Rad-Onc Treatment

Room #: A006G1

Room Notes: Located in Patient Prep Bay area

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Alcove, Nourishment **Department:** Rad-Onc Treatment

Room #: A006G1

Room Notes: Located in Patient Prep Bay area

Ice Maker / Water Dispenser — AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Alcove, Nourishment **Department:** Rad-Onc Treatment

Room #: A006G1

Room Notes: Located in Patient Prep Bay area

Refrigerator, Undercounter, ADA Height

AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white. View Cutsheet 211261

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.
HVAC Notes: Refrigerant R600a

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: HDR Treat **Department:** Rad-Onc Treatment

Room #: A006H

Allowance, Relocation of Existing Equipment

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	Bravos			EX/VI	Project

Bravos afterloader

No Cutsheet 213107

Pricing confirmed with Varian & Jennifer on 8/26/24

Cart, Supply

AE #: CASU-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Tall		Floor	OF/VI	Project

Single wide, tall Starsys cart with clear doors on top and bottom; 3 each poly shelves, 3 each 6" totes

View Cutsheet 204781

W x D x H: 22.7 x 24.9 x 78.4 in.

Container, Lead Storage, Mobile

AE #: COLS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radiation Products Design, Inc.	994-071		Floor	OF/OI	Project

The Lead Storage Container for HDR has a 2" thick (5.08 cm) lead wall and is designed to store the source end of an HDR cable if there is a problem with the retracting system. This container can be easily moved in the cart which has 2" diameter (5.08 cm) swivel casters. The container wall and lid are made of 2" thick (5.08 cm) lead, and the container has an inside diameter of 1" (2.54 cm) and a depth of 10" (25.4 cm)

View Cutsheet 209585

Placeholder. May be included with afterloader

W x D x H: 10 x 10 x 12 in.

Weight: 115 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: HDR Treat

Department: Rad-Onc Treatment

Room #: A006H

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: HDR Treat

Department: Rad-Onc Treatment

Room #: A006H

HDR Afterloader, Position Calibrator

AE #: ALPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	Camscale		Floor	OF/VI	Project

CamScale™ provides simple, fast and precise position verification that is recordable and reproducible. Camscale delivers wire position calibration and accuracy for QA purposes. Connects to the CamScale Connection Box. Price is included in the cost of the Bravos Afterloader.

View Cutsheet 211485

Price included in Bravos Afterloader

W x D x H: 17.8 x 20.3 x 34.8 in.

Weight: 91 lbs.

Meter, Survey

AE #: MESU-26

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	26-3	48-4232	Countertop	OF/OI	Project

High-range frisker features standard 15.51 cm2 GM pancake detector, loud audible click output, and large auto-ranging LCD display with LCD backlighting. Water resistant housing. Used to frisk people and objects. Three modes of operation available: Rate, Max, and Count.

View Cutsheet 209460

See accessories for energy compensation filter and holder.

W x D x H: 2.7 x 10.7 x 1.8 in.

Weight: 1 lbs.

Elect Notes: Uses (2) standard AA batteries.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Dose energy compensation filter w/tether	4519-041-02	1	1
Sample Holder for M-26	47-3948	1	1

Room: HDR Treat **Department:** Rad-Onc Treatment

Room #: A006H

Monitor, Radiation

AE #: MORA-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	CNMC Company, Inc.	7008 RT		Wall	OF/CI/VI	Project

The Model 7008 RT is a wall-mounted radiation monitor designed to meet the specific needs of radiation therapy. It is designed to operate continuously from an AC power line. In the event of power failure, the built-in, continuously trickle charged NiMH battery automatically switches in to begin supplying power immediately,

View Cutsheet 209586

Include remote alarm unit - see accessories, plan for 75' cable to connect the two monitors If unable to obtain this model, replace with Ludlum 375/2 model**

W x D x H: 4.5 x 2.7 x 7.6 in.
Electrical: 208V 60Hz **Weight:** 1.5 lbs.
Elect Notes: AC power with back up battery. Power: 95–230 VAC, 50/60 Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Remote Alarm Unit	7008 R	1	1

Radiation Therapy, HDR Afterloader

AE #: RTHA-01E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	Bravos		Cabinet	EX/VI	Existing

BRAVOS™ HDR afterloader system for radiation oncology. Pair with CamScale. Includes Treatment Room Interconnection Box. Price also include Camscale.

View Cutsheet 209192

Changed to existing on 8/26/24 per Jennifer Ratner. UKHC will purchase new Bravos in '25 and relocate as existing to new building. Pricing confirmed with Varian & Jennifer, see allowance

W x D x H: 21.2 x 27 x 44.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 315.3 lbs.
Elect Notes: Electrical Power Requirements
• System power rating: 100 – 240 VAC | 50 – 60 Hz |
110V/60 Hz or 240 V |50 Hz models available
• Power consumption: 100 VA maximum
• Afterloader system is powered through an uninterruptible power supply (UPS). If all power is lost, retract is powered by emergency back-up batteries situated in the afterloader system.

Room: HDR Treat

Department: Rad-Onc Treatment

Room #: A006H

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Stretcher, Non-Ferrous, Bariatric

AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety. MR conditional to 3T. Optional IV pole available.

View Cutsheet 210322

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Room: HDR Treat

Department: Rad-Onc Treatment

Room #: A006H

Treatment Tube Holder

AE #: TRTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	GM11001430		Wall	OF/CI	Project

Wall holder for source and transfer guide tubes. View Cutsheet 210597

W x D x H: 12.2 x 3.9 x 3.15 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Physics Work Area

Department: Rad-Onc Treatment

Room #: A006J

Room Notes: Assumes space for 9 people

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Brachy **Department:** Rad-Onc Treatment

Room #: A006K

Anesthesia Machine

AE #: ANMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	PERSEUS A500		Floor	OF/VI	Project

Configurable anesthesia workstation; 15.3" touch screen; minute volume (mv) and tidal volume (vt), respiratory rate (rr) and peak inspiratory pressure (pip); integrated gas bench for measuring inspiratory and expiratory gas concentrations of o2, n2o, co2 and anesthetic agents; simultaneous display of 3 real-time curves for co2, o2 and anesthetic agent concentrations, airway pressure, inspiratory and expiratory flow

View Cutsheet 163801

W x D x H: 45.2 x 31.1 x 58.3 in.
Network: Networked
Electrical: 120V 60Hz 12A **Weight:** 353 lbs.
Plumb Notes: Med gas connections to anesthesia and/or equipment booms. Requires (1) WAGD, (1) Oxygen, (1) Air

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Room: Brachy

Department: Rad-Onc Treatment

Room #: A006K

Cart, Anesthesia

AE #: CAAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Harloff Company, Inc.	AP7D		Floor	OF/OI	Project

This MRI safe anesthesia cart is designed and engineered for use in 3 Tesla or less MRI suites. Comes with a unique anesthesia accessory package made up of items constructed from non or “weakly magnetic” materials. The anesthesia accessory package includes a 3-tier aluminum raised back rail system, four aluminum siderails, two plastic drawer trays and a set of organizers for each tray. Drawer configuration: (1) - 4", (4) - 3.25", (1) - 6.5", (1) - 9.75"

View Cutsheet 207987

W x D x H: 31.8 x 23.8 x 46 in.

Weight: 127 lbs.

Cart, Supply

AE #: CASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	STARSYS DOUBLE		Floor	OF/VI	Project

Double wide starsys mobile unit with glass doors and angled shelves with 270 degree hinge angle.

View Cutsheet 172108

W x D x H: 42.5 x 24.9 x 78.3 in.

Room: Brachy **Department:** Rad-Onc Treatment

Room #: A006K

Cart, Transfer, Components

AE #: CATC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Diacor	Transfer Systems		Cart	OF/VI	Project

Various Zephyr® Patient Positioning and Transfer Systems. See accessories for all options. View Cutsheet 209403

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Armboard		1	1
Patient Cushions		1	1
Patient Safety Straps		1	1
Stirrup Cart		1	1
Stirrups		1	1
Universal Clamp Bracket		1	1
Zephyr Blower		1	1
Zephyr HDR For HDR GYN/Prostate		1	1
Zephyr HDR Pt Hover Board		1	1
Zephyr Hose		1	1
Zephyr HP For external beam H/N		1	1
Zephyr HP Pro For external beam H/N		1	1
Zephyr Stretcher Mount		1	1
Zephyr XL For external beam thoracic/pelvic		1	1

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Brachy

Room #: A006K

Department: Rad-Onc Treatment

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Room: Brachy
Room #: A006K

Department: Rad-Onc Treatment

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Imaging System, C.T. Scanner

AE #: IMCT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Solutions Usa, Inc.	SOMATOM CONFIDENCE with Sliding Gantry		Floor/Ceiling	OF/CI/VI	Project

The SOMATOM Confidence CT is a CT scanner that generates and processes cross-sectional images of patients by computer reconstruction of X-ray transmission data to be used to aid in diagnosis, treatment preparation, and radiation therapy planning. It is one of the first CT scanners specifically designed to fulfill the needs of two professions in radiation therapy (RT): radiation oncologists and physicists. This SOMATOM Confidence CT Scanner includes a Sliding Gantry which moves on rails where it needs to be when you want to perform CT imaging, or just out of the way when you need space. View Cutsheet 200643

Lasers are integrated into machine**Pricing from Siemens Package, quote #CPQ-1173498-0** Supplemental Info

Network: Wired
Elect Notes: **Refer to Siemens site planning information.**
Plumb Notes: **Refer to Siemens site planning information.**
HVAC Notes: **Refer to Siemens site planning information.**
Struct Notes: **Refer to Siemens site planning information.**

Room: Brachy
Room #: A006K

Department: Rad-Onc Treatment

Imaging, Positioning Laser

AE #: IMPL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lap Of America, L.C.	Apollo Ceiling		Ceiling	OF/CI/VI	Project

Apollo room lasers are used for precise and repeatable positioning of radiotherapy patients. The Apollo system has three (optionally four) lasers for the coronal, sagittal, and transversal body planes. You can choose the color, line and or/cross laser, and mounting option, all adapted to your individual room situation. A fourth laser prevents possible shadowing from the linac gantry in its initial position.

View Cutsheet 209948

Model confirmed with Megan Gilmore 11/4/24. See Siemens site specific for drawings, pair with wall mounted lasers

W x D x H: 2.48 x 4.13 x 9.33 in.
Electrical: 120V 60Hz 1.5A
Elect Notes: Requires 120 VAC duplex outlet above finished ceiling. **Refer to LAP site planning guide.**
Struct Notes: All 8 structural frame pads must be secured to concrete ceiling above, or structural steel support. **Refer to LAP site planning guide.**

Imaging, Positioning Laser

AE #: IMPL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Lap Of America, L.C.	Apollo Wall		Wall	OF/CI/VI	Project

WALL MOUNTED LASERS. Apollo room lasers are used for precise and repeatable positioning of radiotherapy patients. The Apollo system has three (optionally four) lasers for the coronal, sagittal, and transversal body planes. You can choose the color, line and or/cross laser, and mounting option, all adapted to your individual room situation. A fourth laser prevents possible shadowing from the linac gantry in its initial position.

View Cutsheet 213072

W x D x H: 4.3 x 3.9 x 8.7 in.
Electrical: 120V 60Hz 1.5A

Light, Procedure

AE #: LIEP-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Aurora Astro		Ceiling	OF/CI/VI	Project

Max intensity output: 126,000 =/- 5K lux. Spot size 7.2" with 46" depth of field. 360 degree rotation on all axes. Color temperature 4,141K. Light head diameter 17.5". CRI 97.

View Cutsheet 211872

Per Skytron quote Q-90711-12 dated 9/26/2024. **Placeholder for updated model from Skytron - (1) light, (2) monitors on 2 arms**

Supplemental Info

W x D x H: 17.5 x 17.5 x N/A in.
Electrical: 120V 60Hz

Room: Brachy **Department: Rad-Onc Treatment**

Room #: A006K

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, MMX, cables, hemodynamic extension, BIS module, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Monitor, Physiological, Module, BiSpectral Index — AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC). View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Room: Brachy
Room #: A006K

Department: Rad-Onc Treatment

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Probe Cleaner

AE #: PRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON2		Wall	OF/OI	Project

Ultrasound probe high level disinfection system. Captures user id, instrument id, disinfectant information and chemical indicator. Can download data to usb or to hospital network.

View Cutsheet 172692

W x D x H: 14.3 x 12.6 x 21.2 in.
Network: Wired
Electrical: 120V 60Hz 5A **Weight:** 48.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount	E8350NG	1	1

Probe Cleaner Accessory, Printer

AE #: PCAP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON PRINTER		Wall	OF/OI	Project

Printer To Accompany Trophon 2. Connected to Trophon2 Unit via USB Cable. Printer is a Traceability Solution, Printing Trophon Disinfection Labels.

View Cutsheet 171574

W x D x H: 4.33 x 6.89 x 9.84 in.
Electrical: 120V 60Hz 1.8A

Probe Cleaner, Component

AE #: PRCC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	PRINTER WALL MOUNT	N00105	Wall	OF/CI	Project

Printer wall mount for trophon printer.

View Cutsheet 172899

W x D x H: 4.33 x 6.89 x 9.84 in.

Room: Brachy **Department:** Rad-Onc Treatment

Room #: A006K

Probe Cleaner, Component

AE #: PRCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	WALL MOUNT	N05009	Wall	OF/CI	Project

Wall mount for probe cleaner. View Cutsheet 172898

W x D x H: 14.2 x 12.8 x 10.8 in. **Clearance:** Left 10 in.; Right 10 in.

Rack, Tube Storage

AE #: RATU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radiation Products Design, Inc.	950-098		Wall	OF/CI	Project

HDR Transfer Tube Holder for Ten Tubes View Cutsheet 209195

W x D x H: 11 x 1.13 x 1.67 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Brachy

Department: Rad-Onc Treatment

Room #: A006K

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Instrument

AE #: TAIN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MPH08MCM505LC		Floor	OF/OI	Project

Stainless Steel Instrument Table with Shelf. Three Inch Locking Casters.

View Cutsheet 206929

W x D x H: 36 x 24 x 34 in.

Room: Brachy **Department:** Rad-Onc Treatment

Room #: A006K

Table, Instrument, Angular

AE #: TAIA-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	0147862000		Floor	OF/OI	Project

This table is 34” tall, which is in the safety zone for reduced back stress, and it travels on 3” casters. Select the surface area with dimensions that fit your needs. 304 stainless construction. Gauge: 1 1/4" tube legs, 18 gauge table top. Add a lower shelf or drawers for additional storage. View Cutsheet 209583

W x D x H: 60 x 15 x 34 in.

Weight: 120 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Brachy / CT Equipment **Department:** Rad-Onc Treatment

Room #: A006K1

C-Arm, Portable

AE #: CAPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	CIOS Fusion		Floor	OF/VI	Project

Mobile C-Arm X-ray unit. Features: Full View FD imaging, Retina Imaging Chain with IDEAL (Intelligent Dose Efficiency Algorithm) dose reduction. 19 inches TFT high-brightness color display. Flat detector 20 centimeters x 20 centimeters (8 x 8 inches) standard. Optional flat detector 30 centimeters x 30 centimeters (12 x 12 inches). DICOM network interfaces. View Cutsheet 208654

W x D x H: 31 x 77 x 63.8 in.
Electrical: 120V 60Hz 16A **Weight:** 600 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
DICOM Print		1	1
DICOM Query / Retrieve		1	1
DICOM Send / Storage Commitment		1	1
DICOM Services		1	1
DICOM Worklist / MPPS		1	1

Cabinet, Supply Sterile

AE #: CASS-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Terra Universal	4205-21D-HD		Floor	OF/OI	Project

Storage cabinet with HEPA filter and blower. Built-in variable-speed blower is mounted above a HEPA filter to provide a vertical laminar flow of clean air through the storage area. Sloped top. Perforated bottom shelf allows for laminar airflow. Materials: powder-coated steel chamber and reinforced doors; stainless steel door frame with static dissipative PVC panels, and stainless steel vertical supports for shelves to allow for shelf height adjustment. Shelves sold separately. View Cutsheet 209393

W x D x H: 40 x 26.5 x 94 in.
Electrical: 120V 60Hz 4.2A **Weight:** 440 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Perforated Shelf		2	4

Room: Brachy / CT Equipment **Department:** Rad-Onc Treatment

Room #: A006K1

Cart, Transfer

AE #: CATR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Diacor	Procedural Stretcher		Floor	OF/VI	Project

Zephyr Procedural Stretcher. Continuous flat surface with translating top enables smooth patient transfer from imaging/treatment to the stretcher. Safety stops at the head and foot of the stretcher. Customizable end stops are available. Brake and steer activated foot pedals with true direction steering. Adjustable height: Minimum: 24.8", Maximum: 34.2", Side rail Ht: 14" Wt capacity: 600lb.

View Cutsheet 209401

W x D x H: 32 x 82.3 x 48.2 in.

Weight: 405 lbs.

Imaging, Ultrasound Scanner

AE #: ULPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	ST		Floor	OF/VI	Project

With 21" portrait, gray scale, touchscreen display and mobile, adjustable height stand; 2 transducer ports and on-stand storage; In-plane needle visualization.

View Cutsheet 209454

** Dimensions noted with Stand

Includes mobile stand May not need, Erin to confirm w/providers.

W x D x H: 25.5 x 23 x 68 in.

Network: Networked

Electrical: 120V 60Hz

Weight: 110 lbs.

Stepper Device

AE #: STDE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Civco Medical Solutions	Classic Stepper		Stand	OF/VI	Project

The Classic Stepper is a lightweight precision stepping device capable of fitting a host of ultrasound manufacturers transducers. Its module design is adaptable to a variety of Brachytherapy / Cryotherapy Transrectal transducers. The Classic Stepper features a secure centerline detent with angular rotation both counter and clockwise. Also, easy-to-read marking scales are aligned on either side.

View Cutsheet 208866

Place Holder

Room: Brachy / CT Equipment

Department: Rad-Onc Treatment

Room #: A006K1

Table, Surgical

AE #: TASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	6702 HERCULES		Floor	OF/VI	Project

Surgical table; 1,200 lb lift capacity; 1,000 lb articulation lift capacity; 210 degree table top rotation; removable back and leg sections; power beach chair positioner; 23.625" to 41.875" adjustable table height; 30 degree lateral tilt; 30 degree trendelenburg and reverse trendelenburg; pendant control and foot control

View Cutsheet 148223

W x D x H: 21.9 x 79 x 41.5 in.
Electrical: 120V 60Hz

Room: Brachy Control

Department: Rad-Onc Treatment

Room #: A006L

Room Notes: Workstations for 4 people.

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Computer, Tablet

AE #: COTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lap Of America, L.C.	CARINAnav		Countertop	OF/VI	Project

Remote tablet for positioning laser

View Cutsheet 213091

Price included with lasers

W x D x H: 11 x 10.1 x 0.9 in.
Network: Networked
Electrical: 120V 60Hz

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Imaging, Control Panel

AE #: IMCP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Solutions Usa, Inc.	Somatom Confidence		Countertop	OF/VI	Project

Included in price of Somatom Confidence CT Scanner

View Cutsheet 209584

Network: Wired
Electrical: 120V 60Hz

Room: Brachy Control **Department:** Rad-Onc Treatment

Room #: A006L

Room Notes: Workstations for 4 people.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Workstation, US Infection Control

AE #: WOIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	AuditPro		Countertop	OF/OI	Project

Infection control workflow compliance management in the form of a workstation and mobile unit to be used with the Nanosonic Trophon2. Handheld computer/barcode scanner dimensions: 6.18 x 3.08 x 0.67 in

View Cutsheet 210430

W x D x H: 5.1 x 5.9 x 2.3 in.

Network: Wireless **Network Notes:** WLAN, WLAN/WWAN

Electrical: 120V 60Hz

Room: CT Simulator

Department: Rad-Onc Treatment

Room #: A007A

Board, Breast

AE #: BOBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Civco Medical Solutions	TBD		Rack	OF/OI	Project

Breast board for radiation therapy . Model to be determined

View Cutsheet 207292

W x D x H: 24 x N/A x N/A in.

Board, Breast, Component

AE #: BOBC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Civco Medical Solutions	C-Qual	013156	Wall	OF/CI	Project

Wall mounted bracket holder for the C-Qual Breast Board Positioning System.

View Cutsheet 209269

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Room: CT Simulator

Department: Rad-Onc Treatment

Room #: A007A

Camera, Scanner

AE #: CAMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	RGSC		Wall	OF/CI/VI	Project

Respiratory Gating for Scanners (RGSC). Monitor patient respiratory movements for precise CT image acquisition to enhance treatment accuracy. Track patient movements, including breathing, to ensure that your treatments hit their mark accurately. Camera located in scanner room. Remainder of items located in control room. Price included in cost of scanner.

View Cutsheet 213059

W x D x H: 8 x 8 x 14 in.
Electrical: 120V 60Hz
Elect Notes: Input voltage: 100 - 240 VAC. Input Frequency: 50 or 60 Hz +/- 3 Hz. System Load: 240 VA

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Supply

AE #: CASU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	Super Adjustable Erecta Wire		Floor	OF/VI	Project

Super Adjustable Erecta model with chrome finish to include (6) wire shelves, (2) braking casters, (2) swivel casters, and (4) 68" posts

View Cutsheet 208894

For QA Items & Supplies

W x D x H: 60 x 18 x 68 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Room: CT Simulator

Department: Rad-Onc Treatment

Room #: A007A

CT Simulator

AE #: CTSI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	SOMATOM go.Open Pro		Floor	OF/CI/VI	Project

Advanced CT simulator with large bore (85cm). Enables 4D images with virtually no artifacts related to incomplete breathing cycles. Optimize clinical operations to minimize error. More confident treatment planning with potential for smaller target margins. Allows more patients to benefit from 4DCT

View Cutsheet 209054

Pricing from Siemens Package, quote #CPQ-900445-1. Laser integrated in CT Sim. No additional positioning lasers needed

Supplemental Info

Network: Wired
Electrical: 480V
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: CT Simulator

Department: Rad-Onc Treatment

Room #: A007A

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208701

Request per Dr. Lockhart - occasional Pt's that need emergent anesthesia and/or resp care.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: CT Simulator **Department:** Rad-Onc Treatment

Room #: A007A

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Injector, Contrast Media

AE #: INCM-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad/Bayer Healthcare Services	Stellant FLEX		Gantry	OF/CI/VI	Project

CT injection system with options for 150ml and 200ml syringe sizes. Also cleared for use with contrast enhanced mammography (CEM). System uses barcodes to determine syringe size, expiration date, and if the syringe has already been used.

View Cutsheet 205858

Place holder until decision made on Ulrich mobile injector (209987)

W x D x H: 12.1 x 9 x 14.5 in.

Network Notes: Control panels are networked but not the actual injector.

Electrical: 115V 60Hz 1.5A

Weight: 16.8 lbs.

Elect Notes: 300 volts-amps

Oven, Drying

AE #: OVDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Qfix	Rapid Heat RT-2075-110		Cart	OF/OI	Project

Dry air heating solution for thermoplastic masks and custom bolus. Two non-stick sliding racks and 7.5cm digital display

View Cutsheet 207393

W x D x H: 32 x 30 x 19.1 in.

Electrical: 110V 60Hz

Weight: 12 lbs.

Oven, Drying, Cart

AE #: OVDC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Klarity Medical	Airflow Cart		Floor	OF/OI	Project

Stainless steel cart to support the AirFlow Oven with an additional shelf below. Locking wheels on feet.

View Cutsheet 207295

W x D x H: 36 x 30 x 28 in.

Weight: 50 lbs.

Room: CT Simulator

Department: Rad-Onc Treatment

Room #: A007A

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

660 lb capacity

Supplemental Info

Electrical: 115V 60Hz 2.5A

Positioning Device

AE #: PODE-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924954		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Regular. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205980

W x D x H: 9.5 x 14 x 6.5 in.

Positioning Device

AE #: PODE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924951		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Long. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205979

W x D x H: 9.75 x 24 x 6.75 in.

Positioning Device

AE #: PODE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924960		Cabinet	OF/OI	Project

Positioning flat bottom roll for lower body support. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205981

W x D x H: 8.5 x 14 x 4.25 in.

Room: CT Simulator

Department: Rad-Onc Treatment

Room #: A007A

Positioning Device

AE #: PODE-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	931177		Cabinet	OF/OI	Project

Curved toboggan arm/leg guard; size small. Provides extra protection on top of extremities while shielding physician from sharp edges.. Easy to clean, crystal clear radiolucent shield keeps arms and legs on the table, helping to prevent interference. View Cutsheet 205982

W x D x H: 10 x 10.3 x 6 in.

Pump, Vacuum

AE #: PUVA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Civco Medical Solutions	MTVP1		Cart	OF/OI	Project

Dual function vacuum compressor with hand and foot controls. Audible alarm when optimum vacuum level is reached. Dimensions are approximate. View Cutsheet 207464

W x D x H: 8 x 12 x 6 in.
Electrical: 115V 60Hz

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: CT Simulator

Department: Rad-Onc Treatment

Room #: A007A

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters.

View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Table, Prep

AE #: TAPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	SG-80-SS		Floor	OF/OI	Project

Stainless steel construction; features table top with rail; single drawer; shelf; 3" double ball bearing casters, rubber wheels.

View Cutsheet 141195

W x D x H: 20 x 16 x 34 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height

View Cutsheet 172941

Red

W x D x H: 22 x 22 x 33.8 in.

Room: CT Sim Control **Department:** Rad-Onc Treatment

Room #: A007A1

Room Notes: Assumes space for 4 people

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Camera, Scanner, Component — AE #: CAMS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens / Varian Medical Systems	RGSC		Countertop	OF/VI	Project

Workstation console/monitor, undercounter cabinet, and charging station. Dimensions are for undercounter cabinet. Price included with Siemens scanner View Cutsheet 213061

W x D x H: 11.3 x 29.8 x 24.5 in.

Electrical: 120V 60Hz **Weight:** 132 lbs.

Elect Notes: Cabinet: 100-240 VAC, 50 or 60Hz (+/- 3Hz), 240 VA. All power outlets should be within 3' of the component they are supplying. (1) standard power outlet for the cabinet, (1) standard power outlet for the charging station - uses an AC to DC power supply, 5 Vdc, 2.6A maximum. The cabinet requires an independent Ground/Protective Earth (G/PE) conductor. Terminate the G/PE with an 8mm diameter ring lug at the rear of the cabinet. The dedicated G/PE must be common to power outlet ground for the cabinet

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: CT Sim Control **Department:** Rad-Onc Treatment

Room #: A007A1

Room Notes: Assumes space for 4 people

Display Control Unit

AE #: DICU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad/Bayer Healthcare Services	CT		Countertop	OF/VI	Project

Display control unit for the CT Scanner / Stellant D injector. Price included in cost of Injector. View Cutsheet 165555

W x D x H: 12.5 x 8.9 x 13.5 in.
Electrical: 120V 60Hz 1.2A **Weight:** 8.2 lbs.

Injector, Contrast Media, Component

AE #: INCM-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad/Bayer Healthcare Services	STELLANT D	SCT321	Countertop	OF/VI	Project

Certegra touchscreen workstation (10.2"wx15.8"dx13.5"h) with base unit (11"w x 8.8"d x 11.5"h); **see procedure room injector for funding** View Cutsheet 162440

Place holder pending determination of injector manufacturer. May change to GE/ulrich INJECT CT Motion injector control panel (209988).

W x D x H: 15.8 x 10.2 x 13.5 in.
Network: Wired
Electrical: 120V 60Hz 2.5A **Weight:** 17.6 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Block Fabrication **Department:** Rad-Onc Treatment

Room #: A007B

Block, Styrofoam

AE #: BLST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radiation Products Design, Inc.	870-710		Cabinet	OF/OI	Project

3/4" Styrofoam Blocks. The Dow Chemical 25 PSI Styrofoam Blocks have planed flat top and bottom surfaces. This extremely smooth surface, when placed against a flat Cooling Plate, does not allow the alloy to leak out when filling the Styrofoam. View Cutsheet 210477

W x D x H: 10 x 10 x 0.75 in.

Cart, Tool

AE #: CATO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fastenal	0225938		Floor	OF/OI	Project

Gray steel 4 drawer professional service cart with 5"x2" casters. With key lock. Two drawers 11.6"W x 17.1"D, x 5"H, one drawer 24.6"W x 17.1"D x 3.1"H, and one 24.6"W x 17.1"D x 5"H. View Cutsheet 208611

W x D x H: 30 x 19.3 x 41.3 in.

Weight: 137.5 lbs.

Cooling Plate

AE #: COPL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Radiation Products Design, Inc.	878-270		Countertop	OF/OI	Project

Aluminum cooling plate aids in the cooling process of alloy blocks. Comes with 4 leveling feet. View Cutsheet 207396

W x D x H: 24 x 12 x 1 in.

Weight: 24.6 lbs.

Cordless Drill

AE #: CODR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bosch Home Appliances	PS21-2A		Drawer	OF/OI	Project

The Bosch PS21 12 V Max Two-Speed Pocket Driver provides users with the shortest head-length in class at only 5.6" to allow users to drive screws in many hard-to-reach areas straight on. Dimensions are for the carrying case. View Cutsheet 210486

W x D x H: 12 x 9 x 3.5 in.

Electrical: 120V 60Hz 20W **Weight:** 1.8 lbs.

Elect Notes: Comes with: (2) 12V Max Lithium-Ion 2.0 Ah Batteries, (1) 12V Max Charger

Room: Block Fabrication **Department:** Rad-Onc Treatment

Room #: A007B

Dispenser, Alloy

AE #: DIAL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radiation Products Design, Inc.	878-060		Undercounter	OF/OI	Project

Stainless steel 1.5 gallon digital alloy dispenser for high (203F) and low (158 F) melting alloy. It has two digital readouts, temperature and set point. Alloy capacity 120lb. View Cutsheet 207394

Under hood

W x D x H: 12 x 9.75 x 14.5 in.
Electrical: 120V 60Hz 5.6A 665W 1-Phase **Weight:** 17.5 lbs.
Elect Notes: 6 foor AC cord with grounded hospital grade plug.

Dispenser, Personal Protection

AE #: DIPP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bowman Manufacturing	RE101-0012		Wall	OF/CI	Project

Semi-recessed ppe dispensing system; hold variety of gowns, three boxes of gloves, one box of earloop-style face masks, one box of shield-styel face masks and built-in storage area for a variety of medical supplies, fourth box of gloves, or one box of n-95 face masks. View Cutsheet 171483

Place just outside room.

W x D x H: 24.4 x 4.77 x 27.7 in.
Weight: 22.4 lbs.
Struct Notes: Dimensions for part of dispenser that is recessed in the wall is 23.38"w x 3.5"d x 26.72"h.

Dispenser, Soap, D-Lead

AE #: DISL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Esca-Tech	DW402		Wall	OF/CI	Project

Dispenser 2.5 liter Stainless steel pump Aluminium housing Adjustable dosage (2.3 to 5.7 mL) 1 bottle included DW-402. Dimensions are an approximation based off of shipping box. View Cutsheet 209923

W x D x H: 5 x 4 x 16 in.
Weight: 4 lbs.

Room: Block Fabrication

Department: Rad-Onc Treatment

Room #: A007B

Dispenser, Wipes

AE #: DIWI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Esca-Tech	DW-150		Wall	OF/CI	Project

Wall Bracket for D-Wipe WT-150, Non-Locking Stainless Steel Fits standard 5" diameter wipe canisters DW-150. View Cutsheet 209924

W x D x H: 6 x N/A x 8.5 in.

Drill Press

AE #: DRPR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Dayton	16N196		Countertop	OF/CI	Project

Dayton 10" Drill Press: Belt, 120V AC, Fixed Speed, 650 RPM – 3,070 RPM, 10 in Swing, 5 in, 1/3 hp View Cutsheet 210214

Model confirmed with Dan Farrer

W x D x H: 11.3 x 19.3 x 27.5 in.
Electrical: 120V 60Hz 4.1A

File

AE #: FILE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Craftsman	CMHT82525		Drawer	OF/OI	Project

3 pc. set includes 1 mill file, 1 round file, and 1 half round file. Includes carry pouch. View Cutsheet 210483

W x D x H: 10.8 x 4.61 x 1.54 in.
Weight: 0.5 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Block Fabrication **Department:** Rad-Onc Treatment

Room #: A007B

Hood, Canopy

AE #: HOCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hemco Corporation	13130		Wall	OF/CI	Project

36" wide canopy hood designed to collect and exhaust corrosive vapors, steam, heat, and odors

View Cutsheet 207662

W x D x H: 36 x 30 x 18 in.
Electrical: 120V 60Hz

Imaging, Block Cutter

AE #: IBLC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radiation Products Design, Inc.	869-900		Countertop	OF/OI	Project

Styro-foam block cutter with replaceable nic-chrome cutting wire and lighted power switch.

View Cutsheet 207164

W x D x H: 11.8 x 14 x 7 in.
Electrical: 110V 60Hz 3A

Mallet, Rubber

AE #: MARU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Amazon	B08TGD7KSP		Drawer	OF/OI	Project

Fiberglass Handle Rubber Mallet Hammer Set, 8 OZ and 16 OZ, Soft Blow Tasks without Damage, Black with Red, 2 Packs.

View Cutsheet 210480

W x D x H: 11.5 x 4.4 x 3.7 in.
Weight: 2.2 lbs.

Melting Alloy

AE #: MEAL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Radiation Products Design, Inc.	879-202		Countertop	OF/OI	Project

Cadmium free 203 degree F high melting alloy

View Cutsheet 207395

Weight: 50 lbs.

Room: Block Fabrication **Department:** Rad-Onc Treatment

Room #: A007B

Plier

AE #: PLIE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Irwin Tools	2078306		Drawer	OF/OI	Project

IRWIN VISE-GRIP Diagonal Cutting Pliers, 6-Inch. Durably constructed from nickel chromium steel, and have an induction hardened cutting edge. The ProTouch grips provide comfort and help to reduce hand fatigue. Backed by the IRWIN Lifetime Guarantee, they meet or exceed ANSI specifications. View Cutsheet 210481

W x D x H: 6.7 x 2.9 x N/A in.

Saw

AE #: SAWW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Craftsman	CMHT20880		Drawer	OF/OI	Project

15 in general purpose saw. View Cutsheet 210484

W x D x H: 19.1 x 1.4 x 5.7 in.

Weight: 0.8 lbs.

Sheet, Lead

AE #: SHLE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Radiation Products Design, Inc.	3000-062, 0.063"			OF/OI	Project

Lead Thickness: 0.063". These pure, cold-rolled Lead Sheets can be formed or cut into any shape to shield areas of concern. They will conform to irregularities. Common applications include electron and superficial shielding to protect against small amounts of radiation. View Cutsheet 210475

W x D x H: 12 x 24 x N/A in.

Weight: 7.5 lbs.

Sheet, Lead

AE #: SHLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Radiation Products Design, Inc.	3000-125, 0.125"			OF/OI	Project

Lead Thickness: 0.125". These pure, cold-rolled Lead Sheets can be formed or cut into any shape to shield areas of concern. They will conform to irregularities. Common applications include electron and superficial shielding to protect against small amounts of radiation. View Cutsheet 210476

W x D x H: 12 x 24 x N/A in.

Weight: 15 lbs.

Room: Block Fabrication **Department:** Rad-Onc Treatment

Room #: A007B

Snip, Tinners

AE #: SNTI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Amazon	WISEPRO		Drawer	OF/OI	Project

10” Aviation Snips (Straight/Left/Right), Compound Action Metal Cutter, Heavy Duty Tin Cutting Shears View Cutsheet 210482

W x D x H: 9.8 x N/A x N/A in.

Tool Box

AE #: TOBO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Craftsman	CMMT99448		Countertop	OF/OI	Project

CRAFTSMAN Home Tool Set/Mechanics Tools Kit, 102-Piece. All pieces fit in fiberglass case. View Cutsheet 210478

W x D x H: 15.1 x 17 x 4.1 in.

Weight: 13.2 lbs.

Vacuum, Wet/ Dry

AE #: VAWD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nilfisk-Advance, Inc.	Attix 50	302004233	Floor	OF/OI	Project

ATTIX 50 combines high Wet&Dry performance with big container capacity. The improved ergonomic design ensures functional and user-friendly operation. View Cutsheet 206595

H.E.P.A filter model

W x D x H: 15 x 17.7 x 29.5 in.

Electrical: 120V 60Hz 8.3A **Weight:** 24.25 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Physics Storage

Department: Rad-Onc Treatment

Room #: A007C

Room Notes: Need guidance on MEQ

Cart, Supply

AE #: CASU-69

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Intermetro Industries	SUPER ERECTA	A566BC/A2460BR	Floor	OF/VI	Project

Adjustable super erecta chrome plated wire stem caster cart with 5 shelves, (4) posts; 5" casters (2 swivel, 2 brake). 60"w x 24"d x 69"h. View Cutsheet 62298

W x D x H: 60 x 24 x 69 in.

Room: 3D Printing **Department:** Rad-Onc Treatment

Room #: A007D

Room Notes: Assume 1-2 printers as new for now. 1 or 2 may be brought over as existing pending replacements

Cabinet, Safety, Flammable Storage

AE #: CASF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Uline	H-4177M-Y		Floor	OF/OI	Project

Undercounter Flammable Storage Cabinet - Manual Doors, Yellow, 22 Gallon View Cutsheet 209113

Under cabinet/counter

W x D x H: 35 x 22 x 35 in.

Weight: 190 lbs.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. hand sanitizers requested outside doors to room

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: 3D Printing **Department:** Rad-Onc Treatment

Room #: A007D

Room Notes: Assume 1-2 printers as new for now. 1 or 2 may be brought over as existing pending replacements

Hood, Canopy

AE #: HOCA-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Terra Universal	5015-14		Wall	OF/CI	Project

Wall mounted canopy hood: Unit discharge connects to in-house ventilation system and integral high-airflow baffle with filters conduct gas flow into the hood and away from the operator. Units are equipped with a 4 speed internal blower controlled by heavy-duty stainless steel mechanical rotating switches. See accessory for work bench. View Cutsheet 211733

W x D x H: 48 x 25 x 18 in.
Electrical: 120V 60Hz 6.7A 804W **Weight:** 80 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Solid SS work station	9603-03	1	1

Printer, 3D

AE #: PR3D-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	FormLabs	Form 4		Countertop	OF/OI	Project

Form 4 is a blazing fast masked SLA 3D printer that combines an industry-leading materials library, easy workflows, and a reliable, accurate print engine. View Cutsheet 211709

To be used for SLA printing, confirmed with Dr. Johnson Uses Medical grade resins from FormLabs such as BioMed White and BioMed Flex

W x D x H: 15.7 x 14.5 x 21.9 in.
Network: Wireless **Network Notes:** Wi-Fi (2.4 and 5 GHz; IEEE 802.11 b/g/n/ac, WPA/WPA2)
Ethernet (1000 Mbit)
USB-C 2.0
Electrical: 120V 60Hz 4.8A 480W **Weight:** 40.4 lbs.
Elect Notes: Power Requirements: 100–240 VAC, 4.8 A, 50/60 Hz, 480 W. A UPS may be needed depending on use.

Room: 3D Printing **Department: Rad-Onc Treatment**

Room #: A007D

Room Notes: Assume 1-2 printers as new for now. 1 or 2 may be brought over as existing pending replacements

Printer, 3D — AE #: PR3D-01E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lulzbot	TAZ ProS		Countertop	EX/OI	Project

Industrial desktop 3D printer that provides large, 1.75mm material printing. Create large functional prototypes, manufacturing aids, and print-on-demand parts with easy, professional results. View Cutsheet 211708

Current model being used for FDM printing, confirmed with Dr. Johnson. This model will likely be replaced before new CC opens, and may be existing

Occasionally print with ABS or POM**

W x D x H: 32.8 x 26.1 x 20.5 in.

Network Notes: USB Serial and USB Flash Drive

Electrical: 120V 60Hz 21A 500W

Elect Notes: Power Requirements: 100VAC - 240VAC. Output: 24 volt DC, 500 watts, 21 amps
Power Supply: Auto-switching MEAN WELL RSP-500-24. Connectivity: USB Serial and USB Flash Drive

Printer, 3D — AE #: PR3D-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lulzbot	TAZ Pro Long Bed		Countertop	OF/OI	Project

3D Printing Technology FDM / FFF (Fused Filament Fabrication). This advanced machine features a Y-axis over twice the size for optimal layer continuity and a factory 1.2mm nozzle Tool Head for robust parts quickly. Large build platform: 11.10 x 22.91 x 11.22 inches. View Cutsheet 211762

W x D x H: 15 x 53 x 24 in.

Electrical: 240V 7A 500W

Elect Notes: Power Supply: 500W 24V Mean Well, Auto-Switching
Power Input: 100VAC-240VAC

Room: 3D Printing **Department: Rad-Onc Treatment**

Room #: A007D

Room Notes: Assume 1-2 printers as new for now. 1 or 2 may be brought over as existing pending replacements

Printer, 3D, Cure

AE #: CURE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	FormLabs	Form Cure		Hood	OF/OI	Project

The Form Cure provides the light and heat necessary to post-cure 3D printed parts to their optimal properties. The final performance characteristics of cured photopolymer resin may vary according to your compliance with the instructions for use, application, operating conditions, material combined with, end use, or other factors. View Cutsheet 211710

To sit on workbench under canopy hood

W x D x H: 10.3 x 10.3 x 13.4 in. **Clearance:** Top 12 in.
Network: Wireless
Electrical: 120V 60Hz 6A 144W **Weight:** 12.4 lbs.
Elect Notes: Power Requirements: 100–240 V ~, 6.0 A, 50/60 Hz, 144 W

Printer, 3D, Washer

AE #: WASH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	FormLabs	Form Wash		Hood	OF/OI	Project

Form Wash automatically cleans printed parts thoroughly and efficiently with IPA or alternative solvents. Keep parts directly on the Build Platform as you transition them from the printer to Form Wash, or remove parts and place them in the wash basket. Parts are precisely and thoroughly agitated in solvent with an impeller, getting every nook and cranny perfectly clean, automatically for the appropriate time. When washing completes, the Form Wash automatically raises parts out of the IPA so they can air dry. View Cutsheet 211705

To sit on workbench under canopy hood

W x D x H: 12.4 x 11.5 x 15.9 in. **Clearance:** Top 12.2 in.
Electrical: 120V 60Hz 50W **Weight:** 18.9 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Office, Shared

Department: Rad-Onc Treatment

Room #: A007E

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Dosimetry **Department:** Rad-Onc Treatment

Room #: A008A

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Dosimetry Office

Department: Rad-Onc Treatment

Room #: A008A1, A008A2

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Physicist Work Area

Department: Rad-Onc Treatment

Room #: A008C

Room Notes: Assumes space for 4 people

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Hot Lab

Department: Rad-Onc Treatment

Room #: A008D

Cabinet, Lead Lined, Preparation Enclosure

AE #: CLPE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	244-190		Floor	OF/CI	Project

This Cabinet is designed to support the Lead-Lined Preparation Enclosure. Full height, overlapping double doors with key locks open to an adjustable shelf with a 100 lb capacity. The cabinet may be used for decay and storage. 0.25" lead protection.

View Cutsheet 208707

W x D x H: 36.5 x 24 x 36.5 in.

Weight: 1063 lbs.

Cart, Transport

AE #: CATR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radiation Products Design, Inc.	950-100		Floor	EX/OI	Existing

Pig Cart with Two 4 1/8" Square Holes.

View Cutsheet 210490

Placeholder for existing Cesium Pig Transport Cart. Allow 2'x2'x4'

W x D x H: 16 x 22 x 45 in.

Check Source

AE #: CHSO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Spectrum Techniques	Cs-137		Cabinet	OF/OI	Project

BETA/Gamma Disk Sources. Disk sources are designed for use as reference sources in laboratories, radiation protection, training and education, security, and up-and-coming technology

View Cutsheet 209648

For Geiger Counters. Will sit in source holder mounted on Ludlum 26-3 meter survey

W x D x H: 2 x N/A x 0.13 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Hot Lab
Room #: A008D

Department: Rad-Onc Treatment

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dose Calibrator

AE #: DOCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	CRC-55TW	5130-2216	Countertop	OF/OI	Project

CRC-55TR Dose Calibrator and CAPRAC-T Wipe Test Well Counter; 28 programmable nuclide keys; Built-in dose calibration; 256 channel MCA; System comprised of:

View Cutsheet 122416

Touchscreen Display (8" color): 9"w x 10.5"d x 9.5"h, 120V, 7.5 lbs. with Epson Printer (120V)

Dose Calibrator (2.4"diameter x 10" d well): 7"w x 7"d x 17.25"h, 30 lbs. w/cable length 12'

Well Counter: 6"w x 6"w x 9.5"h, 15.5 lbs, w/cable length of 9'

Ionization Chamber: 12 atm Ultra-Pure Argon

Will also need a background shield

W x D x H: 6.76 x 6.76 x 17.3 in.
Network: Networked
Electrical: 120V 60Hz 0.1A **Weight:** 30 lbs.

Room: Hot Lab

Department: Rad-Onc Treatment

Room #: A008D

Dose Calibrator Syringe Reference Source Set

AE #: DCSR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	063-586		Cabinet	OF/OI	Project

Set includes: Co-57, 5 mCi; Cs-137, 200 Ci; Ba-133, 250 C. The daily calibration of dose calibrators is recommended to ensure accurate and reproducible instrument response. They are calibrated with ±5% accuracy at the 99% confidence level, NIST traceable.

View Cutsheet 210497

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Meter, Survey

AE #: MESU-26

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	26-3	48-4232	Countertop	OF/OI	Project

High-range frisker features standard 15.51 cm2 GM pancake detector, loud audible click output, and large auto-ranging LCD display with LCD backlighting. Water resistant housing. Used to frisk people and objects. Three modes of operation available: Rate, Max, and Count.

View Cutsheet 209460

See accessories for energy compensation filter and holder.

W x D x H: 2.7 x 10.7 x 1.8 in.

Weight: 1 lbs.

Elect Notes: Uses (2) standard AA batteries.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Dose energy compensation filter w/tether	4519-041-02	1	1
Sample Holder for M-26	47-3948	1	1

Room: Hot Lab

Department: Rad-Onc Treatment

Room #: A008D

Shield, Environmental Background

AE #: SHEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	7300-2450		Table	OF/OI	Project

Reduce background radiation more than 10 times with the environmental shield. Fitting any Capintec CRC dose calibrator with a remote ionization chamber, the shield consists of nine interlocking lead rings that surround the chamber. For use with dose calibrator. View Cutsheet 210496

W x D x H: 10.1 x N/A x 17.6 in.

Weight: 310 lbs.

Shield, L-Block with Cave

AE #: SLBC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MarShield Radiation Shieldling	MS-042-449, MS-042-426		Countertop	OF/OI	Project

L Block Shield with Adjustable Window. Calibrator Shield 2 in Thick. With Cave to provide lateral shielding around the full perimeter of the L-Block's base View Cutsheet 210339

W x D x H: 18 x 21.5 x 26 in.

Weight: 532 lbs.

Shielded Syringe Carrier

AE #: SHSC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	001-181, 0.125" small		Countertop	OF/OI	Project

Size small, 0.125" Lead Shielded syringe carriers reduce exposure while storing or transporting radioactive material. The overlapping lid design with snap-latch closure prevents streaming. The ends of the carriers are double thick to reduce the exposure from the ends of syringes. View Cutsheet 210348

W x D x H: 9.25 x 3.4 x 2.6 in.

Weight: 7.5 lbs.

Shielded Syringe Carrier

AE #: SHSC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	001-179, 0.125" large		Countertop	OF/OI	Project

Size large, 0.125" Lead Shielded syringe carriers reduce exposure while storing or transporting radioactive material. The overlapping lid design with snap-latch closure prevents streaming. The ends of the carriers are double thick to reduce the exposure from the ends of syringes. View Cutsheet 210349

W x D x H: 9.5 x 4.4 x 3.5 in.

Weight: 11.3 lbs.

Room: Hot Lab

Department: Rad-Onc Treatment

Room #: A008D

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: MRI & CT Equipment

Department: Rad-Onc Treatment

Room #: A008E

Room Notes: Large equip that comes with imaging

Imaging, Mechanical Equipment

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	Multiple		Floor / Wall	OF/CI/VI	Project

Cabinets for MR Sim and Brachy room imaging systems — No Cutsheet 212906

Equipment for MR Sim A009H1 and Brachy A006K — Supplemental Info

Room: Resident Work Area **Department:** Rad-Onc Treatment

Room #: A008F

Room Notes: Seating for (8)

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: MRI Zone 3 (MR Sim) **Department: Rad-Onc Treatment**

Room #: A009H

Flowmeter, Non-Ferrous — AE #: FLNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Magmedix, Inc.	03-3-700AL		Wall	OF/OI	Project

Non-magnetic aluminum body oxygen flowmeter; color-coded to assure accurate gas i.d.; 0-15 lpm with flood. View Cutsheet 72534

W x D x H: 1 x 6 x 3.5 in.

Regulator, Suction, Non-Ferrous — AE #: RESU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Precision Medical, Inc.	PM3015MRT		Wall	OF/OI	Project

Non-ferrous continuous suction regulator 0-200mmhg and 'full vacuum' w/ ohmeda diamond quick connection View Cutsheet 172975

W x D x H: 3.5 x 4.8 x 10 in.

Room: MRI Simulator **Department:** Rad-Onc Treatment

Room #: A009H1

Allowance

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - Allowance				OF/CI/VI	Project

No Cutsheet 85682

Remaining MRI Sim equip

Supplemental Info

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	QA Equipment			OF/VI	Project

Allowance for QA equipment including phantoms

No Cutsheet 208897

Anesthesia Machine

AE #: ANMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	FABIUS MRI		Floor	OF/VI	Project

MRI compatible; LED alarm indicators; high resolution color display; vapor 2000 system; label 40 mtesla / 400 gauss- distance to mrt system during operation; e-vent; compact breathing system; three drawers; central brake with four wheels

View Cutsheet 104023

W x D x H: 39 x 35.5 x 55 in.
Electrical: 120V 60Hz **Weight:** 365 lbs.
Elect Notes: 70va
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.
Struct Notes: Wall backing may be required.

Room: MRI Simulator **Department:** Rad-Onc Treatment

Room #: A009H1

Board, Transfer, Accessory, MR Safe

AE #: BTAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Magmedix, Inc.	03-PTB-HGR		Wall	OF/CI	Project

MRI safe hanger for transfer boards. Made of white HDPE (plastic). Comes with brass mounting screws. View Cutsheet 210611

W x D x H: 0.38 x 2.25 x 5 in.

Weight: 0.5 lbs.

Container, Sharps

AE #: CASC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/OI	Supply Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available. View Cutsheet 209938

Red, no dolly.

W x D x H: 11.5 x 16 x 16.5 in.

Detector, Ferromagnetic

AE #: DEFE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	ASSURE		Wall	OF/CI/VI	Project

Ferroguard assure is always wall mounted outside the MRI door in zone iii, rather than inside the door frame. This means no detection gaps or sensor activation delays even with outswing doors. Eye level traffic light display gives time to react to prevent an accident. A secondary audible alert gives additional warning if the visual early warning is ignored; dimensions are for each sensor View Cutsheet 164592

W x D x H: 3.1 x 3.5 x 53.9 in.

Network: Wired

Electrical: 110V 60Hz 1A **Weight:** 9.8 lbs.

Room: MRI Simulator **Department:** Rad-Onc Treatment

Room #: A009H1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Nitrous Oxide

AE #: FLNO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Porter Instrument	MXR 3000-OS		Wall	OF/CI	Project

The Porter MXR-3000 flowmeter is constructed with precision Porter glass flow tubes and ergonomic control valves for flow and percentage. An oxygen quick connect is conveniently located on the side of the meter. The 3000 package includes the MXR-3000 meter and a threaded bag tee. View Cutsheet 207990

W x D x H: 5 x 5.5 x 8.5 in.

Weight: 6 lbs.

Flowmeter, Non-Ferrous

AE #: FLNF-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Magmedix, Inc.	03-3-700AL-A		Wall	OF/OI	Project

Non-magnetic aluminum body air flowmeter; color-coded to assure accurate gas i.d.; 0-15 lpm with flood. View Cutsheet 90458

W x D x H: 2 x 3 x 6 in.

Flowmeter, Non-Ferrous

AE #: FLNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Magmedix, Inc.	03-3-700AL		Wall	OF/OI	Project

Non-magnetic aluminum body oxygen flowmeter; color-coded to assure accurate gas i.d.; 0-15 lpm with flood. View Cutsheet 72534

W x D x H: 1 x 6 x 3.5 in.

Room: MRI Simulator **Department:** Rad-Onc Treatment

Room #: A009H1

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Non-Ferrous — AE #: HANF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7772MR		Cabinet	OF/OI	Project

Round tubular ring that is seamlessly welded to three legs. Solid triangular platform protects bag from contact w/floor. No lid. View Cutsheet 129419

W x D x H: 18 x 18 x 35 in.

Imaging, MRI — AE #: IMMR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	MAGNETOM Free.Max 0.55T		Floor	OF/CI/VI	Project

Large bore, High-V, 0.55T MRI. Weight capacity 700lb View Cutsheet 209132

Include coil cart from Siemens. **Pricing from Siemens Package, quote #CPQ-900400-1** Supplemental Info

Network: Wired
Elect Notes: Refer to manufacturers site planning documentation
Plumb Notes: Refer to manufacturers site planning documentation
HVAC Notes: Refer to manufacturers site planning documentation
Struct Notes: Refer to manufacturers site planning documentation

Injector, Contrast Media — AE #: INCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	MRXPERION	BMRXP200	Floor	OF/CI/VI	Project

Mr injection system. Delivers contrast fluid and management. Floor pedestal includes integrated iv pole. Mrxperion penetration panel required if no shielded electrical outlet. View Cutsheet 158505

W x D x H: 23.3 x 23.3 x 71.4 in.

Network Notes: Control panels are networked but not the actual injector.

Electrical: 120V 60Hz 1A

Weight: 95.7 lbs.

Room: MRI Simulator **Department:** Rad-Onc Treatment

Room #: A009H1

Monitor, Physiological, Non-Ferrous

AE #: MOPH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iradimed Corporation	3880Q		Stand	OF/VI	Project

Lightweight, portable monitor has been meticulously engineered to meet the needs of today's complex MRI workflow. View Cutsheet 209190

W x D x H: 11.4 x 5 x 8.8 in.

Weight: 8.9 lbs.

Phantom, MRI

AE #: PHMR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Calimetrix	PDFF-R2* (725)		Cabinet	OF/OI	Project

The Calimetrix PDFF-R2* Phantom simultaneously controls PDFF and R2* in each vial. It is designed for testing and quality control of magnetic resonance (MR)-based fat and iron quantification; 16 Vials; Phantom vials are filled with gels to minimize motion-related artifacts; Asymmetrically positioned vials to avoid left-right and superior-inferior vial identification ambiguities; Doped fill solution to minimize water-fat swap artifacts View Cutsheet 209575

Per quote # QUOTE-536 dated 3/15/2024 from Calimetrix (Rachel Krause).

Pump, I.V., Non-Ferrous

AE #: PINF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	CONTINUUM MRIP		Stand	OF/OI	Project

Continuum mr i.v. System compatible with scanners up to and including 1.5t; allows placement of pump next to scanner bore; standard configuration includes dual channel pump with flow rate to 1200ml/hr; integrated 20-60ml syringe holder; bolus function with bolus weight and duration options; anti-bolus feature prevents delivery of false bolus after a downstream occlusion is detected View Cutsheet 76044

W x D x H: 3.5 x 1.6 x 4.5 in.
Electrical: 120V 60Hz 0.12A
Elect Notes: Battery operated; charger included

Regulator, Suction, Non-Ferrous

AE #: RESU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Precision Medical, Inc.	PM3015MRT		Wall	OF/OI	Project

Non-ferrous continuous suction regulator 0-200mmhg and 'full vacuum' w/ ohmeda diamond quick connection View Cutsheet 172975

W x D x H: 3.5 x 4.8 x 10 in.

Room: MRI Simulator **Department:** Rad-Onc Treatment

Room #: A009H1

Stand, IV, MRI

AE #: STIM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7792MR-2	0537792002	Floor	OF/OI	Project

5 Leg MR compatible IV stand with a stainless steel pole and stand at a 24" diameter. Height adjusts from 74" to 110". Comes with 2 removable hooks View Cutsheet 208728

W x D x H: 24 x 24 x 110 in.

Stand, Mayo, Non-Ferrous

AE #: STMN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	8841MR		Floor	OF/OI	Project

Mayo stand - tray size: 12-5/8" x 19-1/8"; height adjust 39 1/2" x 62" and travels easily on two inch MR conditional casters. View Cutsheet 142257

W x D x H: 12.6 x 19.1 x 39.5 in.

Stool, Foot, With Handrail

AE #: STFH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7757MR-HR		Floor	OF/OI	Project

MR conditionally safe, step-stool with handrail; stainless steel construction. Height of step is 8". View Cutsheet 123939

W x D x H: 18 x 12 x 41 in.

Weight: 20 lbs.

Table, Instrument, Non-Ferrous

AE #: TINF-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7833MR		Floor	OF/OI	Project

MR conditional instrument table made of 18 gauge, 304 stainless steel with bottom shelf, 1 1/4" diameter legs with 2" MR casters. View Cutsheet 202603

W x D x H: 36 x 24 x 34 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: MRI Sim Control

Department: Rad-Onc Treatment

Room #: A009H2

Room Notes: Assumes space for 3 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Cart, Anesthesia

AE #: CAAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Harloff Company, Inc.	AP7D		Floor	OF/OI	Project

This MRI safe anesthesia cart is designed and engineered for use in 3 Tesla or less MRI suites. Comes with a unique anesthesia accessory package made up of items constructed from non or “weakly magnetic” materials. The anesthesia accessory package includes a 3-tier aluminum raised back rail system, four aluminum siderails, two plastic drawer trays and a set of organizers for each tray. Drawer configuration: (1) - 4", (4) - 3.25", (1) - 6.5", (1) - 9.75"

View Cutsheet 207987

Discuss with Anesthesia

W x D x H: 31.8 x 23.8 x 46 in.

Weight: 127 lbs.

Detector, Ferromagnetic, Handheld

AE #: DEFH-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kopp Development Inc	Eagle Target Scanner		Wall	OF/CI	Project

Handheld ferromagnetic detection system. Wall holder 5"W x 3.5"D x 12"H. Desktop 2-bay battery charger included.

View Cutsheet 210983

W x D x H: 3.5 x 2.3 x 15 in.

Weight: 1.94 lbs.

Room: MRI Sim Control

Department: Rad-Onc Treatment

Room #: A009H2

Room Notes: Assumes space for 3 people

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Imaging, Console

AE #: IMCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems			Countertop	OF/VI	Project

Control console for MRI

No Cutsheet 164950

Price included in cost of scanner

Electrical: 120V 60Hz

Room: MRI Sim Control **Department:** Rad-Onc Treatment

Room #: A009H2

Room Notes: Assumes space for 3 people

Injector, Control Panel — AE #: INCP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	MRXPERION		Countertop	OF/CI/VI	Project

Control room display — View Cutsheet 158506

W x D x H: 15.8 x 10.2 x 13.5 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 19.2 lbs.

Monitor, CCTV — AE #: MCCT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems			Wall	OF/VI	Project

Patient monitor to view patient in MRI scanner within the control room — No Cutsheet 206213

Price included with MRI

W x D x H: 13 x 8 x 12.5 in.
Electrical: 120V 60Hz **Weight:** 9 lbs.
Elect Notes: **Refer to manufacturer shop drawings.**
Struct Notes: **Refer to manufacturer shop drawings.**

Monitor, Physiological, Non-Ferrous, Component — AE #: MPNC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iradimed Corporation	3885B Wireless Control Room Base		Countertop	OF/CI/VI	Project

The Base Station is the control room communication hub that facilitates the printing and wireless communication through the MRI shielding between the Patient Monitor and the Tablet. The Remote Viewing Station allows for clinicians to oversee up to four patients on a single screen. — View Cutsheet 209238

W x D x H: 15 x 5 x 7.4 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 4.6 lbs.

Room: MRI Sim Control

Department: Rad-Onc Treatment

Room #: A009H2

Room Notes: Assumes space for 3 people

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Mobile Equipment (MRI Safe) **Department:** Rad-Onc Treatment

Room #: A009H3

Room Notes: Zone 3

Cart, Cylinder, Medical Gas, Non-Ferrous

AE #: MGNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIequip.com	OX-4501		Floor	OF/OI	Project

Mri compatible single e-cylinder tank cart — View Cutsheet 165314

Cylinder to be provided by med gas vendor per Melinda Chapman

W x D x H: 12 x 10 x 41 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
MRI Click Style Regulator 1/4 to 25 LPM	OX-4502	1	1
MRI Oxygen Cylinder Wrench	OX-103X	1	1

Rack, Gas Cylinder Storage

AE #: RGCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIequip.com	OX-1050		Floor	OF/OI	Project

Mri non-magnetic 6-tank oxygen stand; holds d or e size tanks; all aluminum construction. View Cutsheet 142149

W x D x H: 15 x 10.3 x 16 in.

Weight: 7 lbs.

Stretcher, Non-Ferrous, Bariatric

AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety. View Cutsheet 210322

MR conditional to 3T. Optional IV pole available.

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Wheelchair, MRI

AE #: WHMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Staxi Corporation	MRI		Floor	OF/VI	Project

MRI Wheelchair, 600lb weight capacity. Non removable foot rests. Five inch casters. View Cutsheet 204144

W x D x H: 31 x 33 x 41 in.

Room: MRI Vestibule (MR Sim) **Department:** Rad-Onc Treatment

Room #: A009H4

Detector, Ferromagnetic

AE #: DEFE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	Ultra		Wall	OF/CI/VI	Project

The most advanced, efficient, and flexible ferromagnetic threat detection system—versatile enough to implement in a huge variety of places and spaces so you can keep your people, property, and sensitive information safe. Can be wall-mounted, or used with the portable, freestanding base. Width is for the floor base. Wall mounted width is 4.9"

View Cutsheet 209310

Door way from Corridor to Zone 3

W x D x H: 17.4 x 6.3 x 72.3 in.
Network: Wired
Electrical: 120V 60Hz 1.3A **Weight:** 46 lbs.

Room: Linac Equipment

Department: Rad-Onc Treatment

Room #: CSA00H

Room Notes: Need guidance on MEQ

Room: Linac Power Conditioner

Department: Rad-Onc Treatment

Room #: CSA00J

Room Notes: Need guidance on MEQ

Room: CT / MR Radiologist Work Room (Neuro Reading) **Department: Imaging (1st Floor)**

Room #: A108J

Room Notes: Assumes Diagnostic grade PACS are to be carried in IT scope. Height adjustable tables to be carried in furniture scope. 4 workstations.

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883552		Floor	OF/OI	Project

Slim jim step-on 90l/24 gal resin front waste container. Quiet, controlled lid closure minimizes noise. Internal hinge design to prevent wall damage. View Cutsheet 148391

Factory mutual certified ensures fire safety. Meets osha and obra standards for worker and environmental safety. Color: beige.

other available colors include: yellow, green, black, red, white, blue and gray.

W x D x H: 22.4 x 13.9 x 32.5 in.

Clearance: Top 13.9 in.

Weight: 16.8 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: MRI Zone 3 / Med Alcove

Department: Imaging (1st Floor)

Room #: A109

Detector, Ferromagnetic

AE #: DEFE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	Ultra		Wall	OF/CI/VI	Project

The most advanced, efficient, and flexible ferromagnetic threat detection system—versatile enough to implement in a huge variety of places and spaces so you can keep your people, property, and sensitive information safe. Can be wall-mounted, or used with the portable, freestanding base. Width is for the floor base. Wall mounted width is 4.9"

View Cutsheet 209310

On wall from corridor to MRI Zone 3

W x D x H: 17.4 x 6.3 x 72.3 in.
Network: Wired
Electrical: 120V 60Hz 1.3A **Weight:** 46 lbs.

Detector, Ferromagnetic, Handheld

AE #: DEFH-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kopp Development Inc	Eagle Target Scanner		Wall	OF/CI	Project

Handheld ferromagnetic detection system. Wall holder 5"W x 3.5"D x 12"H. Desktop 2-bay battery charger included.

View Cutsheet 210983

W x D x H: 3.5 x 2.3 x 15 in.
Weight: 1.94 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: MRI Zone 3 / Med Alcove

Department: Imaging (1st Floor)

Room #: A109

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit

View Cutsheet 150404

Include Emily Woods in discussion regarding drawer configuration closer to procurement

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A
Elect Notes: Must be located within 6' of the electrical outlet. Fuse: 6.3a. Power and data connections are made to frames at the back right of the computer (53-57" a.f.f.). Power cord length is 15'.
HVAC Notes: 200-600 btu/hr.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: MRI Scan 3T **Department:** Imaging (1st Floor)

Room #: A109A

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory, MR Safe

AE #: BTAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Magmedix, Inc.	03-PTB-HGR		Wall	OF/CI	Project

MRI safe hanger for transfer boards. Made of white HDPE (plastic). Comes with brass mounting screws.

View Cutsheet 210611

W x D x H: 0.38 x 2.25 x 5 in.

Weight: 0.5 lbs.

Cart, Coil

AE #: CACO-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	TBD		Floor	OF/VI	Project

Provided by Siemens. Specs to be determined. Dimensions approximated for space planning.

No Cutsheet 211055

W x D x H: 36 x 24 x 40 in.

Container, Sharps

AE #: CASC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/OI	Supply Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available.

View Cutsheet 209938

Red, no dolly.

W x D x H: 11.5 x 16 x 16.5 in.

Room: MRI Scan 3T **Department:** Imaging (1st Floor)

Room #: A109A

Detector, Ferromagnetic

AE #: DEFE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	ASSURE		Wall	OF/CI/VI	Project

Ferroguard assure is always wall mounted outside the MRI door in zone iii, rather than inside the door frame. This means no detection gaps or sensor activation delays even with outswing doors. Eye level traffic light display gives time to react to prevent an accident. A secondary audible alert gives additional warning if the visual early warning is ignored; dimensions are for each sensor

View Cutsheet 164592

W x D x H: 3.1 x 3.5 x 53.9 in.
Network: Wired
Electrical: 110V 60Hz 1A **Weight:** 9.8 lbs.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Non-Ferrous

AE #: FLNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Magmedix, Inc.	03-3-700AL		Wall	OF/OI	Project

Non-magnetic aluminum body oxygen flowmeter; color-coded to assure accurate gas i.d.; 0-15 lpm with flood.

View Cutsheet 72534

W x D x H: 1 x 6 x 3.5 in.

Room: MRI Scan 3T **Department:** Imaging (1st Floor)

Room #: A109A

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Non-Ferrous

AE #: HANF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7772MR		Cabinet	OF/OI	Project

Round tubular ring that is seamlessly welded to three legs. Solid triangular platform protects bag from contact w/floor. No lid. View Cutsheet 129419

W x D x H: 18 x 18 x 35 in.

Imaging, MRI

AE #: ISMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	MAGNETOM VIDA 3.0T		Floor	OF/CI/VI	Project

3.0t magnetom vida mri; coil package includes biomatrix body 18 together with the standard coil package; also includes tx/rx cp head coil #sk; View Cutsheet 170230

head/neck 64 w/ coilshim #vi; tx/rx knee 18#vi; shoulder shape 16 #vi; hand/wrist 16 #sk; foot/ankle 16 #sk; **see quotation for additional details**

Pricing from Executive Agreement, 6/27/2024, quote #CPQ-988732-0 Supplemental Info

Network: Wired
Elect Notes: Refer to manufacturers site planning documentation
Plumb Notes: Refer to manufacturers site planning documentation
HVAC Notes: Refer to manufacturers site planning documentation
Struct Notes: Refer to manufacturers site planning documentation

Room: MRI Scan 3T **Department:** Imaging (1st Floor)

Room #: A109A

Injector, Contrast Media

AE #: INCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	MRXPERION	BMRXP200	Floor	OF/CI/VI	Project

Mr injection system. Delivers contrast fluid and management. Floor pedestal includes integrated iv pole. Mrxperion penetration panel required if no shielded electrical outlet. View Cutsheet 158505

W x D x H: 23.3 x 23.3 x 71.4 in.

Network Notes: Control panels are networked but not the actual injector.

Electrical: 120V 60Hz 1A **Weight:** 95.7 lbs.

Monitor, Physiological, Non-Ferrous

AE #: MOPH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iradimed Corporation	3880Q		Stand	OF/VI	Project

Lightweight, portable monitor has been meticulously engineered to meet the needs of today's complex MRI workflow. View Cutsheet 209190

W x D x H: 11.4 x 5 x 8.8 in.

Weight: 8.9 lbs.

Phantom, MRI

AE #: PHMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Diagnomatic	Pro-MRI ACR Medium	09-301	Cabinet	OF/OI	Project

ACR accredited Medium MRI phantom for comprehensive evaluation of critical imaging parameters of magnetic resonance imaging (MRI); It can be used to measure geometric distortion, spatial resolution, slice thickness and position, interslice Gap, image bandwidth, low contrast detectability, image uniformity, signal-to-noise ratio (SNR), physical and electronic slice offset, point of reference, bandwidth: water-fat shift View Cutsheet 209559

W x D x H: 7 x 7 x 6 in.

Regulator, Suction, Non-Ferrous

AE #: RESU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Precision Medical, Inc.	PM3015MRT		Wall	OF/OI	Project

Non-ferrous continuous suction regulator 0-200mmhg and 'full vacuum' w/ ohmeda diamond quick connection View Cutsheet 172975

W x D x H: 3.5 x 4.8 x 10 in.

Room: MRI Scan 3T

Department: Imaging (1st Floor)

Room #: A109A

Stand, IV, MRI

AE #: STIM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7792MR-2	0537792002	Floor	OF/OI	Project

5 Leg MR compatible IV stand with a stainless steel pole and stand at a 24" diameter. Height adjusts from 74" to 110". Comes with 2 removable hooks

View Cutsheet 208728

W x D x H: 24 x 24 x 110 in.

Stand, Mayo, Non-Ferrous

AE #: STMN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	8841MR		Floor	OF/OI	Project

Mayo stand - tray size: 12-5/8" x 19-1/8"; height adjust 39 1/2" x 62" and travels easily on two inch MR conditional casters.

View Cutsheet 142257

W x D x H: 12.6 x 19.1 x 39.5 in.

Stool, Foot, With Handrail

AE #: STFH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7757MR-HR		Floor	OF/OI	Project

MR conditionally safe, step-stool with handrail; stainless steel construction. Height of step is 8".

View Cutsheet 123939

W x D x H: 18 x 12 x 41 in.

Weight: 20 lbs.

Training, Clinical

AE #: TRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems				OF/VI	Project

No Cutsheet 128955

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: MRI Scan 3T

Department: Imaging (1st Floor)

Room #: A109A

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height

View Cutsheet 172941

Blue - Recycling. **NO DOLLY**

W x D x H: 22 x 22 x 33.8 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 200448

For contrast bottles

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: MRI Control **Department:** Imaging (1st Floor)

Room #: A109A1, A109B1

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Imaging, Console — AE #: IMCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems			Countertop	OF/VI	Project

Control console for MRI No Cutsheet 164950

Price included in cost of scanner

Electrical: 120V 60Hz

Injector, Control Panel — AE #: INCP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	MRXPERION		Countertop	OF/CI/VI	Project

Control room display View Cutsheet 158506

W x D x H: 15.8 x 10.2 x 13.5 in.

Network: Wired

Electrical: 120V 60Hz

Weight: 19.2 lbs.

Room: MRI Control **Department: Imaging (1st Floor)**

Room #: A109A1, A109B1

Monitor, CCTV — AE #: MCCT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems			Wall	OF/VI	Project

Patient monitor to view patient in MRI scanner within the control room — No Cutsheet 206213

Price included with MRI

W x D x H: 13 x 8 x 12.5 in.
Electrical: 120V 60Hz **Weight:** 9 lbs.
Elect Notes: **Refer to manufacturer shop drawings.**
Struct Notes: **Refer to manufacturer shop drawings.**

Monitor, Physiological, Non-Ferrous, Component — AE #: MPNC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iradimed Corporation	3885B Wireless Control Room Base		Countertop	OF/CI/VI	Project

The Base Station is the control room communication hub that facilitates the printing and wireless communication through the MRI shielding between the Patient Monitor and the Tablet. The Remote Viewing Station allows for clinicians to oversee up to four patients on a single screen. — View Cutsheet 209238

W x D x H: 15 x 5 x 7.4 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 4.6 lbs.

Waste Container — AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents — View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Breast Biopsy Equip **Department:** Imaging (1st Floor)

Room #: A109A2

Breast Biopsy System

AE #: BRBS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	ATEC Sapphire 100		Floor	OF/VI	Project

Vacuum assisted breast biopsy system with footswitch can be used in 3 modalities- ultrasound, MRI, stereotactic 2D and 3D image guided biopsy. View Cutsheet 202595

W x D x H: 25 x 21 x 37 in.
Electrical: 115V 60Hz 11A **Weight:** 110 lbs.
Elect Notes: Hospital grade power cord is 15 ft long

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.
HVAC Notes: 1604 BTU/hr

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Mobile Equipment (MRI-Safe) **Department:** Imaging (1st Floor)

Room #: A109A3

Room Notes: Some equipment located in Breast Biopsy alcove across hall

Anesthesia Machine

AE #: ANMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	FABIUS MRI		Floor	OF/VI	Project

MRI compatible; LED alarm indicators; high resolution color display; vapor 2000 system; label 40 mtesla / 400 gauss- distance to mrt system during operation; e-vent; compact breathing system; three drawers; central brake with four wheels

View Cutsheet 104023

W x D x H: 39 x 35.5 x 55 in.
Electrical: 120V 60Hz **Weight:** 365 lbs.
Elect Notes: 70va
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Cart, Cylinder, Medical Gas, Non-Ferrous

AE #: MGNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	MRIequip.com	OX-4501		Floor	OF/OI	Project

Mri compatible single e-cylinder tank cart

View Cutsheet 165314

Cylinder to be provided by med gas vendor per Melinda Chapman

W x D x H: 12 x 10 x 41 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
MRI Click Style Regulator 1/4 to 25 LPM	OX-4502	1	4
MRI Oxygen Cylinder Wrench	OX-103X	1	4

Cart, Utility, Non-Ferrous

AE #: CUNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	MRIequip.com	MRI Utility Cart 20"x25"		Floor	OF/OI	Project

PVC non-magnetic MRI utility cart with three 20" x 25" shelves. Each shelf has a 75-lb. weight capacity. Space between shelves = 12". Comes with 3" casters.

View Cutsheet 210612

W x D x H: 20 x 31.5 x 36 in.

Room: Mobile Equipment (MRI-Safe) **Department:** Imaging (1st Floor)

Room #: A109A3

Room Notes: Some equipment located in Breast Biopsy alcove across hall

Rack, Gas Cylinder Storage

AE #: RGCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	MRIequip.com	OX-1050		Floor	OF/OI	Project

Mri non-magnetic 6-tank oxygen stand; holds d or e size tanks; all aluminum construction. View Cutsheet 142149

(1) for Full, (1) for empty

W x D x H: 15 x 10.3 x 16 in.

Weight: 7 lbs.

Stretcher, Non-Ferrous, Bariatric

AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety. View Cutsheet 210322

MR conditional to 3T. Optional IV pole available.

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Wheelchair, MRI

AE #: WHMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Staxi Corporation	MRI		Floor	OF/VI	Project

MRI Wheelchair, 600lb weight capacity. Non removable foot rests. Five inch casters. View Cutsheet 204144

W x D x H: 31 x 33 x 41 in.

Room: MRI Scan 3T (Functional) **Department:** Imaging (1st Floor)

Room #: A109B

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory, MR Safe

AE #: BTAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Magmedix, Inc.	03-PTB-HGR		Wall	OF/CI	Project

MRI safe hanger for transfer boards. Made of white HDPE (plastic). Comes with brass mounting screws.

View Cutsheet 210611

W x D x H: 0.38 x 2.25 x 5 in.

Weight: 0.5 lbs.

Cart, Coil

AE #: CACO-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	TBD		Floor	OF/VI	Project

Provided by Siemens. Specs to be determined. Dimensions approximated for space planning.

No Cutsheet 211055

W x D x H: 36 x 24 x 40 in.

Container, Sharps

AE #: CASC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/OI	Supply Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available.

View Cutsheet 209938

Red, no dolly.

W x D x H: 11.5 x 16 x 16.5 in.

Room: MRI Scan 3T (Functional) **Department:** Imaging (1st Floor)

Room #: A109B

Detector, Ferromagnetic

AE #: DEFE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	ASSURE		Wall	OF/CI/VI	Project

Ferroguard assure is always wall mounted outside the MRI door in zone iii, rather than inside the door frame. This means no detection gaps or sensor activation delays even with outswing doors. Eye level traffic light display gives time to react to prevent an accident. A secondary audible alert gives additional warning if the visual early warning is ignored; dimensions are for each sensor

View Cutsheet 164592

W x D x H: 3.1 x 3.5 x 53.9 in.
Network: Wired
Electrical: 110V 60Hz 1A **Weight:** 9.8 lbs.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Non-Ferrous

AE #: FLNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Magmedix, Inc.	03-3-700AL		Wall	OF/OI	Project

Non-magnetic aluminum body oxygen flowmeter; color-coded to assure accurate gas i.d.; 0-15 lpm with flood.

View Cutsheet 72534

W x D x H: 1 x 6 x 3.5 in.

Room: MRI Scan 3T (Functional) **Department:** Imaging (1st Floor)

Room #: A109B

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Non-Ferrous — AE #: HANF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7772MR		Cabinet	OF/OI	Project

Round tubular ring that is seamlessly welded to three legs. Solid triangular platform protects bag from contact w/floor. No lid. View Cutsheet 129419

W x D x H: 18 x 18 x 35 in.

Imaging, MRI — AE #: ISMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	MAGNETOM VIDA 3.0T		Floor	OF/CI/VI	Project

3.0t magnetom vida mri; coil package includes biomatrix body 18 together with the standard coil package; also includes tx/rx cp head coil #sk; View Cutsheet 170230

head/neck 64 w/ coilshim #vi; tx/rx knee 18#vi; shoulder shape 16 #vi; hand/wrist 16 #sk; foot/ankle 16 #sk; **see quotation for additional details**

Functional MRI capability to include a flat screen on mobile stand and another monitor for tech to see images that patient sees. Patient will have buttons Supplemental Info to push to respond to stimuli. Will need additional software, cables, conduits, data, and power. Siemens will provide through partnership with 3rd party vendor. **Pricing from Executive Agreement, 6/27/2024, quote #CPQ-1000732-0**

Network: Wired
Elect Notes: Refer to manufacturers site planning documentation
Plumb Notes: Refer to manufacturers site planning documentation
HVAC Notes: Refer to manufacturers site planning documentation
Struct Notes: Refer to manufacturers site planning documentation

Room: MRI Scan 3T (Functional) **Department:** Imaging (1st Floor)

Room #: A109B

Injector, Contrast Media

AE #: INCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	MRXPERION	BMRXP200	Floor	OF/CI/VI	Project

Mr injection system. Delivers contrast fluid and management. Floor pedestal includes integrated iv pole. Mrxperion penetration panel required if no shielded electrical outlet. View Cutsheet 158505

W x D x H: 23.3 x 23.3 x 71.4 in.

Network Notes: Control panels are networked but not the actual injector.

Electrical: 120V 60Hz 1A **Weight:** 95.7 lbs.

Monitor, Physiological, Non-Ferrous

AE #: MOPH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iradimed Corporation	3880Q		Stand	OF/VI	Project

Lightweight, portable monitor has been meticulously engineered to meet the needs of today’s complex MRI workflow. View Cutsheet 209190

W x D x H: 11.4 x 5 x 8.8 in.

Weight: 8.9 lbs.

Phantom, MRI

AE #: PHMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Diagnomatic	Pro-MRI ACR Medium	09-301	Cabinet	OF/OI	Project

ACR accredited Medium MRI phantom for comprehensive evaluation of critical imaging parameters of magnetic resonance imaging (MRI); It can be used to measure geometric distortion, spatial resolution, slice thickness and position, interslice Gap, image bandwidth, low contrast detectability, image uniformity, signal-to-noise ratio (SNR), physical and electronic slice offset, point of reference, bandwidth: water-fat shift View Cutsheet 209559

W x D x H: 7 x 7 x 6 in.

Regulator, Suction, Non-Ferrous

AE #: RESU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Precision Medical, Inc.	PM3015MRT		Wall	OF/OI	Project

Non-ferrous continuous suction regulator 0-200mmhg and 'full vacuum' w/ ohmeda diamond quick connection View Cutsheet 172975

W x D x H: 3.5 x 4.8 x 10 in.

Room: MRI Scan 3T (Functional) **Department:** Imaging (1st Floor)

Room #: A109B

Stand, IV, MRI — AE #: STIM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7792MR-2	0537792002	Floor	OF/OI	Project

5 Leg MR compatible IV stand with a stainless steel pole and stand at a 24" diameter. Height adjusts from 74" to 110". Comes with 2 removable hooks View Cutsheet 208728

W x D x H: 24 x 24 x 110 in.

Stand, Mayo, Non-Ferrous — AE #: STMN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	8841MR		Floor	OF/OI	Project

Mayo stand - tray size: 12-5/8" x 19-1/8"; height adjust 39 1/2" x 62" and travels easily on two inch MR conditional casters. View Cutsheet 142257

W x D x H: 12.6 x 19.1 x 39.5 in.

Stool, Foot, With Handrail — AE #: STFH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7757MR-HR		Floor	OF/OI	Project

MR conditionally safe, step-stool with handrail; stainless steel construction. Height of step is 8". View Cutsheet 123939

W x D x H: 18 x 12 x 41 in.

Weight: 20 lbs.

Training, Clinical — AE #: TRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems				OF/VI	Project

No Cutsheet 128955

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: MRI Scan 3T (Functional)

Department: Imaging (1st Floor)

Room #: A109B

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height

View Cutsheet 172941

Blue - Recycling. **NO DOLLY**

W x D x H: 22 x 22 x 33.8 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 200448

For contrast bottles

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: MRI Scan 1.5T (Breast) **Department:** Imaging (1st Floor)

Room #: A109D

Room Notes: Plan for breast coils

Board, Transfer — AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory, MR Safe — AE #: BTAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Magmedix, Inc.	03-PTB-HGR		Wall	OF/CI	Project

MRI safe hanger for transfer boards. Made of white HDPE (plastic). Comes with brass mounting screws. View Cutsheet 210611

W x D x H: 0.38 x 2.25 x 5 in.

Weight: 0.5 lbs.

Cart, Coil — AE #: CACO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Imaging	Invivo Sentinelle Companion Cart		Floor	OF/VI	Project

The Sentinelle Accessory Cart is a great way to store your coil and associated padding when not in use. When it comes time to use the coil again, the cart provides an easy View Cutsheet 210457

way to transfer the coil onto the MR gantry. Designed for use in up to 3T environments.

W x D x H: 42.1 x 25.4 x 35.3 in.

Cart, Storage MRI Coil — AE #: CSMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	E8011M		Floor	OF/OI	Project

MR coil storage cart. Features: Holds 6 or more coils. Validated for up to 3T. Holds CTL, NV, brain, extremity, body and shoulder coils. Four swiveling locking casters. View Cutsheet 208877

Is this cart needed. Casework in room for storing coils.

W x D x H: 32 x 48 x 41 in.

Weight: 130 lbs.

Room: MRI Scan 1.5T (Breast) **Department:** Imaging (1st Floor)

Room #: A109D

Room Notes: Plan for breast coils

Coil, Breast

AE #: COBS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Invivo International	Sentinelle		Cart	OF/VI	Project

The 2/10/16-channel Sentinelle Breast Coil can be used as an breast imaging coil, a bilateral biopsy coil as well as an unilateral biopsy coil providing large biopsy access. View Cutsheet 210285

Cost included with scanner

W x D x H: 43.2 x 22.1 x 11 in.

Container, Sharps

AE #: CASC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/OI	Supply Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available. View Cutsheet 209938

Red, no dolly.

W x D x H: 11.5 x 16 x 16.5 in.

Detector, Ferromagnetic

AE #: DEFE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	ASSURE		Wall	OF/CI/VI	Project

Ferroguard assure is always wall mounted outside the MRI door in zone iii, rather than inside the door frame. This means no detection gaps or sensor activation delays even with outswing doors. Eye level traffic light display gives time to react to prevent an accident. A secondary audible alert gives additional warning if the visual early warning is ignored; dimensions are for each sensor View Cutsheet 164592

W x D x H: 3.1 x 3.5 x 53.9 in.
Network: Wired
Electrical: 110V 60Hz 1A **Weight:** 9.8 lbs.

Room: MRI Scan 1.5T (Breast) **Department:** Imaging (1st Floor)

Room #: A109D

Room Notes: Plan for breast coils

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

1 in room, 1 just outside room. Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Non-Ferrous

AE #: FLNF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Magmedix, Inc.	03-3-700AL		Wall	OF/OI	Project

Non-magnetic aluminum body oxygen flowmeter; color-coded to assure accurate gas i.d.; 0-15 lpm with flood. View Cutsheet 72534

W x D x H: 1 x 6 x 3.5 in.

Flowmeter, Non-Ferrous

AE #: FLNF-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Magmedix, Inc.	03-3-700AL-A		Wall	OF/OI	Project

Non-magnetic aluminum body air flowmeter; color-coded to assure accurate gas i.d.; 0-15 lpm with flood. View Cutsheet 90458

W x D x H: 2 x 3 x 6 in.

Room: MRI Scan 1.5T (Breast) **Department:** Imaging (1st Floor)

Room #: A109D

Room Notes: Plan for breast coils

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Non-Ferrous — AE #: HANF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7772MR		Cabinet	OF/OI	Project

Round tubular ring that is seamlessly welded to three legs. Solid triangular platform protects bag from contact w/floor. No lid. View Cutsheet 129419

W x D x H: 18 x 18 x 35 in.

Imaging, MRI — AE #: IMMR-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	MAGNETOM SOLA		Floor	OF/CI/VI	Project

1.5T MRI. Option for un-dockable patient table available. 70cm open bore. The first 1.5T MRI system with BioMatrix Technology: automatically adjusts View Cutsheet 168155

to patient biovariability to overcome unwarranted variations in MRI examinations.

Pricing from Executive Agreement, 6/27/2024, quote #CPQ-988547-0 Supplemental Info

Network: Wired
Elect Notes: Refer to manufacturers site planning documentation
Plumb Notes: Refer to manufacturers site planning documentation
HVAC Notes: Refer to manufacturers site planning documentation
Struct Notes: Refer to manufacturers site planning documentation

Room: MRI Scan 1.5T (Breast) **Department:** Imaging (1st Floor)

Room #: A109D

Room Notes: Plan for breast coils

Injector, Contrast Media — AE #: INCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	MRXPERION	BMRXP200	Floor	OF/CI/VI	Project

Mr injection system. Delivers contrast fluid and management. Floor pedestal includes integrated iv pole. Mrxperion penetration panel required if no shielded electrical outlet. View Cutsheet 158505

W x D x H: 23.3 x 23.3 x 71.4 in.

Network Notes: Control panels are networked but not the actual injector.

Electrical: 120V 60Hz 1A **Weight:** 95.7 lbs.

Monitor, Physiological, Non-Ferrous — AE #: MOPH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iradimed Corporation	3880Q		Stand	OF/VI	Project

Lightweight, portable monitor has been meticulously engineered to meet the needs of today's complex MRI workflow. View Cutsheet 209190

W x D x H: 11.4 x 5 x 8.8 in.

Weight: 8.9 lbs.

Phantom, MRI — AE #: PHMR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Calimetrix	PDFF-R2* (725)		Cabinet	OF/OI	Project

The Calimetrix PDFF-R2* Phantom simultaneously controls PDFF and R2* in each vial. It is designed for testing and quality control of magnetic resonance (MR)-based fat and iron quantification; 16 Vials; Phantom vials are filled with gels to minimize motion-related artifacts; Asymmetrically positioned vials to avoid left-right and superior-inferior vial identification ambiguities; Doped fill solution to minimize water-fat swap artifacts View Cutsheet 209575

Per quote # QUOTE-536 dated 3/15/2024 from Calimetrix (Rachel Krause).

Room: MRI Scan 1.5T (Breast) **Department:** Imaging (1st Floor)

Room #: A109D

Room Notes: Plan for breast coils

Phantom, MRI — AE #: PHMR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Diagnomatic	Pro-MRI ACR Medium	09-301	Cabinet	OF/OI	Project

ACR accredited Medium MRI phantom for comprehensive evaluation of critical imaging parameters of magnetic resonance imaging (MRI); It can be used to measure geometric distortion, spatial resolution, slice thickness and position, interslice Gap, image bandwidth, low contrast detectability, image uniformity, signal-to-noise ratio (SNR), physical and electronic slice offset, point of reference, bandwidth: water-fat shift

View Cutsheet 209559

W x D x H: 7 x 7 x 6 in.

Regulator, Suction, Non-Ferrous — AE #: RESU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Precision Medical, Inc.	PM3015MRT		Wall	OF/OI	Project

Non-ferrous continuous suction regulator 0-200mmhg and 'full vacuum' w/ ohmeda diamond quick connection

View Cutsheet 172975

W x D x H: 3.5 x 4.8 x 10 in.

Stand, IV, MRI — AE #: STIM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7792MR-2	0537792002	Floor	OF/OI	Project

5 Leg MR compatible IV stand with a stainless steel pole and stand at a 24" diameter. Height adjusts from 74" to 110". Comes with 2 removable hooks

View Cutsheet 208728

W x D x H: 24 x 24 x 110 in.

Stand, Mayo, Non-Ferrous — AE #: STMN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	8841MR		Floor	OF/OI	Project

Mayo stand - tray size: 12-5/8" x 19-1/8"; height adjust 39 1/2" x 62" and travels easily on two inch MR conditional casters.

View Cutsheet 142257

W x D x H: 12.6 x 19.1 x 39.5 in.

Room: MRI Scan 1.5T (Breast) **Department:** Imaging (1st Floor)

Room #: A109D

Room Notes: Plan for breast coils

Stool, Foot, With Handrail — AE #: STFH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7757MR-HR		Floor	OF/OI	Project

MR conditionally safe, step-stool with handrail; stainless steel construction. Height of step is 8". View Cutsheet 123939

W x D x H: 18 x 12 x 41 in.

Weight: 20 lbs.

Training, Clinical — AE #: TRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems				OF/VI	Project

No Cutsheet 128955

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: MRI Control **Department:** Imaging (1st Floor)

Room #: A109E

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Detector, Ferromagnetic, Handheld — AE #: DEFH-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kopp Development Inc	Eagle Target Scanner		Wall	OF/CI	Project

Handheld ferromagnetic detection system. Wall holder 5"W x 3.5"D x 12"H. Desktop 2-bay battery charger included. View Cutsheet 210983

W x D x H: 3.5 x 2.3 x 15 in.

Weight: 1.94 lbs.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Imaging, Console — AE #: IMCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems			Countertop	OF/VI	Project

Control console for MRI No Cutsheet 164950

Price included in cost of scanner

Electrical: 120V 60Hz

Room: MRI Control **Department:** Imaging (1st Floor)

Room #: A109E

Injector, Control Panel — AE #: INCP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad, Inc.	MRXPERION		Countertop	OF/CI/VI	Project

Control room display — View Cutsheet 158506

W x D x H: 15.8 x 10.2 x 13.5 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 19.2 lbs.

Monitor, CCTV — AE #: MCCT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems			Wall	OF/VI	Project

Patient monitor to view patient in MRI scanner within the control room — No Cutsheet 206213

Price included with MRI

W x D x H: 13 x 8 x 12.5 in.
Electrical: 120V 60Hz **Weight:** 9 lbs.
Elect Notes: **Refer to manufacturer shop drawings.**
Struct Notes: **Refer to manufacturer shop drawings.**

Monitor, Physiological, Non-Ferrous, Component — AE #: MPNC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iradimed Corporation	3885B Wireless Control Room Base		Countertop	OF/CI/VI	Project

The Base Station is the control room communication hub that facilitates the printing and wireless communication through the MRI shielding between the Patient Monitor and the Tablet. The Remote Viewing Station allows for clinicians to oversee up to four patients on a single screen. — View Cutsheet 209238

W x D x H: 15 x 5 x 7.4 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 4.6 lbs.

Waste Container — AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents — View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: CT / MR Ferromagnetic Alcove / Corridor

Department: Imaging (1st Floor)

Room #: B101

Detector, Ferromagnetic

AE #: DEFE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrasens	Ultra		Wall	OF/CI/VI	Project

The most advanced, efficient, and flexible ferromagnetic threat detection system—versatile enough to implement in a huge variety of places and spaces so you can keep your people, property, and sensitive information safe. Can be wall-mounted, or used with the portable, freestanding base. Width is for the floor base. Wall mounted width is 4.9"

View Cutsheet 209310

W x D x H: 17.4 x 6.3 x 72.3 in.
Network: Wired
Electrical: 120V 60Hz 1.3A **Weight:** 46 lbs.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Toilet (Patient)

Department: Imaging (1st Floor)

Room #: B101A, B101L, B103B, B103K1, B103E2

Room Notes: (1) US, (2) X/F, (2) CT/MR

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Imaging (1st Floor)

Room #: B101A, B101L, B103B, B103K1, B103E2

Room Notes: (1) US, (2) X/F, (2) CT/MR

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: CT / MR Sub-Wait

Department: Imaging (1st Floor)

Room #: B101C, B101D

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. One dispenser needed by each door.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Alcove, Height / Weight **Department:** Imaging (1st Floor)

Room #: B101D2

Room Notes: Located in CT / MR by dressing rooms

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Scale, Wheelchair — AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Room: Alcove, Height / Weight **Department:** Imaging (1st Floor)

Room #: B101D2

Room Notes: Located in CT / MR by dressing rooms

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: CT / MR Dressing

Department: Imaging (1st Floor)

Room #: B101E, B101B, B101C2, B101C1

Room Notes: Assumes no MEQ. No linen hamper in these rooms

Room: CT / MR Private Wait

Department: Imaging (1st Floor)

Room #: B101F

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: MRI Prep (rec) **Department: Imaging (1st Floor)**

Room #: B101G

Room Notes: (7) Pt bays

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock with auto-locking feature

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: MRI Prep (rec) **Department:** Imaging (1st Floor)

Room #: B101G

Room Notes: (7) Pt bays

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: MRI Prep (rec) **Department:** Imaging (1st Floor)

Room #: B101G

Room Notes: (7) Pt bays

Hook, IV Wall

AE #: HOIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Novum Medical Products	IV WALL HOOK		Wall	OF/CI	Project

Stainless steel hook, 1/4" diameter, 16 guage powder coated white wall bracket, plastic cap fda complient, #10 screws (2) with board anchors are included

View Cutsheet 165573

W x D x H: 1.5 x 5 x 3 in.

Lab Analyzer, Electrolyte

AE #: LAAE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Abbott Labs / Point Of Care	I-STAT1		Countertop	OF/OI	Project

Handheld point-of-care testing device; includes docking station for downloading data and recharging device.

View Cutsheet 123820

W x D x H: 3 x 8 x 10 in.
Electrical: 120V 60Hz

Lab Analyzer, Electrolyte Downloader Kit

AE #: LAED-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Abbott Labs / Point Of Care	04P73-04		Countertop	OF/OI	Project

I-stat 1 downloader recharger kit

View Cutsheet 117000

W x D x H: 4.12 x 9.6 x 5 in.
Network: Wired
Electrical: 120V 60Hz 1.1A

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case

View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.
Network: Wireless
Network Notes: Connectivity: ir port, rj45 or usb

Room: MRI Prep (rec) **Department:** Imaging (1st Floor)

Room #: B101G

Room Notes: (7) Pt bays

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter — View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care. — View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.

Network Notes: Stand alone monitor, not connected to a central station

Electrical: 120V 60Hz

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. — View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Network: Wired

Room: MRI Prep (rec) **Department:** Imaging (1st Floor)

Room #: B101G

Room Notes: (7) Pt bays

Refrigerator, Undercounter, ADA Height

AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white. View Cutsheet 211261

For iSTAT supplies and nourishment

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.
HVAC Notes: Refrigerant R600a

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: MRI Prep (rec) **Department:** Imaging (1st Floor)

Room #: B101G

Room Notes: (7) Pt bays

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Stand, Mayo — AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stand, Monitor — AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department.

W x D x H: 20 x 20 x 24.5 in.

Room: MRI Prep (rec) **Department:** Imaging (1st Floor)

Room #: B101G

Room Notes: (7) Pt bays

Thermometer, Temporal — AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Wall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.
Elect Notes: Requires a 9-volt alkaline battery

Thermometer, Temporal, Wall Mount — AE #: TTWM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	134201		Wall	OF/CI	Project

Wall mount for Exergen TAT-5000 or TAT-5000S temporal thermometer. Includes mounting hardware. View Cutsheet 207661

W x D x H: 3 x 1 x 1 in.

Waste Container — AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: MRI Prep (rec) **Department:** Imaging (1st Floor)

Room #: B101G

Room Notes: (7) Pt bays

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

For contrast bottles

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: CT / MR Tech

Department: Imaging (1st Floor)

Room #: B101G1, B101R1

Room Notes: Space for (3)

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: MRI Prep (reg stretcher) **Department:** Imaging (1st Floor)

Room #: B101H, B101J

Room Notes: Cardiac Pts

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: MRI Prep (reg stretcher) **Department:** Imaging (1st Floor)

Room #: B101H, B101J

Room Notes: Cardiac Pts

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.

Network Notes: Stand alone monitor, not connected to a central station

Electrical: 120V 60Hz

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Room: MRI Prep (reg stretcher) **Department:** Imaging (1st Floor)

Room #: B101H, B101J

Room Notes: Cardiac Pts

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-900		Wall	OF/OI	Project

Push to set suction regulator View Cutsheet 208749

W x D x H: 2.8 x 4.8 x 6.5 in.

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: MRI Prep (reg stretcher) **Department:** Imaging (1st Floor)

Room #: B101H, B101J

Room Notes: Cardiac Pts

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department.

W x D x H: 20 x 20 x 24.5 in.

Room: MRI Prep (reg stretcher) **Department:** Imaging (1st Floor)

Room #: B101H, B101J

Room Notes: Cardiac Pts

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.
Weight: 25 lbs.

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Wall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.
Elect Notes: Requires a 9-volt alkaline battery

Room: MRI Prep (reg stretcher) **Department:** Imaging (1st Floor)

Room #: B101H, B101J

Room Notes: Cardiac Pts

Thermometer, Temporal, Wall Mount

AE #: TTWM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	134201		Wall	OF/CI	Project

Wall mount for Exergen TAT-5000 or TAT-5000S temporal thermometer. Includes mounting hardware. View Cutsheet 207661

W x D x H: 3 x 1 x 1 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Resuscitation / Holding

Department: Imaging (1st Floor)

Room #: B101K

Room Notes: Zone 2. By CT / MR suites, will be curtained off

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white.

View Cutsheet 152856

For suction and other misc. supplies

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W.

View Cutsheet 208699

To include a keypad lock with auto-locking feature

W x D x H: 27 x 18 x 33 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. To be placed across corridor by door to Anteroom.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208701

CO2, and N2O. All Flowmeters come with a standard 1/8

Room: Alcove, Resuscitation / Holding

Department: Imaging (1st Floor)

Room #: B101K

Room Notes: Zone 2. By CT / MR suites, will be curtained off

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.

Network Notes: Stand alone monitor, not connected to a central station

Electrical: 120V 60Hz

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Room: Alcove, Resuscitation / Holding

Department: Imaging (1st Floor)

Room #: B101K

Room Notes: Zone 2. By CT / MR suites, will be curtained off

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

660 lb capacity

Supplemental Info

Electrical: 115V 60Hz 2.5A

Regulator, Suction, Continuous & Intermittent

AE #: RESC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	8705-1251-900		Wall	OF/OI	Project

Push to set suction regulator

View Cutsheet 208749

Qty (2) confirmed

W x D x H: 2.8 x 4.8 x 6.5 in.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: Alcove, Resuscitation / Holding

Department: Imaging (1st Floor)

Room #: B101K

Room Notes: Zone 2. By CT / MR suites, will be curtained off

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops

View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stretcher, Non-Ferrous, Bariatric

AE #: SNFB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MRIMed	TR-148		Floor	OF/OI	Project

Bariatric Aluminum Non-magnetic stretcher boasts a 600 pound weight capacity and 12" fold down side rails for easy accessibility and patient safety.

View Cutsheet 210322

MR conditional to 3T. Optional IV pole available.

Include IV pole accessory

W x D x H: 24.5 x 73 x 29.5 in.

Room: Alcove, Resuscitation / Holding

Department: Imaging (1st Floor)

Room #: B101K

Room Notes: Zone 2. By CT / MR suites, will be curtained off

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Wall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Elect Notes: Requires a 9-volt alkaline battery

Thermometer, Temporal, Wall Mount

AE #: TTWM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	134201		Wall	OF/CI	Project

Wall mount for Exergen TAT-5000 or TAT-5000S temporal thermometer. Includes mounting hardware.

View Cutsheet 207661

W x D x H: 3 x 1 x 1 in.

Room: Mobile Equipment (Gen Dept) **Department:** Imaging (1st Floor)

Room #: B101L1

Room Notes: Located in CT / MR

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care. View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.

Network Notes: Stand alone monitor, not connected to a central station

Electrical: 120V 60Hz

Room: Mobile Equipment (Gen Dept) **Department:** Imaging (1st Floor)

Room #: B101L1

Room Notes: Located in CT / MR

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Mobile Equipment (Gen Dept) **Department:** Imaging (1st Floor)

Room #: B101L1

Room Notes: Located in CT / MR

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Ultrasound

AE #: ULTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Mindray Medical Usa Corp.	TE7 TOUCH ENABLED ULTRASOUND SYSTEM	121-001187-00	Stand	OF/VI	Project

Touch enabled ultrasound system for emergency medicine and critical care. 15" high resolution, anti-glare touchscreen. Three transducer connectors. Built-in wireless communications. Battery provides 2+ hours of continuous scanning. Cart includes storage bin, printer shelf, retractable cord and 11.4" of height adjustment. View Cutsheet 160925

For ultrasound guided peripheral IV insertion. Confirm transducers during procurement.

W x D x H: 21.1 x 24.4 x 61.3 in.

Electrical: 115V 60Hz 2A **Weight:** 110.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Umt-400 Mobile Trolley	0023E-PA00001	1	1

Room: Alcove, Crash Cart **Department:** Imaging (1st Floor)

Room #: B101L2

Room Notes: Located between CT & MR

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Alcove, Crash Cart

Department: Imaging (1st Floor)

Room #: B101L2

Room Notes: Located between CT & MR

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure

View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

3 pieces of lead per room (S, M, L), plus 1 XL to be shared between both CT rooms

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	4

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white.

View Cutsheet 152856

For suction supplies

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Struct Notes: Wall backing may be required.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Cart, Procedure

AE #: CAPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Basic Single Wide 7-Drawer	SXRS5110L	Floor	OF/VI	Project

Pre configured cart featuring 5" caster wheels, mechanical keylock, and 7 drawers. Color chosen when ordering. View Cutsheet 208764

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 22.7 x 24.9 x 41.7 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad- includes auto lock	SXRX412	1	1

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. (1) HS to go on wall in corridor/entry way

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging System, C.T. Scanner

AE #: ISCT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	NAEOTOM Alpha		Floor	OF/CI/VI	Project

The world's first photon-counting CT--offers high-resolution images at minimal dose, spectral information in every scan, and improved contrast at lower noise. The QuantaMax detector directly converts X-rays into an electrical signal, which is then used to create an image. Combining the high spatial resolution of the QuantaMax photon-counting detector with our Dual Source temporal resolution enables the visualization of fine details for increased diagnostic confidence.

View Cutsheet 210062

Pricing from Executive Agreement, 6/27/2024, quote #CPQ-987532-1

Supplemental Info

Network: Wired
Elect Notes: **Refer to Siemens site planning information.**
Plumb Notes: **Refer to Siemens site planning information.**
HVAC Notes: **Refer to Siemens site planning information.**
Struct Notes: **Refer to Siemens site planning information.**

Injector, Contrast Media

AE #: INCM-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad/Bayer Healthcare Services	Stellant FLEX		Ceiling	OF/CI/VI	Project

CT injection system with options for 150ml and 200ml syringe sizes. Also cleared for use with contrast enhanced mammography (CEM). System uses barcodes to determine syringe size, expiration date, and if the syringe has already been used.

View Cutsheet 205858

Place holder until decision made on Ulrich mobile injector (209987)

W x D x H: 12.1 x 9 x 14.5 in.

Network Notes: Control panels are networked but not the actual injector.

Electrical: 115V 60Hz 1.5A

Weight: 16.8 lbs.

Elect Notes: 300 volts-amps

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.

Network Notes: Stand alone monitor, not connected to a central station

Electrical: 120V 60Hz

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Phantom, CT

AE #: PHCT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	Mercury 4.0		Cabinet	OF/OI	Project

Mercury 4.0 Phantom Advanced CT Performance Assessment; Collect and analyze data for, Automatic Exposure Control, Noise Power Spectrum, Modulation Transfer Function, Task Transfer Function, Detectability (d'), Cone-beam artifacts, Superior-Inferior resolution; 5-tiered sections reflect canonical patient sizes, Includes a stand with a handle and leveling feet, and a wheeled case; Material - Polyethylene; Diameter - 16.0, 21.0, 26.0, 31.0, and 36.0 cm; Length - 52.0 cm

View Cutsheet 209553

W x D x H: 14 x 20.5 x 14 in.

Phantom, CT

AE #: PHCT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	CT ACR 464		Cabinet	OF/OI	Project

CT ACR 464 Phantom Multi-Modality CT Accreditation; enables comprehensive testing, including positioning and alignment accuracy, CT number accuracy, slice thickness, low contrast detectability, image resolution and uniformity, spatial resolution, and inter- and intra-plane distance measurement accuracy; Additional Accessories - Phantom Stand, Soft Case, RapidCHECK™ Image Analysis Software

View Cutsheet 209557

W x D x H: 7 x 8 x 8 in.

Phantom, CTDI

AE #: PHCT-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	468-BH / 468-BHP		Cabinet	OF/OI	Project

Computed Tomography Dose Index Phantom; Measure absorbed dose and monitor scanner output; Offered as a 2-piece (model 468-BH) or 3-piece (model 468-BHP) telescopic configuration, with each configuration consisting of nested modules, allowing to adapt to the desired size required by the protocol in use; Includes customized, water-tight hard case for easy transport & safe storage; Case includes built-in wedges for use as a phantom holder. Pricing is both 2-piece and 3-piece combined.

View Cutsheet 209555

W x D x H: 12.6 x 12.6 x 6 in.

Weight: 30.5 lbs.

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Phantom, Dynamic Cardiac

AE #: PHDC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	008C		Cabinet	OF/OI	Project

The CIRS Dynamic Cardiac Phantom is a precision instrument that simulates the realistic motion of an average human heart; It provides known, accurate and repeatable 3D motion of a solid heart model inside the tissue-equivalent thorax phantom; The Model 008C-01 rod is designed as a comprehensive image analysis tool for calcification detection, iodine contrast resolution and ECG signal gating.

View Cutsheet 209554

Positioning Device

AE #: PODE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924951		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Long. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205979

W x D x H: 9.75 x 24 x 6.75 in.

Positioning Device

AE #: PODE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924960		Cabinet	OF/OI	Project

Positioning flat bottom roll for lower body support. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205981

W x D x H: 8.5 x 14 x 4.25 in.

Positioning Device

AE #: PODE-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924954		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Regular. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205980

W x D x H: 9.5 x 14 x 6.5 in.

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Rack, Apron

AE #: RAAP-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf X-Ray Corporation	Penta 16410		Wall	OF/CI	Project

5 Apron

View Cutsheet 205923

W x D x H: 17 x 23.5 x 4.6 in.

Struct Notes: Wall backing required. Mounting screws not included.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks

View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops

View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Wall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Elect Notes: Requires a 9-volt alkaline battery

Room: CT

Department: Imaging (1st Floor)

Room #: B101M

Thermometer, Temporal, Wall Mount

AE #: TTWM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	134201		Wall	OF/CI	Project

Wall mount for Exergen TAT-5000 or TAT-5000S temporal thermometer. Includes mounting hardware. View Cutsheet 207661

W x D x H: 3 x 1 x 1 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling Can/ Bottle

AE #: WRCB-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	Project

Green slim jim recycling with venting channels; 23 gallon View Cutsheet 124391

(1) for Injector, (1) Saline bags

W x D x H: 11 x 22 x 30 in.

Room: CT Control **Department: Imaging (1st Floor)**

Room #: B101N

Room Notes: Shared control room for both CT scan rooms. Seating for (4). Include CT control monitors (2) plus PACs.

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Control Console

AE #: COCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems, Inc.	TBD		Countertop	OF/VI	Project

No Cutsheet 204327

Price included in cost of scanner

Network: Wired
Electrical: 120V 60Hz

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: CT Control **Department: Imaging (1st Floor)**

Room #: B101N

Room Notes: Shared control room for both CT scan rooms. Seating for (4). Include CT control monitors (2) plus PACs.

Drug Dispensing Unit — AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit — View Cutsheet 150404

Needed for contrast and medications, no refrigerator needed.

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A
Elect Notes: Must be located within 6' of the electrical outlet. Fuse: 6.3a. Power and data connections are made to frames at the back right of the computer (53-57" a.f.f.). Power cord length is 15'.
HVAC Notes: 200-600 btu/hr.

Drug Dispensing Unit, Auxiliary — AE #: DDUA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	PYXIS ES SINGLE COLUMN		Floor	OF/VI	Lease

Single column auxiliary with 4 doors. — View Cutsheet 150661

W x D x H: 31 x 28 x 79.5 in.
Electrical: 120V 60Hz 3A
Elect Notes: Powered via connection to main unit

Injector, Contrast Media, Component — AE #: INCM-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad/Bayer Healthcare Services	STELLANT D	SCT321	Countertop	OF/VI	Project

Certegra touchscreen workstation (10.2"wx15.8"dx13.5"h) with base unit (11"w x 8.8"d x 11.5"h); **see procedure room injector for funding** — View Cutsheet 162440

Place holder pending determination of injector manufacturer. May change to GE/ulrich INJECT CT Motion injector control panel (209988).

W x D x H: 15.8 x 10.2 x 13.5 in.
Network: Wired
Electrical: 120V 60Hz 2.5A **Weight:** 17.6 lbs.

Room: CT Control **Department:** Imaging (1st Floor)

Room #: B101N

Room Notes: Shared control room for both CT scan rooms. Seating for (4). Include CT control monitors (2) plus PACs.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Contrast Warmer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Warmer, Contrast

AE #: WACO-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Boekel Scientific	133001		Countertop	OF/OI	Project

Incubator only for contrast media with locking door, LCD temperature display, analog dial control, temperature probe compatible, pilot light indicates when heater is on, magnetic latch. Includes 2 shelves. Holds up to (10) 500 ml +PLUSPAK bulk packages of contrast media. Temperature range ambient +5-60 degrees C. View Cutsheet 210977

Requires temperature monitoring via Tridium system.

W x D x H: 13 x 14 x 16.3 in.
Electrical: 115V 60Hz **Weight:** 22 lbs.
HVAC Notes: Vent on top of cabinet for temperature probe.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: MRI Equip. (Generator / Cold Room)

Department: Imaging (1st Floor)

Room #: B101P, A108H, B101K1

Room Notes: Included in cost of MRI System. See typical drawings for space planning.

Room: CT Prep Bay (rec) **Department: Imaging (1st Floor)**

Room #: B101R

Room Notes: 6 bays

Cart, Procedure — AE #: CAPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Basic Single Wide 7-Drawer	SXRS5110L	Floor	OF/VI	Project

Pre configured cart featuring 5" caster wheels, mechanical keylock, and 7 drawers. Color chosen when ordering. View Cutsheet 208764

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 22.7 x 24.9 x 41.7 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad- includes auto lock	SXRX412	1	1

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: CT Prep Bay (rec)

Department: Imaging (1st Floor)

Room #: B101R

Room Notes: 6 bays

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: CT Prep Bay (rec)

Department: Imaging (1st Floor)

Room #: B101R

Room Notes: 6 bays

Hook, IV Wall

AE #: HOIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Novum Medical Products	IV WALL HOOK		Wall	OF/CI	Project

Stainless steel hook, 1/4" diameter, 16 guage powder coated white wall bracket, plastic cap fda complient, #10 screws (2) with board anchors are included

View Cutsheet 165573

W x D x H: 1.5 x 5 x 3 in.

Lab Analyzer, Electrolyte

AE #: LAAE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Abbott Labs / Point Of Care	I-STAT1		Countertop	OF/OI	Project

Handheld point-of-care testing device; includes docking station for downloading data and recharging device.

View Cutsheet 123820

W x D x H: 3 x 8 x 10 in.
Electrical: 120V 60Hz

Lab Analyzer, Electrolyte Downloader Kit

AE #: LAED-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Abbott Labs / Point Of Care	04P73-04		Countertop	OF/OI	Project

I-stat 1 downloader recharger kit

View Cutsheet 117000

W x D x H: 4.12 x 9.6 x 5 in.
Network: Wired
Electrical: 120V 60Hz 1.1A

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case

View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.
Network: Wireless
Network Notes: Connectivity: ir port, rj45 or usb

Room: CT Prep Bay (rec) **Department:** Imaging (1st Floor)

Room #: B101R

Room Notes: 6 bays

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter — View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care. — View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.

Network Notes: Stand alone monitor, not connected to a central station

Electrical: 120V 60Hz

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. — View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Network: Wired

Room: CT Prep Bay (rec)

Department: Imaging (1st Floor)

Room #: B101R

Room Notes: 6 bays

Refrigerator, Undercounter, ADA Height

AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white.

View Cutsheet 211261

One for iSTAT supplies and one for Nourishment

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A
Weight: 102 lbs.
HVAC Notes: Refrigerant R600a

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: CT Prep Bay (rec)

Department: Imaging (1st Floor)

Room #: B101R

Room Notes: 6 bays

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" Backless preferred by department. View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Room: CT Prep Bay (rec) **Department:** Imaging (1st Floor)

Room #: B101R

Room Notes: 6 bays

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 200448

For contrast bottles

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Ultrasound Corridor

Department: Imaging (1st Floor)

Room #: B103

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Registration / Scheduling **Department:** Imaging (1st Floor)

Room #: B103A

Room Notes: (1) reg, (1) sched workstation, (1) TBD. Keep space for Interp. by printer.

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

CD Burner

AE #: CDBU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Epson	Discproducer PP-100III	C11CH40001	Countertop	OF/OI	Project

CD burner for moderate production use. Input capacity: Speed mode up to 60 discs/hour at 1440 x 720 dpi, Quality mode up to 40 discs/hour at 1440 x 1440 dpi. It includes MicroPiezo® inkjet technology and six individual ink cartridges. View Cutsheet 206525

W x D x H: 14.8 x 18.3 x 19.4 in.

Electrical: 120V 60Hz 1A 52W **Weight:** 46.2 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Consult

Department: Imaging (1st Floor)

Room #: B103C

Room Notes: Located near CT / MR

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: XR / RF Corridor / Sub-Wait **Department: Imaging (1st Floor)**

Room #: B103D

Room Notes: Located in X-Ray/Fluoro

Cabinet, Warming

AE #: CAWA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7922TG		Countertop	OF/VI	Project

Single compartment warming cabinet with glass door; 9.02 cu. Ft. Capacity; 2 shelves; to be used for heating and storage of fluids or warming blankets; built-in temperature data recorder; keypad for setting internal temperature located above door.

View Cutsheet 122436

Half-height confirmed

W x D x H: 30 x 26.6 x 35.5 in.
Electrical: 120V 60Hz 7.5A 750W **Weight:** 325 lbs.
HVAC Notes: 1535 btu/hr.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: XR / RF Corridor / Sub-Wait **Department: Imaging (1st Floor)**

Room #: B103D

Room Notes: Located in X-Ray/Fluoro

Ice Maker / Water Dispenser

AE #: IMWD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	7CI112A-IW-CL-ST-00	Champion 7	Countertop	OF/CI	Project

Ice and Water Dispenser. 7 LB Ice Storage Capacity. Integral Air-Cooled Machine with up to 100 Lb. Daily Production of Chewblet Ice. Internal Claris Filter. View Cutsheet 210599

** If unit is to be connected to drain, specify Follett Drip Tray Drain Kit/4" legs part #01535343

For chilling contrast

W x D x H: 14.6 x 22.4 x 17.6 in.
Clearance: Rear 2 in.; Left 3 in.; Right 3 in.
Electrical: 115V 60Hz 3.8A
Weight: 74 lbs.
Elect Notes: NEMA 5-15
Plumb Notes: See Attached Spec Sheet. Water inlet: 1/4" push-in. Factory equipped external water filter connection: (2) 1/4" push-in (in and out) (hot water models only).
Water temperature: 40 - 90 F (4 - 32 C). Water pressure: 10 - 70 psi (69 - 482 kpa). Water consumption: 12 gal (45.4 L) of potable water per 100 lb (45.4 kg) of ice
** If unit is to be connected to drain, specify Follett Drip Tray Drain Kit/4" legs part #01535343
Struct Notes: ** if using 4" accessory legs, add 4" to height

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.
Weight: 1 lbs.

Room: XR / RF Dressing Room

Department: Imaging (1st Floor)

Room #: B103D2, B103D1, B103D3

Room Notes: Linen outside of room

Room: XR / RF Tech

Department: Imaging (1st Floor)

Room #: B103D4

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: XR / RF

Department: Imaging (1st Floor)

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
14	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure

View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order 2 of all sizes When ordering, include UK Radiology monogram. Confirmed, thyroid shield to be tethered with magnetic closure** Per email follow up from dept signoff, increase quantity to 14 to include 2 male L and 2 male XL.

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	14

Apron, Lead, 3-5XL

AE #: ALXL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Infab Corporation	EBA		Rack	OF/OI	Project

Elastic Back Apron. Built-in orthopedic elastic panels for lower back support and comfort. Comfortable shoulder pads. Double welt pockets.

View Cutsheet 209998

COLORS: Classic Nylon Colors. CORE: Lightweight Lead, KIARMOR Bi-Layer Lead-Free. PROTECTION: .25mm LE, .35 mm LE, .50mm LE. SIZES: Male S-5XL, Female XS-5XL

Include (1) of each size. When ordering, include UK Radiology monogram. Confirmed, thyroid shield to be tethered with magnetic closure

Apron, Lead, XXL

AE #: ALXL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf	67090LW-XX		Rack	OF/OI	Project

Light weight lead apron with 0.5mm protection. The special procedure apron has an elastic belt that helps lift the apron weight off your shoulders. A full back panel gives you all-around protection and the over-the-shoulder hook-n-loop closure makes putting it on and removing it a cinch.

View Cutsheet 209950

When ordering, include UK Radiology monogram. Confirmed, thyroid shield to be tethered with magnetic closure

W x D x H: 25 x N/A x 42 in.

Room: XR / RF

Department: Imaging (1st Floor)

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Block, Finger

AE #: BLFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Infab Corporation	INF-NCAA		Countertop	OF/OI	Project

Adult oblique finger block. Coated Sponges feature a patented medical grade, fluid-resistant coated surface that is easy to clean with any medical grade disinfectant wipe or spray. View Cutsheet 210514

W x D x H: 10.5 x 6 x 3 in.

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Struct Notes: Wall backing may be required

Cart, Sharps Container

AE #: CASC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/VI	Service Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available. View Cutsheet 208721

For red container

W x D x H: 11.5 x 16 x 16.5 in.

Room: XR / RF **Department: Imaging (1st Floor)**

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Chair, Imaging

AE #: CHIM-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hausted / GF Health Products	EPC500 Procedure Chair		Floor	OF/OI	Project

Procedure chair; height adjustable 20" to 40"; weight capacity 600 lbs.; full radiolucent back; hand pendant; seat tilt; Trendelenburg and reverse Trendelenburg; back up lithium ion battery; patient surface width 26". View Cutsheet 210949

Added per signoff email follow up list

W x D x H: 26 x 78.5 x 40 in.
Electrical: 120V 60Hz **Weight:** 265 lbs.

Chair, X-Ray

AE #: CHXR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Vela	Turn+ Thorax	70031	Floor	OF/OI	Project

Patient chair designed for thoracic X-rays, where the patient must be stabilized to obtain correct images. Lockable seat rotation (45°/90° right and left) and fold-down armrests allow easy access to capture X-ray images from multiple angles. The patient is placed at the apparatus and the armrests are folded down. View Cutsheet 210044

W x D x H: 21.7 x 21.7 x 35.8 in.
Electrical: 120V 60Hz

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: XR / RF

Department: Imaging (1st Floor)

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: XR / RF

Department: Imaging (1st Floor)

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Glove, Lead

AE #: GLLE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	69303		Countertop	OF/OI	Project

Pair of vinyl handcoverings covered with soft urethane materials for rugged durability. Breathable nylon liner keeps hands cool during procedures. View Cutsheet 146882

0.5mm protection. Navy blue.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: XR / RF

Department: Imaging (1st Floor)

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Imaging, Digital Radiographic/ Fluoroscopic Unit

AE #: IMDR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	LUMINOS AGILE MAX		Floor / Wall	OF/CI/VI	Project

two in one imaging system. Large 43 cm x 43 cm / 17” x 17” max dynamic flat detector distortion free images with up to 3.4 lp/mm. ddo and diamondview plus for improved image quality. high heat capacity x-ray tube. comprehensive dose reduction with care.

View Cutsheet 172701

User request: Contact Vendor to coordinate lighting controls on the machine and the room. This is what they currently have. **Pricing from Siemens Package, quote #CPQ-1144840-0**

Supplemental Info

Network: Wired
Elect Notes: **please reference site planning drawings**
Plumb Notes: **please reference site planning drawings**
HVAC Notes: **please reference site planning drawings**
Struct Notes: **please reference site planning drawings**

Imaging, Positioning Device

AE #: IMPD-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7187-EF-B		Cabinet	OF/OI	Project

4 inch Decubitus Block, coated, extra firm.

View Cutsheet 209930

W x D x H: 24 x 18 x 4 in.

Imaging, Positioning Device

AE #: IMPC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7117-EF-B		Cabinet	OF/OI	Project

45 Degree Spinal Wedge. Coated, extra firm.

View Cutsheet 209931

W x D x H: 7 x 24 x 7 in.

Imaging, Positioning Device

AE #: IMPD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7100EFB		Cabinet	OF/OI	Project

Extra firm coated torso block 15.5” x 12” x 7”

View Cutsheet 123251

Room: XR / RF **Department: Imaging (1st Floor)**

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Lead Glasses — AE #: LAGL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Burlington Medical, Inc.	ES90/91		Cabinet	OF/OI	Project

Radiation protection leaded eye frames are designed to fit over your current prescription lenses, providing side shields to protect from lateral exposure. An excellent selection for easy and affordable protection without sacrificing the convenience of your own RX glasses. Best suited for medium width faces. Anti-fog, plano non-Rx. View Cutsheet 209380

Phantom, Radiography Fluoroscopy — AE #: PHRF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	903		Cabinet	OF/OI	Project

CIRS Model 903 is manufactured from Polymethyl Methacrylateyeate (PMMA) equivalent epoxy that offers the same x-ray attenuation properties as PMMA; Model Consists of three attenuation plates, one test object plate and a detachable stand for easy, reproducible set-up; Test objects include high-resolution copper mesh targets from 12 – 80 lines per inch, two separate contrast detail test objects. View Cutsheet 209552

W x D x H: 10 x 10 x 8 in.

Weight: 37 lbs.

Rack, Apron — AE #: RAAP-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Eljay Medical	722025	520	Wall	OF/CI	Project

This lead apron and glove rack will hold five aprons and four gloves. The body is heavy gauge steel finished in gray baked enamel and the apron arms and glove supports are anodized aluminum. The unit is designed so that weight is supported by the floor which minimizes wall stress and simplifies installation. Specifications Dimensions: 30" wide x 69" high. Shipping Weight: 25 lbs. Body made of heavy gauge steel finished in grey enamel. Glove brackets and apron support rods are made from anodized aluminum. View Cutsheet 209350

W x D x H: 30 x N/A x 69 in.

Weight: 25 lbs.

Room: XR / RF

Department: Imaging (1st Floor)

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sandbag

AE #: SAND-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide, Inc.	SBK-CB		Cabinet	OF/OI	Project

Set includes two 10lb 11" x 11" sandbags; choose color when ordering

View Cutsheet 122392

W x D x H: 11 x N/A x 11 in.

Shield, Lead Free

AE #: SHLF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide	LPSG-T2424S		Floor	OF/OI	Project

Lead free mobile shield 24x24

View Cutsheet 208753

W x D x H: 24 x N/A x 24 in.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks

View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: XR / RF **Department: Imaging (1st Floor)**

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Table, Instrument

AE #: TAIN-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MCM503		Floor	OF/OI	Project

Stainless Steel Instrument Table with Shelf. Heavy duty 16 gauge stainless steel with solid welded construction. Revealed edge is 1.5" to give the strongest table. Reinforcing channels welded into larger models for additional strength 3" Ball bearing casters. No open cavities to collect unwanted substances View Cutsheet 209352

W x D x H: 18 x 33 x 34 in.

Walker

AE #: WALK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS864104BA		Floor	OF/OI	Project

Assembled Basic Walker, 2-Button, Folding, Adult, 400 lb. Easy-to-use, push-button mechanisms let walkers fold easily. Each side folds independently to allow easy movement through narrow spaces. Side cross braces provide extra durability. Push-button, height-adjustable legs. Height adjusts from approx. 32" to 39". View Cutsheet 210028

W x D x H: 18 x 21 x 39 in.

Weight: 8 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: XR / RF

Department: Imaging (1st Floor)

Room #: B103E

Room Notes: Day 1 is Fluoro. X-Ray in Day 2. Deleted table pad per signoff email follow up list.

Wheelchair

AE #: WHEE-47

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	PRIME TC		Floor	OF/VI	Project

Transport chair has big wheels for easier maneuvering. Stand assist armrests fold back to allow easy patient access. Flip up foot rests with optional swing away functionality. Anti-tip wheels standard. Power washable. Upright o2 tank holder. 1" thick iv pole. 500 lb safe working load. Nestable frame.

View Cutsheet 148367

Added per signoff email follow up list

W x D x H: 28.3 x 40.2 x 45 in.

Room: XR / RF Control **Department: Imaging (1st Floor)**

Room #: B103E1

Room Notes: Assumes space for 2 people/workstations + 3 additional tech workstations

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Cart, Procedure

AE #: CAPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Basic Single Wide 7-Drawer	SXRS5110L	Floor	OF/VI	Project

Pre configured cart featuring 5" caster wheels, mechanical keylock, and 7 drawers. Color chosen when ordering. View Cutsheet 208764

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 22.7 x 24.9 x 41.7 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad- includes auto lock	SXRX412	1	1

Control Console

AE #: COCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems, Inc.	TBD		Countertop	OF/VI	Project

No Cutsheet 204327

Price included in cost of scanner

Network: Wired

Electrical: 120V 60Hz

Room: XR / RF Control **Department:** Imaging (1st Floor)

Room #: B103E1

Room Notes: Assumes space for 2 people/workstations + 3 additional tech workstations

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

Confirm w/Pharmacy, May need a double integrated main instead to accommodate various types and sizes of oral contrast including gallon jugs of barium. Also use 4-5 different meds ("vials").

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: XR / RF Radiologist Work Room (Reading-Abd) **Department:** Imaging (1st Floor)

Room #: B103G

Room Notes: Assumes Diagnostic grade PACS are to be carried in IT scope. Height adjustable tables to be carried in furniture scope. X-Ray (4 people)

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883552		Floor	OF/OI	Project

Slim jim step-on 90l/24 gal resin front waste container. Quiet, controlled lid closure minimizes noise. Internal hinge design to prevent wall damage. View Cutsheet 148391

Factory mutual certified ensures fire safety. Meets osha and obra standards for worker and environmental safety. Color: beige.

other available colors include: yellow, green, black, red, white, blue and gray.

W x D x H: 22.4 x 13.9 x 32.5 in.

Clearance: Top 13.9 in.

Weight: 16.8 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: XR / RF Lead

Department: Imaging (1st Floor)

Room #: B103G1, B103G2

Room Notes: Closets for Pt lead. Only (1) Apron will be kept in scan rooms.

Rack, Apron

AE #: RAAP-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	MR4-AH3		Floor	OF/OI	Project

Heavy duty mobile, nesting Z style rack that offers stability for lead apron storage, With (10) AH3 Hangers. View Cutsheet 210323

W x D x H: 51 x 23 x 55 in.

Room: Ultrasound Ht / Wt **Department:** Imaging (1st Floor)

Room #: B103G3

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug. View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz

Weight: 61 lbs.

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Room: Ultrasound Ht / Wt

Department: Imaging (1st Floor)

Room #: B103G3

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: CT / MR Radiologist Work Room (CV/Thor Reading) **Department:** Imaging (1st Floor)

Room #: B103H

Room Notes: Assumes Diagnostic grade PACS are to be carried in IT scope. Height adjustable tables to be carried in furniture scope. 4 workstations.

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883552		Floor	OF/OI	Project

Slim jim step-on 90l/24 gal resin front waste container. Quiet, controlled lid closure minimizes noise. Internal hinge design to prevent wall damage. View Cutsheet 148391

Factory mutual certified ensures fire safety. Meets osha and obra standards for worker and environmental safety. Color: beige.

other available colors include: yellow, green, black, red, white, blue and gray.

W x D x H: 22.4 x 13.9 x 32.5 in.

Clearance: Top 13.9 in.

Weight: 16.8 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Ultrasound Alcove, BW, Linen, and Mobile Equip **Department:** Imaging (1st Floor)

Room #: B103J2

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.
HVAC Notes: 1604 BTU/hr

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

W x D x H: 11 x 22 x 25 in.
Weight: 6.5 lbs.

Room: Ultrasound Room **Department: Imaging (1st Floor)**

Room #: B103K, B103L

Room Notes: No procedures

Cabinet, Probe Rack

AE #: CAPR-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cone Instruments	GUS	CN17211	Wall	OF/CI	Project

The GUS Storage System comes in two variations: To hold up to six Vaginal, Rectal and General Purpose probes and to hold up to three TEE probes. View Cutsheet 209577

Continuous flow of HEPA filtered air protects delicate probes from recontamination. In addition, hang probes vertically in a cabinet and store in a clean, dry environment.

W x D x H: 24 x 10 x 74 in.
Electrical: 120V 60Hz 15A **Weight:** 100 lbs.
Elect Notes: Service: 110-120VAC, 60Hz, 15A Hospital Grade GFCI receptacle
Fuse: 1.0Amp, 250V, 5mm x 20mm, FSF Panel Mounted
Current Draw: 0.5 Amp
Struct Notes: Minimum Space Required: W: 30", D: 36", H: 84"

Cart, Procedure

AE #: CAPR-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys	SXRS1310L	Floor	OF/VI	Project

Starsys General Use Medical Cart includes one 3" drawer, three 6" drawers and one 9" drawer with taupe drawer pulls. View Cutsheet 208744

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 24.8 x 22.8 x 41.8 in.
Weight: 167 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad- Includes Auto Lock	SXRX412	1	1

Chair, Ultrasound Tech

AE #: CHUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hag Ergonomic Chairs / Izzy Design	H8106		Floor	OF/OI	Project

Hag capisco (the saddle chair) with seat and back. Saddle seat is height adjustable between low and high working positions all the way to standing. View Cutsheet 150834

Standard 200mm gas lift.

No footring per department feedback. Color: Gray. Material: whatever is most durable

W x D x H: 27.6 x 27.6 x 55.1 in.

Room: Ultrasound Room

Department: Imaging (1st Floor)

Room #: B103K, B103L

Room Notes: No procedures

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Ultrasound Room

Department: Imaging (1st Floor)

Room #: B103K, B103L

Room Notes: No procedures

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Hook, IV Wall

AE #: HOIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Novum Medical Products	IV WALL HOOK		Wall	OF/CI	Project

Stainless steel hook, 1/4" diameter, 16 guage powder coated white wall bracket, plastic cap fda complient, #10 screws (2) with board anchors are included View Cutsheet 165573

W x D x H: 1.5 x 5 x 3 in.

Imaging, Ultrasound Scanner

AE #: IMUS-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Imaging	EPIQ Elite		Floor	OF/VI	Project

EPIQ Elite ultrasound with nSIGHT imaging, FlexVue with orthoganal view, MFI HD and 24" HD display View Cutsheet 207839

Model currently used at UK

W x D x H: 23.9 x 43 x 67.5 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 230 lbs.

Room: Ultrasound Room **Department:** Imaging (1st Floor)

Room #: B103K, B103L

Room Notes: No procedures

Table, Ultrasound

AE #: TAUL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Biodex Medical Systems, Inc	Ultra Pro	058-720	Floor	OF/VI	Project

The Biodex Ultra Pro Ultrasound Table 115 VAC is designed for general ultrasound procedures, including OB/GYN. Wt capacity: 500lb. Height adjustable: 23" - 35". Depth has optional side rails included. Enhanced ergonomics reduce sonographer fatigue. Redesigned Fowler back provides utmost patient comfort and require less patient repositioning. View Cutsheet 209451

See accessories: Include stirrups and side raila

W x D x H: 70 x 35 x 39 in.
Electrical: 115V 60Hz **Weight:** 335 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side Rails	058-633	1	1
Stirrups, Retractable	058-652	1	1

Warmer, Gel

AE #: WAGE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Parker Laboratories, Inc.	83-03		Cart	OF/OI	Project

Multi bottle gel warmer (three bottles) with LED temperature readout View Cutsheet 147051

W x D x H: 11.5 x 4.3 x 9 in.
Electrical: 120V 60Hz 2.8A

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Ultrasound Room

Department: Imaging (1st Floor)

Room #: B103K, B103L

Room Notes: No procedures

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Ultrasound Dressing Room

Department: Imaging (1st Floor)

Room #: B103M, B103N, B103Q

Room Notes: Assumes no MEQ. Linen hamper and clean linen cabinet just outside.

Room: Trophon / HLD **Department: Imaging (1st Floor)**

Room #: B103P

Room Notes: US. US phantoms to be stored here.

Cart, Probe Cleaner — AE #: CAPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	Trophon Cart	N05010	Floor	OF/OI	Project

Trophon Cart Makes trophon2 devices fully mobile for convenient point of care use and adaptability where there are space constraints. Trophon Printer Cart Mount 2^ designed for securely attaching the trophon Printer to the trophon Cart, in an easily accessible, convenient location. View Cutsheet 209452

W x D x H: 20 x 20.5 x 34.5 in.

Weight: 45 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Trophon printer cart mount	N05013	1	1

Cart, Procedure — AE #: CAPR-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys	SXRS1310L	Floor	OF/VI	Project

Starsys General Use Medical Cart includes one 3" drawer, three 6" drawers and one 9" drawer with taupe drawer pulls. View Cutsheet 208744

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 24.8 x 22.8 x 41.8 in.

Weight: 167 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad- Includes Auto Lock	SXRX412	1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Trophon / HLD

Department: Imaging (1st Floor)

Room #: B103P

Room Notes: US. US phantoms to be stored here.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Phantom, Ultrasound

AE #: PHUL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	049 / 049A		Cabinet	OF/OI	Project

Elasticity QA Phantom; Provides Acoustic Targets of Discrete Known Stiffness; Four types of lesions with discrete elastic moduli (Contact CIRS for custom moduli); Compatible with both shear wave and compression elastography; Customized versions available for magnetic resonance elastography.

View Cutsheet 209571

Price is combined 049 + 049A.

Confirmed, ok to keep here

W x D x H: 8.5 x 6 x 4 in.

Weight: 6.5 lbs.

Room: Trophon / HLD

Department: Imaging (1st Floor)

Room #: B103P

Room Notes: US. US phantoms to be stored here.

Phantom, Ultrasound

AE #: PHUL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	039		Cabinet	OF/OI	Project

Shear Wave Liver Fibrosis Phantom, Set of 4 phantoms, each with a different stiffness (Young's modulus ranges from 2-36 kPa); Enables quantitative assessment of shear wave speed measurements used in the diagnosis of diffuse liver disease; Certified measurement of shear wave speed according to protocol developed by Quantitative Imaging Biomarkers Alliance Ultrasound Shear Wave committee

View Cutsheet 209570

Confirmed, ok to keep here

W x D x H: 4.5 x 4.5 x 5.5 in.

Phantom, Ultrasound

AE #: PHUL-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	403		Cabinet	OF/OI	Project

Doppler 403 Flow Phantom; System Velocity Testing by using precision flow rates and proprietary blood-mimicking fluid

View Cutsheet 209574

Confirmed, ok to keep here

W x D x H: 11 x 12 x 8.7 in.

Weight: 18 lbs.

Probe Cleaner

AE #: PRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON2		Cart	OF/OI	Project

Ultrasound probe high level disinfection system. Captures user ID, instrument ID, disinfectant information and chemical indicator. Can download data to USB or to hospital network.

View Cutsheet 170055

See accessories: include AcuTrace Medical Instrument Tag and Operator Card.

Supplemental Info

W x D x H: 14.3 x 12.6 x 21.2 in.
Clearance: Left 10 in.; Right 10 in.
Network: Wired
Electrical: 120V 60Hz 6A
Weight: 48.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
AcuTrace Medical Instrument Tag	N05007	1	1
AcuTrace Operator Card	N05006	1	1

Room: Trophon / HLD **Department:** Imaging (1st Floor)

Room #: B103P

Room Notes: US. US phantoms to be stored here.

Probe Cleaner Accessory, Printer — AE #: PCAP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON PRINTER		Cart	OF/OI	Project

Printer To Accompany Trophon 2. Connected to Trophon2 Unit via USB Cable. Printer is a Traceability Solution, Printing Trophon Disinfection Labels. View Cutsheet 171574

W x D x H: 4.33 x 6.89 x 9.84 in.
Electrical: 120V 60Hz 1.8A

Vacuum, Handheld — AE #: VAHA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Black & Decker	HNVC215BW52		Countertop	OF/OI	Project

The BLACK+DECKER® dustbuster®™ QuickClean™ wet/dry cordless handheld vacuum will help you clean up spills and messes with ease. Cleaning will become fast with this convenient and versatile hand vacuum. View Cutsheet 209453

W x D x H: 4.5 x 17.1 x 5.4 in.
Electrical: 120V 60Hz **Weight:** 2.4 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin — AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

W x D x H: 11 x 22 x 25 in.
Weight: 6.5 lbs.

Room: Ultrasound Tech Room **Department: Imaging (1st Floor)**

Room #: B103R

Room Notes: Assumes space for 3 people

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Workstation, US Infection Control

AE #: WOIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	AuditPro		Countertop	OF/OI	Project

Infection control workflow compliance management in the form of a workstation and mobile unit to be used with the Nanosonic Trophon2. Handheld computer/barcode scanner dimensions: 6.18 x 3.08 x 0.67 in View Cutsheet 210430

W x D x H: 5.1 x 5.9 x 2.3 in.

Network: Wireless **Network Notes:** WLAN, WLAN/WWAN

Electrical: 120V 60Hz

Room: Clean Supply **Department: Imaging (1st Floor)**

Room #: B103S

Room Notes: Centrally located for all modalities

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system — No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas — AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. — View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Supply, 36x24x67 — AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) — View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility — AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. — View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Room: Clean Supply **Department:** Imaging (1st Floor)

Room #: B103S

Room Notes: Centrally located for all modalities

Docking Station — AE #: DOST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3/MX100		Countertop	OF/VI	Project

A docking solution for X3 and MX100 monitors, providing mounting, AC power, LAN, and Flexible Sync Out. To be used with standalone IntelliVue X3 or IntelliVue MX100 monitors. Includes Universal Clamp and Cable Management Hook. View Cutsheet 209937

W x D x H: 7.5 x 4.4 x 3.9 in.
Electrical: 120V 60Hz **Weight:** 1.6 lbs.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.
Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.
Network: Wired **Network Notes:** Rj-45 ethernet jack
Electrical: 120V 60Hz 15W

Lifter, Patient — AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor. View Cutsheet 208837

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Room: Clean Supply **Department: Imaging (1st Floor)**

Room #: B103S

Room Notes: Centrally located for all modalities

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Rack, Gas Cylinder Storage — AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Suction Machine — AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: PET/SPECT Corridor (Hot)

Department: Imaging (1st Floor)

Room #: B106

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: SPECT CT

Department: Imaging (1st Floor)

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Struct Notes: Wall backing may be required.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Cart, Procedure

AE #: CAPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Basic Single Wide 7-Drawer	SXRS5110L	Floor	OF/VI	Project

Pre configured cart featuring 5" caster wheels, mechanical keylock, and 7 drawers. Color chosen when ordering.

View Cutsheet 208764

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 22.7 x 24.9 x 41.7 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad- includes auto lock	SXRX412	1	1

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: SPECT CT **Department: Imaging (1st Floor)**

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: SPECT CT **Department: Imaging (1st Floor)**

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Camera, Spect CT — AE #: ICSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Solutions Usa, Inc.	Symbia Pro.specta		Floor	OF/CI/VI	Project

A single photon emission SPECT CT. Capabilities include: low-dose CT of 32 to 64 slices , automatic SPECT motion correction, an improved workflow. View Cutsheet 210449

All-purpose system that can be customized to accommodate a wide range of clinical exams, patient types, and department settings.

Pricing from Executive Agreement, 6/27/2024, quote #CPQ-1065049-1 Supplemental Info

Network: Wired
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Room: SPECT CT **Department: Imaging (1st Floor)**

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Injector, Contrast Media Mobile — AE #: ICMM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bayer Corp, Diagnostics Div	MEDRAD Stellant FLEX		Floor	OF/VI	Project

MEDRAD Stellant FLEX CT injection system on mobile stand with Certegra Workstation. Mobile Base dimensions: W 11.0", D 9.0", H 11.3". View Cutsheet 209189

Place holder until decision made on Ulrich mobile injector (209987)

W x D x H: 12.1 x 6 x 14.5 in.
Electrical: 120V 60Hz
Elect Notes: Electrical Requirements (VAC/Hz): 100–240 VAC, 50/60 Hz, 300 Volts-Amps

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care. View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.
Network Notes: Stand alone monitor, not connected to a central station
Electrical: 120V 60Hz

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Room: SPECT CT **Department: Imaging (1st Floor)**

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Patient Lift, Ceiling Mount — AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Phantom, SPECT — AE #: PHSP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	043-750		Countertop	OF/OI	Project

The Jaszczak SPECT Phantom is used for system performance valuation of:

View Cutsheet 208711

collimator, Artifacts, Calibration, and Reconstruction Parameters, Acceptance testing. Routine quality assurance and control. Evaluation of: Center-of-rotation error, Non-uniformity artifact, Changes of radius-of-rotation on spatial resolution

Reconstruction filters on spatial resolution, Attenuation and scatter compensation.

Will most likely live in hot lab. Need confirmation on all phantom location from Dr. Yang,

W x D x H: 8.7 x 8.7 x 7.3 in.

Elect Notes: No power/electrical to Phantom

Positioning Device — AE #: PODE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924951		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Long. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205979

W x D x H: 9.75 x 24 x 6.75 in.

Room: SPECT CT

Department: Imaging (1st Floor)

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Positioning Device

AE #: PODE-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	2970014893		Cabinet	OF/OI	Project

Size: Standard. Bolster is shaped to fit under the knees at just the right angle, alleviating pressure on the back in supine. Also improves access to knees and provides gradual slope for better support for back of thighs. With AliMed Protecta-Coat: protective vinyl coating offers long-lasting durability and is radiolucent above 60kVp. View Cutsheet 210505

W x D x H: 21 x 12.5 x 7.25 in.

Positioning Device

AE #: PODE-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924954		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Regular. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam. View Cutsheet 205980

W x D x H: 9.5 x 14 x 6.5 in.

Positioning Device

AE #: PODE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924960		Cabinet	OF/OI	Project

Positioning flat bottom roll for lower body support. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam. View Cutsheet 205981

W x D x H: 8.5 x 14 x 4.25 in.

Positioning Device

AE #: PODE-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	931177		Cabinet	OF/OI	Project

Curved toboggan arm/leg guard; size small. Provides extra protection on top of extremities while shielding physician from sharp edges.. Easy to clean, crystal clear radiolucent shield keeps arms and legs on the table, helping to prevent interference. View Cutsheet 205982

W x D x H: 10 x 10.3 x 6 in.

Room: SPECT CT **Department:** Imaging (1st Floor)

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: SPECT CT **Department: Imaging (1st Floor)**

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1). View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Room: SPECT CT **Department: Imaging (1st Floor)**

Room #: B106A

Room Notes: Water phantom and shielded syringe pumps + carriers will live in Hot Lab when not in use

Thermometer, Temporal — AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Wall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.
Elect Notes: Requires a 9-volt alkaline battery

Thermometer, Temporal, Wall Mount — AE #: TTWM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	134201		Wall	OF/CI	Project

Wall mount for Exergen TAT-5000 or TAT-5000S temporal thermometer. Includes mounting hardware.

View Cutsheet 207661

W x D x H: 3 x 1 x 1 in.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: SPECT CT Control

Department: Imaging (1st Floor)

Room #: B106A1

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder Smaller/Narrow model preferred in this space.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Injector, Contrast Media, Component

AE #: INCM-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad/Bayer Healthcare Services	STELLANT D	SCT321	Countertop	OF/VI	Project

Certegra touchscreen workstation (10.2"wx15.8"dx13.5"h) with base unit (11"w x 8.8"d x 11.5"h); **see procedure room injector for funding** View Cutsheet 162440

Place holder pending determination of injector manufacturer. May change to GE/ulrich INJECT CT Motion injector control panel (209988).

W x D x H: 15.8 x 10.2 x 13.5 in.

Network: Wired

Electrical: 120V 60Hz 2.5A

Weight: 17.6 lbs.

Room: SPECT CT Control

Department: Imaging (1st Floor)

Room #: B106A1

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Wall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Elect Notes: Requires a 9-volt alkaline battery

Thermometer, Temporal, Wall Mount

AE #: TTWM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	134201		Wall	OF/CI	Project

Wall mount for Exergen TAT-5000 or TAT-5000S temporal thermometer. Includes mounting hardware.

View Cutsheet 207661

W x D x H: 3 x 1 x 1 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: PET/SPECT Radiologist Work Room (Nuc Reading) **Department: Imaging (1st Floor)**

Room #: B106B

Room Notes: Assumes Diagnostic grade PACS are to be carried in IT scope. Height adjustable tables to be carried in furniture scope. CT-4 people, MRI-4 people, PET-3 people, US-2 people.

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle — AE #: WARE-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883552		Floor	OF/OI	Project

Slim jim step-on 90l/24 gal resin front waste container. Quiet, controlled lid closure minimizes noise. Internal hinge design to prevent wall damage. View Cutsheet 148391

Factory mutual certified ensures fire safety. Meets osha and obra standards for worker and environmental safety. Color: beige.

other available colors include: yellow, green, black, red, white, blue and gray.

W x D x H: 22.4 x 13.9 x 32.5 in.

Clearance: Top 13.9 in.

Weight: 16.8 lbs.

Waste Receptacle, Recycle Bin — AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: PET/SPECT Tech Room

Department: Imaging (1st Floor)

Room #: B106C

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. One dispenser needed by each door.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled

View Cutsheet 100085

resin will not rust and resists chips and dents

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: PET/SPECT Uptake (Stretcher)

Department: Imaging (1st Floor)

Room #: B106D

Bracket, Sharps Container

AE #: BRSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	0203WMA		Cart	OF/OI	Project

Locking wall mount bracket and key for 2 & 3 gallon containers

View Cutsheet 209292

For 2 gallon sharps container

W x D x H: 13 x 5.75 x 2.75 in.

Cart, Supply

AE #: CASU-88

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Armstrong Medical Industries	AMC-4		Floor	OF/VI	Project

Auto locking cart with 5 sureseal drawers: (3) 3"h, (1) 6"h and (1) 9"h. Drawers are 15"w x 17"d. Specify color.

View Cutsheet 134924

Changed from Midmark Synthesis cart (Cabinet, Storage) to this cart for auto-locking feature and ability to mount sharps container to side of cart.

Mount sharps bracket directly to cart using predrilled holes in sides of cart.

W x D x H: 21.4 x 20.7 x 34.6 in.

Weight: 70 lbs.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: PET/SPECT Uptake (Stretcher)

Department: Imaging (1st Floor)

Room #: B106D

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Wipes

AE #: DIWI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrex	13-1175		Wall	OF/CI	Project

Wall mounted bracket for CaviWipe canisters.

View Cutsheet 210056

Confirmed for this space. Pt's will be monitored on camera.

W x D x H: 6.65 x 6.1 x 6.4 in.

Weight: 1.59 lbs.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Room: PET/SPECT Uptake (Stretcher) **Department:** Imaging (1st Floor)

Room #: B106D

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: PET/SPECT Uptake (Stretcher) **Department:** Imaging (1st Floor)

Room #: B106D

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Hot-Patient) **Department:** Imaging (1st Floor)

Room #: B106E, B106F

Room Notes: Located in PET/SPECT

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard — AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance. View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Hot-Patient)

Department: Imaging (1st Floor)

Room #: B106E, B106F

Room Notes: Located in PET/SPECT

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: SPECT Injection / Dress

Department: Imaging (1st Floor)

Room #: B106G

Bracket

AE #: BRAC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	53505		Wall	OF/CI	Project

Dual Mount Wall Bracket for Stat Strip Glucose Meter Docking Station.

View Cutsheet 207910

W x D x H: 5.38 x 5.23 x 2.62 in.

Weight: 0.33 lbs.

Bracket, Sharps Container

AE #: BRSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	0203WMA		Cart	OF/OI	Project

Locking wall mount bracket and key for 2 & 3 gallon containers

View Cutsheet 209292

For 2 gallon sharps container

W x D x H: 13 x 5.75 x 2.75 in.

Cart, Supply

AE #: CASU-17

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Innerspace Corp / Stanley	Narrow Pace 21	SPN21W4	Floor	OF/VI	Project

The narrow version of the Pace 21 cart accommodates a variety of interior and exterior accessories. It has a lightweight aluminum case, durable and stable bumper and base, seamless work surface with raised edges, 5” medical-grade casters, and keyed lock.

View Cutsheet 211771

Changed from Armstrong AMC-4 cart, item 134924

W x D x H: 17 x 24.5 x 33 in.

Weight: 75 lbs.

Room: SPECT Injection / Dress

Department: Imaging (1st Floor)

Room #: B106G

Chair, Recliner

AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

To be confirmed by Jennifer Ratner if equipment or furniture. Needs to be able to be cleaned and be resistant to absorbing isotopes that are used in this setting.

W x D x H: 34 x 73 x 61 in.
Electrical: 120V 60Hz 4A

Container, Sharps

AE #: COSH-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203		Cart	OF/OI	Service Agreement

Red 3-gallon sharps container with vertical drop lid View Cutsheet 211070

W x D x H: 12.5 x 4.7 x 21.1 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: SPECT Injection / Dress

Department: Imaging (1st Floor)

Room #: B106G

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Wall	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case

View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless

Network Notes: Connectivity: ir port, rj45 or usb

Room: SPECT Injection / Dress

Department: Imaging (1st Floor)

Room #: B106G

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Wall	OF/CI	Project

Docking station for statstrip glucose meter

View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: PET/SPECT Dressing

Department: Imaging (1st Floor)

Room #: B106G1

Room Notes: Assumes no medical equipment required in this area.

Room: PET/SPECT Uptake (Recliner) **Department:** Imaging (1st Floor)

Room #: B106H, B106J, B106K, B106L

Bracket — AE #: BRAC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	53505		Wall	OF/CI	Project

Dual Mount Wall Bracket for Stat Strip Glucose Meter Docking Station. View Cutsheet 207910

W x D x H: 5.38 x 5.23 x 2.62 in.

Weight: 0.33 lbs.

Bracket, Sharps Container — AE #: BRSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	0203WMA		Cart	OF/OI	Project

Locking wall mount bracket and key for 2 & 3 gallon containers View Cutsheet 209292

For 2 gallon sharps container

W x D x H: 13 x 5.75 x 2.75 in.

Cart, Supply — AE #: CASU-88

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Armstrong Medical Industries	AMC-4		Floor	OF/VI	Project

Auto locking cart with 5 sureseal drawers: (3) 3"h, (1) 6"h and (1) 9"h. Drawers are 15"w x 17"d. Specify color. View Cutsheet 134924

Changed from Midmark Synthesis cart (Cabinet, Storage) to this cart for auto-locking feature and ability to mount sharps container to side of cart.

Mount sharps bracket directly to cart using predrilled holes in sides of cart.

W x D x H: 21.4 x 20.7 x 34.6 in.

Weight: 70 lbs.

Chair, Recliner — AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

Changed from furniture recliner to MEQ per discussion w/HGA. This may change as furniture planning progresses.

W x D x H: 34 x 73 x 61 in.
Electrical: 120V 60Hz 4A

Room: PET/SPECT Uptake (Recliner) **Department: Imaging (1st Floor)**

Room #: B106H, B106J, B106K, B106L

Container, Sharps — AE #: COSH-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203		Cart	OF/OI	Service Agreement

Red 3-gallon sharps container with vertical drop lid

View Cutsheet 211070

W x D x H: 12.5 x 4.7 x 21.1 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: PET/SPECT Uptake (Recliner)

Department: Imaging (1st Floor)

Room #: B106H, B106J, B106K, B106L

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Wipes

AE #: DIWI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Metrex	13-1175		Wall	OF/CI	Project

Wall mounted bracket for CaviWipe canisters. View Cutsheet 210056

Confirmed for this space. Pt's will be monitored on camera.

W x D x H: 6.65 x 6.1 x 6.4 in.

Weight: 1.59 lbs.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: PET/SPECT Uptake (Recliner) **Department:** Imaging (1st Floor)

Room #: B106H, B106J, B106K, B106L

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Wall	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case — View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Wall	OF/CI	Project

Docking station for statstrip glucose meter — View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. — View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks — View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: PET/SPECT Uptake (Recliner)

Department: Imaging (1st Floor)

Room #: B106H, B106J, B106K, B106L

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: PET/SPECT Alcove, Pyxis/BW **Department: Imaging (1st Floor)**

Room #: B106K1

Room Notes: Located on other side of PET CT control room.

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Drug Dispensing Unit

AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit View Cutsheet 150404

Still need confirmation on size/configuration from Katie for this area. *Confirmed, no ref needed here*

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A
Elect Notes: Must be located within 6' of the electrical outlet. Fuse: 6.3a. Power and data connections are made to frames at the back right of the computer (53-57" a.f.f.). Power cord length is 15'.
HVAC Notes: 200-600 btu/hr.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

Will go in cabinet between patient bathrooms

W x D x H: 23.7 x 21.2 x 32 in.

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white

View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.
Struct Notes: Wall backing may be required.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included.

View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.
Struct Notes: Wall backing may be required

Cart, Procedure

AE #: CAPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Basic Single Wide 7-Drawer	SXRS5110L	Floor	OF/VI	Project

Pre configured cart featuring 5" caster wheels, mechanical keylock, and 7 drawers. Color chosen when ordering.

View Cutsheet 208764

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 22.7 x 24.9 x 41.7 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad- includes auto lock	SXRX412	1	1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, PET / CT Scanner

AE #: IPET-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	United Imaging Healthcare	uMI Panorama			OF/CI/VI	Project

The uMI Panorama has the highest NEMA PET resolution, fastest timing resolution, and fastest CT rotation in the industry.* The AI-empowered workflow, 35 cm axial field of view (FOV), wide-bore and 700 lbs. table weight capacity

View Cutsheet 210560

To be used for basis of design, confirmed with Jennifer Ratner on 8/28/24. Subject to change to Siemens prior to procurement. Must be purchased with a pump and heat exchanger set for the chiller. Noted as a separate item in the equipment list.

Supplemental Info

Plumb Notes: Must use vendor-provided water or air cooling unit. Using a house chilled water loop to cool the equipment does not provide the level of cooling needed.

Imaging, Positioning Laser

AE #: IMPL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Lap Of America, L.C.	Apollo Wall		Wall	OF/CI/VI	Project

WALL MOUNTED LASERS. Apollo room lasers are used for precise and repeatable positioning of radiotherapy patients. The Apollo system has three (optionally four) lasers for the coronal, sagittal, and transversal body planes. You can choose the color, line and or/cross laser, and mounting option, all adapted to your individual room situation. A fourth laser prevents possible shadowing from the linac gantry in its initial position.

View Cutsheet 213072

Model confirmed with Megan Gilmore 11/4/24. See Siemens site specific for drawings, pair with wall mounted lasers

W x D x H: 4.3 x 3.9 x 8.7 in.
Electrical: 120V 60Hz 1.5A

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Imaging, Positioning Laser

AE #: IMPL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lap Of America, L.C.	Apollo Ceiling		Ceiling	OF/CI/VI	Project

Apollo room lasers are used for precise and repeatable positioning of radiotherapy patients. The Apollo system has three (optionally four) lasers for the coronal, sagittal, and transversal body planes. You can choose the color, line and or/cross laser, and mounting option, all adapted to your individual room situation. A fourth laser prevents possible shadowing from the linac gantry in its initial position.

View Cutsheet 209948

Model confirmed with Megan Gilmore 11/4/24. See Siemens site specific for drawings, pair with wall mounted lasers

W x D x H: 2.48 x 4.13 x 9.33 in.
Electrical: 120V 60Hz 1.5A
Elect Notes: Requires 120 VAC duplex outlet above finished ceiling. **Refer to LAP site planning guide.**
Struct Notes: All 8 structural frame pads must be secured to concrete ceiling above, or structural steel support. **Refer to LAP site planning guide.**

Injector, Contrast Media

AE #: INCM-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medrad/Bayer Healthcare Services	Stellant FLEX		Ceiling	OF/CI/VI	Project

CT injection system with options for 150ml and 200ml syringe sizes. Also cleared for use with contrast enhanced mammography (CEM). System uses barcodes to determine syringe size, expiration date, and if the syringe has already been used.

View Cutsheet 205858

Place holder until decision made on Ulrich mobile injector (209987)

W x D x H: 12.1 x 9 x 14.5 in.
Network Notes: Control panels are networked but not the actual injector.
Electrical: 115V 60Hz 1.5A
Weight: 16.8 lbs.
Elect Notes: 300 volts-amps

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

W x D x H: 15 x 7.2 x 12.1 in.

Network Notes: Stand alone monitor, not connected to a central station

Electrical: 120V 60Hz

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Phantom, PET-CT

AE #: PHPE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	043-771		Cabinet	OF/OI	Project

The PET-CT Phantom includes internal structures (three rods and six spheres) which demonstrate how accurately the two image sets are aligned; Used for acceptance testing and routine quality evaluation of PET/CT and SPECT/CT systems, evaluating image fusion software, assessing new attenuation correction algorithms, and research; Aluminum tubes are for registration; The outer 2" OD micro cylinder compares attenuation region to non attenuation region; 6" ring is for contrast solution

View Cutsheet 209550

W x D x H: 10 x 9 x 12 in.

Positioning Device

AE #: PODE-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	931177		Cabinet	OF/OI	Project

Curved toboggan arm/leg guard; size small. Provides extra protection on top of extremities while shielding physician from sharp edges.. Easy to clean, crystal clear radiolucent shield keeps arms and legs on the table, helping to prevent interference.

View Cutsheet 205982

W x D x H: 10 x 10.3 x 6 in.

Positioning Device

AE #: PODE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924951		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Long. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam.

View Cutsheet 205979

W x D x H: 9.75 x 24 x 6.75 in.

Positioning Device

AE #: PODE-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	2970014893		Cabinet	OF/OI	Project

Size: Standard. Bolster is shaped to fit under the knees at just the right angle, alleviating pressure on the back in supine. Also improves access to knees and provides gradual slope for better support for back of thighs. With AliMed Protecta-Coat: protective vinyl coating offers long-lasting durability and is radiolucent above 60kVp.

View Cutsheet 210505

W x D x H: 21 x 12.5 x 7.25 in.

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Positioning Device

AE #: PODE-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924954		Cabinet	OF/OI	Project

Positioning double angle wedge, 35-55 degree; Regular. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam. View Cutsheet 205980

W x D x H: 9.5 x 14 x 6.5 in.

Positioning Device

AE #: PODE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	924960		Cabinet	OF/OI	Project

Positioning flat bottom roll for lower body support. Protecta-coat positioning rectangle. Antimicrobial, waterproof and fluid proof. Radiolucent foam. View Cutsheet 205981

W x D x H: 8.5 x 14 x 4.25 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Safe, Lead Lined

AE #: SALL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	244-006		Floor	OF/CI	Project

Storage Safe is ideal for storing large quantities of high-activity radioisotopes. Shielded with a thickness of 2" of lead, the safe is encased in a powdercoated steel jacket and features an adjustable shelf. View Cutsheet 208712

Placeholder pending PET scanner selected. May need to change model/size based on source

W x D x H: 17.4 x 17 x 19 in.

Weight: 1050 lbs.

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks

View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops

View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Table, Treatment

AE #: TATR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Medical Systems	mCT RT Pallet		Wall	OF/CI	Project

RT Pallet overlay for mCT (PET/CT) system with 500 lb weight capacity. Includes wall mounting bracket for storage. Bracket dimensions are 23"W x 9.8"H, Bracket weighs 3.5lb.

View Cutsheet 207603

Will need wall mounted table extension holder - contractor vs HGA. Pricing confirmed with Siemens Rep, Landon Tong

W x D x H: 21 x 0.59 x 85.3 in.

Weight: 20 lbs.

Struct Notes: **Recommend wall backing for bracket**

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Wall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Elect Notes: Requires a 9-volt alkaline battery

Room: PET CT

Department: Imaging (1st Floor)

Room #: B106M

Thermometer, Temporal, Wall Mount

AE #: TTWM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	134201		Wall	OF/CI	Project

Wall mount for Exergen TAT-5000 or TAT-5000S temporal thermometer. Includes mounting hardware. View Cutsheet 207661

W x D x H: 3 x 1 x 1 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: PET CT Control **Department: Imaging (1st Floor)**

Room #: B106M1

Room Notes: Shared room for both PET CTs. Space for 6.

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder Smaller/Narrow model preferred in this space.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Computer, Tablet — AE #: COTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lap Of America, L.C.	CARINAnav		Countertop	OF/VI	Project

Remote tablet for positioning laser View Cutsheet 213091

Price included with lasers

W x D x H: 11 x 10.1 x 0.9 in.
Network: Networked
Electrical: 120V 60Hz

Control Console — AE #: COCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Siemens Medical Systems, Inc.	TBD		Countertop	OF/VI	Project

No Cutsheet 204327

To include PACs and Vendor Acquisition Station. CPUs to sit on ledge under counter. Price included in cost of scanner

Network: Wired
Electrical: 120V 60Hz

Room: PET CT Control **Department: Imaging (1st Floor)**

Room #: B106M1

Room Notes: Shared room for both PET CTs. Space for 6.

Injector, Contrast Media, Component

AE #: INCM-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medrad/Bayer Healthcare Services	STELLANT D	SCT321	Countertop	OF/VI	Project

Certegra touchscreen workstation (10.2"wx15.8"dx13.5"h) with base unit (11"w x 8.8"d x 11.5"h); **see procedure room injector for funding** View Cutsheet 162440

Place holder pending determination of injector manufacturer. May change to GE/ulrich INJECT CT Motion injector control panel (209988).

W x D x H: 15.8 x 10.2 x 13.5 in.
Network: Wired
Electrical: 120V 60Hz 2.5A **Weight:** 17.6 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: PET CT Generator / Cold Room **Department: Imaging (1st Floor)**

Room #: B106M2

Room Notes: Included in cost of PET CT System. See typical drawings for space planning. Located between PET rooms, serves both

Imaging, PET / CT Scanner, Component

AE #: IPSC-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	United Imaging Healthcare	Non-Refrigerated Water Recirculating System	WW3/B24-2G2T4M-X-K	Wall	OF/CI	Project

Non-refrigerated water recirculating system for water-cooled chiller for uMI Panorama PET / CT scanner. Regenerative single speed turbine pump with robust seal and bypass relief valve. Brazed plate heat exchanger without a control valve. Visual pressure gauge. Modifications for optional city water backup. Integrated non-pressurized fluid tank with fluid level switch. Powder-coated galvanized metal frame and enclosure. Front clearance required for service.

View Cutsheet 212432

Pricing per Radon Medical quote RMI-QU-24-016 dated 10/2/2024.

W x D x H: 31.5 x 11.8 x 31.5 in. **Clearance:** Front 24 in.
Electrical: 208V 60Hz 20A 1-Phase
Plumb Notes: Plumbing required.

Room: PET CT (Shelled)

Department: Imaging (1st Floor)

Room #: B106N

Room Notes: Shelled for Day 2

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Bin, Biohazard Waste — AE #: BIBW-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medicus Health	5200M8		Countertop	OF/OI	Project

Benchtop biohazard bin with 1.5L capacity. Starter kit comes with 400 autoclavable bags. View Cutsheet 210982

W x D x H: 7 x 5 x 7 in.

Cabinet, Lead Lined — AE #: CALL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	244-205		Floor	OF/CI	Project

Unit dose cabinet designed for PET; 0.25" lead; accommodates lead brick cave 042-434. The cabinet is also available with .5 and 1 lead shielding. View Cutsheet 209438

PET 1" lead shielding.

W x D x H: 36.5 x 24 x 36.5 in.

Weight: 1240 lbs.

Cabinet, Lead Lined, Preparation Enclosure — AE #: CLPE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	244-191		Floor	OF/CI	Project

This Cabinet is designed to support the Lead-Lined Preparation Enclosure. Full height, overlapping double doors with key locks open to an adjustable shelf with a 100 lb capacity. The cabinet may be used for decay and storage. 0.5" Lead Shielding. Countertop weight capacity: View Cutsheet 210494

SPECT

W x D x H: 36.5 x 24 x 36.5 in.

Weight: 1541 lbs.

Cabinet, Lead Lined, Waste — AE #: CALW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	244-152, 1"		Floor	OF/CI	Project

Lead-Lined Waste Cabinet is designed for storing non-sharps radioactive waste. 1" thick lead. A spacious chute with shielded cover allows waste to be dropped directly into a polyethylene container prior to decay and disposal. View Cutsheet 210337

PET

W x D x H: 30 x 25.3 x 40.3 in.

Room: Hot Lab

Department: Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Cabinet, Lead Lined, Waste

AE #: CALW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	244-151, 0.5"		Floor	OF/CI	Project

Lead-Lined Waste Cabinet is designed for storing non-sharps radioactive waste. 0.5" thick lead. A spacious chute with shielded cover allows waste to be dropped directly into a polyethylene container prior to decay and disposal. View Cutsheet 210338

SPECT Same as Shielded Sharps Container that is being built into hood?

W x D x H: 30 x 25.3 x 40.3 in.

Calibration Source

AE #: CASO-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	RADQUAL	BM06V-20-37		Cabinet	OF/OI	Project

V-Vial dose calibration source. Nuclide Cs-137. Activity 0.2mCi. Vial 20cc. View Cutsheet 211038

Calibration Source

AE #: CASO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	RADQUAL	BM06V-20-57		Cabinet	OF/OI	Project

V-Vial dose calibrator source. Nuclide Co-57. Activity 5.0 mCi. Vial 20cc. View Cutsheet 211037

Calibration Source

AE #: CASO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	RADQUAL	BM06V-20-33		Cabinet	OF/OI	Project

V-Vial dose calibrator source. Nuclide Ba-133. Activity 0.25 mCi. Vial 20cc. View Cutsheet 211039

Room: Hot Lab

Department: Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Cart, Supply, 48x24x60

AE #: CASU-59

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	SUPER ERECTA	2448NC / 63P	Floor	OF/VI	Project

Super Erecta chrome wire shelving unit, stationary; 4 shelves total - 24"d x 48"w (2448nc); 4 each 62-7/16" high posts (54P); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 210125

Stationary confirmed

W x D x H: 48 x 24 x 63 in.

Cart, Utility

AE #: CAUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Grainger	16D086		Floor	OF/OI	Project

Corrosion-Resistant Utility Cart with Deep Lipped Metal Shelves: 30 in x 16 in. Capacity per shelf: 300lb View Cutsheet 210208

(2) for infusion pumps with shields, (1) for misc use

W x D x H: 36.5 x 17 x 34 in.

Check Source

AE #: CHSO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Spectrum Techniques	Cs-137		Cabinet	OF/OI	Project

BETA/Gamma Disk Sources. Disk sources are designed for use as reference sources in laboratories, radiation protection, training and education, security, and up-and-coming technology View Cutsheet 209648

For Geiger Counters. Will sit in source holder mounted on Ludlum 14C meter survey with Pancake Probe

W x D x H: 2 x N/A x 0.13 in.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Container, Sharps, Lead Lined — AE #: CSLL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	5730-2271		Hood	OF/OI	Project

PET Sharps Container Shield. Constructed to stand alone or to be recessed within a countertop. The shield is constructed of steel with 1 lead lining and allows for simple and convenient disposal of 511 keV radionuclides. Hinged cover for syringe disposal. Sliding top with lock for container removal.

View Cutsheet 209592

Still needed on PET side? Included in cost of Hood. Will also live in SPECT Hood.

W x D x H: 10.6 x 10.6 x 13.6 in.

Weight: 160 lbs.

Counter, Gamma — AE #: COGA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hidex	AMG	425-601	Floor	OF/VI	Project

The first gamma counter dedicated to Nuclear Medicine and PET applications. Combine all necessary individual measurement data in glomerular filtration rate (GFR) assay to get a final report for secure work flow in hospitals. With sample balance option - see accessory.

View Cutsheet 209647

Research

Supplemental Info

W x D x H: 24.4 x 27.6 x 23.6 in.

Network Notes: Connects to external PC via USB port

Electrical: 120V 60Hz

Weight: 447.5 lbs.

Elect Notes: 100-240V AC and 24 V DC.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Sample Balance	425-645	1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Personal Protection

AE #: DIPP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bowman Manufacturing	PS412-0512		Wall	OF/CI	Project

Provides storage for gowns, (4) glove boxes, (1) standard face mask box and (1) shielded face mask box View Cutsheet 160955

W x D x H: 22.8 x 4 x 25.6 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Hot Lab

Department: Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Dose Calibrator

AE #: DOCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Capintec, Inc	CRC-55TW	5130-2216	Countertop	OF/OI	Project

CRC-55TR Dose Calibrator and CAPRAC-T Wipe Test Well Counter; 28 programmable nuclide keys; Built-in dose calibration; 256 channel MCA; System comprised of:

View Cutsheet 122416

Touchscreen Display (8" color): 9"w x 10.5"d x 9.5"h, 120V, 7.5 lbs. with Epson Printer (120V)

Dose Calibrator (2.4"diameter x 10" d well): 7"w x 7"d x 17.25"h, 30 lbs. w/cable length 12'

Well Counter: 6"w x 6"w x 9.5"h, 15.5 lbs, w/cable length of 9'

Ionization Chamber: 12 atm Ultra-Pure Argon

PET, SPECT, and hood

W x D x H: 6.76 x 6.76 x 17.3 in.
Network: Networked
Electrical: 120V 60Hz 0.1A **Weight:** 30 lbs.

Dose Calibrator, Rod Source

AE #: DCRS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	RADQUAL	S-Vial		Countertop	OF/OI	Project

A patented design unique to RadQual, the S-Vial allows for use in either the syringe or vial positions on your dose calibrator dipper. All dose calibrator sources are calibrated against a traceable National Institute of Standards (NIST) solution in a similar geometry, using a pressurized ion chamber.

View Cutsheet 210437

W x D x H: 1.13 x N/A x 3 in.

Flood Source, Rectangular

AE #: FLSR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	043-840		Floor	OF/OI	Project

Used to test the response uniformity of gamma cameras to ensure camera response is consistent over the total head area(s). An optional Radshield case and Radscooter are available.

View Cutsheet 208708

W x D x H: 16.7 x 0.3 x 24.1 in.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Freezer, Ultra-Low

AE #: FRUL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Helmer, Inc.	SU105UE		Undercounter	OF/VI	Project

-20 to -86 degrees Celsius. 3.7 c.f capacity. <4 kWh/day at -80 degree energy consumption. uses 100% natural refrigerants. 7 year warranty for engine and thermosiphon with 2 years of included parts and labor coverage. View Cutsheet 206437

W x D x H: 27 x 28 x 34 in.
Electrical: 120V 60Hz 3A **Weight:** 220 lbs.
Elect Notes: Nema 5-15P plug

Freezer, Undercounter

AE #: FRLA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Helmer, Inc.	iLF105-GX		Undercounter	OF/VI	Project

Lab freezer. 5.3 cu ft. -15°c to -30°c. ADA compliant. View Cutsheet 209341

W x D x H: 24.3 x 28.4 x 31.9 in. **Clearance:** Rear 3 in.
Network: Networked
Electrical: 115V 60Hz 4.1A **Weight:** 179 lbs.
Elect Notes: NEMA 5-15 hospital-grade | 115V 60Hz, 8 to 10 ft (2.4-3.0m)

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Holder, Sample

AE #: HOSA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	180-2	47-1665	Countertop	OF/OI	Project

Sample holder for use with 44-9 detector; indicated use: repeatable geometry counting of wipes, filter paper, or slides. Sample size 5.1 cm diameter maximum. View Cutsheet 209545

W x D x H: 3 x 6 x 3.6 in.

Weight: 0.9 lbs.

Holder, Syringe Shield

AE #: HOSS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	007-999		Countertop	OF/OI	Project

The Syringe Shield Holder offers a means of protecting syringe shields from scratches or misplacement while freeing up extra work space. The Syringe Shield Holder will support up to eight shields and is counterbalanced to prevent tipping. Know exactly where syringe shields are when you need them. View Cutsheet 209614

W x D x H: 7.5 x 4 x 6 in.

Weight: 5 lbs.

Hood, Biological Safety, Radioisotope

AE #: HOBI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Labconco Corp.	Logic+ Class II, B2	B2TE	Floor	OF/CI/VI	Project

4ft, Class II, Type B2 Biological Safety Cabinet with radioisotope capabilities. ISO Class 5. Fume Exhaust Hood, fully ducted. Lead lined bottom, back, and sides 0.25". To hold sliding L-Block, dose calibrator, and sharp shield. View Cutsheet 210434

W x D x H: 55 x 34 x 106 in.
Electrical: 120V 60Hz

Kit, Spill Clean-Up

AE #: KSCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	0601-0009	0601-0009	Cabinet	OF/OI	Operational

Includes: 13 gal. Metal drum, 2 pair latex glove, 2 large coveralls, 2 each hoods and shoe covers, 2 respirators, 1 liter radiclean, rad-con hand and surface cleaner, 10 poly bags, nip tongs (12"), sponge mop, scrub brush, plastic pail, assorted warning signs, placards and rope View Cutsheet 122357

Keep price at $0, operational cost

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Lab Oven — AE #: LAOV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Fisher Scientific- Thermo	HERATHERM	50125590	Countertop	OF/OI	Project

Compact microbiological incubator; mechanical convection; chamber volume 18l (0.65 cu. Ft.); led display; 17 to 40 degree c. Temperature range View Cutsheet 122715

W x D x H: 10.2 x 18.5 x 16.3 in.
Electrical: 120V 60Hz 0.45A 45W **Weight:** 15.9 lbs.

Lab Refrigerator, Undercounter — AE #: LARU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	TSX505SAVK		Undercounter	OF/VI	Project

5.5 cu. Ft. Undercounter lab refrigerator. Automatic defrost. Solid door. Three shelves. Full color tft-lcd; 4:3"; 480 x 272 display. View Cutsheet 164935

Research Counter

W x D x H: 23.6 x 26 x 31.8 in.
Electrical: 115V 60Hz 5A
Elect Notes: Plug type: nema 5-15p. 100-240v, 50-60hz. 10 amps max / 3 amp steady state.

Lab, Pipette — AE #: LAPI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 200-2000	17014410	Rack	OF/OI	Project

The Rainin LiteTouch System Pipette XLS+ with UNV Tip: Volume range 200ul - 2000ul View Cutsheet 210340

W x D x H: N/A x N/A x 10.7 in.
Weight: 0.26 lbs.

Lab, Pipette — AE #: LAPI-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 100-1000	17014407	Rack	OF/OI	Project

The Rainin LiteTouch System Pipette XLS+ with UNV Tip: Volume range 100ul - 1000ul View Cutsheet 210260

W x D x H: N/A x N/A x 10.7 in.
Weight: 0.26 lbs.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Lift, Scissor Double — AE #: LISD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Global Industrial	273713		Floor	OF/OI	Project

DC BATTERY POWERED MOBILE SCISSOR LIFT TABLE. Features 12V rechargeable deep-cycle batteries with an onboard charger and battery level gauge. Push-button remote , emergency stop button, raised height limit switch and keyed On / Off switch are standard features. Easily maneuvered with a chrome-plated push handle, and rolls smoothly with mold-on polyurethane wheels, 2 swivel with brakes and 2 rigid. View Cutsheet 209646

W x D x H: 19.6 x 33 x 51 in.
Electrical: 120V 60Hz 3A **Weight:** 300 lbs.
Elect Notes: 12V Battery, rechargeable.

Meter, Survey — AE #: MESU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ludlum Measurements, Inc.	14C	48-1611	Desk	OF/OI	Project

Survey meter; 5 ranges; internal high range energy compensated G-M; utilizes G-M or scintallation detectors; total range from 0-2000 mr/hr. Includes handle View Cutsheet 39690

Include 44-9 pancake probe with energy compensated filters, probe clip, and check source holder.

W x D x H: 3.5 x 8.5 x 6.5 in.
Weight: 3.5 lbs.
Elect Notes: Requires 2 each "d" cell batteries.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Mechanical Check Source Holder	4062-166	1	2
Probe Clips		2	4

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Monitor, Humidity — AE #: MOHU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sensoscientific Inc.	Wi-Fi Ambient Temperature/Humidity Sensor	B13-100-K001C	Wall	OF/VI	Project

Wi-Fi internal temperature/humidity transmitter supports one external temperature sensor and one external relative humidity sensor. SensoScientific Wi-Fi transmitters are high speed wireless modules with PEAPv0 enterprise security, capable of collecting, storing and transmitting data wirelessly over a standard 802.11 b/g (Wi-Fi – RF Frequency 2.4 to 2.497 Ghz) with TCP protocol. The transmitter passes information to a standard access point which can be accessed by any Wi-Fi-enabled network. View Cutsheet 208762

Tridium??

W x D x H: 3 x 2.13 x 4.75 in.
Network: Wireless **Network Notes:** RF Frequency 2.4 to 2.497 GHz
Electrical: 120V 60Hz 0.5A
Elect Notes: Powered by 4 AA batteries or an external AC/DC Power Supply

Monitor, Radiation, Hand And Foot — AE #: MORA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ludlum Measurements, Inc.	3276HFM	48-4160-2	Floor	OF/OI	Project

Low cost hand-foot radiation detection monitor. View Cutsheet 209439

1 by each door

W x D x H: 12 x 12.6 x 54.3 in.
Electrical: 120V 60Hz
Elect Notes: 4 alkaline “AA” batteries with approximately 50 hours expected life, or 9 Vdc input via wall mount transformer (input 100-250 Vac, 50-60 Hz

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Hot Lab

Department: Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Wall	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Ambient Room

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Needle Recapper

AE #: NERE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Sabra Dental Products	NMC-600		Countertop	OF/OI	Project

This innovative needle recapping device facilitates OSHA compliant one-handed needle recapping. Suction cup base provides stable positioning. View Cutsheet 209645

Accepts most needle brands, sizes and gauges. Small size makes it easily transportable and won't clutter the work area. Made of solid rubber in a highly visible color. Easily cleaned and decontaminated

(2) at each counter

W x D x H: 1.5 x 1.5 x 1.25 in.

Phantom, NEMA IEC PET

AE #: PHNE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	5250-0161		Cabinet	OF/OI	Project

The NEMA IEC Body Phantom Set consists of a body phantom, a lung insert and an insert with six spheres with various sizes; Recommended for use in the evaluation of reconstructed image quality in whole body PET imaging; Interior length of phantom - 180 mm; Fillable spheres (6) inner diameter - 10 mm, 13 mm, 17 mm, 22 mm, 28 mm, and 37 mm; Distance from sphere plane to inside wall - 70 mm; Volume of empty cylinder - 9.7 liters; Cylindrical insert dimension- Outside diameter: 51 mm; Length: 180 View Cutsheet 209548

To live in Hot Lab

W x D x H: 7 x 4 x 7 in.

Room: Hot Lab **Department:** Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Phantom, SPECT, Anthropomorphic

AE #: PHSA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	043-795	5220-rs800T	Cabinet	OF/OI	Project

Anthropomorphic Torso Phantom - evaluation of non-uniform attenuation and scatter compensation methods; Consists of a large, body-shaped cylinder with lung, liver and spine inserts; Simulates the anatomical structures of radioactivity distributions for the upper torso of average to large male/female patients; Lung inserts can be filled with Styrofoam beads and water to simulate lung tissue density; Cardiac Insert Option - used for cardiac ECT data acquisition and reconstruction methods may also be evaluated

View Cutsheet 209547

To live in Hot Lab

W x D x H: 15 x 10.5 x 6 in.

Phantom, SPECT, Flangeless, Esser

AE #: PHSF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	043-772		Cabinet	OF/OI	Project

ECT and Flangeless Phantoms for PET and SPECT, meets ACR requirements. The flangeless PET and SPECT phantoms provide consistent performance information for any PET or High Resolution SPECT system. Multiple performance characteristics of PET and SPECT systems are evaluated from a single scan of the phantom. On-axis and off-axis transverse line spread function may be easily measured without removing the cover plate. Measurements of full-width-half (or tenth) maximum can be readily determined, either in air or in water. Includes PET and SPECT phantom lids

View Cutsheet 209964

To live in Hot Lab

Probe, Pancake

AE #: PRPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ludlum Measurements, Inc.	44-9	47-1539	Meter	OF/OI	Project

Pancake g-m detector able to be used with survey meters, scaler, ratemeters and alarm ratemeters; alpha beta gamma survey; frisking; pancake type halogen quenched g-m detector; window is 1.7 plus or minus 0.3 mg/cm2 mica

View Cutsheet 39691

Pair with 14-C Survey Meters. See probe detector clip in accessories

W x D x H: 2.7 x 10.7 x 1.8 in.

Weight: 1 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Probe Clip	4010-008-01	1	2

Room: Hot Lab **Department:** Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Pump, Infusion, Syringe

AE #: PUIS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pinestar Technology, Inc.	3400		Cart	OF/OI	Project

The Graseby 3400 Syringe Pump is the premium syringe pump for pharmacological stress testing. Generally IV drugs infused with the 3400 are Adenosine, Dobutamine, Persantine, Zevalin, Cholecystokinan (Kinevac) and more.

View Cutsheet 210206

W x D x H: 12.8 x 7.7 x 4.5 in.

Weight: 8 lbs.

Rack, Pipette

AE #: RAPI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Poltex	PIPRK6		Countertop	OF/OI	Project

6 position pipette (pipettor) rack. Fits most popular brands of pipettes.

View Cutsheet 209043

Super durable and cleanable (alcohol resistant) PETG construction. Rubber bumpons on base for a non-slip surface.

W x D x H: 11.4 x 6 x 8.6 in.

Rack, Wall, Unit Dose Pig

AE #: RUDP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Biodex Medical Systems, Inc	008-400		Wall	OF/CI	Project

Wall rack to hold up to 25 unit doses; holds pigs up to 2.25" diameter

View Cutsheet 107723

W x D x H: 17 x 17 x 18 in.

Shield, Auxiliary Wipe Test

AE #: SHAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Capintec, Inc	5420-2072		Countertop	OF/OI	Project

Auxiliary shiled wipe test of caprac and crc -25w dose calibrators

View Cutsheet 122596

W x D x H: 4 x 4 x 9.75 in.

Weight: 22 lbs.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Shield, Environmental Background — AE #: SHEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	7300-2450		Table	OF/OI	Project

Reduce background radiation more than 10 times with the environmental shield. Fitting any Capintec CRC dose calibrator with a remote ionization chamber, the shield consists of nine interlocking lead rings that surround the chamber. For use with dose calibrator. View Cutsheet 210496

SPECT side

W x D x H: 10.1 x N/A x 17.6 in.

Weight: 310 lbs.

Shield, Infusion Pump — AE #: SHIP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pinestar Technology, Inc.	007-GIPS		Cart	OF/OI	Project

0.5" lead shielding with SS exterior. For use with Graseby Injection Pumps. Designed to reduce exposure during the injection of radionuclides that require an infusion protocol. View Cutsheet 210207

W x D x H: 22.1 x 10.9 x 7 in.

Weight: 120 lbs.

Shield, Positron Lead, Well Chamber — AE #: SHPL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Capintec, Inc	7300-2903		Table	OF/OI	Project

Positron Shield is constructed with nine sets of split lead rings, and provides maximum radiation protection. The shield can either be flush mounted to a work surface or mounted on a table or cabinet. View Cutsheet 208729

PET side

W x D x H: 11.4 x N/A x 20.3 in.

Weight: 560 lbs.

Room: Hot Lab

Department: Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Shield, Syringe

AE #: SHSY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Capintec, Inc	007-945	Z-PET 5cc	Countertop	OF/OI	Project

The Z-PET Syringe Shield greatly reduces hand exposure from syringes containing 511 keV radionuclides. The barrel of the shield is constructed of .55 thick (14 mm) tungsten that attenuates FDG F-18 by 97%. The shield accommodates standard 5 cc syringes. View Cutsheet 209641

SPECT

W x D x H: 1.7 x N/A x 2.75 in.

Weight: 3.7 lbs.

Shield, Syringe

AE #: SHSY-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Capintec, Inc	007-985	Pro-Tec PET 3cc	Countertop	OF/OI	Project

The Pro-Tec™ PET Syringe Shield; for syringes containing 511 keV radionuclides; Barrel of the shield constructed of .34 thick tungsten; Accommodates 1 cc, 3 cc, 5 cc and 10 cc syringes. View Cutsheet 209644

SPECT

Weight: 1.4 lbs.

Shield, Syringe

AE #: SHSY-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pinestar Technology, Inc.	ssb5-2m		Countertop	OF/OI	Project

5cc bullet syringe shield, without lead glass. Simply insert syringe and twist, it locks in place. Available with or without Lead Glass Window. No Screws. No Springs. 2.0 mm tungsten View Cutsheet 209966

SPECT

W x D x H: 0.75 x N/A x 2.56 in.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Shield, Syringe — AE #: SHSY-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pinestar Technology, Inc.	ssb10-2m		Countertop	OF/OI	Project

10cc bullet syringe shield, without lead glass. Simply insert syringe and twist, it locks in place. Available with or without Lead Glass Window. No Screws. View Cutsheet 209967

No Springs. 2.0 mm tungsten

SPECT

W x D x H: 0.89 x N/A x 3.13 in.

Shield, Syringe — AE #: SHSY-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pinestar Technology, Inc.	ssb3-2m		Countertop	OF/OI	Project

3cc bullet syringe shield, without lead glass. Simply insert syringe and twist, it locks in place. Available with or without Lead Glass Window. No Screws. View Cutsheet 209965

No Springs. 2.0 mm tungsten

SPECT

W x D x H: 0.63 x N/A x 2.56 in.

Shield,"L" Block — AE #: SHLB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MarShield Radiation Shieldling	MS-042-433		Countertop	OF/OI	Project

L Block Shield with adjustable window. Calibrator Shield 1" thick. View Cutsheet 206190

(1) for PET SPECT L-Block will be inside hood and included on that quote

W x D x H: 18 x 21.5 x 26 in.

Weight: 822 lbs.

Room: Hot Lab

Department: Imaging (1st Floor)

Room #: B106Q

Room Notes: To be shared with Precision Med

Shielded Syringe Carrier

AE #: SHSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Capintec, Inc	001-182, 0.25" small		Countertop	OF/OI	Project

Size small, 0.25" Lead Shielded syringe carriers reduce exposure while storing or transporting radioactive material. The overlapping lid design with snap-latch closure prevents streaming. The ends of the carriers are double thick to reduce the exposure from the ends of syringes. View Cutsheet 210347

W x D x H: 9.25 x 3.4 x 2.6 in.

Weight: 11 lbs.

Shielded Syringe Carrier

AE #: SHSC-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Capintec, Inc	001-180, 0.25" large		Countertop	OF/OI	Project

Size large, 0.25" Lead Shielded syringe carriers reduce exposure while storing or transporting radioactive material. The overlapping lid design with snap-latch closure prevents streaming. The ends of the carriers are double thick to reduce the exposure from the ends of syringes. View Cutsheet 50230

W x D x H: 9.5 x 4.4 x 3.5 in.

Weight: 17 lbs.

Shielded Syringe Carrier

AE #: SHSC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Capintec, Inc	001-179, 0.125" large		Countertop	OF/OI	Project

Size large, 0.125" Lead Shielded syringe carriers reduce exposure while storing or transporting radioactive material. The overlapping lid design with snap-latch closure prevents streaming. The ends of the carriers are double thick to reduce the exposure from the ends of syringes. View Cutsheet 210349

W x D x H: 9.5 x 4.4 x 3.5 in.

Weight: 11.3 lbs.

Shielded Syringe Carrier

AE #: SHSC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Capintec, Inc	001-181, 0.125" small		Countertop	OF/OI	Project

Size small, 0.125" Lead Shielded syringe carriers reduce exposure while storing or transporting radioactive material. The overlapping lid design with snap-latch closure prevents streaming. The ends of the carriers are double thick to reduce the exposure from the ends of syringes. View Cutsheet 210348

W x D x H: 9.25 x 3.4 x 2.6 in.

Weight: 7.5 lbs.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Shielding, Flood Source

AE #: SHFS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	RADQUAL	BM01L-10NC		Cabinet	OF/VI	Project

RadShield was designed to provide an easier alternative for transferring your source to the camera with minimal exposure without moving a much heavier case. Weighing only 30 pounds it provides similar radiation dose reduction as the typical hard case. See cutsheet for specific model pertaining to flood source size/series. View Cutsheet 209734

See accessories, include Radshield. Pricing from quote 316712 received 3/15/24 (Tom Sobinovsky)

W x D x H: 24.1 x 16.7 x N/A in.

Weight: 30 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Lead Lined Case	BM01 Radshield	1	1

Stirrer, Magnetic

AE #: STMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	S07977S		Countertop	OF/OI	Project

Strong magnetic coupling ensures consistent stirring during experimental procedures. Low profile, lightweight design with small footprint. Speed Control: 150 to 2500rpm View Cutsheet 209750

Research

W x D x H: 5.12 x 5.12 x 2.56 in.

Electrical: 120V 60Hz

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Hot Lab **Department: Imaging (1st Floor)**

Room #: B106Q

Room Notes: To be shared with Precision Med

Water Phantom — AE #: PHWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pinestar Technology, Inc.	NMC-76801		Cabinet	OF/OI	Project

Our fillable flood phantoms feature extra strength side walls and clear Lucite for easy positioning. Easy to fill and easy to drain, the phantoms are leak proof and are excellent for transmission imaging. View Cutsheet 210205

Confirmed, will in hot lab, not scan room

W x D x H: 28 x 1.25 x 20.5 in.

Weight: 18 lbs.

Well Counter, Rod Source — AE #: DCRS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	RADQUAL	BM08		Countertop	OF/OI	Project

Calibrated rod sources, 3". Calibration accuracy of ± 3% – 5% at a 95% confidence level. See accessories for nuclide choices. Price is quoted for Barium, Cesium, and Cobalt. View Cutsheet 210436

Price still pending response from RadQual

W x D x H: 0.47 x N/A x 3 in.

Room: Alcove, Crash Cart **Department:** Imaging (1st Floor)

Room #: B106Q1

Room Notes: Located just outside hot lab

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Alcove, Crash Cart

Department: Imaging (1st Floor)

Room #: B106Q1

Room Notes: Located just outside hot lab

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Office, Shared / Meeting

Department: Imaging (1st Floor)

Room #: B107A

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Office, Private

Department: Imaging (1st Floor)

Room #: B107B

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Off-Stage, Team Work Area

Department: Imaging (1st Floor)

Room #: B107C, B107D

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Staff)

Department: Imaging (1st Floor)

Room #: B107E

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Hold

Department: Imaging (1st Floor)

Room #: D104

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Room: Soiled Hold

Department: Imaging (1st Floor)

Room #: D104

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Hold

Department: Imaging (1st Floor)

Room #: D104

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Waiting

Department: Lab - Phlebotomy

Room #: A100W2

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Greeter

Department: Lab - Phlebotomy

Room #: A101A

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Storage **Department: Lab - Phlebotomy**

Room #: A101B

Room Notes: All mobile MEQ from alcove moved here.

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons — View Cutsheet 166130

W x D x H: 20.5 x 16 x 36 in.

Cart, Supply — AE #: CASU-62

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	5 FT METROMAX		Floor	OF/VI	Project

5-tier polymer shelving unit, unit consists of 5 shelves, solid bottom shelf, (2) swivel and (2) swivel brake casters, on casters; with side and back enclosure panels — View Cutsheet 127935

W x D x H: 60 x 24 x 72 in.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Network: Wired

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. — View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz
Struct Notes: Wall mount: wall channel is 19"h. Basket is 12.75"w x 7.75"d x 5.9"h. Pivot arm is 8"d.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Storage **Department:** Lab - Phlebotomy

Room #: A101B

Room Notes: All mobile MEQ from alcove moved here.

Monitor, Vital Signs, Component — AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Refrigerator, Undercounter, ADA Height — AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white. View Cutsheet 211261

For Pt nourishment

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A
Weight: 102 lbs.
HVAC Notes: Refrigerant R600a

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Storage **Department: Lab - Phlebotomy**

Room #: A101B

Room Notes: All mobile MEQ from alcove moved here.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Vein Illuminator — AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz. View Cutsheet 168583

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	2

Room: Draw Bay **Department: Lab - Phlebotomy**

Room #: A101C, A101D, A101E, A101G, A101H, A101J, A101K, A101L, A101S, A101T, A101V, A101X, A101Y, A101Z

Bracket, Sharps Container — AE #: BRSC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	FL584		Cart	OF/VI	Project

Sharps container bracket for Flexline and Starsys overbridge systems. Sharps containers sold separately. Bracket also mounts to universal clamp in addition to overbridge hanger rail. View Cutsheet 209427

W x D x H: 9.12 x 6.75 x 8 in.

Cart, Phlebotomy Supply — AE #: CAPS-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Clinton Industries, Inc.	67200		Floor	OF/OI	Project

Gray 2-bin phlebotomy cart with 5 leg aluminum base and lockable door. View Cutsheet 208741

W x D x H: 20 x 24 x 43 in.

Cart, Procedure — AE #: CAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

Polymer cart on caster; with (1) 3", (3) 6" and (1) 9" drawer; Electronic PIN locking; Pull handles. View Cutsheet 200197

Drawer configuration to be determined by dept Include side mounted sharps Supplemental Info

W x D x H: 22.7 x 24.9 x 44.7 in.

Chair, Recliner — AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

W x D x H: 34 x 73 x 61 in.
Electrical: 120V 60Hz 4A

Room: Draw Bay **Department: Lab - Phlebotomy**

Room #: A101C, A101D, A101E, A101G, A101H, A101J, A101K, A101L, A101S, A101T, A101V, A101X, A101Y, A101Z

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Cart	OF/OI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Draw Bay **Department: Lab - Phlebotomy**

Room #: A101C, A101D, A101E, A101G, A101H, A101J, A101K, A101L, A101S, A101T, A101V, A101X, A101Y, A101Z

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Rack, Tube Storage

AE #: RATS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Market Lab Inc.	ML7889		Countertop	OF/OI	Project

Extra large acrylic tube organizer for maximum storage of blood collection supplies. 12 tube compartments; 4 with pull out trays for easy tube retrieval; View Cutsheet 90669

organizer on top has hinged lid and 8 compartments; use as freestanding or wall mount

W x D x H: 15.5 x 5.25 x 17.5 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Room: Draw Bay **Department: Lab - Phlebotomy**

Room #: A101C, A101D, A101E, A101G, A101H, A101J, A101K, A101L, A101S, A101T, A101V, A101X, A101Y, A101Z

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Work Area **Department: Lab - Phlebotomy**

Room #: A101F

Room Notes: With clean sink and dirty sink

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Work Area **Department: Lab - Phlebotomy**

Room #: A101F

Room Notes: With clean sink and dirty sink

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Ice Maker — AE #: ICMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	7CI112A-NW-CL-ST-0000	Champion 7	Countertop	OF/CI	Project

Champion 7 ice maker only, does not dispense water. Produces up to 100 lbs. of Chewblet ice daily and has 7 lbs. ice storage capacity. Touchless dispensing. Claris ion exchange scale-inhibiting filter. View Cutsheet 211074

** If unit is to be connected to drain, specify Follett Drip Tray Drain Kit/4" legs part #01535343

For specimens that need to be on ice.

W x D x H: 14.6 x 22.4 x 17.6 in. **Clearance:** Rear 2 in.; Left 3 in.; Right 3 in.
Electrical: 115V 60Hz 3.8A 1-Phase **Weight:** 74 lbs.
Elect Notes: Connect to 15A dedicated circuit, fuse, or breaker.
Plumb Notes: Push in 1/4" water connection. Does not require drain. Water pressure 10-70 psi. Water temperature 40-90 F.
HVAC Notes: Air cooled. Refrigerant R513A.

Room: Work Area **Department: Lab - Phlebotomy**

Room #: A101F

Room Notes: With clean sink and dirty sink

Lab Refrigerator, Undercounter — AE #: LARU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	TSX505SAVK		Undercounter	OF/VI	Project

5.5 cu. Ft. Undercounter lab refrigerator. Automatic defrost. Solid door. Three shelves. Full color tft-lcd; 4:3"; 480 x 272 display. View Cutsheet 164935

For specimen integrity and chilled tubes. Per Amy Gewirtz, does NOT need emergency power.

W x D x H: 23.6 x 26 x 31.8 in.
Electrical: 115V 60Hz 5A
Elect Notes: Plug type: nema 5-15p. 100-240v, 50-60hz. 10 amps max / 3 amp steady state.

Lab Splash Shield — AE #: LASS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fisher Scientific - Thermo	14-293-38		Countertop	OF/OI	Project

Nalgene polycarbonate safety splash shield with 14" flexible arm. Shield is 0.12" thick. Magnetic base grips to magnetic surfaces. Provides UV protection from 200-360 nm. Do not use with radioisotopes. View Cutsheet 210685

W x D x H: 12 x 8.5 x 15 in.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet, (Patient Specimen) **Department: Lab - Phlebotomy**

Room #: A101F1, A101F2, A101F3, A101F4

Room Notes: Pass-thru to be spec'd by HGA

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard — AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance. View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet, (Patient Specimen) **Department: Lab - Phlebotomy**

Room #: A101F1, A101F2, A101F3, A101F4

Room Notes: Pass-thru to be spec'd by HGA

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office, Shared

Department: Lab - Phlebotomy

Room #: A101M, A101P

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Clean Supply / Meds **Department: Lab - Phlebotomy**

Room #: A101N

Room Notes: Will need further direction from Supply Chain - Dept does not currently use PAR-Ex. Will still likely need additional supply carts.

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system — No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Supply, 36x24x67 — AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) — View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility — AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Clean Supply / Meds **Department: Lab - Phlebotomy**

Room #: A101N

Room Notes: Will need further direction from Supply Chain - Dept does not currently use PAR-Ex. Will still likely need additional supply carts.

Drug Dispensing Unit

AE #: DRDU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 2-Drawer Main		Countertop	OF/VI	Lease

ES platform: 2-drawer main unit

View Cutsheet 150403

W x D x H: 22.8 x 27 x 27.8 in.
Network: Wired
Electrical: 120V 60Hz 3A **Weight:** 300 lbs.
Struct Notes: Counter height recommended 24" max to provide good ergonomics. Countertop depth required 30" to accommodate unit and provide stability. Raised edge countertop recommended.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Equipment **Department: Lab - Phlebotomy**

Room #: A101N1

Room Notes: Leave space for Interpretor IPad and WOW. All other mobile MEQ moved to new storage room.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. hand sanitizers requested outside doors to room

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Equipment (Stretcher)

Department: Lab - Phlebotomy

Room #: A101N2

Room Notes: Parking space for stretcher.

Room: Nourishment
Department: Lab - Phlebotomy
Room #: A101Q
Room Notes: Staff Nourishment

Coffee Brewer

AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately.

View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Nourishment
Department: Lab - Phlebotomy
Room #: A101Q
Room Notes: Staff Nourishment

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in.
Clearance: Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A
Weight: 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in.
Clearance: Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Nourishment **Department: Lab - Phlebotomy**

Room #: A101Q

Room Notes: Staff Nourishment

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers — No Cutsheet 141809

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter, ADA Height — AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white. — View Cutsheet 211261

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.
HVAC Notes: Refrigerant R600a

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. — View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Soiled Hold

Department: Lab - Phlebotomy

Room #: A101R

Room Notes: *Allow space for hopper*

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/VI	Service Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available.

View Cutsheet 208721

For red container

W x D x H: 11.5 x 16 x 16.5 in.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-17/L2-17		Floor	OF/OI	Supply Agreement

17 Gallon Red Sharps Container with Slide Lid Top.

View Cutsheet 205911

W x D x H: 13.3 x 17.5 x 24.8 in.

Room: Soiled Hold

Department: Lab - Phlebotomy

Room #: A101R

Room Notes: *Allow space for hopper*

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Room: Soiled Hold

Department: Lab - Phlebotomy

Room #: A101R

Room Notes: *Allow space for hopper*

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Draw Bay, Large

Department: Lab - Phlebotomy

Room #: A101U, A101W

Bracket, Sharps Container

AE #: BRSC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	FL584		Cart	OF/VI	Project

Sharps container bracket for Flexline and Starsys overbridge systems. Sharps containers sold separately. Bracket also mounts to universal clamp in addition to overbridge hanger rail. View Cutsheet 209427

W x D x H: 9.12 x 6.75 x 8 in.

Cart, Phlebotomy Supply

AE #: CAPS-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Clinton Industries, Inc.	67200		Floor	OF/OI	Project

Gray 2-bin phlebotomy cart with 5 leg aluminum base and lockable door. View Cutsheet 208741

W x D x H: 20 x 24 x 43 in.

Cart, Procedure

AE #: CAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

Polymer cart on caster; with (1) 3", (3) 6" and (1) 9" drawer; Electronic PIN locking; Pull handles. View Cutsheet 200197

Drawer configuration to be determined by dept Include side mounted sharps Supplemental Info

W x D x H: 22.7 x 24.9 x 44.7 in.

Chair, Recliner

AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

W x D x H: 34 x 73 x 61 in.
Electrical: 120V 60Hz 4A

Room: Draw Bay, Large

Department: Lab - Phlebotomy

Room #: A101U, A101W

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Cart	OF/OI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Draw Bay, Large

Department: Lab - Phlebotomy

Room #: A101U, A101W

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Rack, Tube Storage

AE #: RATS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Market Lab Inc.	ML7889		Countertop	OF/OI	Project

Extra large acrylic tube organizer for maximum storage of blood collection supplies. 12 tube compartments; 4 with pull out trays for easy tube retrieval; View Cutsheet 90669

organizer on top has hinged lid and 8 compartments; use as freestanding or wall mount

W x D x H: 15.5 x 5.25 x 17.5 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Room: Draw Bay, Large

Department: Lab - Phlebotomy

Room #: A101U, A101W

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Toilet (Staff)

Department: Lab - Phlebotomy

Room #: A108E, A108F, A108G

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Specialty Pharmacy

Department: Pharmacy (Specialty) and Boutique

Room #: C100D

Room Notes: Assumes no medical equipment required in this area

Room: Display

Department: Pharmacy (Specialty) and Boutique

Room #: C102

Coffee Brewer

AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Cup

AE #: DICU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	San Jamar	C3200PGR	GRAINGER 6ADL7	Wall	OF/CI	Project

Stainless steel cup dispenser for 6-10 oz cups. View Cutsheet 141423

W x D x H: 4.75 x 4.75 x 34.8 in.

Ice Maker / Water Dispenser

AE #: IMWD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	7CI112A-IW-CL-ST-00	Champion 7	Countertop	OF/CI	Project

Ice and Water Dispenser. 7 LB Ice Storage Capacity. Integral Air-Cooled Machine with up to 100 Lb. Daily Production of Chewblet Ice. Internal Claris Filter. View Cutsheet 210599

** If unit is to be connected to drain, specify Follett Drip Tray Drain Kit/4" legs part #01535343

W x D x H: 14.6 x 22.4 x 17.6 in. **Clearance:** Rear 2 in.; Left 3 in.; Right 3 in.
Electrical: 115V 60Hz 3.8A **Weight:** 74 lbs.
Elect Notes: NEMA 5-15
Plumb Notes: See Attached Spec Sheet. Water inlet: 1/4" push-in. Factory equipped external water filter connection: (2) 1/4" push-in (in and out) (hot water models only).
Water temperature: 40 - 90 F (4 - 32 C). Water pressure: 10 - 70 psi (69 - 482 kpa). Water consumption: 12 gal (45.4 L) of potable water per 100 lb (45.4 kg) of ice
** If unit is to be connected to drain, specify Follett Drip Tray Drain Kit/4" legs part #01535343
Struct Notes: ** if using 4" accessory legs, add 4" to height

Room: Display

Department: Pharmacy (Specialty) and Boutique

Room #: C102

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Cashier **Department: Pharmacy (Specialty) and Boutique**

Room #: C102A

Room Notes: Point of sale system works on UKHC PC.

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Cash Drawer — AE #: CADR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	APG Vasario	JB554A-BL1820-C		Desk	OF/CI	Project

Series 4000 cash drawer heavy duty black cash drawer, industrial-grade steel ball bearing slides. Lock has latch mechanism and a four-function lock assembly. View Cutsheet 210219

W x D x H: 18.8 x 20 x 4.2 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Undercounter mounting brackets (2) and screws (4)	PK-27-D-BX	1	1

Pole Display, Point of Sale — AE #: PDPS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Logic Controls	LDX9000		Desk	OF/OI	Project

2x20 line pole display with 9.5mm character height. View Cutsheet 210225

W x D x H: 8.5 x 8 x 23.2 in.

Network Notes: Options for interface include USB or serial

Electrical: 115V 60Hz 1A

Weight: 2.7 lbs.

Room: Cashier **Department: Pharmacy (Specialty) and Boutique**

Room #: C102A

Room Notes: Point of sale system works on UKHC PC.

Printer, Receipt — AE #: PRRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Epson	TM-T88V w/USB connection	C31CA85084	Desk	OF/OI	Project

Thermal receipt printer; supports all leading mobile operating systems including iOS, Android, and Windows. Printing up to 300mm/second. View Cutsheet 210218

W x D x H: 5.71 x 7.68 x 5.83 in.
Network: Wired
Network Notes: DHCP enabled model available for IP/network configuration. Supports 802.11a/b/g/n with 2.4GHz/5GHz compatibility and Bluetooth 2.1+EDR.
Electrical: 115V 60Hz
Weight: 3.5 lbs.

Reader, Credit Card — AE #: RECC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	VeriFone	MX915		Desk	OF/OI	Project

Desktop credit card reader View Cutsheet 210226

To be acquired through the Treasury Department at UK.

W x D x H: 8.9 x 7.2 x 2.2 in.
Network: Wired
Network Notes: Connect I/O with Ethernet 10/100BaseT, USB host/device, serial interfaces; RS-232, RS-485, IBM Tailgate, WiFi, Bluetooth optional. ***PC at POS station is to be configured with (7) USB ports.***
Electrical: 115V 60Hz
Weight: 1.3 lbs.

Scanner, Barcode — AE #: SCBA-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Honeywell Safety Products	Hyperion 1300g		Desk	OF/OI	Project

General duty handheld linear scanner, wireless. Automatic interface detection. View Cutsheet 210221

W x D x H: 3.1 x 4.4 x 5.9 in.
Network Notes: Multi-Interface/includes RS232 (TTL +5V, 4 Signals)/KBW/USB (HID keyboard, serial, IBM OEM); RS-232C (±12V) and IBM RS485 supported via adapter cable
Weight: 0.35 lbs.

Room: Cashier

Department: Pharmacy (Specialty) and Boutique

Room #: C102A

Room Notes: Point of sale system works on UKHC PC.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Cashier Work Area

Department: Pharmacy (Specialty) and Boutique

Room #: C102B

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Exam

Department: Pharmacy (Specialty) and Boutique

Room #: C102C

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department.

W x D x H: 20 x 20 x 24.5 in.

Room: Exam

Department: Pharmacy (Specialty) and Boutique

Room #: C102C

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended.

View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.

Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Consult

Department: Pharmacy (Specialty) and Boutique

Room #: C102D, C102E

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department.

W x D x H: 20 x 20 x 24.5 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Pharmacy Receiving

Department: Pharmacy (Specialty) and Boutique

Room #: C103A

Allowance, Bins

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Akro-Mils / Myers Industries			Cart	OF/OI	Project

specify color when ordering

View Cutsheet 76370

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

Cart for collecting cardboard waste.

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Cart, Supply

AE #: CASU-69

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	SUPER ERECTA	A566BC/A2460BR	Floor	OF/VI	Project

Adjustable super erecta chrome plated wire stem caster cart with 5 shelves, (4) posts; 5" casters (2 swivel, 2 brake). 60"w x 24"d x 69"h.

View Cutsheet 62298

To have 3 wire shelves and solid bottom shelf

W x D x H: 60 x 24 x 69 in.

Cart, Supply, Corner Unit

AE #: CSCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	5N567C / 5AN557C		Floor	OF/VI	Project

Chrome plated 5-tier unit with 74" posts. Configuration consists of a 60"w x 24"D x 74" starter unit and a 48"W x 24"D x 74"H add on unit. Two S hooks for each shelf come with the add-on unit and connect the two units together.

View Cutsheet 209457

W x D x H: N/A x N/A x 74 in.

Room: Pharmacy Receiving

Department: Pharmacy (Specialty) and Boutique

Room #: C103A

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Sani Wipe

AE #: DISW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Professional Disposables International	P010901		Wall	OF/CI	Supply Agreement

Sani-Bracket 3-in-1; for use with Sani-Cloth canisters

View Cutsheet 146438

W x D x H: 6 x 6 x 8.25 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Pharmacy Receiving

Department: Pharmacy (Specialty) and Boutique

Room #: C103A

Rack, Crutch

AE #: RACR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sammons Preston / Patterson	081186501		Wall	OF/CI	Project

Wall mounted storage rack for storing up to 12 canes, crutches and/or walkers. Designed to hold up to 30 lbs of weight. The rack comes with 2 bases each 33"L x 5.25"H to provide a combined 66" of storage space. Hangers extend 16.5" from the wall.

View Cutsheet 207964

W x D x H: 66 x 16.5 x 5.25 in.

Rack, Drying

AE #: RADR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	20080		Countertop	OF/OI	Project

Wire drying rack designed for countertop use

For CPAP equipment (masks, etc.)

View Cutsheet 171508

W x D x H: 18 x 7 x 20.5 in.

Safe

AE #: SAFE-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gardall Safe Corporation	DS3020-G-C		Cabinet	OF/CI	Project

Heavy duty cash register safe features recessed door, hard plate around lock with independent relocker, front loading depository, UL listed, anchoring holes in bottom, (3) 1" round bolts and full length dead bolt, 1/2" plate steel door. "B" rate construction. Add 2" to outside depth for dial and handle.

Inside dimensions for cash drawer section: 19.5"W x 17.2"D x 12.25"H.

View Cutsheet 209177

W x D x H: 20 x 20 x 30 in.

Weight: 233 lbs.

Shelving, High Density

AE #: SHHD-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Spacesaver Corp.	Custom		Floor	OF/CI/VI	Project

High density shelving system with two stationary end units (84"W x 18"D) and two moving center carriages (84"W x 36"D). Each section has 4 shelves that are 16-3/4" apart, which are adjustable at 1-1/2" increments.

View Cutsheet 210235

W x D x H: 154 x 94.5 x 82.3 in.

Room: Pharmacy Receiving

Department: Pharmacy (Specialty) and Boutique

Room #: C103A

Slat Wall

AE #: SLWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	SWO4W		Wall	OF/CI	Project

Slat wall will hold bins, hooks and accessories / package of 6 View Cutsheet 158038

To be mounted to wall above countertops. Set of 6 sections. Place as many as will fit on south and west wall.

W x D x H: 48 x 0.75 x 12 in.

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA View Cutsheet 150156

standards. Liner retainer band holds bags in place. Color: Red

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

For collecting packaging

W x D x H: 22 x 22 x 33.8 in.

Room: Break Room
Room #: C103C

Department: Pharmacy (Specialty) and Boutique

Coffee Brewer

AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Break Room
Room #: C103C

Department: Pharmacy (Specialty) and Boutique

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in.
Clearance: Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A
Weight: 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in.
Clearance: Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Break Room
Room #: C103C

Department: Pharmacy (Specialty) and Boutique

Ice Maker / Water Dispenser, Component

AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers

No Cutsheet 141809

Microwave Oven, Commercial

AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required

View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Request from Mark Filburn to monitor temperature for all staff breakroom refrigerators.

Network: Wired

Refrigerator Freezer, Upright

AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant.

View Cutsheet 208926

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Room: Break Room

Department: Pharmacy (Specialty) and Boutique

Room #: C103C

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling w/ Lid/Sign

AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Toilet (Staff)

Department: Pharmacy (Specialty) and Boutique

Room #: C103D

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Pharmacy Work Area **Department: Pharmacy (Specialty) and Boutique**

Room #: C104

Room Notes: Plan for undercounter printers and 1 MFD (IT). Need room temp monitoring. May need arms for PCs at workstations (IT). Configurations to be verified.

Allowance, Pharmacy Shelving

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Southwest Solutions Group			Floor	OF/VI	Project

Allowance for Pharmacy shelving and workstations — View Cutsheet 208862

Allowance to cover shelving units, bag storage racks, narcotic cabinet, drying rack, and workstations/tables. — Supplemental Info

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons — View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Cabinet, Narcotics — AE #: CANA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Spacesaver Corp.	Custom		Floor	OF/CI/VI	Project

Cost included in shelving allowance. — No Cutsheet 208806

Prefer to be mounted to floor, in end-cap positions at end of two rows of shelving.

W x D x H: 24 x 12 x 72 in.

Cart, Sharps Container — AE #: CASC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/VI	Service Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available. — View Cutsheet 208721

For black pharmacy waste bin

W x D x H: 11.5 x 16 x 16.5 in.

Room: Pharmacy Work Area **Department:** Pharmacy (Specialty) and Boutique

Room #: C104

Room Notes: Plan for undercounter printers and 1 MFD (IT). Need room temp monitoring. May need arms for PCs at workstations (IT). Configurations to be verified.

Cart, Utility

AE #: CAUT-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Lakeside Mfg. Co.	311C		Floor	OF/OI	Project

Cart, utility, three shelves, 22 gauge stainless steel capacity of 200 lbs., 4" swivel casters, option available 2 with brakes, shelves of 15-1/2"; shelf clearance of 11-3/4". View Cutsheet 165092

W x D x H: 27.5 x 16.3 x 32.1 in.

Weight: 29 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
4" Casters, 2 With Brake		1	2

Counter, Tablet

AE #: COTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Kirby Lester	KL1		Countertop	OF/OI	Project

Tablet counter for almost all non translucent oral solid medication. Funnel diameter of 5.2 inches. Up to 15 tables/capsules per second. View Cutsheet 169814

W x D x H: 5.6 x 12.5 x 14.6 in.

Electrical: 110V 60Hz **Weight:** 6.95 lbs.

Data Management System

AE #: DAMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Scriptpro	SP Datapoint		Desk	OF/VI	Lease

Compact, interactive countertop unit for entering, filling, verifying, dispensing, and tracking prescriptions. It integrates an adjustable height touchscreen monitor, barcode scanner, and optional SP Printer labeling device to provide workflow control and dispensing accuracy. SP Datapoint works in conjunction with ScriptPro's SP Central Pharmacy Management, Workflow, Telepharmacy, and Pouch Packaging Systems to process prescriptions from point of entry to point of sale. It displays on-screen prescription status lists, automates the collation of patient prescriptions, and provides paperless prescription tracking and batching for each patient. Width includes barcode scanner. Width without scanner: 14.5". View Cutsheet 209650

W x D x H: 18 x 12.5 x 20.4 in.

Network: Wired

Electrical: 120V 60Hz 1.4A **Weight:** 43.2 lbs.

Room: Pharmacy Work Area **Department: Pharmacy (Specialty) and Boutique**

Room #: C104

Room Notes: Plan for undercounter printers and 1 MFD (IT). Need room temp monitoring. May need arms for PCs at workstations (IT). Configurations to be verified.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Freezer, Undercounter, ADA Height

AE #: FRUA-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	FZR4P-00-00		Undercounter	OF/VI	Project

Medical grade freezer with forced air cooling. Stainless steel construction on interior/exterior. 3.9 cu ft. Storage capacity. Programmed automatic defrost. External product temperature display in degrees f or c. Top mounted led controls. Mechanical lock with 2 keys. Integral high/low temperature alarm. 2 epoxy coated wire shelves. Self closing stainless steel door. Depth of unit is 25.6. With façade, depth is 27". View Cutsheet 158910

W x D x H: 23.8 x 27 x 31.4 in.
Electrical: 115V 60Hz 7.1A 1-Phase
Elect Notes: Nema 5-15 90 degree hospital grade plug. 7' cord
HVAC Notes: R404a refrigerant 10 oz. 2157 btu/hr

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Glycerine 16 Oz Bottle	959296	1	1

Mat, Anti-Fatigue

AE #: MAAF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Grainger	45WM09		Floor	OF/OI	Project

Antifatigue Mat. Pebble, 2 ft x 4 ft, 3/8 in Thick, Black, PVC Foam, Beveled Edge. View Cutsheet 207951

One at each workstation and at Robot

W x D x H: 48 x 24 x 0.38 in.

Room: Pharmacy Work Area **Department: Pharmacy (Specialty) and Boutique**

Room #: C104

Room Notes: Plan for undercounter printers and 1 MFD (IT). Need room temp monitoring. May need arms for PCs at workstations (IT). Configurations to be verified.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Printer, Label — AE #: PRLA-33

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Scriptpro	SP Printer		Desk	OF/VI	Lease

ScriptPro's SP Printer works with ScriptPro's SP Datapoint to produce high quality direct thermal prescription labels. The printer can be used in a horizontal or vertical position. View Cutsheet 209653

One at each workstation in the center of the work area. Not needed at workstation by receiving area.

W x D x H: 13.8 x 11 x 6.2 in.
Electrical: 120V 60Hz 2A **Weight:** 53 lbs.
HVAC Notes: Dissipated heat 200 BTU/hr.

Room: Pharmacy Work Area **Department: Pharmacy (Specialty) and Boutique**

Room #: C104

Room Notes: Plan for undercounter printers and 1 MFD (IT). Need room temp monitoring. May need arms for PCs at workstations (IT). Configurations to be verified.

Refrigerator, Double Door Glass

AE #: RDDG-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Lab Research Products Inc.	LRP-HC-LP-49-TS		Floor	OF/VI	Project

Glass door laboratory refrigerator with 49 cu. ft. capacity. Two swing glass doors, self closing, right hinged, not reversible. Touchscreen digital temperature display and alarm module. 8 shelves adjustable in 1/2" increments. White powder coated steel exterior and interior. Swivel casters 3.5" diameter. Probe access port (3/8"). Keyed door locks. Cycle defrost. ETL listed.

View Cutsheet 208935

Model confirmed by Brooke Rauch in email to Jennifer Ratner 7/10/2023.

W x D x H: 54 x 34.8 x 81.8 in.
Clearance: Front 25 in.
Electrical: 115V 60Hz 4.5A 1-Phase
Weight: 488 lbs.
Elect Notes: NEMA 5-15 plug; cord located near bottom on left side while facing the front of the unit.
HVAC Notes: Refrigerant R290; 1/4 H.P.

Robotic System, Pharmacy

AE #: ROSP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Scriptpro	SP100		Floor	OF/VI	Lease

Robotic prescription dispensing center with 6-slot collating control center. Interfaces with Pharmacy computer system to fill, label, and collate up to 150 vials/hr. Holds up to 100 dispensing cells. Count accuracy of 99.7%. Gravity based dispensing.

View Cutsheet 208808

W x D x H: 123 x 28.5 x 78 in.
Clearance: Left 0.5 in.; Right 0.5 in.; Front 16.5 in.
Network: Wired
Network Notes: Ethernet pharmacy computer connection. Firewall provided for network connectivity. Remote support requirements: VPN over high-speed internet connection.
Electrical: 115V 60Hz 16A
Weight: 1198 lbs.
Elect Notes: UPS included with system. Dedicated 20A power outlet required within 10' of power connection.
HVAC Notes: Heat dissipation: 1926 BTU/hour max

Shelving, Pharmacy

AE #: SHPH-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
28	Southwest Solutions Group	12x30		Floor	OF/VI	Project

Custom shelving unit 30"W x 12"D x 85.25"H

No Cutsheet 211634

W x D x H: 30 x 12 x 85.3 in.

Room: Pharmacy Work Area **Department:** Pharmacy (Specialty) and Boutique

Room #: C104

Room Notes: Plan for undercounter printers and 1 MFD (IT). Need room temp monitoring. May need arms for PCs at workstations (IT). Configurations to be verified.

Shelving, Pharmacy — AE #: SHPH-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Southwest Solutions Group	12x48		Floor	OF/VI	Project

No Cutsheet 209094

W x D x H: 48 x 12 x 85.3 in.

Shelving, Pharmacy — AE #: SHPH-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
12	Southwest Solutions Group	12x36		Floor	OF/VI	Project

Custom shelving unit 36"W x 12"D x 85.25"H

No Cutsheet 209128

W x D x H: 36 x 12 x 85.3 in.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin — AE #: WARR-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Rubbermaid Commercial Products	2957-73		Floor	OF/OI	Project

Large blue recycle bin with universal recycle symbol. 41.25 qt capacity.

View Cutsheet 90480

W x D x H: 11 x 15.3 x 19.9 in.

Weight: 2.5 lbs.

Room: Pharmacy Work Area **Department: Pharmacy (Specialty) and Boutique**

Room #: C104

Room Notes: Plan for undercounter printers and 1 MFD (IT). Need room temp monitoring. May need arms for PCs at workstations (IT). Configurations to be verified.

Workbench

AE #: WORK-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Southwest Solutions Group	Custom		Floor	OF/VI	Project

Workstation with work surface and upright section with bins for tech/pharmacist access. Can fit back to back to allow tech/pharmacist interaction. Cost included in allowance. No Cutsheet 208809

Cost included in allowance.

W x D x H: 72 x 35 x 78 in.
Electrical: 115V 60Hz

Room: Pharmacy Will Call **Department:** Pharmacy (Specialty) and Boutique

Room #: C104A

Cabinet, Storage

AE #: CAST-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
9	Southwest Solutions Group	Custom		Floor	OF/VI	Project

Storage cabinet with 4 horizontal rods and reusable bags that hold patient prescriptions in pick up / will call area. Cost carried in allowance. View Cutsheet 208811

Cost included in allowance noted in Pharmacy Work room.

W x D x H: 30 x 12 x 55.3 in.

Cash Drawer

AE #: CADR-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Scriptpro	Single Cash Drawer		Desk	OF/VI	Lease

Single cash drawer for use with ScriptPro SP Datapoint, SP Checkpoint, or SP Station systems. Includes 5 bill storage compartments, 5 coin storage compartments, media storage lockable. View Cutsheet 210241

Will sit directly on desk under SP label printer.

W x D x H: 18 x 16.8 x 3.85 in. **Clearance:** Front 10 in.
Weight: 25.3 lbs.

Data Management System

AE #: DAMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Scriptpro	SP Datapoint		Desk	OF/VI	Lease

Compact, interactive countertop unit for entering, filling, verifying, dispensing, and tracking prescriptions. It integrates an adjustable height touchscreen monitor, barcode scanner, and optional SP Printer labeling device to provide workflow control and dispensing accuracy. SP Datapoint works in conjunction with ScriptPro's SP Central Pharmacy Management, Workflow, Telepharmacy, and Pouch Packaging Systems to process prescriptions from point of entry to point of sale. It displays on-screen prescription status lists, automates the collation of patient prescriptions, and provides paperless prescription tracking and batching for each patient. Width includes barcode scanner. Width without scanner: 14.5". View Cutsheet 209650

W x D x H: 18 x 12.5 x 20.4 in.
Network: Wired
Electrical: 120V 60Hz 1.4A **Weight:** 43.2 lbs.

Room: Pharmacy Will Call **Department:** Pharmacy (Specialty) and Boutique

Room #: C104A

Mat, Anti-Fatigue

AE #: MAAF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Grainger	45WM09		Floor	OF/OI	Project

Antifatigue Mat. Pebble, 2 ft x 4 ft, 3/8 in Thick, Black, PVC Foam, Beveled Edge. View Cutsheet 207951

W x D x H: 48 x 24 x 0.38 in.

Printer, Label

AE #: PRLA-33

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Scriptpro	SP Printer		Desk	OF/VI	Lease

ScriptPro's SP Printer works with ScriptPro's SP Datapoint to produce high quality direct thermal prescription labels. The printer can be used in a horizontal or vertical position. View Cutsheet 209653

W x D x H: 13.8 x 11 x 6.2 in.
Electrical: 120V 60Hz 2A **Weight:** 53 lbs.
HVAC Notes: Dissipated heat 200 BTU/hr.

Printer, Receipt

AE #: PRRE-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Scriptpro	Receipt Printer w/Customer Display		Desk	OF/VI	Lease

Thermal receipt printer with customer display. View Cutsheet 210242

W x D x H: 7.27 x 13.3 x 13.5 in.
Electrical: 115V 60Hz 1.6A 1-Phase **Weight:** 14.55 lbs.

Scanner, Prescription

AE #: SCPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Scriptpro	Script Scanner		Desk	OF/VI	Lease

Script Scanner interfaces with ScriptPro's Workflow Management and Pharmacy Management Systems to scan and electronically store images of hard copy prescriptions. View Cutsheet 209654

W x D x H: 11.8 x 9.5 x 8.5 in.
Network Notes: Connects directly to SP Datapoint. Does not require a dedicated network jack.
Electrical: 120V 60Hz 1.5A **Weight:** 9.2 lbs.

Room: Pharmacy Will Call

Department: Pharmacy (Specialty) and Boutique

Room #: C104A

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	2957-73		Floor	OF/OI	Project

Large blue recycle bin with universal recycle symbol. 41.25 qt capacity.

View Cutsheet 90480

W x D x H: 11 x 15.3 x 19.9 in.

Weight: 2.5 lbs.

Room: Pharmacy Consult

Department: Pharmacy (Specialty) and Boutique

Room #: C104B

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Pharmacy Consult
Room #: C104B

Department: Pharmacy (Specialty) and Boutique

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department.

W x D x H: 20 x 20 x 24.5 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance. View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Pharmacy Compounding

Department: Pharmacy (Specialty) and Boutique

Room #: C104C

Bin, Plastic

AE #: BIPL-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Uline	S-16295		Refrigerator	OF/OI	Project

One carton with 24 clear plastic shelf bins. Each bin is 4"W x 18"D x 4"H. Nestable when empty. Molded-in label holder. View Cutsheet 210455

W x D x H: 4 x 18 x 4 in.

Bin, Plastic

AE #: BIPL-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Uline	S-16297		Refrigerator	OF/OI	Project

One carton of (12) clear plastic shelf bins. Each bin measures 8.5"W x 18"D x 4"H. Nestable when empty. Molded-in label holder. View Cutsheet 210456

W x D x H: 8.5 x 18 x 4 in.

Cart, Sharps Container

AE #: CASC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/VI	Service Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available. View Cutsheet 208721

For black pharmacy waste bin

W x D x H: 11.5 x 16 x 16.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Pharmacy Compounding

Department: Pharmacy (Specialty) and Boutique

Room #: C104C

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Pharmacy Compounding
Room #: C104C

Department: Pharmacy (Specialty) and Boutique

Hood, Powder

AE #: HOPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nu Aire, Inc.	NU-S813-400		Floor	OF/VI	Project

Class i containment ventilated enclosure; intended to provide personnel protection when handling low-risk aerosols and particulate matter; can be single hepa filtered and externally exhausted or dual hepa filtered and recirculated; interior work area 46-3/8"w x 24"d x 28"h; to include motorized stand; custom 11"" access opening; led lighting; "s" in part number is due to the special access opening and lighting. **overall height reflects highest dimension with motorized stand.**

View Cutsheet 168376

W x D x H: 48.1 x 30.8 x 91.1 in.
Electrical: 115V 60Hz 2A **Weight:** 400 lbs.
Elect Notes: **refer to vendor's specification sheets.** hood has 12’ power cord 14 ga-3 wire, 15 amps; motorized stand should be a 15-amp rating. Requires two separate electrical connections - one for hood and one for motorized stand.
Plumb Notes: **refer to vendor's specification sheets.**
HVAC Notes: **refer to vendor's specification sheets.** required exhaust 287 cfm; inflow 80 fpm; static 0.1" w.g.**
Struct Notes: **refer to vendor's specification sheets.**

Lab Stirrer

AE #: LSTI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	VWR Scientific Products	76447-032		Hood	OF/OI	Project

Advanced magnetic hotplate-stirrer with aluminum 7"x7" top plate. Temperature range 5-340 degrees C. Maximum capacity 10L. Speed range 60-1600 rpm.

View Cutsheet 208810

W x D x H: 8.8 x 12.2 x 4.8 in.
Electrical: 120V 60Hz 10A 1200W **Weight:** 7.8 lbs.

Pharmacy, Accessory

AE #: PHAC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	Glass Ointment Slab	3098	Countertop	OF/OI	Project

Glass ointment slab suitable for mixing various preparations.

View Cutsheet 210450

W x D x H: 12 x 12 x 0.25 in.

Room: Pharmacy Compounding

Department: Pharmacy (Specialty) and Boutique

Room #: C104C

Pharmacy, Accessory

AE #: PHAC-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	Flint Glass Mortar and Pestle Set, 16 oz	3075	Countertop	OF/OI	Project

Flint glass mortar and pestle set, 16 oz. Can be sterilized, cleaned w/alcohol, or washed with soap and water. Not recommended for drastic temperature changes.

View Cutsheet 210454

Pharmacy, Accessory

AE #: PHAC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	Flint Glass Mortar and Pestle Set, 8 oz	3075	Countertop	OF/OI	Project

Flint glass mortar and pestle set, 8 oz. Can be sterilized, cleaned with alcohol, or washed with soap and water. Not recommended for use with drastic temperature changes.

View Cutsheet 210453

Pharmacy, Accessory

AE #: PHAC-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	Glass Graduated Cylinder Kit, Small	11166	Countertop	OF/OI	Project

Glass graduated cylinder kit, small includes (1) each of the following glass cylinder sizes: 5ml, 10ml, 25ml, 50ml, 100ml, and two cylinder brushes 9" and 13" long.

View Cutsheet 210452

Pharmacy, Accessory

AE #: PHAC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	Beaker Kit, Small	11169	Countertop	OF/OI	Project

Kit includes (2) glass beakers of each of the following sizes: 30ml, 50ml, 100ml, and 250ml. White enamel scale on glass. Safe for use on hot plates.

View Cutsheet 210451

Rack, Drying

AE #: RADR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Southwest Solutions Group			Wall	OF/CI	Project

Wall mounted pharmacy drying rack with pegs

No Cutsheet 209099

W x D x H: 36 x 36 x 4 in.

Room: Pharmacy Compounding
Room #: C104C

Department: Pharmacy (Specialty) and Boutique

Scale, Gram

AE #: SCGR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sartorius	QUINTIX213-1S 210g		Hood	OF/OI	Project

Weighing capacity 210g. Readability and repeatability 1mg. Weighing pan size 120mm. Weighing chamber height 209mm. Fully automatic internal adjustment, direct data transfer, ergonomic style, touchscreen user interface.

View Cutsheet 208772

W x D x H: 8.58 x 14.1 x 12.6 in.
Electrical: 115V 15Hz 0.2A

Sink Module

AE #: SIMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Southwest Solutions Group	Custom		Floor / Wall	OF/CI/VI	Project

Module with double basin sink and black epoxy countertop.

View Cutsheet 211784

Supplemental Info

W x D x H: 81 x N/A x 84 in.
Plumb Notes: Hot and cold water required. Exact specifications to be determined. Fillmaster water purification filter system (WPSC-02) to connect to plumbing under sink.

Stool, With Back

AE #: STWB-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-555-GS		Floor	OF/OI	Project

16" x 17" cushioned seat. 21 1/2" diameter chrome base. Adjustable back support. Easy rolling 2.5" casters. Pneumatic height adjustment of 25 5/8" to 33". Adjustable back rest.

View Cutsheet 143172

W x D x H: 21.5 x 21.5 x 33 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Pharmacy Compounding
Room #: C104C

Department: Pharmacy (Specialty) and Boutique

Waste Receptacle, Recycle Bin

AE #: WARR-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2957-73		Floor	OF/OI	Project

Large blue recycle bin with universal recycle symbol. 41.25 qt capacity. View Cutsheet 90480

W x D x H: 11 x 15.3 x 19.9 in.

Weight: 2.5 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

For collecting HDPE #2 plastic

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Water Purification System, Component

AE #: WPSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fillmaster Systems, Llc	Fillmaster Digital	3600	Wall	OF/CI/VI	Project

Fillmaster Digital push button water dispenser for reconstituting medications. Integrated reconstitution database and NDC barcode reader (optional); View Cutsheet 208800

connects to FillPure Water Purification System. Wall mountable. Dispensing quantity 9ml - 999ml. Accuracy: +/-0.3ml at 9ml, +/- 3ml at 300ml.

W x D x H: 5 x 3 x 18 in.
Elect Notes: Battery powered
Plumb Notes: Dispenses water from system tank.

Water Purification System, Component

AE #: WPSC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fillmaster Systems, Llc	FillPure Water Purification System		Wall	OF/CI	Project

System taps into incoming water line to supply pharmacy with unlimited USP grade purified water on demand. For reconstitution, non-sterile View Cutsheet 208801

compounding. System consists of: filter (16"W x 5.75"D x 14.5"H; 7.5 lbs.) and water tank (12" diameter x 15.5"H, 8 lbs. empty).

Plumb Notes: Requires water source. Refer to manufacturer's site planning guide.

Room: Pharmacy Work / Office

Department: Pharmacy (Specialty) and Boutique

Room #: C104D

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2957-73		Floor	OF/OI	Project

Large blue recycle bin with universal recycle symbol. 41.25 qt capacity.

View Cutsheet 90480

W x D x H: 11 x 15.3 x 19.9 in.

Weight: 2.5 lbs.

Room: Resource Library **Department:** Resource Center

Room #: A100W4

Room Notes: Pamphlet racks/shelving (furniture), Computers

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. One dispenser needed by each door.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult, Family **Department:** Resource Center

Room #: A100W7, A106F

Bin, Shredder

AE #: BISH-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	MINI CONSOLE		Countertop	OF/VI	University

18 Gal Capacity Mini Console Shred Bin. Front Loading with Small Access Slot. View Cutsheet 143985

W x D x H: 20.3 x 19.6 x 26 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Meditation **Department:** Resource Center

Room #: A104

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Consult **Department:** Resource Center

Room #: A106A, A106B, A106C, A106D, A106E, A106G, A106H, A106J, A106K, A106L, A106M, A106N, A106Q

Room Notes: (9) Reg Consult, (4) Genetics Consult with additional shelving.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Office, Shared

Department: Resource Center

Room #: A106R, A106S, A106T, A106P

Room Notes: Space for 3-4 people

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Office, Shared **Department:** Resource Center

Room #: A106U

Room Notes: Space for 3-4 people

Safe, Valuables

AE #: SAVA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Barska	AX13496		Floor	OF/CI	Project

The Biometric Fireproof Security Safe series by BARSKA is designed to provide maximum security for your valuables. Features with fireproof construction, two solid-steel long locking bar bolts, and pry-resistant recessed door for maximum security. The biometric scanner module allows you to quickly and securely access to your valuables in seconds with a simple scan of the fingerprint.

View Cutsheet 209496

To be stacked per Joan.

W x D x H: 17.3 x 19.7 x 228 in.

Weight: 100.8 lbs.

Elect Notes: Operates on 4 AA batteries

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Storage **Department:** Resource Center

Room #: A106V

Room Notes: Resource Center FL1. ParEx may not be used here. Still TBD

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023. ParEx may not be used here. Still TBD.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Supply, 48x24x68 AE #: CASU-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Intermetro Industries	Super Adjustable Super Erecta	5A556BC	Floor	OF/VI	Project

Supply Cart, 5-Shelf Wire Shelving Stem Caster Cart, Chrome, 5" wheel size with 600lb load capacity View Cutsheet 208682

6 shelves preferred

W x D x H: 50 x 26.2 x 67.9 in.

Weight: 92 lbs.

Room: RC Nutrition Storage Closet (6th Floor) **Department:** Resource Center

Room #: B605C1

Cart, Supply, 48x24x68

AE #: CASU-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	Super Adjustable Super Erecta	5A556BC	Floor	OF/VI	Project

Supply Cart, 5-Shelf Wire Shelving Stem Caster Cart, Chrome, 5" wheel size with 600lb load capacity View Cutsheet 208682

6 shelves preferred

W x D x H: 50 x 26.2 x 67.9 in.

Weight: 92 lbs.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter, ADA Height

AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white. View Cutsheet 211261

W x D x H: 19.8 x 22.6 x 32 in.

Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.

Room: Waiting

Department: Urgent Care

Room #: A100W3

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Reception **Department: Urgent Care**

Room #: A103A

Room Notes: 1 registration workstation

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight **Department:** Urgent Care

Room #: A103A1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz 15W

Weight: 107 lbs.

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Room: Alcove, Height / Weight

Department: Urgent Care

Room #: A103A1

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Treatment Room **Department: Urgent Care**

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Chair, Recliner

AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

To be same as Infusion recliner. Place holder pending confirmation of that model.

W x D x H: 34 x 73 x 61 in.
Electrical: 120V 60Hz 4A

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Treatment Room **Department:** Urgent Care

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Room: Treatment Room **Department:** Urgent Care

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation.

includes installation

View Cutsheet 212153

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Room: Treatment Room **Department:** Urgent Care

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Monitor, Physiological

AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 115V 60Hz 1.8A
Weight: 12.3 lbs.

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.
Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: Treatment Room **Department: Urgent Care**

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Treatment Room **Department:** Urgent Care

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Treatment Room **Department:** Urgent Care

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1). View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Thermometer, Electronic, Oral

AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Room: Treatment Room **Department: Urgent Care**

Room #: A103B, A103C, A103E, A103F, A103H, A103R, A103T, A103U, A103V, A103W, A103X

Room Notes: Patient recliners to be provided as furniture.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area

Department: Urgent Care

Room #: A103D

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case

View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless

Network Notes: Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter

View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area

Department: Urgent Care

Room #: A103G

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Medication Alcove **Department:** Urgent Care

Room #: A103G1

Room Notes: Located within On-Stage Team Work Area

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Crusher, Tablet — AE #: CRTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	Rx Crush	19846	Countertop	OF/OI	Project

Rolling mechanism pulverizes tablets into fine powder, works with ENFit bags and syringe (sold separately). View Cutsheet 201339

W x D x H: 6.74 x 12 x 4.25 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Medication Alcove **Department: Urgent Care**

Room #: A103G1

Room Notes: Located within On-Stage Team Work Area

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

Per Katie Plahn email 9/14/2023

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Medication Alcove **Department:** Urgent Care

Room #: A103G1

Room Notes: Located within On-Stage Team Work Area

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
Elect Notes: 15a dedicated ground circuit; nema 5-15 hospital grade plug 8-10 ft. Battery backup.
HVAC Notes: Variable speed compressor-based forced air refrigeration system; r600a, isobutane, epa snap compliant refrigerant charge

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, POCT

Department: Urgent Care

Room #: A103H1

Bracket, Sharps Container

AE #: BRSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	0203WMA		Wall	OF/CI	Project

Locking wall mount bracket and key for 2 & 3 gallon containers

View Cutsheet 209292

For 2 gallon sharps container

W x D x H: 13 x 5.75 x 2.75 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Alcove, POCT **Department: Urgent Care**

Room #: A103H1

Lab Analyzer, Urine — AE #: LAUR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	CLINITEK STATUS +	BAH1780	Countertop	OF/OI	Project

Point-of-care urinalysis with touch screen user interface. View Cutsheet 103504

Likely not needed, confirm in upcoming meetings.

W x D x H: 6.7 x 10.7 x 6.2 in.
Network: Wired
Network Notes: Uni-directional via serial port rs232
Electrical: 120V 60Hz 15W
Weight: 3.65 lbs.
Elect Notes: 6 aa batteries, non-rechargeable

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter — AE #: REUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF4P		Undercounter	OF/VI	Project

3.9 cu ft refrigerator fits below ada height counter. Stainless steel interior and exterior. Top-mounted controls. User-selectable product or air temp display. High/low temp alarms. Programmable operating range 2-10 degrees celsius / 36-50 dg fahrenheit (factory preset 4 dg c). Two (2) epoxy-coated wire shelves. Dry contacts. Magnetic gasket, self-closing door. User-selectable temp display in unit c or f. Cabinet-wide temp remains within =/- 1 degree c with frequent door opening. Programmed defrost cycles. Depth of cabinet is 25.6". Depth with façade is 27". View Cutsheet 139889

W x D x H: 23.8 x 27 x 31.4 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 4.1A
Weight: 205 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Room: Alcove, POCT

Department: Urgent Care

Room #: A103H1

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Undercounter	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Office, APP

Department: Urgent Care

Room #: A103J

Room Notes: Space for 6 people

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient)

Department: Urgent Care

Room #: A103K, A103L

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Urgent Care

Room #: A103K, A103L

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Nourishment Alcove **Department:** Urgent Care

Room #: A103M

Coffee Brewer

AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately. View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Nourishment Alcove **Department:** Urgent Care

Room #: A103M

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Nourishment Alcove **Department:** Urgent Care

Room #: A103M

Ice Maker / Water Dispenser, Component

AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers

No Cutsheet 141809

Microwave Oven, Commercial

AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required

View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter, ADA Height

AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white.

View Cutsheet 211261

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.
HVAC Notes: Refrigerant R600a

Room: Nourishment Alcove

Department: Urgent Care

Room #: A103M

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Crash Cart **Department:** Urgent Care

Room #: A103M1

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Alcove, Crash Cart **Department:** Urgent Care

Room #: A103M1

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Soiled Utility **Department:** Urgent Care

Room #: A103N

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

Increased quantity to put in exam rooms when needed for procedures.

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.*** View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly. View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Room: Soiled Utility

Department: Urgent Care

Room #: A103N

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Soiled Utility **Department:** Urgent Care

Room #: A103N

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue.

View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supplies / Equipment / Linen **Department:** Urgent Care

Room #: A103P

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.
HVAC Notes: 1604 BTU/hr

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.
Weight: 6 lbs.

Room: Clean Supplies / Equipment / Linen **Department:** Urgent Care

Room #: A103P

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Room: Clean Supplies / Equipment / Linen **Department:** Urgent Care

Room #: A103P

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Network Notes: Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails View Cutsheet 107953

Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A
Weight: 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Room: Clean Supplies / Equipment / Linen **Department:** Urgent Care

Room #: A103P

Pump, I.V., Component — AE #: PIVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	BD / Alaris Medical Systems	8120 - PCA		Shelf	OF/VI	Lease

Pca module. View Cutsheet 148466

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 4.5 x 7.5 x 15 in.

Pump, I.V., Component — AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Pump, I.V., Component — AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Becton Dickinson	Alaris 8100	8100	Shelf	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	4

Room: Clean Supplies / Equipment / Linen

Department: Urgent Care

Room #: A103P

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Scanner, Bladder

AE #: SCBL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Verathon Inc. - Medical	i10	0270-1014	Stand	OF/VI	Project

Bladder scanner i10 system; on rolling stand.

View Cutsheet 200466

Electrical: 120V 60Hz 1.4A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand	0800-0631	1	1

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff.

View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: Clean Supplies / Equipment / Linen **Department:** Urgent Care

Room #: A103P

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

For holding spare IV pump components

W x D x H: 24 x 24 x 72 in.

Suction Machine — AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments View Cutsheet 159014 allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Vein Illuminator — AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x View Cutsheet 168583 2.4" x 7.9", 9.7 oz.

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	2

Room: Clean Supplies / Equipment / Linen **Department:** Urgent Care

Room #: A103P

Warmer, Blood/ Fluid

AE #: WABF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Smiths Medical Md Inc	HOTLINE	HL-90	Stand	OF/OI	Project

Blood and iv fluid warmer can deliver normothermic fluid at routine flow rates. Tubing design surrounds the patient line with a layer of 42dgc circulating fluid, eliminating patient line cool down. System is compatible with standard iv sets, infusion pumps an in-line hand pumps. View Cutsheet 63925

W x D x H: 24 x 18 x 67 in.
Electrical: 120V 60Hz 3A **Weight:** 7.6 lbs.
Struct Notes: Dimensions shown are with stand

Room: Equipment **Department: Urgent Care**

Room #: A103Q

Room Notes: For stretchers and patient lift

Lifter, Patient — AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor. View Cutsheet 208837

Want higher weight capacity than this model has. Walsh to review options.

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Stretcher — AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Room: Treatment AII

Department: Urgent Care

Room #: A103S

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Chair, Recliner

AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

To be same as Infusion recliner. Place holder pending confirmation of that model.

W x D x H: 34 x 73 x 61 in.
Electrical: 120V 60Hz 4A

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Treatment All

Department: Urgent Care

Room #: A103S

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes.

View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208701

CO2, and N2O. All Flowmeters come with a standard 1/8

Room: Treatment AII

Department: Urgent Care

Room #: A103S

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation.

includes installation

View Cutsheet 212153

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz
Weight: 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Monitor, Physiological

AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle.

View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 115V 60Hz 1.8A
Weight: 12.3 lbs.

Room: Treatment All **Department:** Urgent Care

Room #: A103S

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Room: Treatment AII

Department: Urgent Care

Room #: A103S

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A
Weight: 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Room: Treatment AII

Department: Urgent Care

Room #: A103S

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks

View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Treatment AII **Department:** Urgent Care

Room #: A103S

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Thermometer, Electronic, Oral

AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius

View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet, Connected (Patient)

Department: Urgent Care

Room #: A103S1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet, Connected (Patient)

Department: Urgent Care

Room #: A103S1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Staff)

Department: Urgent Care

Room #: A108A

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office, Private

Department: Urgent Care

Room #: A108C

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Clean Supply (Pick)

Department: ASC Materials Management

Room #: A202A

Bin, Shredder

AE #: BISH-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	95 GALLON TOTE		Floor	OF/OI	University

95 gallon tote with high security lid.

View Cutsheet 166419

W x D x H: 25 x 34.3 x 48 in.

Cart, Supply

AE #: CASU-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Single		Floor	OF/VI	Project

Single Starsys cart with clear glass door and combination lock. One shelf with 2' above and the others 1'. Height adjustable.

View Cutsheet 211378

For room temp tissue. Sports med, ENT, Ophthalmology, Breast Oncology will have items in this cart.

W x D x H: 22.7 x 28 x 78 in.

Weight: 158 lbs.

Cart, Supply

AE #: CASU-70

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Logiquip Healthcare Storage Solutions	72x24x80		Floor	OF/VI	Project

Stainless steel cart with 8 solid shelves

No Cutsheet 211737

W x D x H: 72 x 24 x 80 in.

Cart, Supply

AE #: CASU-98

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Logiquip Healthcare Storage Solutions	60x18x80		Floor	OF/VI	Project

Stainless steel wire cart with 8 shelves

No Cutsheet 211738

W x D x H: 60 x 18 x 80 in.

Cart, Supply

AE #: CASU-97

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Logiquip Healthcare Storage Solutions	48x18x80		Floor	OF/VI	Project

Stainless steel cart with 8 solid shelves

No Cutsheet 211739

W x D x H: 48 x 18 x 80 in.

Room: Clean Supply (Pick) **Department:** ASC Materials Management

Room #: A202A

Cart, Supply — AE #: CASU-96

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Logiquip Healthcare Storage Solutions	36x24x80		Floor	OF/VI	Project

Stainless steel cart with 8 solid shelves — No Cutsheet 211740

W x D x H: 36 x 24 x 80 in.

Cart, Supply — AE #: CASU-95

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Logiquip Healthcare Storage Solutions	36x18x80		Floor	OF/VI	Project

Stainless steel cart with 8 solid shelves — No Cutsheet 211741

W x D x H: 36 x 18 x 80 in.

Chest, Dry Ice — AE #: CHDI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Global Industrial	POLAR PB02	WB442903	Floor	OF/OI	Project

Polar chest insulated dry ice container designed for storing and transporting dry ice. Rubber strap holds lid in place. Lockable lid included. Optional lockable lid w/silicone gasket to reduce sublimation. 2 cu ft capacity. Color blue. — View Cutsheet 150885

W x D x H: 29 x 20 x 23 in.

Freezer, Ultra-Low — AE #: FLUL-31

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Panasonic Healthcare	MDF-DU502VHA-PA		Floor	OF/VI	Project

Ultra Low (-86 Degrees Celsius) Freezer. 18.6 Cubic Feet. Door mounted color LCD touchscreen control. Three adjustable shelves. 110 lb. shelf capacity. Optional monitoring system. — View Cutsheet 203695

W x D x H: 31.1 x 34.7 x 78.5 in.
Clearance: Rear 4.1 in.; Left 3 in.; Right 0.8 in.
Electrical: 115V 60Hz 9.6A
Weight: 542 lbs.
Elect Notes: Requires NEMA 5-20P Receptacle.
Struct Notes: External cabinet depth of 3.75" permits passage through a standard 38" doorway when rear stand off brackets are removed (four screws). Bracket removal not required for a 40" doorway.

Room: Clean Supply (Pick) **Department:** ASC Materials Management

Room #: A202A

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Blood Bank, Single Door — AE #: REBB-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF25i-BB		Floor	OF/VI	Project

Upright 24.6 ft. capacity refrigerator with 6 full-extension stainless steel drawers, dual pane glass door with full length handle w/cylinder lock, and (4) swiveling dual wheel casters with toe locks. Full stainless steel cabinet interior and exterior. Audible and visual high/low temperature, door open, power failure, and low battery alarms. Energy star rated View Cutsheet 211193

model: REF25i-BB-R-00-00-G

W x D x H: 29.8 x 36.5 x 79.5 in. **Clearance:** Rear 2 in.; Top 10 in.
Electrical: 115V 60Hz 2.5A **Weight:** 427 lbs.
Elect Notes: NEMA 5-15P hospital grade plug and 9' cord. Maximum size of branch circuit overcurrent device - 15A dedicated circuit.
HVAC Notes: Integral top-mounted refrigeration module with 1/3 hp compressor and air-cooled condenser. Non-CFC R134a refrigerant (11.4 oz). BTU/hr normal heat rejection 1060 BTU/hr; maximum heat rejection continuous operation 3210 BTU/hr.
Struct Notes: 10" top clearance needed

Room: Clean Supply (Pick) **Department:** ASC Materials Management

Room #: A202A

Shelving, High Density

AE #: SHHD-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Logiquip Healthcare Storage Solutions	Custom		Floor	OF/CI/VI	Project

High-density shelving system with a total of (18) 72"w x 24"D racks with 8 solid stainless steel shelves each. Units are 72"W x 24"D and are stacked two-deep in an end-to-end configuration. The units on each end are stationary and the remaining units are mobile along a surface mounted floor track with handles for moving. Weight reflects anticipated total weight of system including carts and contents.

View Cutsheet 211735

Supplemental Info

W x D x H: 290 x 152 x 80 in.

Weight: 5.31E+04 lbs.

Struct Notes: Surface mounted floor track / frame is made of heat-treated aluminum. It must be bolted to the floor using Hilti bolts.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Materials Management **Department:** ASC Materials Management

Room #: A208E

Cart, Utility

AE #: CAUT-46

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	1066BE		Floor	OF/OI	Project

Tough structural foam won't rust, chip or dent. Two 2-5/8" deep trays are 18 7/8" apart. Non-marking 5" casters: 2 swivel, 2 rigid View Cutsheet 159705

W x D x H: 26 x 46 x 33 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Staff Lockers

Department: ASC Materials Management

Room #: A210A, A210B

Receiver, Scrub

AE #: RSCR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cintas Corporation	R-110		Floor	OF/VI	Lease

150 to 200 Piece Scrub Receiver. View Cutsheet 208634

Rent, $0. Each staff can have up to 5 pieces: tops, pants, jacket (any combination up to 5 pieces). Want in an area where there is a camera, can have male and female to share.

W x D x H: 41 x 33 x 78 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 440 lbs.
Elect Notes: 20 Amp Service Required

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Vending (Scrubs) **Department:** ASC Materials Management

Room #: B200S4

Dispenser, Scrub

AE #: DSCR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cintas Corporation	D-16		Floor	OF/VI	Lease

800 Piece Scrub Dispenser. View Cutsheet 208635

W x D x H: 108 x 35 x 90 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 1100 lbs.
Elect Notes: 20 AMP Service Required.

Receiver, Scrub

AE #: RSCR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cintas Corporation	R-110		Floor	OF/VI	Lease

150 to 200 Piece Scrub Receiver. View Cutsheet 208634

Rent, $0. Each staff can have up to 5 pieces: tops, pants, jacket (any combination up to 5 pieces). Want in an area where there is a camera, can have male and female to share.

W x D x H: 41 x 33 x 78 in.
Network: Networked
Electrical: 120V 60Hz **Weight:** 440 lbs.
Elect Notes: 20 Amp Service Required

Room: Vendor Scrub Alcove

Department: ASC Materials Management

Room #: SP09583

Dispenser, Scrub

AE #: DISB-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	RepScrubs	ScrubPort	TCN NSC-10C	Floor	OF/VI	Service Agreement

RepScrubs® supports vendor visits by ensuring compliance with credentialing management program, infection prevention, expense reduction, patient safety, and tracking reports, all with one closed-loop system. Automated system is built on connecting supply chain, surgical services, vendor compliance and infection control teams with an automated process. Holds 140 sets of scrubs.

View Cutsheet 211223

W x D x H: 44.1 x 33.4 x 76.4 in.

Clearance: Left 37 in.; Right 11 in.

Network: Wireless

Network Notes: Uses cellular modem technology. An IT interface isn't required.

Electrical: 120V 60Hz 46W

Weight: 430 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, Compact Breathing System (CBS) specifically designed for low-flow anesthesia. View Cutsheet 211557

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Quote Q-90711-14 received from Scott Campbell on 9-30-2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera Head

AE #: CAHE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TH121		Boom	OF/VI	Project

IMAGE1 S 4U RUBINA, OPAL1® NIR/ICG S-TECHNOLOGIES — No Cutsheet 204782

Price included in Storz video integration

Camera, In-Light

AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Room: Operating Room

Department: ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer.

View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined.

View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid

View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization. View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit

AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit

AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System

AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.
Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.

Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC).

View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices

View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system

View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression — AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V. — AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component — AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System — AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Scope, Endoscope — AE #: SCEN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 5MM X29 CM, Autoclave.

View Cutsheet 211801

Price included in Storz Video Integration

Scope, Endoscope — AE #: SCEN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 5MM X 29CM, AUTOCLAVE

View Cutsheet 211803

Price included in Storz Video Integration.

Smoke Evacuation — AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, Basin, Double — AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and View Cutsheet 11322

polished stainless steel construction; 2" conductive double ball bearing swivel casters.

W x D x H: 21.3 x 16.3 x 39 in.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: View Cutsheet 123850

black

W x D x H: 24 x 24 x 44 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs

View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5";

View Cutsheet 123943

specify teardrop, wedge or saddle seat type.

Without back or arms

Table, Instrument

AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters

View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Instrument

AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters

View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Surgical

AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based. View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8") View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Monitor — AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes View Cutsheet 140046

pole mounting clamp. All mounting options/accessories are free of charge.

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201A

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Alcove, Scrub **Department: ASC Operating Rooms**

Room #: A201A1, A201C1, A201E1, A201F1, A201G1, A207B1, A207D1, A210C1

Room Notes: Per responsibility matrix, scrub sinks to be planned by architects and engineers.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Stretcher **Department:** ASC Operating Rooms

Room #: A201A2, A201C2, A201E2, A201F2, A201G2, A207B2, A207D2, A210C2

Room Notes: Assumes parking spot for patient stretcher while in OR

Rack, Video Integration

AE #: RAVI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Middle Atlantic	SRSR-X-14		Cabinet/Wall	OF/CI	Project

Slide out and rotate 14RU rack with 14 usable rack spaces. Weight capacity 200 lbs. Usable depth: 21.25" (2" setback) - 23" (1/4" setback). Color black. View Cutsheet 213000

W x D x H: 19.1 x 23.1 x 27.5 in. **Clearance:** Left 5.6 in.; Right 5.6 in.
Weight: 57 lbs.

HVAC Notes: Cabinet needs to be cooled to dissipate heat created by electronics.
Struct Notes: Left and right clearances are outside the cabinet when rack is rotated. They are NOT required inside the cabinet.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Room: Anesthesia Workroom

Department: ASC Operating Rooms

Room #: A201B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, Compact Breathing System (CBS) specifically designed for low-flow anesthesia. View Cutsheet 211557

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera Head

AE #: CAHE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TH121		Boom	OF/VI	Project

IMAGE1 S 4U RUBINA, OPAL1® NIR/ICG S-TECHNOLOGIES — No Cutsheet 204782

Price included in Storz video integration

Camera, In-Light

AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer.

View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined.

View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid

View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization. View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit

AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit

AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System

AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.
Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.

Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC).

View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices

View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system

View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System

AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Scope, Endoscope

AE #: SCEN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 5MM X29 CM, Autoclave.

View Cutsheet 211801

Price included in Storz Video Integration

Scope, Endoscope

AE #: SCEN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 5MM X 29CM, AUTOCLAVE

View Cutsheet 211803

Price included in Storz Video Integration.

Smoke Evacuation

AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, Basin, Double — AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and View Cutsheet 11322

polished stainless steel construction; 2" conductive double ball bearing swivel casters.

W x D x H: 21.3 x 16.3 x 39 in.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: View Cutsheet 123850

black

W x D x H: 24 x 24 x 44 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; View Cutsheet 123943

specify teardrop, wedge or saddle seat type.

Without back or arms

Table, Instrument

AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Instrument

AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Surgical

AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based. View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8") View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Monitor — AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes View Cutsheet 140046

pole mounting clamp. All mounting options/accessories are free of charge.

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Alcove, Imaging Work **Department:** ASC Operating Rooms

Room #: A201C3

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure

View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	10

Rack, Apron

AE #: RAAP-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Wolf X-Ray Corporation	Penta 16410		Wall	OF/CI	Project

5 Apron

View Cutsheet 205923

W x D x H: 17 x 23.5 x 4.6 in.

Struct Notes: Wall backing required. Mounting screws not included.

Room: Dictation / Physician Work

Department: ASC Operating Rooms

Room #: A201D1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, Compact Breathing System (CBS) specifically designed for low-flow anesthesia. View Cutsheet 211557

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera Head

AE #: CAHE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TH121		Boom	OF/VI	Project

IMAGE1 S 4U RUBINA, OPAL1® NIR/ICG S-TECHNOLOGIES — No Cutsheet 204782

Price included in Storz video integration

Camera, In-Light

AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Room: Operating Room

Department: ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer.

View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined.

View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid

View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization. View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit — AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit — AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System — AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.

Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.

Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC).

View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices

View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system

View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System

AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Smoke Evacuation

AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, Basin, Double — AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo — AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: black View Cutsheet 123850

W x D x H: 24 x 24 x 44 in.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; specify teardrop, wedge or saddle seat type. View Cutsheet 123943

Without back or arms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Instrument — AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters — View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Table, Instrument — AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters — View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Surgical — AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. — No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based.

View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8")

View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Video Integration System, Monitor

AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system

View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201E

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes pole mounting clamp. All mounting options/accessories are free of charge. View Cutsheet 140046

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, Compact Breathing System (CBS) specifically designed for low-flow anesthesia. View Cutsheet 211557

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera Head

AE #: CAHE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TH121		Boom	OF/VI	Project

IMAGE1 S 4U RUBINA, OPAL1® NIR/ICG S-TECHNOLOGIES — No Cutsheet 204782

Price included in Storz video integration

Camera, In-Light

AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Room: Operating Room

Department: ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer.

View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined.

View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid

View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization. View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit — AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit — AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System — AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.
Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.
Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC). View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System

AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Smoke Evacuation

AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, Basin, Double — AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo — AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: black View Cutsheet 123850

W x D x H: 24 x 24 x 44 in.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; View Cutsheet 123943

specify teardrop, wedge or saddle seat type.

Without back or arms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Instrument

AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Instrument

AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Table, Surgical

AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based.

View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8")

View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Video Integration System, Monitor

AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system

View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201F

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes View Cutsheet 140046
pole mounting clamp. All mounting options/accessories are free of charge.

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, Compact Breathing System (CBS) specifically designed for low-flow anesthesia. View Cutsheet 211557

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera, In-Light — AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia — AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. — View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart — View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer. View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined. View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser.

View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization.

View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit

AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit

AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System

AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.
Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.

Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC).

View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices

View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system

View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System — AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Scope, Endoscope — AE #: SCEN-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 10MM X31 CM, Autoclave.

View Cutsheet 211800

Price included in Storz Video Integration.

Scope, Endoscope — AE #: SCEN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 10MM X 31CM, AUTOCLAVE

View Cutsheet 211802

Price included in Storz Video Integration.

Scope, Endoscope — AE #: SCEN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 5MM X29 CM, Autoclave.

View Cutsheet 211801

Price included in Storz Video Integration

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Scope, Endoscope — AE #: SCEN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 5MM X 29CM, AUTOCLAVE

View Cutsheet 211803

Price included in Storz Video Integration.

Smoke Evacuation — AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, Basin, Double — AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo — AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and View Cutsheet 11322

polished stainless steel construction; 2" conductive double ball bearing swivel casters.

W x D x H: 21.3 x 16.3 x 39 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: black View Cutsheet 123850

W x D x H: 24 x 24 x 44 in.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; View Cutsheet 123943

specify teardrop, wedge or saddle seat type.

Without back or arms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Instrument — AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters — View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Table, Instrument — AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters — View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Surgical — AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. — No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based.

View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8")

View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Video Integration System, Monitor

AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system

View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A201G

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes pole mounting clamp. All mounting options/accessories are free of charge. View Cutsheet 140046

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Alcove, Equipment (Large Items) **Department:** ASC Operating Rooms

Room #: A201G3

Imaging, Portable C-Arm

AE #: IMPC-31

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC Elite CFD 31		Floor	OF/VI	Project

OEC Elite CFD Super C-arm with 31 cm digital mobile Ergo c-arm. Efficient positioning with 90°/180° flip flop. Additional range of motion and positioning flexibility with smartview pivot joint. Productive with low lateral height and small ap/lat offset. Max orbital rotation 178° (9") and 181° (12"). View Cutsheet 206509

Software: PMCare

Detector: 31 cm

** Workstation specified separately (34.1"w x 25.8"d x 68.1"h)

Per GE quote 2011152679.2 dated 8/13/2024. Includes wireless DICOM and Sony printer.

W x D x H: 33.2 x 78.7 x 78.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 654 lbs.
Elect Notes: Refer to vendor specifications

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wireless DICOM		1	1

Imaging, Portable C-Arm, Component

AE #: IPCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC ELITE CFD WORKSTATION		Floor	OF/VI	Project

Workstation with 4k display; used in coordination with c-arm for system control and image monitoring View Cutsheet 165014

W x D x H: 34.1 x 25.8 x 68.1 in.
Electrical: 120V 60Hz **Weight:** 428 lbs.

Imaging, Portable Mini C-Arm

AE #: PMCA-001

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC MiniView MAX		Floor	OF/VI	Project

MiniView Max mini C-Arm with wireless DICOM, wireless footswitch, and a printer. View Cutsheet 209331

keep same in database, Quote 2011160625.1 from Winny Wearren 8/14/23.

W x D x H: 29 x 39.1 x 71.7 in.
Network: Wireless
Electrical: 120V 60Hz 4.5A **Weight:** 485 lbs.

Room: Alcove, Equipment (Large Items) **Department:** ASC Operating Rooms

Room #: A201G3

Microscope, Ophthalmic — AE #: OPMI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Zeiss, Inc., Carl	LUMERA 700		Floor	OF/VI	Project

Floor standing surgical microscope with integrated intraoperative rescan 700 oct; assistant & electric zoom

View Cutsheet 164427

700 with optical coherence tomography(OCT) X1. OCT is part of same scope. Quote 00223774 from Philip Loprinzi 4/17/2024 (worked on configurations with Kristine Thompson and Rebecca Webster).

W x D x H: 73 x 31.7 x 74 in.
Electrical: 120V 60Hz 12A **Weight:** 617.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Callisto - Integrated		1	1

Microscope, Ophthalmic — AE #: OPMI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Zeiss, Inc., Carl	LUMERA 700		Floor	OF/VI	Project

Floor standing surgical microscope with integrated intraoperative rescan 700 oct; assistant & electric zoom

View Cutsheet 164427

Lumera 700 x2. Quote 00223771 from Philip Loprinzi 4/17/2024 (worked on configurations with Kristine Thompson and Rebecca Webster).

W x D x H: 73 x 31.7 x 74 in.
Electrical: 120V 60Hz 12A **Weight:** 617.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Callisto - Integrated		1	2

Microscope, Surgical — AE #: MISU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Zeiss, Inc., Carl	Pentero 800 S		Floor	OF/VI	Project

Mobile surgical microscope

View Cutsheet 211333

Quote 00231903 received on 8/15 from Ivan Lyons, set up for ENT, specific configurators not determined with users yet

W x D x H: 32.3 x 59.1 x 105 in.
Network: Wireless
Electrical: 120V 60Hz 10A **Weight:** 804.7 lbs.
Elect Notes: Class 2 laser product

Room: Clean Core **Department: ASC Operating Rooms**

Room #: A202

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023. ParEx may not be used here.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Scope Drying

AE #: CASD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Harloff Company, Inc.	SCW2448DRDP		Wall	OF/CI	Project

Sure Dry wall-mounted scope cabinet holds 4 bronchoscopes or 8 ENT scopes. HEPA filtered positive pressure with 2 high volume intake fans and 1 exhaust fan. Customizable scope holders to fit most common scope types. Adjustable timer (10-180 minutes) for fan operation. Fans automatically activated upon closing of doors. Choose from over 20 colors. View Cutsheet 211480

W x D x H: 24 x 12.8 x 48 in.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Dri-Scope Aid		1	1
Keyless Electronic Push Button Lock		1	1
LED UV-Disinfecting Lights		1	1
Stainless Steel Finish		1	1

Room: Clean Core **Department:** ASC Operating Rooms

Room #: A202

Cart, Crisis

AE #: CACR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Armstrong Medical Industries	PBL-HG-30		Floor	OF/VI	Project

Premier aluminum cart with 30" of drawer space including (1) 3" drawer, (3) 6" drawers, and (1) 9" drawer. Hunter Green drawer fronts. With left sided pull up shelf, 30" breakaway lock bar, and sharps container holder with accessory bar bracket. View Cutsheet 211413

W x D x H: 34.1 x 25 x 46.1 in.

Weight: 109 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Breakaway Locking Bar 30"	PBR-30	1	1
Premier Accessory Panel (2)	PHP-1	1	1
Premier Sharps Container Bracket	PSB-1	1	1
Premier Side Shelf	PSN-3	1	1

Cart, Procedure, Malignant Hyperthermia

AE #: CPMH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Armstrong Medical Industries	PBL-XX-27		Floor	OF/VI	Project

Premier aluminum two-tone cart with (2) 3" drawers, (2) 6" drawers, and (1) 9" drawer. Fold up shelf on left side, and breakaway lock bar. Drawer color TBD. View Cutsheet 211409

Color of existing MH cart is orange, but orange not available from Armstrong. Drawer front color and dividers to be specified at time of purchase.

W x D x H: 34.1 x 25 x 43 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Breakaway Locking Bar 27"	PBR-27	1	1
Premier Side Shelf	PSN-3	1	1

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole. View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Room: Clean Core
Room #: A202

Department: ASC Operating Rooms

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.
Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.
Electrical: 120V 60Hz 1.8A
Weight: 17.5 lbs.
Elect Notes: Lithium-ion battery

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit

View Cutsheet 150404

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A

Room: Clean Core **Department:** ASC Operating Rooms

Room #: A202

Drug Dispensing Unit, Auxiliary — AE #: DDUA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES DOUBLE COLUMN AUXILIARY		Floor	OF/VI	Lease

Double column auxiliary (8 doors) View Cutsheet 158541

W x D x H: 52 x 28 x 79.5 in.
Electrical: 120V 60Hz 3A

Drug Dispensing Unit, Auxiliary — AE #: DRUA-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	PYXIS ES 7-DRAWER AUX		Floor	OF/VI	Lease

Es platform 7-drawer auxiliary drug cabinet View Cutsheet 156732

W x D x H: 22.8 x 27 x 47 in.
Electrical: 120V 60Hz 3A

Evacuation Sled — AE #: EVSL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ethos Evacuation Strategies, LLC	MS36		Bag	OF/OI	Project

Standard 36" sled. Tether and stairwell braking system included. Dimensions are for deployed sled. Stored sled is 9" dia. X 36"w. View Cutsheet 169692

Per direction of Patty Hughes. Confirm specs. Keep here. Amy Boone to review regulations re: OR quantity and number of sleds.

W x D x H: 36 x 87 x N/A in.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Clean Core **Department:** ASC Operating Rooms

Room #: A202

Refrigerator, Pyxis, Full Height — AE #: RPFH-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES REFRIGERATOR		Floor	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the pyxis medstation es system. Features secure locking bins that release when remotely accessed by the medstation es system. Medical grade and supports meeting cdc vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 f / 2-10 c. Casters are standard with unit. View Cutsheet 171479

W x D x H: 24.3 x 29.5 x 70.5 in. **Clearance:** Top 8 in.
Electrical: 115V 60Hz 1.4A **Weight:** 363 lbs.
Elect Notes: 15 amp dedicated ground circuit; NEMA 5-15 hospital grade plug

Suction Machine — AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Equipment

Department: ASC Operating Rooms

Room #: A203

Bracket, Cassette Holder

AE #: BRCH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Phillips Safety Products Inc.	CAS-MB-38479		Floor	OF/VI	Project

Height adjustment from the floor is 6" to 46.5" (Bottom edge of your cassette). Dual pivoting joints enable full 360-degree rotation of the cassette. +/- 90 degrees tilts, allowing for optimal positioning and flexibility. Includes four lockable casters and a heavy base for stability. Compatible with cassettes ranging from 8" x 10" to 17" x 17" including DR Panel Protectors and Grid Encasements.

View Cutsheet 211714

Color: Gunmetal

W x D x H: 22 x 22 x 76 in.

Room: Anesthesia Storage **Department: ASC Operating Rooms**

Room #: A203A

Room Notes: For anesthesia supplies and equipment storage.

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Airway AE #: CAAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	WM-NP3 Mobile Workstation		Floor	OF/VI	Project

Anesthesia airway cart. To include mobile workstation, sterile water holder, drawer unit, 4K 32 inch monitor, video processor, light source and mounting adaptor for flat panel. View Cutsheet 211245

Olympus is current vendor. Anesthesia is open to other vendors. Quote Q-01738835 provided by rep Michael Garvas 08/29/2024.

W x D x H: 27 x 26 x 84 in.

Electrical: 120V 60Hz 16A **Weight:** 185 lbs.

Cart, Supply AE #: CASU-69

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	A566BC/A2460BR	Floor	OF/VI	Project

Adjustable super erecta chrome plated wire stem caster cart with 5 shelves, (4) posts; 5" casters (2 swivel, 2 brake). 60"w x 24"d x 69"h. View Cutsheet 62298

Solid bottom shelf

W x D x H: 60 x 24 x 69 in.

Room: Anesthesia Storage **Department:** ASC Operating Rooms

Room #: A203A

Room Notes: For anesthesia supplies and equipment storage.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glidescope

AE #: GLID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Verathon Inc. - Medical	GS Core		Floor	OF/VI	Project

10” HD touchscreen monitor. Multimodal views simultaneously. Picture-in-picture. Dual connection ports for two video inputs. HDMI out port for external video display. View Cutsheet 201197

W x D x H: 21.3 x 21.3 x 52.8 in.
Electrical: 120V 60Hz 2.5A

Monitor, Neuromuscular

AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.
Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Room: Anesthesia Storage **Department:** ASC Operating Rooms

Room #: A203A

Room Notes: For anesthesia supplies and equipment storage.

Monitor, Transport — AE #: MOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	X3		Shelf	OF/VI	Project

MMS module X3; touchscreen user interface View Cutsheet 170125

W x D x H: 7.4 x 3.4 x 6 in.
Network: Wireless
Electrical: 120V 60Hz 1.3A

Monitor, Transport, Component — AE #: MOTC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Philips Medical Systems - Monitoring	Intellivue Dock	867043	Shelf	OF/VI	Project

Dock provides power to X3, MX100, X2, and MP2 for charging monitors. Additionally intended to provide the connected device with a LAN and flexible sync out interface. Supports variety of measurement extensions. View Cutsheet 209449

W x D x H: 7.5 x 3.9 x 4.4 in.
Electrical: 120V 60Hz **Weight:** 1.61 lbs.
Elect Notes: Power consumption <30 W average

Pump, Epidural — AE #: PUEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Hospira Inc.	SAPPHIRE	16312	Shelf	OF/OI	Project

Epidural infusion pump with delivery rates 0.1-99.9 ml/hr in increments of 0.1 ml/hr; 100-999 ml/hr with increments of 1 ml/hr; system alarms include air in line, cassette misplaced, occlusions, flow error, insufficient battery; battery lifr 24 hours at 125 ml/hr View Cutsheet 161681

W x D x H: 3.78 x 1.93 x 5.63 in.
Electrical: 100V 60Hz 0.6A **Weight:** 0.9 lbs.

Room: Anesthesia Storage **Department:** ASC Operating Rooms

Room #: A203A

Room Notes: For anesthesia supplies and equipment storage.

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
8	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	8

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
16	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	16

Pump, Infusion, Syringe

AE #: PUIS-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
8	Becton Dickinson	SYRINGE MODULE	8110	Pump	OF/VI	Lease

Syringe pump module designed to work with the pc unit. Flow rates from 0.1 cc/hr to 999 cc/hr.accepts syringe sizes from 1 cc up to 60 cc with automatic syringe size detection. View Cutsheet 122746

W x D x H: 4.5 x 5 x 15 in.

Room: Anesthesia Storage **Department:** ASC Operating Rooms

Room #: A203A

Room Notes: For anesthesia supplies and equipment storage.

Scope, Bronchoscope

AE #: SCBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Olympus America, Inc.	Diagnostic		Cart	OF/VI	Project

Diagnostic bronchoscope for airway cart. Model(s) to be determined. No Cutsheet 211376

2 standard adult size approved by Dr. Hassan 6/5/2024. Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

Scope, Bronchoscope Slim

AE #: SCBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Olympus America, Inc.	Diagnostic		Cart	OF/VI	Project

Diagnostic slim bronchoscope for airway cart. Model(s) to be determined. No Cutsheet 211847

2 slim scopes approved by Dr. Hassan 6/5/2024. Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Table, Work

AE #: TAWO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	TWS2460FS-316-S		Floor	OF/VI	Project

316 ALL-STAINLESS WORKTABLE with bottom shelf. Height adjustable 34"-39". View Cutsheet 208668

W x D x H: 60 x 24 x 35 in.

Room: Anesthesia Storage **Department:** ASC Operating Rooms

Room #: A203A

Room Notes: For anesthesia supplies and equipment storage.

Ultrasound, Portable

AE #: ULPO-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Sonosite, Inc.	PX		Stand	OF/VI	Project

15.6 monitor; (3) Transducer ports total; horizontal to vertical work surface; Adjustable height (max 65", min 42"); IPX-7 rated for immersion; Drop-tested to 1 meter; SonoADAPT Imaging Technology; Wifi, Ethernet port

View Cutsheet 209960

W x D x H: 28.3 x 28.3 x 65 in.
Network: Networked
Electrical: 120V 60Hz

Warmer, Rapid Infuser

AE #: WARI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Belmont Medical Technologies	RI-2	903-00037	Stand	OF/VI	Project

Uses electromagnetic induction heating technology. Automatic priming and air removal. Roller type peristaltic fluid pump flow rate 2.5-1000 ml/min. Internal, rechargable battery for transport operates all functions without heating.

View Cutsheet 158305

W x D x H: 7.5 x 13.5 x 12 in.
Electrical: 115V 60Hz **Weight:** 28 lbs.

Warmer, Rapid Infuser, Stand

AE #: WARI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Belmont Medical Technologies	599-00403		Floor	OF/OI	Project

Custom IV pole for Belmont Rapid Infuser RI-2

View Cutsheet 202641

W x D x H: 24 x 24 x 72 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Equipment **Department:** ASC Operating Rooms

Room #: A203G4

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure

View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	5

Imaging, Ultrasound Scanner

AE #: IMUS-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sonosite, Inc.	LX	L28354	Floor	OF/VI	Project

Multipurpose imaging ultrasound system. Features: 11 lbs. storage bin capacity, 19.45 in. W x 15.31 in. H clinical monitor with 1600 x 1200 px resolution, (32 to 104 degrees F operating temperature, 15 to 95 percent R.H. humidity, and 700 to 1060 hPa atmospheric pressure. Imaging modes: 2D (256 gray shades), Color Power Doppler (CPD) (256 colors), Color Doppler (Color) (256 colors), M Mode, Continuous wave (CW) Doppler, Tissue Doppler Imaging (TDI), and Tissue Harmonic Imaging (THI).

View Cutsheet 207216

Becca to follow up.

W x D x H: 23 x 23 x 68 in.
Network: Networked
Electrical: 120V 60Hz 6A **Weight:** 152 lbs.

Rack, Apron

AE #: RAAP-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf X-Ray Corporation	Penta 16410		Wall	OF/CI	Project

5 Apron

View Cutsheet 205923

W x D x H: 17 x 23.5 x 4.6 in.
Struct Notes: Wall backing required. Mounting screws not included.

Room: Med Gas Room **Department:** ASC Operating Rooms

Room #: A207A

Cabinet, Medical Gas Tank

AE #: CMGT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	E.L.S. Products Corp	MG121		Floor	OF/OI	Project

Lockable oxygen storage cabinet, holds 21-24 D and/or E cylinders. With self latch standard door. Optional casters add 4" to height and 30 pounds to weight

View Cutsheet 209279

W x D x H: 44 x 18 x 43 in.

Weight: 265 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Casters-Factory Installed (2 Rigid, 2 Swivel)	CA18	1	2

Cart, Cylinder, Medical Gas

AE #: CCMG-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6061		Floor	OF/OI	Project

Medical gas cylinder cart; holds six (6) m7, m9, c, d or e size cylinders; wheel diameter 10" x 1.75" solid

View Cutsheet 75703

For holding oxygen cylinders (full and empty)

W x D x H: 18 x 15 x 42 in.

Weight: 30 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, View Cutsheet 211557

Compact Breathing System (CBS) specifically designed for low-flow anesthesia.

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera, In-Light — AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia — AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. — View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart — View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer. View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined. View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser.

View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization.

View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit — AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit — AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System — AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.

Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.

Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC).

View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices

View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system

View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit.

View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System — AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Scope, Endoscope — AE #: SCEN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 5MM X 29CM, AUTOCLAVE

View Cutsheet 211803

Price included in Storz Video Integration.

Scope, Endoscope — AE #: SCEN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 5MM X29 CM, Autoclave.

View Cutsheet 211801

Price included in Storz Video Integration

Scope, Endoscope — AE #: SCEN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 10MM X 31CM, AUTOCLAVE

View Cutsheet 211802

Price included in Storz Video Integration.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Scope, Endoscope

AE #: SCEN-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 10MM X31 CM, Autoclave. View Cutsheet 211800

Price included in Storz Video Integration.

Smoke Evacuation

AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, Basin, Double

AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: black View Cutsheet 123850

W x D x H: 24 x 24 x 44 in.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; View Cutsheet 123943

specify teardrop, wedge or saddle seat type.

Without back or arms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Instrument — AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters — View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Instrument — AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters — View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Table, Surgical — AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. — No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based.

View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8")

View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Video Integration System, Monitor

AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system

View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207B

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes pole mounting clamp. All mounting options/accessories are free of charge. View Cutsheet 140046

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Soiled Hold (Neptune Dock) **Department:** ASC Operating Rooms

Room #: A207C

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Hold (Neptune Dock) **Department: ASC Operating Rooms**

Room #: A207C

Fluid Waste Management System — AE #: FWMS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stryker Corp.	Neptune 3 Docking Station		Wall / Floor	OF/CI	Project

Docking station is used in coordination with the Neptune 3 waste management system Rover (listed separately); 2 part system supports the collection of fluid waste in the operating room and disposal of fluids through the docking station. View Cutsheet 156829

W x D x H: 23 x 23 x 16 in.
Electrical: 120V 60Hz 3A
Plumb Notes: **refer to manufacturer's site planning information.** water requirements: pressure range 345 kpa to 827 kpa (50 to 120 psi); temperature range 4.4 to 43.4 deg. C (40 to 110 f) note: for optimal cleaning of the rover canisters, use 37.8 to 43.3 c (100 to 110 f); facility source is equipped with a 3/4" male (garden) hose thread (mht) fitting and has a dedicated shutoff valve; potable tap water; approximately 34 liters (9 gallons) per rinse cycle at default settings on standard cycle, water usage fluctuates due to selected cycle and facility flow; facility backflow prevention device refer to local plumbing codes to determine whether an external backflow prevention device is required. Drainage requirements: floor drain or permanent service connection per local plumbling codes; 2.44 m (8 feet) drain connection distance maximum; internal backflow prevention device: single check valve constructed of materials that comply with nsf / ansi 61 drinking water system components - health effects; water inlet hose 1.27 cm (0.50 inch) inner diameter, 1.83m (6 feet) length; water outlet hose 2.54 cm (1.0 inch) inner diameter, 1.83 m (6 feet) length; water pump outlet flow 23.8 liters/ minute (6.3 gallons/minute); detergent inlet tube 0.635 cm (0.25 inch) outer diameter, 1.2 m (4 feet) length.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, Compact Breathing System (CBS) specifically designed for low-flow anesthesia. View Cutsheet 211557

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera, In-Light — AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia — AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. — View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart — View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer. View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined. View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser.

View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization.

View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit — AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit — AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System — AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.

Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.

Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC).

View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices

View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system

View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System — AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Scope, Endoscope — AE #: SCEN-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 10MM X31 CM, Autoclave.

View Cutsheet 211800

Price included in Storz Video Integration.

Scope, Endoscope — AE #: SCEN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 10MM X 31CM, AUTOCLAVE

View Cutsheet 211802

Price included in Storz Video Integration.

Scope, Endoscope — AE #: SCEN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 5MM X29 CM, Autoclave.

View Cutsheet 211801

Price included in Storz Video Integration

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Scope, Endoscope

AE #: SCEN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 5MM X 29CM, AUTOCLAVE

View Cutsheet 211803

Price included in Storz Video Integration.

Smoke Evacuation

AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, Basin, Double — AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo — AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: black View Cutsheet 123850

W x D x H: 24 x 24 x 44 in.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; View Cutsheet 123943

specify teardrop, wedge or saddle seat type.

Without back or arms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Instrument — AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters — View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Instrument — AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters — View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Table, Surgical — AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. — No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based.

View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8")

View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Video Integration System, Monitor

AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system

View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A207D

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes pole mounting clamp. All mounting options/accessories are free of charge. View Cutsheet 140046

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Ablation System

AE #: ABSY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Arthrex	AR-9800		Cart	OF/VI	Project

Radio-frequency ablation system. Features: Minimally invasive system that effectively ablates and coagulates tissue in arthroscopic procedures. View Cutsheet 208823

Includes footswitch.

W x D x H: 16 x 14.7 x 5.2 in.
Electrical: 110V 60Hz 8A **Weight:** 20 lbs.

Allowance, Positioning Device

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	ZZZ - To Be Determined			Cabinet	OF/OI	Project

Positioning device allowance. No Cutsheet 75402

Allowance for leg/knee positioning devices

Allowance, Scope

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cabinet	OF/VI	Project

No Cutsheet 158668

Autotransfusion Unit

AE #: AUUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	AUTOLOG IQ		Stand	OF/VI	Project

Autotransfusion unit. Variable speed wash process, 3 min processing cycle returns 135 ml to holding bag. Two stage filling process (1st stage 600 ml/min, 2nd stage 600 or 250 ml/min based on incoming volume). Self-start feature. Includes Ship Kit of power cord, how-to-video, allen wrench, tubing insertion tool, and extra fuses. View Cutsheet 208849

W x D x H: 13 x 9 x 66 in.
Electrical: 110V 60Hz 1.6A **Weight:** 70 lbs.

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Axillary Roll, Positioning Device — AE #: ARPD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Action Products, Inc.	Axillary Roll		Cabinet	OF/OI	Project

To aid in positioning patients safely and effectively during procedures. Comes in size small, large and extra long. SMALL: 10" x 4 1/2" x 2" (25.4 x 11.4 x 5 cm) | 40602 LARGE: 14" x 4 1/2" x 2" (35.5 x 11.4 x 5 cm) | 40605 EXTRA-LONG: 18" x 4" x 2" (46 x 10 x 5 cm) | 40615

View Cutsheet 211361

Battery Charger — AE #: BACH-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	FLYTE CHARGER	408-655-000	Cart	OF/OI	Project

8 bay battery charger station for "flyte" helmet.

View Cutsheet 126055

W x D x H: 15 x 10 x 6 in.
Electrical: 120V 60Hz 1.7A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Power Pack	0408-660-000	8	8

Breast Biopsy Guidance System — AE #: BBGS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Mammotome	Neoprobe Gamma Detection System	NPCU4	Cart	OF/VI	Project

Gamma cancer detection system with Bluetooth probes.

View Cutsheet 211386

W x D x H: 14 x 14 x 42 in.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Check Source Holder	P-405	1	1
Neoprobe GDS Cart	NEOCART1	1	1

Cart, Electrosurgical — AE #: CAES-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medtronic / Covidien	VLFTCRT		Floor	OF/OI	Project

Mobile cart for electrosurgical unit. Three shelves. Dimensions include cart and electrosurgical unit.

View Cutsheet 161483

W x D x H: 24 x 24 x 35 in.

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Cart, Equipment

AE #: CAEQ-88

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Arthrex	Lateral Cart with Weights		Floor	OF/VI	Project

Lateral cart with weights to be used with the 3-point shoulder distraction system

No Cutsheet 211363

W x D x H: 24 x 24 x 48 in.

Cart, Equipment

AE #: CAEQ-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Atricure, Inc.	Cart		Floor	OF/VI	Project

General equipment cart. Can accommodate Ablation and Sensing Unit (ASU), Switch Box (ASB3), cryoICE BOX (ACM), Exhaust hose, N2O tank and N2O tank with heater band. ** Provided free of charge with service contract.

View Cutsheet 208847

W x D x H: 27.4 x 35.4 x 67.3 in.

Weight: 150 lbs.

Cart, Equipment

AE #: CAEQ-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	2460FS		Floor	OF/VI	Project

Standard type 304 solid stainless steel shelves with (2) revolving and (2) braking caster wheels.

View Cutsheet 171780

For holding small equipment on shelves

W x D x H: 60 x 24 x 68 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Multi-Tier Shelving		4	8

Cart, Equipment

AE #: CAEQ-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	Starsys Double	SXRD43CM4	Floor	OF/VI	Project

Mobile cart with 2 wire shelves and non-locking doors. Select 2 solid stainless-steel shelves as option.

View Cutsheet 211489

For holding leg positioners

W x D x H: 42.5 x 24.9 x 43 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Double-Wide Full Extension Stainless Steel Shelf	SXR2436FSE	2	4

Room: Equipment

Department: ASC Operating Rooms

Room #: A207E

Cart, Equipment

AE #: CAEQ-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	2448FS / 63UPS		Floor	OF/VI	Project

Cart with 4 solid stainless-steel shelves (2448FS), 4 posts (63UPS), and stem casters (2x 5MPGSA and 2x 5MPBGSA). View Cutsheet 211385

For holding Elucent Envisio navigation system mattress, risers, etc.

W x D x H: 48 x 24 x 68 in.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer. View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Video Procedure

AE #: CAVP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	WM-NP3/OEV-262H		Floor	OF/VI	Project

Mobile workstation (K10035366) with 27" high definition LCD monitor (OEV-262H) View Cutsheet 171517

To include light source, image processor, printer, camera, and all other components. Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

W x D x H: 26.2 x 26.6 x 81.6 in.

Electrical: 120V 60Hz 15A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Ent Scope Hanger	MAJ-2145	2	2
Lcd Monitor Arm	MAJ-2216	1	1
Mountng Adaptor For Flat Panel	FLP-0002-17C	1	1
Nurses Control Arm	MAJ-2167	1	1
Sliding Keyboard	MAJ-2146	1	1
Videoscope Cable Evis Exera Ii	MAJ-1430	1	1
Visera Elite Keyboard	MAJ-1921	1	1

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Cart, Video Procedure

AE #: CAVP-88

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Storz, Karl, Endoscopy America	XUSM0015		Floor	OF/VI	Project

Video Endoscopy Procedure Cart Featuring Image I Connect II Camera with Image I S X-Link Module for Flexible Endoscopes, High Performance 300W LED Light Source, Turret Adapter, 32" 4K Display Monitor [View Cutsheet 201695]

Storz ENT items for Boom mounting

W x D x H: 33 x 29.1 x 75.2 in.
Electrical: 120V 60Hz 12A **Weight:** 396 lbs.

Chair, Beach

AE #: BECH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Smith And Nephew	T Max	7210996	Floor	OF/VI	Project

T-MAX Beach Chair Positioner helps position patients for beach chair shoulder arthroscopy and open procedures. Helps to securely position patients up to 350lbs with a minimum height of 5’2”. Securely holds the patient while positioning and re-positioning between 0 and 90 degrees. The T-Max Beach Chair is designed to be used in conjunction with the Smith and Nephew Spider 1 and Spider 2 Limb Positioners. [View Cutsheet 211338]

Electrical: 120V 60Hz

Charger Stand

AE #: CHST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	719-DSK		Shelf	OF/OI	Project

Universal desk charger with two wells. Compatible with 71140, 719-3, 71910, 71670 handles. 12800 and 22800 used with 71249 adapter sleeve. [View Cutsheet 207032]

For Retinoscope 18245 / 71670

W x D x H: 7.48 x 4.33 x 3.94 in.
Electrical: 110V 60Hz 0.1A **Weight:** 2.65 lbs.
Elect Notes: Comes with 6' long medical grade detachable cord.

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Cochlear Implant System

AE #: COIS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cochlear America	Baha-Cochlear Osscora Console SI-915	SI-915	Shelf	OF/VI	Project

The Baha Osscora Surgical system – which combines a small titanium implant, an abutment, and a sound processor – has yielded excellent results for adults with hearing loss. View Cutsheet 211353

Price includes case and bone conduction instrument set.

W x D x H: 10 x 10 x 3.5 in.
Electrical: 130V 60Hz 1.7A 70W **Weight:** 4.1 lbs.

Electrosurgical Unit

AE #: ELUN-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Arthrocare Corp	COBLATOR II	EC-8000	Cart	OF/OI	Project

Ent coblator ii bipolar surgery system; flow control valve unit dimensions are 4.3"w4.3"h x 8.7"d x 3.5"h View Cutsheet 114496

Need place holder, trialing options, on a cart

W x D x H: 12.5 x 12.4 x 5.25 in.
Electrical: 120V 60Hz 8A

Electrosurgical Unit

AE #: ELUN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	LIGASURE		Cart	OF/OI	Project

Designed to permanently seal vessels and tissue bundles; includes dual function bipolar footswitch and bipolar connector adapter; optional universal mounting cart View Cutsheet 50153

W x D x H: 15.2 x 16 x 5 in.
Electrical: 120V 60Hz 7A **Weight:** 13 lbs.

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Electrosurgical Unit

AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Cart	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Electrosurgical Unit, Ultrasonic

AE #: ELUU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ethicon Endo-Surgery / Johnson & Johnson	GEN11		Cart	OF/OI	Project

Combines advanced technology with touchscreen simplicity in one compact, easy-to-operate unit. Supports current and future HARMONIC® Ultrasonic and ENSEAL® Advanced Bipolar Devices. View Cutsheet 207789

W x D x H: 15 x 14 x 7.5 in.
Electrical: 120V 60Hz 5W

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Cart	CRT11	1	1

Fluid Management System

AE #: FLMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Smith And Nephew	Dyonics 25		Cart	OF/VI	Project

A high-flow pump for arthroscopic applications. The Dyonics 25 has flow rates up to 2.5 l/min, outflow control, and a Lavage function. Minimizes saline usage. View Cutsheet 211340

W x D x H: 12 x 14 x 6 in.
Electrical: 120V 60Hz

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Generator, Radiofrequency

AE #: GERF-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Smith And Nephew	Werewolf Coblation		Boom	OF/OI	Project

Generator combining Coblation technology with FLOW-IQ technology to remove tissue; controlled plasma field produced by Coblation allows for precise removal of soft tissue with minimal thermal damage. View Cutsheet 209332

W x D x H: 16.1 x 17.7 x 5.12 in.
Electrical: 120V 60Hz

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Placeholder only. Ten total corded headlight systems requested during MEQ review. - 1 in each OR and 2 additional in Equipment Room.

W x D x H: 24 x 24 x 42 in.
Electrical: 115V 60Hz **Weight:** 22 lbs.

Helmet, Personal Protection

AE #: HEPP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Stryker Corp.	Flyte	0408-645-000	Wall	OF/OI	Project

Flyte lighted (steri-shield) personal protection helmet features battery powered variable speed fan with multiple ports for ventilation; helmet is draped with a sterile hood to provide protection during procedures. ***system requires t5 battery charger (listed separately) View Cutsheet 130180

May change vendors.

W x D x H: 11 x 15 x 6 in.
Elect Notes: Battery charged

Helmet, Personal Protection, Component

AE #: HEPP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	0400-204-000		Wall	OF/CI	Project

Wall rack designed to support (4) flyte steri-shield helmets View Cutsheet 142212

W x D x H: 48 x 2.05 x 1.94 in.

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Holder, Leg, Arthroscopy — AE #: HOLA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Alimed, Inc.	2970013547		Cart	OF/OI	Project

Used to safely position the non-affected leg during arthroscopic knee procedures. Tri-clamp is not included, but recommended View Cutsheet 211500

Item specified by Becca Webster 06/25/2024. Allen Tri-clamp accessory to be ordered with item.

W x D x H: 18 x 23 x 11 in. **Weight:** 5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Allen Tri-Clamp	2970013166	4	16

Holder, Leg, Arthroscopy — AE #: HOLA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	McKesson Corp.	523720		Cart	OF/VI	Project

Leg holder for Surgical Table Osi. Adjusts 9" horizontally and 10" vertically: pivots 360 degrees for use with left or right leg View Cutsheet 211504

Item specified by Becca Webster on 6/25/2024

W x D x H: 16.5 x N/A x 8.5 in. **Clearance:** Right 9 in.; Top 10 in.

Holder, Leg, Arthroscopy — AE #: HOLA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Smith & Nephew Endoscopy	012310		Cart	OF/VI	Project

Leg holder, includes replacement lateral leg pad. Optional table clamp accessory. Adjusts 9" horizontally and 10" vertically. Pivots 360 degrees View Cutsheet 86028

Item specified by Becca Webster 6/25/2024. Table clamp accessory to be ordered with item as well.

W x D x H: 16.5 x N/A x 8.5 in. **Clearance:** Right 10 in.; Top 9 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Table Clamp	13227	4	16

Imaging, Positioning Device — AE #: IMPD-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bone Foam	925.TR		Cart	OF/OI	Project

Lower Extremity Positioning Device. The Ramp Leg Elevator. View Cutsheet 126052

Item specified by Becca Webster 6/25/2024.

W x D x H: 30.5 x 11.5 x 6.25 in.

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Cart	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve.

View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Laminectomy, Positioning Device

AE #: LAPD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	TBD			Cabinet	OF/OI	Project

No Cutsheet 211360

Large x6

Laser, CO2

AE #: COLA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Omniguide, Inc	ADVANCED C-LAS		Floor	OF/OI	Lease

Co2 laser

View Cutsheet 164177

W x D x H: 22.5 x 24.5 x 62.5 in.
Electrical: 120V 60Hz 5A

Laser, Diode

AE #: DILS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	BVI Medical	Endo Optiks E4	OME4000	Floor	OF/OI	Project

Laser microendoscopy offers the unique opportunity to view inside the eye and simultaneously treat in both anterior and posterior applications. Laser box dimensions: W: 15.25", D: 18", H: 8".

View Cutsheet 211352

W x D x H: 23.2 x 30 x 52 in.
Electrical: 120V 60Hz

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Laser, KTP

AE #: KTPL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iridex Corp	Oculight TX		Cart	OF/VI	Lease

Delivers true continuous green laser (532 nm) light. To be used in various ENT and Ophthalmology procedures. View Cutsheet 211356

W x D x H: 12 x 12 x 6 in.
Electrical: 120V 60Hz 3A **Weight:** 13.2 lbs.

Laser, Ophthalmic, Glaucoma

AE #: GLOL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Iridex Corp	CYCLO G6		Cart	OF/VI	Project

Cyclophotocoagulation with micropusle. 810 nm infrared. Countdown timer. Programmable user presets. Color lcd touchscreen interface. Optional footswitch. View Cutsheet 170210

W x D x H: 10.6 x 11.6 x 7.8 in.
Electrical: 115V 60Hz **Weight:** 10.5 lbs.

Navigation System, ENT

AE #: NASY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medtronic, Inc.	StealthStation S8	9735669KIT	Floor	OF/VI	Project

ENT electromagnetic image guidance system configured for ambulatory procedures; StealthStation S8 system includes camera cart (26.9"w x 27.1"d) and main cart (27.3"w x 20.4"d); footpedal free. Video in and out. Optional blue tooth wireless mouse. View Cutsheet 171294

W x D x H: 27.3 x 20.4 x 70 in.
Network: Networked
Electrical: 120V 60Hz 7.5A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ENT Software	9735736	1	2
Instrument Set	9733452XOM	3	6
Side Emitter	9735960	1	2
Stealthmerge Software	9736155	1	2

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Navigation System, Surgical

AE #: SUNS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Elucent Medical	EnVisio-SYS		Floor	OF/VI	Project

The EnVisio Surgical Navigation system utilizes state-of-the-art materials together with an advanced algorithm to precisely locate the SmartClip and the Navigator. EnVisio System Cart will ship and store the System Console (includes heads up display, patient pad and foot pedal)

View Cutsheet 211348

W x D x H: 23.7 x 27.6 x 39.4 in.
Electrical: 120V 60Hz 9.5A 456W **Weight:** 170 lbs.
Elect Notes: Device must be plugged in when not in use.

Nerve Integrity Monitor

AE #: MOIN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medtronic, Inc.	NIM 4.0		Floor	OF/VI	Project

NIM Vital System with Cart featuring NIM 4.0 Wireless Display and Muting Probe

View Cutsheet 202290

W x D x H: 22 x 18 x 35 in.
Electrical: 120V 60Hz 1.8A 78W

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Muting Probe	8220325	1	3
Wireless Display	NIM4CD01	1	3

Ophthalmology, Camera, Retinal Imaging, 3D

AE #: RIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alcon Laboratories Inc	NGENUITY		Floor	OF/VI	Project

Digitally assisted vitreoretinal surgery system interfaces with surgical microscope; features 55" 4k ulra hd display mounted on floor standing console

View Cutsheet 164426

W x D x H: 43 x 30 x 62 in.
Electrical: 120V 60Hz

Ophthalmology, Refractor/Keratometer, Automatic

AE #: ARKO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Right Mfg. Co., Ltd	Retinomax K+ Screeen		Desk	OF/VI	Project

Handheld autorefractor/keratometer with docking/charging station and printer.

View Cutsheet 211346

W x D x H: 6.62 x 8 x 9.3 in.
Electrical: 120V 60Hz **Weight:** 2.2 lbs.

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Ophthalmology, Tonometer

AE #: OPTO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Reichert Analytical Instruments	AVIA		Countertop	OF/OI	Project

Hand held tonomoeter. View Cutsheet 170146

W x D x H: 0.75 x 1.75 x 6.25 in.
Elect Notes: Battery

Ophthalmology, Ultrasound

AE #: OPUS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ellex USA	eye cubed		Cart	OF/VI	Project

With customized configuration of A-Scan and B-Scan modes, Eye Cubed covers all your diagnostic needs for both the posterior and anterior segments. View Cutsheet 211351

Per Dr. Bansal, B-SCAN, 40 MHZ UBM, B-SCAN & 10 MHZ POSTERIOR.

(A-SCAN, BIOMETRY, A-SCAN, STANDARDIZED DIAGNOSTIC are automatically included but no A-Scan probe needed).

W x D x H: 15.5 x 17 x 6.5 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 26 lbs.

Ophthalmoscope Laser, Indirect

AE #: OPLI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Keeler Instruments / Halma Co.	Vantage LIO		Cabinet	OF/OI	Project

Intelligent Optical System with automatic optics and mirrors adjustment View Cutsheet 211359

HiMag Lens with additional 1.6X magnification

*For TruScan and TruScan Pro Only

Ophthalmoscope, Indirect

AE #: OPIN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Keeler Instruments / Halma Co.	Vantage Plus Convertible	1205-P-1020	Wall	OF/VI	Project

LED slimline wireless indirect ophthalmoscope with charger and two batteries. Comes standard with an led module, himag lens and dimmer control. View Cutsheet 150995

IR/UV filters are built into the optics. Offers choice between a neutral 4000, LED or a traditional 3800K xenon bulb. Dimensions of wall charger approximate.

W x D x H: 5.5 x 5.5 x 5.5 in.
Electrical: 120V 60Hz

Room: Equipment

Department: ASC Operating Rooms

Room #: A207E

Positioning Device

AE #: PODE-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Action Products, Inc.	40620		Cart	OF/OI	Project

Adult flat bottom chest rolls is produced in a wide range of sizes to accommodate virtually any adult. They protect the patient's entire chest area from pressure while in the prone position, and offer increased non-roll stability. View Cutsheet 208558

W x D x H: 6 x 5 x 16 in.

Positioning Device

AE #: PODE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Action Products, Inc.	40645		Shelf	OF/OI	Project

Flat bottom pediatric chest rolls is produced in a wide range of sizes to accommodate virtually any patient. They protect the patient's entire chest area from pressure while in the prone position and offer increased non-roll stability. View Cutsheet 200388

W x D x H: 3 x 3 x 10 in.

Positioning Device

AE #: PODE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Action Products, Inc.	40817		Shelf	OF/OI	Project

Flat bottom chest roll accommodates virtually any adult. They protect the patient's entire chest area from pressure while in the prone position, and offer increased non-roll stability. View Cutsheet 200391

SKU 40617

W x D x H: 3.4 x 4.4 x 16.5 in.

Positioning Device

AE #: PODE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Alimed, Inc.	2970014087		Shelf	OF/OI	Project

U-shaped bean bag positioner View Cutsheet 211416

W x D x H: 36 x N/A x 40 in.

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Post, Universal Stress

AE #: POUS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Conmed Corp.	RT.0010		Cart	OF/OI	Project

Items includes two NS. 0011 Replacement Pads. ConMed does not make a clamp to hold item to the bed. They recommend contacting the company that makes their surgical beds for a clamp. Flat part to clamp to is 1/4"x1"x6". View Cutsheet 211503

Item specified by Becca Webster on 6/25/2024

W x D x H: 15 x 4 x 4.25 in.

Power Control System

AE #: POCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Smith And Nephew	Dyonics Power 2 (D2)	72201030	Boom	OF/OI	Project

Consists of a main control unit and a country-specific power cord. A control system interface cable (optional) and a procedure cart (optional) may also be purchased. The control system provides for variable speed operation of handpieces and powered instruments. View Cutsheet 211343

W x D x H: 12 x 14.3 x 5.75 in.
Electrical: 120V 60Hz 4.67A **Weight:** 13.85 lbs.

Power Instrument Console

AE #: POIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Medtronic Powered Surgical Solutions	IPC	189801	Cart	OF/VI	Project

Integrated power console drives power instruments (i.e. Microdebriders, drills, saws); specification includes endoscrub system; **instrument handpieces not included** View Cutsheet 164502

Approximate dimensions of cart 24"W x 20"D x 64"H

W x D x H: 11.1 x 10.7 x 14.1 in.
Electrical: 120V 60Hz 1.66A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
IPC Cart	1898600	1	4

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Radiography System, Specimen

AE #: RASS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Faxitron Trident HD		Floor	OF/VI	Project

Hologic's proven detector technology to generate sharp, highly detailed images for rapid sample verification right in the OR or procedure room. The Trident HD system's sleek, modern, ergonomic design yields a footprint that's 37% smaller than the original, making it easy to maneuver in a crowded room. Yet its imaging area is 71% larger to accommodate the widest range of excisions in the OR.

View Cutsheet 205866

W x D x H: 24 x 26 x 66.5 in.
Electrical: 120V 60Hz 600W **Weight:** 291 lbs.

Retinoscope, Handheld

AE #: RSHH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	18245 / 71670		Base Unit	OF/OI	Project

Rechargeable power handle and elite 3.5 v halogen hpx streak retinoscope

View Cutsheet 143451

RFID System

AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Cart	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Smoke Evacuation

AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Shelf	OF/VI	Project

Surgical smoke evacuator

may be changing vendors

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

Stirrups

AE #: STIR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	O-YFAX		Cart	OF/OI	Project

Yellowfin Apex Stirrups. Patient Weight Capacity:500 lb. Lithotomy Adjustment (from sterile field): Yes. Lithotomy range (from sterile field): +80° to -32°. Abduction range (from sterile field): +23° to -9°. Maximum Medial/Lateral Shift ±20°. Product Weight 18.5 lb.

View Cutsheet 208020

W x D x H: 10 x 12 x 26 in.

Stirrups

AE #: STIR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	Ultrafin	O-UFAS	Floor	OF/OI	Project

Stirrups for operative patient positioning; lift assist neutralizes leg weight; squeeze grip handle; accommodates 800lbs patient; lithotomy and length indicators; includes optional re-usable pads, table clamps, storage cart.

View Cutsheet 202625

W x D x H: 20 x 20 x 58 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Blade Clamps	A-40040	2	2

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; specify teardrop, wedge or saddle seat type.

Without back or arms

View Cutsheet 123943

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; specify teardrop, wedge or saddle seat type.

With back and arms

View Cutsheet 123943

Room: Equipment

Department: ASC Operating Rooms

Room #: A207E

Stretcher, Eye

AE #: STEY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stryker Corp. - Medical	1089		Floor	OF/VI	Project

Eye surgery stretcher; standard features include 3" mattress, 8" casters with wheel covers, dual cylinder pneumatic fowler, dual pedestal hydraulics, dual side control, fold-down siderails, four iv receptacles, four-wheel ring brakes with dual end brake & steer pedals, hands-free trendelenburg, integrated storage tray with oxygen bottle holder, retractable fifth wheel, rubber bumpers, stationary foot-end litter, standard descent hydraulics, unilower pedal, zero articulation tapered headpiece, maximum weight capacity of 500 lbs.

View Cutsheet 160127

Quantity to be verified by Becca Webster. Will need to increase number.

W x D x H: 31.5 x 90 x 36 in.

Surgical Imaging System

AE #: SUIS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Smith And Nephew	LENS 4K		Boom	OF/OI	Project

A surgical video platform with the latest 4K technology, designed for sports medicine and multispecialty centers for arthroscopic and endoscopic procedures. With native 3840 x 2160 resolution, the LENS 4K system provides detailed images with four times as many pixels as HD and over 1 billion colors (10 bit). Includes LENS 4K camera control unit CCU, LENS 4 camera head and 4K Optimized Scopes

View Cutsheet 211341

Network: Networked

Suspension System Lateral, Shoulder

AE #: SSLS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Arthrex	AR-1600M	AR-1650S	Table	OF/OI	Project

3-point shoulder distraction system. Includes caster base. Caster Base dimensions: W: 30", D: 28.7", H: 27.1"

View Cutsheet 211364

W x D x H: 60 x N/A x 51.2 in.

Room: Equipment
Room #: A207E

Department: ASC Operating Rooms

System, Vision, Vitreoretinal

AE #: VRVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Alcon Laboratories Inc	Unity (Constellation/Centurion)		Floor	OF/VI	Project

Unity is a combo machine (Constellation and Centurion) and will be available 2025. It delivers a real-time view of surgical parameters and surgical performance. No Cutsheet 211344

This does not yet exist but should be available in 2025

W x D x H: 29 x 29 x 38 in.
Electrical: 120V 60Hz 12A

Table, Surgical

AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Table, Surgical, Accessory

AE #: SUAT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Smith & Nephew Donjoy, Inc.	SPIDER 2	72203299	Table	OF/VI	Project

Limb positioner allows proper patient positioning for shoulder, knee and small joint arthroscopy; integrated positioning switch rids you of tedious manual adjustments and readjustments during surgery. While in use the spider mounts to the accessory rail on the surgical table. While not in use the spider in stored on a mobile cart that is 22" w x 20" d x 45" h / batteries need to be charged View Cutsheet 139363

Electrical: 120V 60Hz
Elect Notes: *****rechargable battery operated*****

Table, Surgical, Accessory

AE #: SUAT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Smith And Nephew	Spider2 Leg/Knee Positoner		Table	OF/VI	Project

SPIDER2 leg accessory and distal thigh holder are designed for use with SPIDER2 to provide stable positioning for procedures. View Cutsheet 211370

Electrical: 120V 60Hz

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Tourniquet, Pneumatic

AE #: TQPN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Zimmer Biomet / Medtech	ATS 5000	60500010100	Stand	OF/OI	Project

The A.T.S. 5000 Tourniquet System offers multiple ways to measure Limb Occlusion Pressure (LOP), the dual port tourniquet system equips surgeons with efficient tools that meet their preferences. Features include: Pre-Operative Cuff Test, Cuff Alert, Line Occlusion Detection (Acoustic Reflectometry), Automatic IVRA Cuff Lock Out, and Advanced Leak Detection. 10.1" display monitor

View Cutsheet 209410

W x D x H: 11.5 x 9.9 x 9.95 in.
Electrical: 120V 60Hz **Weight:** 12 lbs.

Traction Tower, Lateral Decubitus Shoulder

AE #: TTLD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Arthrex	Traction Tower		Table	OF/VI	Project

The Lateral Decubitus Shoulder Traction Tower allows for abduction, forward flexion and traction during open and arthroscopic procedures. The single boom arm can be easily adjusted with two independent hand cranks for simplified intraoperative adjustment. This tower attaches easily to the standard O.R. table Clark Rail. The universal carabiner clamp makes the system compatible with all STaR™ (Shoulder Traction and Rotation) Sleeves. When not in use, the system can be folded, minimizing storage space required in the O.R. suite.

View Cutsheet 211365

Price includes weights; 1kg, 2.5kg, 5kg. Can attach to table or to caster base provided with the 3-point shoulder distraction system (AR1600M)

W x D x H: 36.6 x N/A x 51.1 in.

Transilluminator, Handheld

AE #: TIHH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	41100/71900/71950		Cart	OF/OI	Project

Handheld finnoff ocular transilluminator; specification includes lithium ion power handle with ac charging module

View Cutsheet 170246

W x D x H: 1.5 x 1.5 x 7.5 in.
Electrical: 120V 60Hz 0.5A

Room: Equipment **Department:** ASC Operating Rooms

Room #: A207E

Ultrasonic Surgical System

AE #: ULSS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Depuy Synthes	PIEZOELECTRIC SYSTEM	05.001.400	Cart	OF/OI	Project

Piezoelectric system; cuts mineralized bone, soft tissue sparing; to include console, hand piece, foot pedal, flat wrench, single lvl modular graphic case, attachment tray for modular graphic case, user's manual, torque wrench, led ring for handpiece, light diffuser cone for handpiece. View Cutsheet 163932

W x D x H: 18.6 x 13.4 x 18.6 in.
Electrical: 120V 60Hz **Weight:** 11.02 lbs.

Ventilator, Jet

AE #: VEJE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Acutronic	monsoon III		Stand	OF/OI	Project

High frequency ventilator works at very high pressures to produce fast gas exchange (jet), which ensures high gas flow, oxygenation, and ventilation for the patient. Delivers 4-1600 breaths per minute. Ability to deliver high pressures allows ventilation with small tubes or narrow catheters. Detachable 9" color touch screen. View Cutsheet 211136

Use for ENT cases. Can go down frequently, Dr. Fritz uses mostly. Increase to 2.

W x D x H: 16.5 x 7.48 x 15.4 in.
Electrical: 120V 60Hz 100W **Weight:** 30.86 lbs.

Room: Lounge - Surgery

Department: ASC Operating Rooms

Room #: A208A

Coffee Brewer

AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Lounge - Surgery
Room #: A208A

Department: ASC Operating Rooms

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser. View Cutsheet 142083

W x D x H: 21 x 24 x 36 in.
Clearance: Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase
Weight: 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90º hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Ice Maker / Water Dispenser, Component

AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series No Cutsheet 211856

Room: Lounge - Surgery **Department:** ASC Operating Rooms

Room #: A208A

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Microwave Oven, Commercial

AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Refrigerator Freezer, Upright

AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant. View Cutsheet 208926

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Lounge - Surgery

Department: ASC Operating Rooms

Room #: A208A

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Cabinet	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Waste Receptacle, Recycling Combination

AE #: WARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Max-R	P-RO-STT10D		Floor	OF/OI	Project

10-gallon Top Load Waste & Recycling Bins. View Cutsheet 209397

W x D x H: 28 x 15 x 30 in.

Room: Toilet (Staff)

Department: ASC Operating Rooms

Room #: A208B, A208C, A210A1, A210B1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: R/O Water

Department: ASC Operating Rooms

Room #: A208H

Room Notes: Assumes RO water system planned by CMTA

Room: Soiled Hold

Department: ASC Operating Rooms

Room #: A208J

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Hold

Department: ASC Operating Rooms

Room #: A208J

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter

AE #: REUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF4P		Undercounter	OF/VI	Project

3.9 cu ft refrigerator fits below ada height counter. Stainless steel interior and exterior. Top-mounted controls. User-selectable product or air temp display. High/low temp alarms. Programmable operating range 2-10 degrees celsius / 36-50 dg fahrenheit (factory preset 4 dg c). Two (2) epoxy-coated wire shelves. Dry contacts. Magnetic gasket, self-closing door. User-selectable temp display in unit c or f. Cabinet-wide temp remains within =/- 1 degree c with frequent door opening. Programmed defrost cycles. Depth of cabinet is 25.6". Depth with façade is 27". View Cutsheet 139889

W x D x H: 23.8 x 27 x 31.4 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 4.1A
Weight: 205 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Room: Soiled Hold

Department: ASC Operating Rooms

Room #: A208J

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, PPE Cart

Department: ASC Operating Rooms

Room #: A209C, A210D1

Cart, Supply

AE #: CASU-50

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	2448FS/74UPS		Floor	OF/VI	Project

24x48 solid s/s shelf (2448fs) 5 each; 74" post with cap only (74ups) 4 each; 5" polyurethane caster s/s swivel (5mpgsa) 2 each and 5" polyurethane caster s/s brake (5mpbgsa) 2 each. Include s/s 4"h ledges on 3 sides for the 2 bottom shelves only.

View Cutsheet 168393

For holding PPE.

W x D x H: 48 x 24 x 79 in.

Room: Shower (Staff)

Department: ASC Operating Rooms

Room #: A210A2, A210B2

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Allowance, Mounting Bracket

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capsule Tech, Inc.			Anesthesia Machine	OF/VI	Project

Capsule Neuron 3 Mounts and Capsule Integration Cables. No Cutsheet 211584

Allowance, OR Video Integration

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America			Cabinet	OF/CI/VI	Project

No Cutsheet 211519

Allowance for video integration includes CollaboratOR interactive display and several scopes. Per quote Q-106073 dated 8/13/2024 from Kory Sensky. Supplemental Info

Anesthesia Machine

AE #: AMNA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	Carestation 750		Floor	OF/VI	Project

Anesthesia Machine with a modern, compact design. 15" touchscreen display. Integrated CARESCAPE respiratory model. Electronic gas mixer. Small, Compact Breathing System (CBS) specifically designed for low-flow anesthesia. View Cutsheet 211557

Price does NOT include GE or Philips physiological monitor. Price from quote 2009722156.16 dated 20240816 from Julie O'Coners.

W x D x H: 35.1 x 32.1 x 56.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 355 lbs.
Elect Notes: **Power Cord: 5 m/16.4 ft. Backup power: Battery time is 90 minutes when fully charged, which supports full system functionality and ventilation. Battery type: Internal rechargeable sealed lead acid.**
Plumb Notes: Med gas connections to anesthesia and/or equipment booms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Board, Transfer

AE #: BOTR-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Allen Medical Systems, Inc / Hill-Rom	A-83001		Wall	OF/OI	Project

Roller free transfer board. 500 lb weight capacity. View Cutsheet 170785

W x D x H: 40 x 16.5 x N/A in.

Board, Transfer, Accessory

AE #: BOTA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midcentral Medical	MCM199		Wall	OF/CI	Project

Wall rack MCM EZ-Tranz Gold Patient Transfer Boards MCM190 and MCM 191. Keeps boards clean and out of the way, yet in the spot you need them. View Cutsheet 211466

Each rack holds one board. Mounting hardware not included due to varying substrates.

W x D x H: 6 x 2 x 2 in.

Boom, Anesthesia, Light and Monitor

AE #: BOAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4UBW		Ceiling	OF/CI/VI	Project

Freedom 320 boom with 4UBW anesthesia carrier, one surgical light, and arm with 32" monitor. Services to include (2) O2, (2) Vac, (1) MA, (1) WAGD, and (1) instrument air, (12) outlets on right panel, 4-in-1 plate for routing vitals, (1) blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. View Cutsheet 211826

No Nitrous Oxide needed in these booms. If provider wishes to administer N2O, will use a cylinder. Wish to base boom configuration on Pav A. Services to include (2) vacuum, (2) O2, (1) MA (for jet ventilator), instrument air, WAGD, 12 outlets on right panel, 4-in-1 plate for routing vitals, 1 blank data for IT Cat 6 (up to 4 cables in plate). Services confirmed 6/3/2024. Supplemental Info

Plumb Notes: Provides med gases to anesthesia machine

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Boom, Equipment W/ Surgical Light/ Monitor Arm

AE #: BOEQ-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Freedom 320 / 4CMW-49		Ceiling	OF/CI/VI	Project

Equipment carrier with 2 surgical lights and 2 monitor arms with 32" monitors. View Cutsheet 211828

To be positioned at 6:00. To include CO2 for equipment, 2-4 vacuum, O2, and instrument air. Supplemental Info

Network: Networked
Elect Notes: **refer to manufacturer's site planning information.**
Plumb Notes: **refer to manufacturer's site planning information.**
HVAC Notes: **refer to manufacturer's site planning information.**
Struct Notes: **refer to manufacturer's site planning information.**

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Pyxis	OF/OI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Camera Head

AE #: CAHE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TH120		Boom	OF/VI	Project

IMAGE1 S 4U-HEAD 4K CAMERA HEAD FOR 4U-LINK View Cutsheet 211795

MODULE. 4k image resolution. Part of the IMAGE S camera platform.

Price included in Storz Video Integration.

W x D x H: 5.24 x 1.82 x 1.46 in.

Weight: 0.47 lbs.

Room: Operating Room **Department: ASC Operating Rooms**

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Camera, In-Light — AE #: CAIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Light	OF/VI	Project

HD Surgical In Light Camera — No Cutsheet 211768

Elect Notes: Refer to Site Specific Drawings
Plumb Notes: Refer to Site Specific Drawings
HVAC Notes: Refer to Site Specific Drawings
Struct Notes: Refer to Site Specific Drawings

Cart, Anesthesia — AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook. — View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart — View Cutsheet 85038

For red, black, and blue bins

W x D x H: 22.5 x 12.8 x 22 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Cart, Stirrup

AE #: CASR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Allen Medical Systems, Inc / Hill-Rom	A-30015-A1		Floor	OF/VI	Project

Cart to store and transport stirrups or legholders. Polymer base with four casters. Two different size hooks to hold a variety of stirrups from any manufacturer. View Cutsheet 163780

W x D x H: 20 x 20 x 58 in.

Cart, Supply

AE #: CASU-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Tall Starsys		Floor	OF/VI	Project

Single wide tall Starsys cart with tambour door. Internal configuration to be determined. View Cutsheet 211250

W x D x H: 22.8 x 24.9 x 77.8 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid View Cutsheet 209270

W x D x H: 12.5 x 17.3 x 24 in.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Cart	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser.

View Cutsheet 161507

One by Anesthesia, one by each door.

W x D x H: 12 x 7 x 8 in.

Dispensing Unit, Drug, Anesthesia

AE #: DUDA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Anesthesia System		Floor	OF/VI	Lease

Anesthesia mobile medication system for the OR; electronic access; racks and securely stores all controlled substances, medications and supplies for all anesthesia providers. System automates verification of patient usage records, documents waste, manages inventory levels and tracks utilization.

View Cutsheet 102256

Allows for emergency access; four pivoting casters with brakes; bar code scanning system; includes 1 mini drawer; latex free.

W x D x H: 47.5 x 28 x 61 in.
Network: Wired
Electrical: 117V 60Hz 3A
HVAC Notes: Generates 355 btu/hr

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Electrosurgical Unit — AE #: ESUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson / Codman	MALIS	80-1788	Floor	OF/OI	Project

Codman malis cmc v bipolar electrosurgical generator (80-1788) 13.75"w x 16.5"d x 8"h - 13 lbs, irrigator (80-1569), footpedal (80-1547), floor stand (80-1559). View Cutsheet 163933

currently uses this, contracts are up and looking at other venders

W x D x H: 24 x 24 x 48 in.
Electrical: 120V 60Hz

Electrosurgical Unit — AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Boom	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bipolar Adapter	FT0501	1	1
Bipolar Foot Pedal	E6019	1	1

Fluid Waste Management System — AE #: FWMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	Neptune 3 Rover		Floor	OF/VI	Project

Mobile unit used to collect surgical fluid and to filter smoke plumes created during surgery. Features a dual canister fluid collection design with 4L and 20L capacities; fluid volume is measured in 20ml increments; used in coordination with a docking station (listed separately) which disposes of the fluid without exposing staff to potentially infectious waste. View Cutsheet 156828

confirmed one for each OR room

W x D x H: 19 x 23 x 70 in.
Electrical: 120V 60Hz 12A

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

One by Anesthesia and one by each door

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headlight System

AE #: HESY-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sunoptic Technologies	X400		Stand	OF/OI	Project

Titan X400 with proprietary 400 watt ceramic Xenon lamp produces 325,000 lux of 5,600 degrees Kelvin pure white light at 16". CRI 97. Manual intensity slide control. 1000 hour lamp life. Four port turret compatible with ACMI, Wolf, Olympus, and Storz connectors. Dimensions are approximate and reflect device on roll stand. View Cutsheet 210128

Specifications to be confirmed. Most recently purchased battery powered. Surgeons are buying their own.

W x D x H: 24 x 24 x 42 in.

Electrical: 115V 60Hz **Weight:** 22 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Insufflator

AE #: INSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	UI 500		Boom	OF/VI	Project

Insufflator with integrated heating element features optimized control for sensitive applications, touch screen interface, scb, active overpressure through secuvent safety valve. View Cutsheet 166840

W x D x H: 12 x 12.4 x 6.5 in.
Electrical: 110V 60Hz 1.3A

Kickbucket

AE #: KICK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1020-SS		Floor	OF/OI	Project

Kickbucket with removable 12-quart stainless-steel pail; balanced; electro-polished stainless steel frame; perimeter bumper to protect walls; 2" conductive, swivel casters for easy mobility. View Cutsheet 11320

W x D x H: 13.5 x 13.5 x 14 in.

Light Source

AE #: LISO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	TL400		Boom	OF/VI	Project

Laser-free LED light source for white light and NIR/ICG excitation. The light source for white light and fluorescence applications for displaying NIR/ICG or autofluorescence in the near infrared range. Min. 30,000 hours of lamp service life. View Cutsheet 208100

Price included in Storz video integration

W x D x H: 12 x 14.5 x 4.72 in.
Electrical: 120V 60Hz 1.8A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ADAPTOR, TURRET	TL005	1	1

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Neuromuscular — AE #: MONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Senzime	TetraGraph	SEN 2001	Anesthesia Machine	OF/OI	Project

Quantitative train of four neuromuscular monitor uses EMG technology. View Cutsheet 211398

W x D x H: 3.94 x 7.09 x 1.38 in.

Weight: 0.88 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TetraGraph Philips Interface	SEN 2007	1	1
TetraGraph Pole Clamp Kit	SEN 2101	1	1

Monitor, Physiological — AE #: MOPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX750	866471	Anesthesia Machine	OF/VI	Project

Patient bedside physiological monitor with 19" display screen. Compatible with IT environment, giving you access to clinical informatics solutions from across your hospital network. +Accessories: IntelliVue FMX-4 module and cables View Cutsheet 206368

Cost includes monitor, FMX racks, cables, hemodynamic extension, IBP module, printer module, EC5, EC10, and NMT module, and all cables.

W x D x H: 18.5 x 8.5 x 13.8 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 22 lbs.
Elect Notes: **See technical/data information in cutsheet**

Monitor, Physiological, Bracket — AE #: MOPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Drager Medical	TBD		Anesthesia Machine	OF/VI	Project

Bracket for mounting Philips MX750 anesthesia monitor to Drager Perseus A500 anesthesia monitor. Specifications to be developed. No Cutsheet 209486

To hold the Philips monitor and the all-in-one PC provided by IT. Per Drager quote 13629367 dated 5/3/2024 provided by Rick Runyon.

Monitor, Physiological, Component — AE #: MOPC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MMX		Monitor	OF/VI	Project

Multi-measurement module without display for use with Philips IntelliVue patient monitors. View Cutsheet 211719

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Monitor, Physiological, Module, BiSpectral Index

AE #: MPMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M1034B		Monitor	OF/VI	Project

BIS measurement uses a single, easy-to-apply low-impedance sensor, placed on the patient's forehead, to capture EEG and Electromyographic (EMG) signals. The BIS Solution consists of: IntelliVue BIS Module, BIS Device, Patient Interface Cable (PIC).

View Cutsheet 208463

W x D x H: 1.4 x 4 x 4.3 in.

Power Instrument Console

AE #: POIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	CORE 2		Boom	OF/VI	Project

Powers small and large bone drills, saws and drivers; small and large joint shavers; ent shavers; also helps place or cut screws, metal, wires, pins and other fixation devices

View Cutsheet 164896

W x D x H: 12.5 x 17 x 5 in.
Electrical: 120V 60Hz 6A

Printer, Label

AE #: PRLA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Codonics, Inc.	Safe Label System	SLS 550i	Drug Dispensing Unit	OF/OI	Project

Point-of-care medication labeling system

View Cutsheet 209484

Price quote received from BD on 7/25/24

W x D x H: 10.4 x 15.7 x 16.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 14.5 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
OR Tubing Connector Assembly 10' Length (5 pairs)	ALP 25LAK	1	1

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Pump, I.V., Component

AE #: PUIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Syringe Pump Module		Pump	OF/VI	Lease

Syringe pump module for use with Alaris PC Unit. View Cutsheet 208838

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

Rack, Sponge Counter

AE #: RASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	R100		Stand	OF/OI	Project

Rack for holding sponge counter bags View Cutsheet 160548

W x D x H: 8 x 2 x 6 in.

Rack, Suture

AE #: RASU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	PX25II-I		Floor	OF/OI	Project

Mobile single-sided narrow suture rack with up to 48 scales. Also available in narrow double-sided and wide single- and double-sided configurations. View Cutsheet 211249

W x D x H: 25.7 x 25.3 x 71.5 in.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Ohio Medical Corporation	8705-1251-907		Boom	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

RFID System

AE #: RFID-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic, Inc.	Situate Detection System X	01-0048	Boom	OF/OI	Project

The Situate Detection System X utilizes sensors to transmit non-ionizing, low frequency radio waves to detect tagged cotton, to help ensure no cotton is left behind. When the tagged cotton is stimulated by the device's signal, it transmits its own signal back to the detector, identifying its presence. Includes Console X, Extremity Scanner, Body Scanner, Room Scanner

View Cutsheet 211339

Electrical: 120V 60Hz

Scope, Endoscope

AE #: SCEN-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 10MM X31 CM, Autoclave.

View Cutsheet 211800

Price included in Storz Video Integration.

Scope, Endoscope

AE #: SCEN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26003BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 10MM X 31CM, AUTOCLAVE

View Cutsheet 211802

Price included in Storz Video Integration.

Scope, Endoscope

AE #: SCEN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046ARA		Boom	OF/VI	Project

Rigid Scope. Hopkins 0 Degree Telescope, Rubina, NIR/ICG Enlarged View, 5MM X29 CM, Autoclave.

View Cutsheet 211801

Price included in Storz Video Integration

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Scope, Endoscope — AE #: SCEN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	26046BRA		Boom	OF/VI	Project

Rigid Scope. HOPKINS 30 Degree TELESCOPE, RUBINA, NIR/ICG ENLARGED VIEW, 5MM X 29CM, AUTOCLAVE

View Cutsheet 211803

Price included in Storz Video Integration.

Smoke Evacuation — AE #: SMEV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Buffalo Filter	ViroVac		Boom	OF/VI	Project

Surgical smoke evacuator

View Cutsheet 165683

W x D x H: 11 x 6 x 15.5 in.
Electrical: 120V 60Hz 1000W **Weight:** 4.3 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, Basin, Double

AE #: STBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	Snyder 7808-SS	727808000	Floor	OF/OI	Project

Two basins with shelf and swivel casters. View Cutsheet 11055

W x D x H: 29 x 15.3 x 33 in.

Weight: 29 lbs.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

2 needed for Anesthesia.

W x D x H: 24 x 24 x 72 in.

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

W x D x H: 20 x 25 x 62 in.

Stool, Anesthesia

AE #: STAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Armstrong Medical Industries	AC-975A		Floor	OF/OI	Project

Wide-seat anesthesia chair with back and adjustable arms; height adjustable from 22" to 32"h; adjustable foot ring; extra-wide wheel base of 27". Color: black View Cutsheet 123850

W x D x H: 24 x 24 x 44 in.

Stool, Foot

AE #: STFO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ansell	1170-B		Floor	OF/OI	Project

Sandel Interlocking Step Stool constructed of composite material; Lightweight; "Bottom" model allows for stacking; sold 4/cs View Cutsheet 204839

W x D x H: 18 x 14 x 5.25 in.

Stool, Surgeon

AE #: STSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	830		Floor	OF/VI	Project

Upholstered chair with adjustable back and arms; 300 lb. Capapcity; height adjustable from 21" to 28.5"; View Cutsheet 123943

specify teardrop, wedge or saddle seat type.

Without back or arms

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Table, Instrument — AE #: TAIN-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7844SS		Floor	OF/OI	Project

Stainless steel instrument table; 48" x 20" with h-brace; on casters — View Cutsheet 122387

W x D x H: 48 x 20 x 34 in.

Table, Instrument — AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters — View Cutsheet 14192

W x D x H: 36 x 20 x 34 in.

Table, Surgical — AE #: TASU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Floor	OF/VI	Project

Mobile surgical table. Manufacturer and model to be determined. — No Cutsheet 211251

Skytron Ultraslide table is current standard, but do not want to commit to this table because it cannot go high enough due to the weight capacity. Will revisit as more is known about cases and patient population.

Electrical: 115V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Interactive Display

AE #: VISI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WUISK07	CollaboratOR Pro	Wall	OF/CI/VI	Project

65" touch control, consolidated display for multiple contents including count sheets, preference cards, charting, PACS, and live in-room imaging into a single canvas. Includes a processing rack. Requires a 41" minimum clearance for mobile Operating Room carts. Option to be wall mounted or cart based.

View Cutsheet 211804

Cost included in Storz Video Integration

W x D x H: 61.8 x 3.76 x 39 in. **Clearance:** Left 41 in.; Right 41 in.; Top 41 in.; Front 41 in.
Network: Networked
Electrical: 120V 60Hz 220W **Weight:** 129 lbs.
Struct Notes: See cutsheet. Appropriate anchorage for the wall mounting bracket & a facilities or construction person to secure the bracket to the structure. Installation of the 14" x 14" Recessed J Box for low profile displays. Conduit leading from the Recessed J-Box to the processing rack as specified in their project's facility drawing set.

Video Integration System, Light Cable

AE #: VILC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	495ND		Boom	OF/VI	Project

Fiber Optic Light Cable, 3.5MM X 300CM (9.8")

View Cutsheet 211797

Price included in Storz Video Integration

W x D x H: 9.8 x 0.14 x N/A in.

Video Integration System, Monitor

AE #: VISM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Storz, Karl, Endoscopy America	TM351		Boom	OF/VI	Project

32" 4K/3D Monitor. Coordinated parameters for an optimal imagine chain in conjunction with the IMAGE1 S camera system

View Cutsheet 211794

Price included in Storz Video Integration.

W x D x H: 30 x 3.61 x 18.3 in.
Electrical: 120V 60Hz

Room: Operating Room **Department:** ASC Operating Rooms

Room #: A210C

Room Notes: RFID scanner/wand needed for each room. Assume covered in IT scope.

Video Integration System, Printer — AE #: VISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Storz, Karl, Endoscopy America	WU1333		Cart	OF/VI	Project

SONY UP- DR80MD Medical Grade Printer for Use with USB View Cutsheet 211796

Price included with Storz Video Integration

W x D x H: 12.5 x 16.7 x 8.1 in.
Electrical: 340W **Weight:** 25.3 lbs.

Warmer, Patient — AE #: WAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	775 Bair Hugger		Stand	OF/OI	Project

Patient temperature management unit for use with all bair hugger blanket styles (pediatric to adult and bair paws gowns). Standard package includes pole mounting clamp. All mounting options/accessories are free of charge. View Cutsheet 140046

W x D x H: 14 x 13 x 14 in.
Electrical: 120V 60Hz 11.7A **Weight:** 16 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rolling Floor Cart		1	1
Wall mount	90080	1	1

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Alcove, Linen
Room #: A210C3

Department: ASC Operating Rooms

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Room: Equipment **Department:** ASC Operating Rooms

Room #: A210C4

Room Notes: Assumes parking spot for patient stretcher while in OR

Imaging, Portable X-Ray

AE #: IMPX-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	United Imaging Healthcare	uDR 380i Pro Mobile		Floor	OF/VI	Project

Mobile digital medical x-ray system with 50kW generator and standard 14"x17" detector size (optional 11"x14" available) and uVision remote touch screen console. Motorized steering and zero radius turn. View Cutsheet 213040

W x D x H: 21.7 x 43.7 x 51 in.

Network: Wireless **Network Notes:** Connects to RIS server and PACS via WIFI

Electrical: 120V 60Hz **Weight:** 769.4 lbs.

Room: Femto Laser

Department: ASC Operating Rooms

Room #: A210D

Allowance, Relocation of Existing Equipment

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson Vision				OF/VI	Project

No Cutsheet 211372

For femtosecond laser system relocation

Allowance, Training

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson Vision				OF/VI	Project

No Cutsheet 211373

Femtosecond laser system training for providers and staff

Cart, Procedure

AE #: CAPR-54

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Short Mobile Cart		Floor	OF/VI	Project

Single width mobile Starsys cart with 2 interior shelves and clear non-locking door. View Cutsheet 211397

W x D x H: 22.7 x 24.9 x 38.7 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Femto Laser

Department: ASC Operating Rooms

Room #: A210D

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Femto Laser **Department:** ASC Operating Rooms

Room #: A210D

Laser, Femtosecond

AE #: LAFE-01E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Johnson & Johnson Vision	Catalys		Floor	EX/VI	Existing

Eye laser and patient table (may be stationary or mobile). Laser controls integrated into patient table. View Cutsheet 211367

System includes stationary patient table with laser controls

W x D x H: 35.3 x 64.7 x N/A in.
Electrical: 208V 60Hz 15A 1-Phase **Weight:** 749.6 lbs.
Elect Notes: **see mfr documentation**
Struct Notes: Minimum room dimensions 10'W x 11'D

Light, Procedure

AE #: LIEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	Aurora Astro		Ceiling	OF/CI/VI	Project

Max intensity output: 126,000 =/- 5K lux. Spot size 7.2" with 46" depth of field. 360 degree rotation on all axes. Color temperature 4,141K. Light head diameter 17.5". CRI 97. View Cutsheet 211872

Per Skytron quote Q-90711-12 dated 9/26/2024.

W x D x H: 17.5 x 17.5 x N/A in.
Electrical: 120V 60Hz

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Stand	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care. View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.
Network: Networked
Electrical: 120V 60Hz

Room: Femto Laser

Department: ASC Operating Rooms

Room #: A210D

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Femto Laser

Department: ASC Operating Rooms

Room #: A210D

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks

View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters.

View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stand, Monitor

AE #: STMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	AG-0018-60G-04		Floor	OF/VI	Project

Roll Stand Kit for Philips IntelliVue MP20/30, MP40/50, MP60/70, MX400-550 and MX600-850. Includes 6" basket with cord loops

View Cutsheet 161894

W x D x H: 25 x 25 x 46 in.

Weight: 10 lbs.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5"

View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Room: Femto Laser

Department: ASC Operating Rooms

Room #: A210D

Table, Prep

AE #: TAPR-81

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	SG-81-SS		Floor	OF/OI	Project

Utility table with shelf and 3-sided 1-1/2" rail; 3" double ball bearing casters

View Cutsheet 49987

W x D x H: 20 x 16 x 34 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Specimen **Department:** ASC Operating Rooms

Room #: A210D2

Room Notes: May need a refrigerator for specimens. Confirm w/department.

Cart, Supply

AE #: CASU-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys Single		Floor	OF/VI	Project

Single Starsys cart with clear glass door and combination lock. One shelf with 2' above and the others 1'. Height adjustable. View Cutsheet 211378

To have drawers on the bottom and two shelves with a clear door on top.

W x D x H: 22.7 x 28 x 78 in.

Weight: 158 lbs.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Refrigerator, Undercounter

AE #: REUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF4P		Undercounter	OF/VI	Project

3.9 cu ft refrigerator fits below ada height counter. Stainless steel interior and exterior. Top-mounted controls. User-selectable product or air temp display. High/low temp alarms. Programmable operating range 2-10 degrees celsius / 36-50 dg fahrenheit (factory preset 4 dg c). Two (2) epoxy-coated wire shelves. Dry contacts. Magnetic gasket, self-closing door. User-selectable temp display in unit c or f. Cabinet-wide temp remains within =/- 1 degree c with frequent door opening. Programmed defrost cycles. Depth of cabinet is 25.6". Depth with façade is 27". View Cutsheet 139889

W x D x H: 23.8 x 27 x 31.4 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 4.1A **Weight:** 205 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Room: Office, Private (OR Manager)

Department: ASC Operating Rooms

Room #: A210E

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Control

Department: ASC Operating Rooms

Room #: A210F

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: OR Scheduling

Department: ASC Operating Rooms

Room #: A210G

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Satellite Pharmacy **Department:** ASC Pharmacy (Satelllite)

Room #: B207F

Allowance, Bins

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/OI	Project

No Cutsheet 39715

bin allowance

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Cart, Supply, 36x24x72

AE #: CASU-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Chrome supply cart; 4-wire shelves; 1-bottom shelf; 4" casters; 2-braking and 2-swivel View Cutsheet 159101

Chrome wire OK

W x D x H: 36 x 24 x 72 in.

Cart, Utility

AE #: CAUT-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	311C		Floor	OF/OI	Project

Cart, utility, three shelves, 22 gauge stainless steel capacity of 200 lbs., 4" swivel casters, option available 2 with brakes, shelves of 15-1/2"; shelf clearance of 11-3/4". View Cutsheet 165092

This cart is OK

W x D x H: 27.5 x 16.3 x 32.1 in.

Weight: 29 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
4" Casters, 2 With Brake		1	1

Room: Satellite Pharmacy

Department: ASC Pharmacy (Satelllite)

Room #: B207F

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Cart	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid

View Cutsheet 209270

Size OK

W x D x H: 12.5 x 17.3 x 24 in.

Container, Pharmacy Waste - Blue

AE #: CPWB-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	18 Gallon		Floor	OF/VI	Service Agreement

18 gallon capacity.

View Cutsheet 159577

placeholder for now. Stericycle to provide.

W x D x H: 17.3 x 12.5 x 24 in.

Container, Sharps

AE #: COSH-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-17/L2-17		Floor	OF/OI	Service Agreement

17 Gallon Red Sharps Container with Slide Lid Top.

View Cutsheet 205911

W x D x H: 13.3 x 17.5 x 24.8 in.

Dispenser, Paper Towel

AE #: DIPT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Contec Healthcare	9451		Wall	OF/CI	Project

Stainless steel dispenser for low-lint disposable hand drying wipes.

View Cutsheet 208769

W x D x H: 10 x 4.75 x 9 in.

Room: Satellite Pharmacy **Department:** ASC Pharmacy (Satelllite)

Room #: B207F

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

Automatic model confirmed

W x D x H: 12 x 7 x 8 in.

Drug Dispensing Unit

AE #: DRDU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 2-Drawer Main		Refrigerator	OF/VI	Lease

ES platform: 2-drawer main unit View Cutsheet 150403

W x D x H: 22.8 x 27 x 27.8 in.
Network: Networked
Electrical: 120V 60Hz 3A **Weight:** 300 lbs.
Struct Notes: Counter height recommended 24" max to provide good ergonomics. Countertop depth required 30" to accommodate unit and provide stability. Raised edge countertop recommended.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Satellite Pharmacy **Department:** ASC Pharmacy (Satelllite)

Room #: B207F

Hood, Laminar Flow

AE #: HOLF-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baker Company, The	EG4252		Floor	OF/VI	Project

Horizontal laminar flow clean bench, 4 foot; hepa supply filter 99.99% minimum efficiency in capturing 0.3 micrometer particles; interior width 46.5"w x 20-3/16"d x 28-1/8"h; removable stainless steel iv bar; caster wheel base

View Cutsheet 164968

Take a long time to receive after ordering.

W x D x H: 50 x 35.9 x 71 in.
Electrical: 115V 60Hz 20A 1-Phase **Weight:** 440 lbs.
Elect Notes: 11 ft external length power cord with 20 amp nema 5-20 plug.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Caster Wheels		1	1
Motorized Base Stand		1	1

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter

AE #: REUN-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF5P-TR-00-00		Floor	OF/VI	Project

Medical-grade undercounter refrigerator with 4.5 cu ft capacity. Programmed defrost every 8 hours. Configuration includes right-hinged solid stainless steel door. 7" LCD capacitive touchscreen digital temperature display available in user-programmable C or F. Integral event and data logging. User-programmable audible and visual high/low alarms. Mechanical (key) lock on door. Programmable operating range 2.2 to 10 degrees C.

View Cutsheet 208473

Do not need Pyxis refrigerator here.

W x D x H: 23.8 x 27 x 34 in. **Clearance:** Front 24 in.
Electrical: 115V 60Hz 4.1A **Weight:** 170 lbs.
Elect Notes: NEMA 5-15 P hospital grade 90 degree plug and 7' cord. Requires 15-amp dedicated circuit.
HVAC Notes: Non-CFC R134a refrigerant. Nominal heat rejection: 415 BTU/hr. Max heat rejection: 2185 BTU/hr.
Struct Notes: Fits below 36"H counter

Room: Satellite Pharmacy

Department: ASC Pharmacy (Satelllite)

Room #: B207F

Table, Work

AE #: TAWO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	WT305FS		Floor	OF/VI	Project

Standard process table, 30"wx48"lx34"h; seamless 14-gauge type 304 stainless steel work surface and support structure; stationary posts and leveling feet; with stainless steel bottom shelf

View Cutsheet 62989

W x D x H: 48 x 30 x 34 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 200448

For collecting HDPE #2 plastic

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Greeter

Department: ASC Prep / Recovery

Room #: B200W2

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Alcove, Scale **Department:** ASC Prep / Recovery

Room #: B201A1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug. View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz **Weight:** 61 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stadiometer		1	1

Room: Consult

Department: ASC Prep / Recovery

Room #: B201A, B200W6

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Equipment **Department: ASC Prep / Recovery**

Room #: B201B

Allowance, Installation

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring			Monitor	OF/VI	Project

No Cutsheet 92570

To cover project management and installation services; covers level 2 areas only.

Allowance, Training

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring				OF/VI	Project

Allowance for clinical training

No Cutsheet 206370

Lifter, Patient

AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor.

View Cutsheet 208837

one total for department

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Ophthalmoscope/ Otoscope

AE #: OPOT-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	77710-71M/7670-12/713263		Floor Stand	OF/OI	Project

Ophthalmoscope/otoscope on mobile stand. Configuration includes: 77710 - green series wall transformer, 11720 - coaxial ophthalmoscope, 23810 - diagnostic macroview otoscope, 7670-12 - mobile stand with basket and 713263 - domestic power adapter.

View Cutsheet 123343

W x D x H: 21 x 21 x 43 in.
Electrical: 120V 60Hz 0.3A

Room: Equipment **Department:** ASC Prep / Recovery

Room #: B201B

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8015		Shelf	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility. Four total for the unit.

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	2

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Shelf	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff.

View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Room: Equipment

Department: ASC Prep / Recovery

Room #: B201B

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

Using ceiling track and stretcher pole most of the time. Have a few poles to bring in. Total poles for 24 beds: 5.

W x D x H: 24 x 24 x 72 in.

Room: Equipment
Room #: B201B

Department: ASC Prep / Recovery

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

Prefer 10 for fast turn cases. May be on staff corridor for storage. 8 will be outside ORs in alcoves + these 2 = 10 spares.

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
11	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.
Weight: 25 lbs.

Vein Illuminator

AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz.

View Cutsheet 168583

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	1

Room: Clean Supply/ Equipment

Department: ASC Prep / Recovery

Room #: B202A

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system — No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. — View Cutsheet 160213

One for linens.

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x72

AE #: CASU-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Chrome supply cart; 4-wire shelves; 1-bottom shelf; 4" casters; 2-braking and 2-swivel — View Cutsheet 159101

Solid bottom shelf

W x D x H: 36 x 24 x 72 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. — View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Room: Clean Supply/ Equipment **Department:** ASC Prep / Recovery

Room #: B202A

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8015		Shelf	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility. Four total for the unit.

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	2

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Shelf	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Warmer, Bath

AE #: WABA-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MSCWARMER24S		Countertop	OF/VI	Supply Agreement

Readybath warmer, intelligent, 24 slot. Pre-programmed to 125 degrees f. First in / first out rotation of products. Electronic reporting of usage and diagnostic data.

View Cutsheet 151300

W x D x H: 25 x 19 x 24.5 in.
Electrical: 120V 60Hz **Weight:** 45 lbs.

Room: Alcove, Blanket Warmer

Department: ASC Prep / Recovery

Room #: B202A1, B204R1

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available.

View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A
Weight: 437 lbs.

Room: Equipment & DME Storage **Department:** ASC Prep / Recovery

Room #: B202B

Cart, Supply

AE #: CASU-69

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	A566BC/A2460BR	Floor	OF/VI	Project

Adjustable super erecta chrome plated wire stem caster cart with 5 shelves, (4) posts; 5" casters (2 swivel, 2 brake). 60"w x 24"d x 69"h. View Cutsheet 62298

cart to accommodate larger items such as commodes.

W x D x H: 60 x 24 x 69 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	3

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Rack, Crutch

AE #: RACR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sammons Preston / Patterson	081186501		Wall	OF/CI	Project

Wall mounted storage rack for storing up to 12 canes, crutches and/or walkers. Designed to hold up to 30 lbs of weight. The rack comes with 2 bases each 33"L x 5.25"H to provide a combined 66" of storage space. Hangers extend 16.5" from the wall. View Cutsheet 207964

W x D x H: 66 x 16.5 x 5.25 in.

Room: Equipment & DME Storage **Department:** ASC Prep / Recovery

Room #: B202B

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Prep / Recovery (Flex) **Department:** ASC Prep / Recovery

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Clippers, Surgical — AE #: CLSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	5513E / 5514A		Countertop	OF/OI	Project

Surgical clipper (5513E) and surgical clipper charger (5514A). Charger is able to be wall mounted. View Cutsheet 200192

W x D x H: 2.4 x 1.73 x 9.15 in.

Electrical: 120V 60Hz **Weight:** 1 lbs.

Container, Recycle, Pulse Ox Probes — AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Room: Prep / Recovery (Flex) **Department:** ASC Prep / Recovery

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Prep / Recovery (Flex) **Department:** ASC Prep / Recovery

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Prep / Recovery (Flex) **Department:** ASC Prep / Recovery

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Headwall, Patient

AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision

View Cutsheet 211253

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino

Supplemental Info

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)
Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 120V 60Hz

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Room: Prep / Recovery (Flex) **Department:** ASC Prep / Recovery

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Monitor, Physiological, Module CO2

AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension

No Cutsheet 171764

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs.

View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls.

View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.

Electrical: 120V 60Hz 14W

Weight: 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Room: Prep / Recovery (Flex) **Department:** ASC Prep / Recovery

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Prep / Recovery (Flex) **Department:** ASC Prep / Recovery

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

with casters

W x D x H: 23 x 23 x 25.5 in.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Room: Prep / Recovery (Flex) **Department: ASC Prep / Recovery**

Room #: B202C, B202D, B202F, B202H, B202J, B202K, B202L, B202N, B202P

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Warmer, Patient — AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius

View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.
Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Warmer, Patient, Bracket — AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor.

View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Alcove, Nourishment **Department:** ASC Prep / Recovery

Room #: B202E1

Coffee Brewer — AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately. View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Alcove, Nourishment **Department:** ASC Prep / Recovery

Room #: B202E1

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Alcove, Nourishment **Department:** ASC Prep / Recovery

Room #: B202E1

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers — No Cutsheet 141809

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Refrigerator, Undercounter, ADA Height — AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white. — View Cutsheet 211261

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. — View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling w/ Lid/Sign — AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. — View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Medication Room

Department: ASC Prep / Recovery

Room #: B202E, B204W

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Wall	OF/CI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket.

View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Medication Room

Department: ASC Prep / Recovery

Room #: B202E, B204W

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit

View Cutsheet 150404

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A
Elect Notes: Must be located within 6' of the electrical outlet. Fuse: 6.3a. Power and data connections are made to frames at the back right of the computer (53-57" a.f.f.). Power cord length is 15'.
HVAC Notes: 200-600 btu/hr.

Drug Dispensing Unit, Auxiliary

AE #: DRUA-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	PYXIS ES 7-DRAWER AUX		Floor	OF/VI	Lease

Es platform 7-drawer auxiliary drug cabinet

View Cutsheet 156732

W x D x H: 22.8 x 27 x 47 in.
Electrical: 120V 60Hz 3A

Drug Dispensing Unit, Auxiliary

AE #: DDUA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	PYXIS ES SINGLE COLUMN		Floor	OF/VI	Lease

Single column auxiliary with 4 doors.

View Cutsheet 150661

W x D x H: 31 x 28 x 79.5 in.
Electrical: 120V 60Hz 3A
Elect Notes: Powered via connection to main unit

Room: Medication Room **Department:** ASC Prep / Recovery

Room #: B202E, B204W

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Pyxis, Undercounter — AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit. View Cutsheet 170325

Department prefers smaller countertop model but Pharmacy standardizing on Pyxis refrigerator. Discuss during MEQ meetings. 5/6 Confirm prefer smaller but want to maintain standards. Keep UC frig.

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Room: Medication Room

Department: ASC Prep / Recovery

Room #: B202E, B204W

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Nursing Station **Department:** ASC Prep / Recovery

Room #: B202G, B203N, B204D, B204Q

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Changed from standard console to this model due to space constraints.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Networked

Network Notes: Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Networked

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Room: Nursing Station **Department:** ASC Prep / Recovery

Room #: B202G, B203N, B204D, B204Q

Monitor, Central Station

AE #: MOCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	PICiXC		Wall	OF/VI	Project

PIC IX Hardware, RVC PIC IX C, New Hardware, HS1 PC Hardware with SSD, UPS Hardware, 27" widescreen LCD Display (Touch), Remote IIC Speaker Kit View Cutsheet 206954

Include PC, keyboard, mouse, Can use network printer for strips.

W x D x H: 26 x 1.5 x 18.5 in.
Electrical: 120V 60Hz
Elect Notes: **Refer to spec. sheet for various component sizes and electrical requirements**

Printer, Strip

AE #: PRST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	M3176C		Countertop	OF/VI	Project

2-Channel Recorder is part of the IntelliVue Information Center, which combines the real-time monitoring surveillance of a central station with sophisticated clinical analysis tools. No Cutsheet 211499

W x D x H: 5.75 x 7.75 x 6 in.
Electrical: 115V 60Hz

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient)

Department: ASC Prep / Recovery

Room #: B202M, B203M, B204J, B204T

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: ASC Prep / Recovery

Room #: B202M, B203M, B204J, B204T

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Room **Department:** ASC Prep / Recovery

Room #: B203A, B204G

Room Notes: Per 4/30/24 DD2 meeting, refrigerator is NOT needed for pregnancy testing supplies.

Bin, Biohazard Waste — AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Soiled Linen — AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.*** View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Pharmacy Waste - Black — AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly. View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Room: Soiled Room **Department:** ASC Prep / Recovery

Room #: B203A, B204G

Room Notes: Per 4/30/24 DD2 meeting, refrigerator is NOT needed for pregnancy testing supplies.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. Request to be placed outside the door to the room.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. hand sanitizers requested outside doors to room

W x D x H: 6.16 x 5.1 x 9.79 in.

Lab Analyzer, Electrolyte — AE #: LAAE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Abbott Labs / Point Of Care	I-STAT1		Countertop	OF/OI	Project

Handheld point-of-care testing device; includes docking station for downloading data and recharging device. View Cutsheet 123820

W x D x H: 3 x 8 x 10 in.
Network: Networked
Electrical: 120V 60Hz

Room: Soiled Room **Department:** ASC Prep / Recovery

Room #: B203A, B204G

Room Notes: Per 4/30/24 DD2 meeting, refrigerator is NOT needed for pregnancy testing supplies.

Lab Analyzer, Electrolyte Downloader Kit

AE #: LAED-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Abbott Labs / Point Of Care	04P73-04		Countertop	OF/OI	Project

I-stat 1 downloader recharger kit

View Cutsheet 117000

W x D x H: 4.12 x 9.6 x 5 in.
Network: Wired
Electrical: 120V 60Hz 1.1A

Lab Analyzer, Urine

AE #: LAUR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	CLINITEK STATUS +	BAH1780	Countertop	OF/OI	Project

Point-of-care urinalysis with touch screen user interface.

View Cutsheet 103504

W x D x H: 6.7 x 10.7 x 6.2 in.
Network: Networked
Network Notes: Uni-directional via serial port rs232
Electrical: 120V 60Hz 15W
Weight: 3.65 lbs.
Elect Notes: 6 aa batteries, non-rechargeable

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue.

View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: PACU **Department: ASC Prep / Recovery**

Room #: B203B, B203C, B203G, B203H, B203J, B203K

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Recycle, Pulse Ox Probes — AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203B, B203C, B203G, B203H, B203J, B203K

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air — AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208701

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203B, B203C, B203G, B203H, B203J, B203K

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Hamper, Linen — AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headwall, Patient — AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision

View Cutsheet 211253

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino

Supplemental Info

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)
Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 120V 60Hz

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203B, B203C, B203G, B203H, B203J, B203K

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Module CO2 — AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension No Cutsheet 171764

Monitor, Physiological, Monitor Arm — AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203B, B203C, B203G, B203H, B203J, B203K

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Pump, Compression — AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203B, B203C, B203G, B203H, B203J, B203K

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

with casters

W x D x H: 23 x 23 x 25.5 in.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203B, B203C, B203G, B203H, B203J, B203K

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Thermometer, Temporal — AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Warmer, Patient — AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.

Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Warmer, Patient, Bracket — AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor. View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Alcove, Sink

Department: ASC Prep / Recovery

Room #: B203C1, B203J1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Supply & Equipment (PACU) **Department:** ASC Prep / Recovery

Room #: B203D

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023. ParEx may not be used here. Still TBD.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

One for linens and one for pillows.

W x D x H: 48 x 24 x 79 in.

Room: Supply & Equipment (PACU) **Department:** ASC Prep / Recovery

Room #: B203D

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Cart, Supply, 36x24x72

AE #: CASU-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Chrome supply cart; 4-wire shelves; 1-bottom shelf; 4" casters; 2-braking and 2-swivel

View Cutsheet 159101

W x D x H: 36 x 24 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Room: Supply & Equipment (PACU) **Department:** ASC Prep / Recovery

Room #: B203D

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203E

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Recycle, Pulse Ox Probes — AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203E

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air — AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208701

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203E

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Hamper, Linen — AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headwall, Patient — AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision

View Cutsheet 211253

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino

Supplemental Info

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)
Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 120V 60Hz

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203E

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Module CO2 — AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension No Cutsheet 171764

Monitor, Physiological, Monitor Arm — AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203E

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Pump, Compression — AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203E

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

with casters

W x D x H: 23 x 23 x 25.5 in.

Stretcher — AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Room: PACU **Department:** ASC Prep / Recovery

Room #: B203E

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Thermometer, Temporal — AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Warmer, Patient — AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.

Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Warmer, Patient, Bracket — AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor. View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: PACU w/Lift

Department: ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Recycle, Pulse Ox Probes

AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps

AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: PACU w/Lift **Department:** ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Air

AE #: FLAI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UA-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208701

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: PACU w/Lift **Department:** ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Headwall, Patient

AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision

View Cutsheet 211253

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino

Supplemental Info

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)
Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 120V 60Hz

Room: PACU w/Lift **Department:** ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Module CO2

AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension No Cutsheet 171764

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: PACU w/Lift **Department:** ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Patient Lift, Ceiling Mount — AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Standard up to 400 lbs or so.

Supplemental Info

Electrical: 115V 60Hz 2.5A

Pump, Compression — AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.

Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: PACU w/Lift **Department:** ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: PACU w/Lift **Department:** ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Warmer, Patient

AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius

View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.
Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Room: PACU w/Lift **Department:** ASC Prep / Recovery

Room #: B203F

Room Notes: Ceiling pendant requested - CF/CI. This room has a 9'W headwall.

Warmer, Patient, Bracket

AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor. View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Alcove, Airway Cart

Department: ASC Prep / Recovery

Room #: B203H1

Cart, Airway

AE #: CAAI-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	BASIX PLUS		Floor	OF/VI	Project

Cart is fabricated of a steel cabinet, aluminum drawers and polymer base; 3",6",9", and 12" deep drawers are specified as desired; accessories can be mounted to cart as desired. View Cutsheet 139811

MBP3210TL, MB-DB top right image on spec sheet is what we want per photo sent by Raymond.

W x D x H: 30 x 24.5 x 56 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Endoscope Holder (2-Scope)	MBA245	1	1

Room: Toilet (Staff)

Department: ASC Prep / Recovery

Room #: B203L, B207B, B207D

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supply **Department:** ASC Prep / Recovery

Room #: B204A

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system — No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023. ParEx may not be used here. Still TBD.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Linen — AE #: CALI-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAXI		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 36" x 24". Two solid (mx2436f) and two grid shelves (mx2436g); on 5" casters - one set swivel (5mdxa) and one set braking (5mdbxa); side and back enclosure panels (mep57e & mep37e); to include blue coated cover with velcro closures (24x36x74vcmb). — View Cutsheet 167067

downsized from a 4' to a 3' cart in order to fit in the clean supply room

W x D x H: 36 x 24 x 80.1 in.

Cart, Linen — AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. — View Cutsheet 160213

One cart for linens and one cart for pillows

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x72 — AE #: CASU-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Chrome supply cart; 4-wire shelves; 1-bottom shelf; 4" casters; 2-braking and 2-swivel — View Cutsheet 159101

Solid bottom shelf

W x D x H: 36 x 24 x 72 in.

Room: Clean Supply **Department:** ASC Prep / Recovery

Room #: B204A

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Monitor, Transport

AE #: MOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3		Shelf	OF/VI	Project

MMS module X3; touchscreen user interface View Cutsheet 170125

W x D x H: 7.4 x 3.4 x 6 in.
Network: Wireless
Electrical: 120V 60Hz 1.3A

Monitor, Transport, Component

AE #: MOTC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	Intellivue Dock	867043	Shelf	OF/VI	Project

Dock provides power to X3, MX100, X2, and MP2 for charging monitors. Additionally intended to provide the connected device with a LAN and flexible sync out interface. Supports variety of measurement extensions. View Cutsheet 209449

W x D x H: 7.5 x 3.9 x 4.4 in.
Electrical: 120V 60Hz **Weight:** 1.61 lbs.
Elect Notes: Power consumption <30 W average

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Shelf	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Shelf	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Room: Clean Supply **Department:** ASC Prep / Recovery

Room #: B204A

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Shelf	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Shelf	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Suction Machine — AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Warmer, Bath — AE #: WABA-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MSCWARMER24S		Countertop	OF/VI	Supply Agreement

Readybath warmer, intelligent, 24 slot. Pre-programmed to 125 degrees f. First in / first out rotation of products. Electronic reporting of usage and diagnostic data. View Cutsheet 151300

W x D x H: 25 x 19 x 24.5 in.
Electrical: 120V 60Hz **Weight:** 45 lbs.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Clippers, Surgical — AE #: CLSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	5513E / 5514A		Countertop	OF/OI	Project

Surgical clipper (5513E) and surgical clipper charger (5514A). Charger is able to be wall mounted. View Cutsheet 200192

W x D x H: 2.4 x 1.73 x 9.15 in.

Electrical: 120V 60Hz **Weight:** 1 lbs.

Container, Recycle, Pulse Ox Probes — AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Room: Prep / Recovery

Department: ASC Prep / Recovery

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Prep / Recovery **Department: ASC Prep / Recovery**

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 [View Cutsheet 208703]

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. [View Cutsheet 209178]

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility [View Cutsheet 13153]

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Headwall, Patient — AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision [View Cutsheet 211253]

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino [Supplemental Info]

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)

Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Room: Prep / Recovery **Department: ASC Prep / Recovery**

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Monitor, Physiological

AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.

Network: Wired **Network Notes:** Required two data ports

Electrical: 120V 60Hz

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Module CO2

AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension

No Cutsheet 171764

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs.

View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Prep / Recovery **Department: ASC Prep / Recovery**

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

with casters

W x D x H: 23 x 23 x 25.5 in.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Warmer, Patient

AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius

View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.
Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Room: Prep / Recovery

Department: ASC Prep / Recovery

Room #: B204B, B204F, B204K, B204L, B204P, B204R, B204S, B204U, B204V

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 10'W headwall.

Warmer, Patient, Bracket

AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor. View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Clippers, Surgical — AE #: CLSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	5513E / 5514A		Countertop	OF/OI	Project

Surgical clipper (5513E) and surgical clipper charger (5514A). Charger is able to be wall mounted. View Cutsheet 200192

W x D x H: 2.4 x 1.73 x 9.15 in.

Electrical: 120V 60Hz **Weight:** 1 lbs.

Container, Recycle, Pulse Ox Probes — AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Room: Prep / Recovery

Department: ASC Prep / Recovery

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Prep / Recovery **Department: ASC Prep / Recovery**

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Headwall, Patient — AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision View Cutsheet 211253

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino Supplemental Info

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)

Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Room: Prep / Recovery **Department: ASC Prep / Recovery**

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.

Network: Wired **Network Notes:** Required two data ports

Electrical: 120V 60Hz

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Module CO2 — AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension

No Cutsheet 171764

Monitor, Physiological, Monitor Arm — AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs.

View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Pump, Compression

AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Room: Prep / Recovery **Department: ASC Prep / Recovery**

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

with casters

W x D x H: 23 x 23 x 25.5 in.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Warmer, Patient

AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius

View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.
Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Room: Prep / Recovery

Department: ASC Prep / Recovery

Room #: B204C, B204E, B204N, B204X

Room Notes: Ceiling pendant requested - CF/CI. These rooms have a 9'W headwall.

Warmer, Patient, Bracket

AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor. View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Alcove, Crash Cart & Airway Cart **Department:** ASC Prep / Recovery

Room #: B204G1

Cart, Airway

AE #: CAAI-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	BASIX PLUS		Floor	OF/VI	Project

Cart is fabricated of a steel cabinet, aluminum drawers and polymer base; 3",6",9", and 12" deep drawers are specified as desired; accessories can be mounted to cart as desired. View Cutsheet 139811

MBP3210TL, MB-DB top right image on spec sheet is what we want per photo sent by Raymond.

W x D x H: 30 x 24.5 x 56 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Endoscope Holder (2-Scope)	MBA245	1	1

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole. View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Room: Alcove, Crash Cart & Airway Cart **Department:** ASC Prep / Recovery

Room #: B204G1

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A

Weight: 6.3 lbs.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Clippers, Surgical — AE #: CLSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	5513E / 5514A		Countertop	OF/OI	Project

Surgical clipper (5513E) and surgical clipper charger (5514A). Charger is able to be wall mounted. View Cutsheet 200192

W x D x H: 2.4 x 1.73 x 9.15 in.

Electrical: 120V 60Hz **Weight:** 1 lbs.

Container, Recycle, Pulse Ox Probes — AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Room: Prep / Recovery

Department: ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Prep / Recovery

Department: ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Headwall, Patient

AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision

View Cutsheet 211253

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino

Supplemental Info

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)

Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.

Network: Wired **Network Notes:** Required two data ports

Electrical: 120V 60Hz

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Module CO2 — AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension

No Cutsheet 171764

Monitor, Physiological, Monitor Arm — AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs.

View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Pump, Compression — AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.
Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

with casters

W x D x H: 23 x 23 x 25.5 in.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Warmer, Patient

AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius

View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.
Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Room: Prep / Recovery **Department:** ASC Prep / Recovery

Room #: B204H

Room Notes: Ceiling pendant requested - CF/CI. This room has an 8'W headwall.

Warmer, Patient, Bracket — AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor. View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Prep / Recovery (w/Lift) **Department:** ASC Prep / Recovery

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Clippers, Surgical — AE #: CLSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	5513E / 5514A		Countertop	OF/OI	Project

Surgical clipper (5513E) and surgical clipper charger (5514A). Charger is able to be wall mounted. View Cutsheet 200192

W x D x H: 2.4 x 1.73 x 9.15 in.

Electrical: 120V 60Hz **Weight:** 1 lbs.

Container, Recycle, Pulse Ox Probes — AE #: CRPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.			Wall	OF/VI	Service Agreement

View Cutsheet 211177

W x D x H: 8 x 4.8 x 10 in.

Container, Sharps — AE #: COSH-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-04RES-04/OC-04-2004		Wall	OF/CI	Service Agreement

4 gallon sharps container with vertical drop lid (12.25"w x 6.81"d x 21.25"h); to include 4 gallon outer cabinet. Beige View Cutsheet 124464

W x D x H: 14.5 x 7.47 x 21.3 in.

Room: Prep / Recovery (w/Lift) **Department:** ASC Prep / Recovery

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Prep / Recovery (w/Lift) **Department:** ASC Prep / Recovery

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	FM-15UO-CHXX-S		Headwall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Headwall, Patient — AE #: HEPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hospital Systems	Custom		Wall	OF/CI	Project

Panel-style headwall with coverage from ceiling to 6" AFF. Panels available in any increment between 12" and 48". To include set of vertical bed bumpers in same laminate as the panels. Services to include: X O2, X MA, X Vacuum, X emergency power duplexes, X data provisions, nurse call provision

View Cutsheet 211253

Increase MA to 2? To be confirmed. Add rails for equipment in headwall for SCDs when not in use, and for suction canister slides. Finish confirmed choices: Headwall Finish: 3D Laminate, Oak on Ash LBB. Wall Guard Finish: Inpro, #0270 Palomino

Supplemental Info

Elect Notes: Single point of connection for power at top of unit for each panel section (A, B, C)
Plumb Notes: Single point of connection for med gases at top of unit for each panel section (A, B, C)

Room: Prep / Recovery (w/Lift) **Department:** ASC Prep / Recovery

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Monitor, Physiological — AE #: MOPH-55

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX550		Arm	OF/VI	Project

Comprehensive patient monitor that can also monitor vital signs. The Philips MX550 comes with a 15-inch touch screen interface. Display screen easily adjustable. Part of the Philips Multi-Measurement Module (MMS) system. Offers multiple plug-in modules that can measure a variety of parameters. Some of these modules include; anesthesia, Intensive, Cardiac, Neonatal, and general care.

View Cutsheet 205942

price includes cables for IntelliVue

W x D x H: 15 x 7.2 x 12.1 in.

Network: Wired **Network Notes:** Required two data ports

Electrical: 120V 60Hz

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Module CO2 — AE #: MPMC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	867041		Monitor	OF/VI	Project

Intellivue microstream extension

No Cutsheet 171764

Monitor, Physiological, Monitor Arm — AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs.

View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Room: Prep / Recovery (w/Lift) **Department: ASC Prep / Recovery**

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Headwall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls.

View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Patient Lift, Ceiling Mount — AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available confirm weight capacity. standard up to 400lbs or so.

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Pump, Compression — AE #: PUCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	ALP 501		Bed	OF/OI	Project

View Cutsheet 211402

W x D x H: 6.5 x 6 x 12 in.

Electrical: 120V 60Hz 14W **Weight:** 6.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Tubing Connector Assembly 5' Length (5 pairs)	ALP 25AK	1	1

Room: Prep / Recovery (w/Lift) **Department:** ASC Prep / Recovery

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Basket	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Prep / Recovery (w/Lift) **Department:** ASC Prep / Recovery

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

with casters

W x D x H: 23 x 23 x 25.5 in.

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Thermometer, Temporal

AE #: THTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Exergen Corporation	TAT-5000		Headwall	OF/OI	Project

Non-invasive temporal thermometer; measures body temperature by placing unit on temporal lobe; 0.1 second response time; LCD display; temperature range 60 to 110 degrees Fahrenheit

View Cutsheet 70167

W x D x H: 2 x 1.25 x 8 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount (With Dispenser)	124306	1	1

Room: Prep / Recovery (w/Lift) **Department:** ASC Prep / Recovery

Room #: B204M

Room Notes: Ceiling pendant requested - CF/CI. This room has a 10'W headwall.

Warmer, Patient — AE #: WAPA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	BAIR PAWS 875	87500	Headwall	OF/OI	Project

Forced-air patient warming system; consists of detachable, flexible hose, warming unit/heating element and hand-held temperature controller, used with disposable warming gowns; temperture range of 43 degrees to +/- 3 degrees celcius

View Cutsheet 164197

W x D x H: 7.75 x 4 x 13 in.
Electrical: 120V 60Hz 4.6A 552W **Weight:** 7 lbs.

Warmer, Patient, Bracket — AE #: WAPB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	Warming Unit Wall Mount	90080	Headwall	OF/CI	Project

Wall hanger for BAIR Paws patient warmer. Provided free from vendor.

View Cutsheet 212978

To be mounted directly to headwall panel by Contractor.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Prep / Recovery Staff Lounge **Department:** ASC Prep / Recovery

Room #: B207A

Coffee Brewer — AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Prep / Recovery Staff Lounge **Department:** ASC Prep / Recovery

Room #: B207A

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser. View Cutsheet 142083

W x D x H: 21 x 24 x 36 in.
Clearance: Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase
Weight: 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90º hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Ice Maker / Water Dispenser, Component

AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series No Cutsheet 211856

Room: Prep / Recovery Staff Lounge **Department:** ASC Prep / Recovery

Room #: B207A

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Microwave Oven, Commercial

AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Sharp	R-21LTF		Shelf	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Refrigerator Freezer, Upright

AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant. View Cutsheet 208926

This style unit requested by level 2 users instead of separate refrigerator and freezer.

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Prep / Recovery Staff Lounge

Department: ASC Prep / Recovery

Room #: B207A

Waste Receptacle, Recycling w/ Lid/Sign

AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Office, Shared / Meeting

Department: ASC Prep / Recovery

Room #: B207C

Room Notes: Used by Prep / Recovery team

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle, Recycling Combination

AE #: WARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Max-R	P-RO-STT10D		Floor	OF/OI	Project

10-gallon Top Load Waste & Recycling Bins.

View Cutsheet 209397

W x D x H: 28 x 15 x 30 in.

Room: Office, Private

Department: ASC Prep / Recovery

Room #: B207G

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Medical Gas Manifold **Department:** ASC Prep / Recovery

Room #: B207J

Cabinet, Medical Gas Tank

AE #: CMGT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	E.L.S. Products Corp	MG109		Floor	OF/OI	Project

Lockable oxygen cylinder storage cabinet for 9-12 D and E size cylinders. Standard self-latch door. Shields cylinders from heat, sparks and flame, and separates them from flammable and combustible materials. Optional accessory of Casters add 4" to height and 30 pounds to weight. View Cutsheet 158939

One for full tanks, one for empty tanks.

W x D x H: 23 x 18 x 44 in.

Weight: 170 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Casters (2 Rigid, 2 Swivel)	CA18	1	2

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Room: Corridor Outside Mat Mgmt **Department:** ASC Sterile Processing

Room #: A208

Cart, Supply

AE #: CASU-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Super erecta model with chrome finish to include (3) wire shelves, (1) solid bottom shelf, (2) braking casters, (2) swivel casters, and (4) 63" posts View Cutsheet 160459

For holding PPE.

W x D x H: 48 x 24 x 68 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Scope Processing **Department:** ASC Sterile Processing

Room #: A208F

Borescope

AE #: BORE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	VERIFEYE		Wall	OF/VI	Project

Specification features tablet with 11.6 inch display; brackets available for tabletop or wall mounted placement; dimensions represent borescope on stand

View Cutsheet 169899

W x D x H: 13.2 x 12.3 x 31 in.
Electrical: 120V 60Hz 150W

Cart, Scope

AE #: CASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	CLEANASCOPE CART	103631	Floor	OF/OI	Project

10-tray cart transport cart system with 10 trays for endoscopes; minimizes direct handling and contact with airborne contaminants; uses green (clean) and red (contaminated) covers

View Cutsheet 159789

W x D x H: 20.5 x 22.4 x 56.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Scope Processing **Department:** ASC Sterile Processing

Room #: A208F

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Pass Through, Window

AE #: PATW-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	PTWAENDO1100		Wall	OF/CI/VI	Project

Automated Pass-Through Window; 28" Wide; dual Microwave Sensor; Shelf extends 4" and 25" beyond window View Cutsheet 202654

W x D x H: 28.3 x 4.5 x 45.3 in.
Electrical: 120V 60Hz 1A

Scope, Flusher

AE #: SCFL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	SCOPE BUDDY PLUS		Wall	OF/VI	Project

Endoscope flushing aid with automatic and manual modes. Countertop or wall mounting. Disposable tubing to reduce cross contamination; continuous monitoring with trace and track feature View Cutsheet 168110

W x D x H: 7.6 x 11.6 x 10.4 in.
Electrical: 120V 60Hz 0.8A **Weight:** 9.9 lbs.

Room: Scope Processing **Department:** ASC Sterile Processing

Room #: A208F

Sink, Processing, Triple

AE #: SIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	AMSCO 50 Series	SINK50106	Floor	OF/CI/VI	Project

Freestanding triple bay sink constructed of 304 stainless steel. Bays 24"W x 10"D x 17"H. Height adjustable 33"-41". Automatically monitors temperature and displays on control screen. Temperature is stored in memory for data retention. Automated chemistry dosing through integrated flow meters, also stored in memory.

View Cutsheet 211044

W x D x H: 106 x 28 x 52.6 in.
Electrical: 120V 60Hz 10A 1-Phase **Weight:** 445 lbs.
Elect Notes: ***Refer to manufacturer cut sheet information.***
Plumb Notes: ***Refer to manufacturer cut sheet information.***
Water: Hot, cold, and pure; 1/2" female NPT.
Compressed air: 1/4" female NPT.
Drain: 1-1/2" ABS.
HVAC Notes: ***Refer to manufacturer cut sheet information.***
Struct Notes: ***Refer to manufacturer cut sheet information.***

Table, Work

AE #: TAWO-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	MWTS2436FS		Floor	OF/VI	Project

Space saver mobile stainless steel work table with solid bottom shelf, 600 lb load rating.

View Cutsheet 207729

ATP testing work area

W x D x H: 36 x 24 x 34 in.
Weight: 64 lbs.

Tester, Leak

AE #: TELE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	ALT PRO		Countertop	OF/VI	Project

Automated endoscope leak tester; Automated or manual options; Can dry leak test two endoscopes at a time; Cycle time of 2 min 20 seconds; With LCD display, built in RFID reader,

View Cutsheet 146215

transitioning to this model at all sites. Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

W x D x H: 11 x 7.9 x 8 in.
Electrical: 120V 60Hz **Weight:** 12.1 lbs.

Room: Scope Processing **Department:** ASC Sterile Processing

Room #: A208F

Washer, Scope, Component — AE #: WASC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	MF01-0072		Wall	OF/CI/VI	Future Purchase

Hard-Plumbed Prefilter assembly to be installed in advance of the Advantage Plus Scope Washer — View Cutsheet 200469

W x D x H: 38 x 6 x 26 in.
Plumb Notes: Requires water and drain. Refer to manufacturer's site planning guide.

Washer, Scope, Component — AE #: WASC-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	78400-931		Wall	OF/CI	Project

Wall mounted hookup rack stores up to (8) hook-up blocks and tube connectors plus up to (2) disinfection blocks — View Cutsheet 141297

W x D x H: 11.3 x 15.8 x 24.5 in.

Washer, Scope, Component — AE #: WASC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	MF01-0072		Wall	OF/CI/VI	Project

Hard-Plumbed Prefilter assembly to be installed in advance of the Advantage Plus Scope Washer — View Cutsheet 200469

W x D x H: 38 x 6 x 26 in.
Plumb Notes: Requires water and drain. Refer to manufacturer's site planning guide.

Room: Scope Processing **Department:** ASC Sterile Processing

Room #: A208F

Washer, Scope, Pass Thru

AE #: WSPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	ADVANTAGE PLUS PASS THRU		Floor	OF/CI/VI	Future Purchase

Automated endoscope reprocessor; pass-thru model with hard wall separation between clean and dirty side; hands free operation and automatic start for ease of operation; dual asynchronous basins; computerized cycle documentation and reporting; continuous leaking testing during cycle; remote diagnostics; large visual display of real time information; barcode scanner for fast and accurate data entry

View Cutsheet 163996

FUTURE WASHER

W x D x H: 51.5 x 31.3 x 78.8 in. **Clearance:** Rear 21 in.; Left 0.5 in.; Right 0.1 in.; Top 1 in.; Front 21 in.
Network: Networked
Electrical: 120V 60Hz 1200W 1-Phase **Weight:** 882 lbs.

Elect Notes: **refer to manufacturer's technical specifications.** facility connections are made inside the wall, access panels (facility supplied) will be required to provide access to these connections. Facility connections must not be more than 3 feet above the top of the system. Facility supplied connection, a gfi protected nema 5-15r outlet located in the wall behind an access panel. Network: facility supplied connection, rj45 receptacle located in the wall behing an access panel. Internet access highly recommended to allow for remote diagnostics.

Plumb Notes: **refer to manufacturer's technical specifications.** facility connections are made inside the wall, access panels (facility supplied) will be required to provide access to these connections. Facility connections must not be more than 3 feet above the top of the system. 1/2" npt female with shutoff valve and pressure gauge located in wall behind access panel. Supplied water must meet minimum requirements: potable water, ro water is preferred; incoming water filtered to 1 micron; water pressure of 30 to 87 psi (2 to 6 bar) is required, with minimum dynamic pressure of 30 psi (2 bar) at 1.3 gal/min (5l/min) flow; incoming waterline must be a minimum of 1/2" id; disinfectant water temperature 95 deg. F +/- ; water hardness less than 200 ppm caco3 (200 mg/l caco3); drain must be located in floor in the location indicated in the installation diagram; drain system must be capable of draining 10.5 gal/min (40l/min); facility supplied connection, a flush floor drain with minimum diameter of 4". Air supply: facility supplied connection 1/4" npt female with shutoff valve and pressure gauge located in wall behind access panel; compressed air must meet requirements of 58 to 145 psi (4 to 10 bar), max. Demand of compressed air is 1.1 scfm (32 l/min anr), filtered to 5 microns, max. Dew point is 45 deg. F.; max. Oil concentration is 5 mg/m3.

HVAC Notes: **refer to manufacturer's technical specifications.** facility connections are made inside the wall, access panels (facility supplied) will be required to provide access to these connections. Facility connections must not be more than 3 feet above the top of the system. Heat load idle 600 btu/hr, cycle 1 basin 1600 btu/hr, cycle 2 basins 2400 btu/hr. Ventilation: minimum of 10 air changes per hour in the room; facility supplied connection, a 4" round duct located in wall behind an access panel; minimum of 25 cfm at 0.25 inches-water (62 pa) static pressure is required to properly vent the system.

Struct Notes: Wall rough opening 52.5"w x 79.75"h. Optional trim kit requires a minimum of 4" uninteruppted wall space on the sides and top of the reprocessor for trim attachment. Optimal wall thickness 4.5" to 7".

Room: Scope Processing **Department:** ASC Sterile Processing

Room #: A208F

Washer, Scope, Pass Thru

AE #: WSPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	ADVANTAGE PLUS PASS THRU		Floor	OF/CI/VI	Project

Automated endoscope reprocessor; pass-thru model with hard wall separation between clean and dirty side; hands free operation and automatic start for ease of operation; dual asynchronous basins; computerized cycle documentation and reporting; continuous leaking testing during cycle; remote diagnostics; large visual display of real time information; barcode scanner for fast and accurate data entry

View Cutsheet 163996

W x D x H: 51.5 x 31.3 x 78.8 in. **Clearance:** Rear 21 in.; Left 0.5 in.; Right 0.1 in.; Top 1 in.; Front 21 in.
Network: Networked
Electrical: 120V 60Hz 1200W 1-Phase **Weight:** 882 lbs.
Elect Notes: **refer to manufacturer's technical specifications.** facility connections are made inside the wall, access panels (facility supplied) will be required to provide access to these connections. Facility connections must not be more than 3 feet above the top of the system. Facility supplied connection, a gfi protected nema 5-15r outlet located in the wall behind an access panel. Network: facility supplied connection, rj45 receptacle located in the wall behing an access panel. Internet access highly recommended to allow for remote diagnostics.
Plumb Notes: **refer to manufacturer's technical specifications.** facility connections are made inside the wall, access panels (facility supplied) will be required to provide access to these connections. Facility connections must not be more than 3 feet above the top of the system. 1/2" npt female with shutoff valve and pressure gauge located in wall behind access panel. Supplied water must meet minimum requirements: potable water, ro water is preferred; incoming water filtered to 1 micron; water pressure of 30 to 87 psi (2 to 6 bar) is required, with minimum dynamic pressure of 30 psi (2 bar) at 1.3 gal/min (5l/min) flow; incoming waterline must be a minimum of 1/2" id; disinfectant water temperature 95 deg. F +/- ; water hardness less than 200 ppm caco3 (200 mg/l caco3); drain must be located in floor in the location indicated in the installation diagram; drain system must be capable of draining 10.5 gal/min (40l/min); facility supplied connection, a flush floor drain with minimum diameter of 4". Air supply: facility supplied connection 1/4" npt female with shutoff valve and pressure gauge located in wall behind access panel; compressed air must meet requirements of 58 to 145 psi (4 to 10 bar), max. Demand of compressed air is 1.1 scfm (32 l/min anr), filtered to 5 microns, max. Dew point is 45 deg. F.; max. Oil concentration is 5 mg/m3.
HVAC Notes: **refer to manufacturer's technical specifications.** facility connections are made inside the wall, access panels (facility supplied) will be required to provide access to these connections. Facility connections must not be more than 3 feet above the top of the system. Heat load idle 600 btu/hr, cycle 1 basin 1600 btu/hr, cycle 2 basins 2400 btu/hr. Ventilation: minimum of 10 air changes per hour in the room; facility supplied connection, a 4" round duct located in wall behind an access panel; minimum of 25 cfm at 0.25 inches-water (62 pa) static pressure is required to properly vent the system.
Struct Notes: Wall rough opening 52.5"w x 79.75"h. Optional trim kit requires a minimum of 4" uninteruppted wall space on the sides and top of the reprocessor for trim attachment. Optimal wall thickness 4.5" to 7".

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height

View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Scope Storage **Department:** ASC Sterile Processing

Room #: A208G

Cabinet, Scope Storage-Drying

AE #: CSSD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medivators, Inc.	ENDODRY		Floor / Wall	OF/CI/VI	Project

Pass-thru storage and drying cabinet continuously forces HEPA filtered air through up to 8 endoscope channels, ensuring a completely dry endoscope and reducing the risk of bacterial growth. Permanent ventilation of channels eliminates residual moisture within the cabinet that can lead to bacterial growth. Circulation of dry HEPA filtered compressed air through each channel and around the outer sheath ensures all channels are completely dry prior to use.

View Cutsheet 150700

W x D x H: 23.6 x 21.3 x 74.8 in.
Network: Networked
Electrical: 120V 60Hz 15A 1-Phase **Weight:** 375 lbs.
Elect Notes: **refer to manufacturer's technical specifications.** a gfi/rcd protected outlet (nema 5-15r) located on the wall a minimum of 78.7 inches off of the floor above the cabinet. 15-amp circuit. All electrical, network (rj45 network jack) and air connections must be placed a minimum of 78.7 inches off of the floor above the cabinet. It is recommended to install a surge protector to protect the endodry storage and drying system from voltage spikes.the nema 5-15 power cord included is approximately 6 feet (1.8 meters) in length.
Plumb Notes: **refer to manufacturer's technical specifications.** endodry storage and drying system requires instrument grade compressed air from the equipment provided cable assemblies (quick connector). The required air pressure is 29-145 psi (2-10 bar). The demand of compressed air is a maximum flow rate of 0.6 cfm (16 l/min) 72 psi (5 bar) for the endodry storage and drying system used with the advantage reprocessor and 1.2 cfm (33 l/min) at 72 psi (5 bar) for the endodry storage and drying system used with the dsd reprocessor. A flexible air pipe with ¼" or 6 mm inner diameter (minimum rating of 150 psi (10.5 bar) is required to connect the endodry storage and drying system with the air pressure system. The 5 foot (1.5 meter) line is included in the shipment. Maximum particle size is 1 micron. Maximum dew point is +3 degrees celcius. Maximum oil content is 0.01 mg/m3.
Struct Notes: **refer to manufacturer's technical specifications.** the two-sided endodry storage and drying cabinet is designed to fit into an opening in the wall. The rough opening from a single unit is h72.5" x w24". Install site has a level floor.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Assy, Cassette, Transport	CAS-1000	8	24
Install Endodry	INS-1011	1	3

Cart, Scope

AE #: CASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medivators, Inc.	CLEANASCOPE CART	103631	Floor	OF/OI	Project

10-tray cart transport cart system with 10 trays for endoscopes; minimizes direct handling and contact with airborne contaminants; uses green (clean) and red (contaminated) covers

View Cutsheet 159789

W x D x H: 20.5 x 22.4 x 56.5 in.

Room: Scope Storage **Department:** ASC Sterile Processing

Room #: A208G

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

For PPE

W x D x H: 36 x 24 x 66.8 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Scope Storage **Department:** ASC Sterile Processing

Room #: A208G

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Anteroom (Clean) **Department:** ASC Sterile Processing

Room #: A208K

Cart, Supply

AE #: CASU-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Super erecta model with chrome finish to include (3) wire shelves, (1) solid bottom shelf, (2) braking casters, (2) swivel casters, and (4) 63" posts View Cutsheet 160459

For holding PPE.

W x D x H: 48 x 24 x 68 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Anteroom (Clean) **Department:** ASC Sterile Processing

Room #: A208K

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Work Room **Department:** ASC Sterile Processing

Room #: A208K1

Allowance, Bins

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Akro-Mils / Myers Industries			Table	OF/OI	Project

specify color when ordering

View Cutsheet 76370

Borescope

AE #: BORE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	VERIFEYE		Cart	OF/VI	Project

Specification features tablet with 11.6 inch display; brackets available for tabletop or wall mounted placement; dimensions represent borescope on stand

View Cutsheet 169899

W x D x H: 13.2 x 12.3 x 31 in.
Electrical: 120V 60Hz 150W

Cabinet, Drying-Pass Thru

AE #: CDPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	DCR201201	00724995216320	Floor / Wall	OF/CI/VI	Project

Passthrough drying cabinet

View Cutsheet 211134

Per quote JSWEIGERT1709460 DATED 4/8/2024. Trim kit provided by manufacturer as an accessory.

W x D x H: 38 x 30.9 x 78.6 in. **Clearance:** Top 15.4 in.; Front 16.9 in.
Electrical: 120V 60Hz 20A 1-Phase **Weight:** 750 lbs.
HVAC Notes: Heat loss 2500 BTU/hr at 70 degrees F.
Struct Notes: Minimum top clearance for service 15.4". Ceiling height minimum recommended 96".

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Installation	SE101812	1	1
Trim Kit	DCAR380	1	1

Cart, Case

AE #: CACA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
30	Skytron	MMCCB12-1PS-SSD		Floor	OF/OI	Project

Short case cart. 2 doors and 1 adjustable shelf.

View Cutsheet 211383

W x D x H: 42 x 30 x 40 in.

Room: Clean Work Room **Department:** ASC Sterile Processing

Room #: A208K1

Cart, Case

AE #: CACA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
20	Skytron	MMCCB5-2PS-SSD		Floor	OF/OI	Project

Tall case cart. 2 doors and 2 adjustable shelves. View Cutsheet 211384

W x D x H: 42 x 30 x 57 in.

Cart, Sterilizer Loading

AE #: CSTL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Steris Corporation	AY1596604- 600 63"	63"	Floor	OF/VI	Project

63" loading car with 2 shelves View Cutsheet 171987

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Extra Shelf	AY1596644	1	4

Cart, Supply, 60x24x79

AE #: CSSS-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	2460NS / 74UPS		Floor	OF/VI	Project

Mobile cart with (5) stainless steel wire shelves, (4) stainless steel posts, (2) stainless steel swivel stem casters, (2) stainless steel brake stem casters, and clear shelf inlays. View Cutsheet 211379

W x D x H: 60 x 24 x 79 in.

Cart, Transfer

AE #: CATR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Steris Corporation	FD179		Floor	OF/VI	Project

Transfer Cart. Autolocking. Long Chamber. View Cutsheet 208936

For use with washer/disinfectors and automated passthrough

W x D x H: 28.8 x 37 x 33.3 in.

Weight: 90 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Cart Adapter	FD209	2	6

Room: Clean Work Room **Department:** ASC Sterile Processing

Room #: A208K1

Cart, Utility

AE #: CUSS-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Intermetro Industries	MW104		Floor	OF/VI	Project

Utility cart with two solid stainless steel shelves and 4" casters. Weight capacity 375 lbs. View Cutsheet 211380

W x D x H: 18 x 30 x 38 in.

Weight: 45 lbs.

Cart, Workstation

AE #: CAWO-1

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Lyon Workspace Products	S353030W2004I		Floor	OF/VI	Project

12 Drawer Mobile Workstation with 216 Compartments. Each modular drawer can support up to 400lbs. Two 6" fixed casters and two 6" swivel casters with brakes. Standard Lock with Single Drawer Access. View Cutsheet 211790

Place holder for now pending department approval

W x D x H: 60 x 28.3 x 39.8 in.

Incubator

AE #: INCU-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	490		Countertop	OF/OI	Project

Auto-reader for use with 3m attest super rapid readout biological indicators 1491 and 1492; includes ethernet cable for web app connectivity View Cutsheet 208004

W x D x H: 8.75 x 9 x 3.25 in.
Electrical: 120V 60Hz 1A

Incubator

AE #: INCU-15

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	CELERITY HP		Countertop	OF/OI	Project

Biological testing system for low temperature VHP sterilizers View Cutsheet 169903

W x D x H: 11.4 x 6.3 x 3.7 in.
Network: Wired
Electrical: 120V 60Hz 1A

Room: Clean Work Room **Department:** ASC Sterile Processing

Room #: A208K1

Instrument Tracking System — AE #: INTS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Censis Technologics, Inc.	CensiTrac		Wall	OF/VI	Project

Cloud-based surgical instrument and asset management system that tracks down to the instrument, procedure and patient level. View Cutsheet 202583

One for each packing station and one by sterilizers

Network: Networked
Electrical: 120V 60Hz

Rack Return, Motorized With Auto Door — AE #: RRAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	SCS-L-034		Floor	OF/CI/VI	Project

Motorized return conveyor system, 3-module, return door, flush mounted. With auto door. View Cutsheet 211787

W x D x H: 42 x 114 x 104 in.
Electrical: 120V 60Hz 15A 1-Phase
Elect Notes: Up to 4 powered conveyors (i.e.: motorized, feed-in, or feed-out) per power supply and up to 2 power supplies per circuit breaker, for a total of up to 8 powered conveyors per circuit breaker.
Plumb Notes: Air supply from washer building 1/4" pneumatic coupling w/80 dynamic to 125 static PSIG; drain with 1-1/2" male connects to the washer or floor drain

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Motorized Door Recess Installation Kit	SCS-15	1	1
Motorized Return Door	SCS-M-RD	1	1

Rack, Wrap — AE #: RAWR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Logiquip Healthcare Storage Solutions	WC60CH		Floor	OF/VI	Project

Lqs sterile wrap cart; chrome; 4 bar with rubber "o" rings View Cutsheet 122985

W x D x H: 60 x 24 x 63 in.

Sealer, Heat — AE #: SEHE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Healthmark Industries	F108		Countertop	OF/OI	Project

Continuous feed heat sealer. Any width packaging can be sealed. View Cutsheet 146707

W x D x H: 16 x 11.5 x 6.25 in.
Electrical: 120V 60Hz 180W **Weight:** 26 lbs.

Room: Clean Work Room **Department:** ASC Sterile Processing

Room #: A208K1

Sterilizer, Steam — AE #: STST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	600		Floor	OF/CI/VI	Project

Single door chamber size 26.5 w x 26.5 h x 63 d — View Cutsheet 168000

House steam fed — Supplemental Info

Elect Notes: ***Refer to manufacturer drawing detail.***
Plumb Notes: ***Refer to manufacturer drawing detail.***
HVAC Notes: ***Refer to manufacturer drawing detail.***
Struct Notes: ***Refer to manufacturer drawing detail.***

Sterilizer, Steam — AE #: STST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	600		Floor	OF/CI/VI	Project

Single door chamber size 26.5 w x 26.5 h x 63 d — View Cutsheet 168000

Electric option w/DI water feed. — Supplemental Info

Elect Notes: ***Refer to manufacturer drawing detail.***
Plumb Notes: ***Refer to manufacturer drawing detail.***
HVAC Notes: ***Refer to manufacturer drawing detail.***
Struct Notes: ***Refer to manufacturer drawing detail.***

Sterilizer, VHP — AE #: STVH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Advanced Sterilization Products / J & J Medical	STERRAD 100NX ALL-CLEAR		Floor	OF/VI	Project

Single door configuration hydrogen peroxide gas plasma technology sterilizer; uses combination of hydrogen peroxide vapor and low-temperature gas plasma to rapidly sterilize; four cycles; standard cycle time is appox. 47 minutes, flex cycle time is approx. 42 minutes, express cycle is appox. 24 minutes and duo cycle time is 60 minutes. Cycle temperature range 116.6 deg. F to 132.8 deg. F. Connectors rj45 for network, usb for barcode reader and printer. Chamber total volume: 152 liters. Four casters (2 locking). — View Cutsheet 165180

W x D x H: 30.5 x 41.5 x 70.9 in. **Clearance:** Left 39.4 in.; Right 39.4 in.; Front 39.4 in.
Network: Wired
Electrical: 208V 60Hz 30A 3-Phase **Weight:** 842 lbs.

Room: Clean Work Room **Department:** ASC Sterile Processing

Room #: A208K1

Table, Processing

AE #: TAPG-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Steris Corporation	PREP 63		Floor	OF/VI	Project

Standard electric height adjustable workstation provides ergonomic solution for processing and instrument tray assembly; features 30" x 60" stainless steel work surface and casters. Capable of handling evenly distributed loads of up to 500 lbs. View Cutsheet 206131

60" confirmed

W x D x H: 60 x 33.8 x 86 in.
Electrical: 120V 60Hz 3A

Table, Work

AE #: TAWO-66

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	MWT305FS		Floor	OF/VI	Project

Stainless steel worktable featuring 30" depth and bottom shelf; 5" poly caster wheels - 2 swivel / 2 brake View Cutsheet 171964

W x D x H: 48 x 30 x 34 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Custom - Add'L Lower Shelf		1	1

Transfer Carriage

AE #: TRCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Steris Corporation	AY1598104		Floor	OF/VI	Project

Transfer carriage, fixed height for 63" sterilizer. View Cutsheet 211112

With variable height option

W x D x H: 26.4 x 74.6 x 45.3 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Variable Height Option		1	4

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Dirty **Department:** ASC Sterile Processing

Room #: A209A

Air Management System

AE #: AIMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	FD448115		Washer	OF/VI	Project

Stainless-steel shroud to enclose piping and ductwork connections between (3) 7053HP washer/disinfectors and 108" ceiling. View Cutsheet 211791

Struct Notes: Wall opening width 129" for use with 3 washers. Refer to manufacturer drawing / cut sheet for additional information.

Borescope

AE #: BORE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Steris Corporation	VERIFEYE		Wall	OF/VI	Project

Specification features tablet with 11.6 inch display; brackets available for tabletop or wall mounted placement; dimensions represent borescope on stand View Cutsheet 169899

W x D x H: 13.2 x 12.3 x 31 in.
Electrical: 120V 60Hz 150W

Cart, Transfer

AE #: CATR-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Steris Corporation	FD179		Floor	OF/VI	Project

Transfer Cart. Autolocking. Long Chamber. View Cutsheet 208936

For use with washer/disinfectors and automated passthrough

W x D x H: 28.8 x 37 x 33.3 in.
Weight: 90 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Cart Adapter	FD209	2	6

Room: Dirty **Department: ASC Sterile Processing**

Room #: A209A

Cleaner, Ultrasonic — AE #: CLUL-29

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	InnoWave Ulta+		Table	OF/VI	Project

Ultra Sonic Irrigator to remove tissue, blood and other contaminants from a variety of surgical instruments; equipped with sonic irrigation, interlocking lid sensor, touch screen and data capture/export capabilities; capacity of 12 connected lumen instruments

View Cutsheet 211072

Plan for use with da Vinci instrumentation.

W x D x H: 29.5 x 21 x 15.6 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 2 in.; Top 13.4 in.
Electrical: 120V 60Hz 13A 1200W **Weight:** 121 lbs.
Plumb Notes: **Refer to manufacturer's specification sheet.** 3/4" hose tail outlet from unit for drain, requires hot and cold water.

Cleaner, Ultrasonic — AE #: CLUL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Steris Corporation	InnoWave Unity 20		Floor	OF/CI/VI	Project

Sonic irrigator 20-gallon. 16 lumens/cycle. 35 lbs/cycle. Can process DaVinci EndoWrist Xi devices.

View Cutsheet 202578

W x D x H: 34.8 x 25.8 x 42.5 in. **Clearance:** Rear 6 in.; Left 4 in.; Right 4 in.; Top 16.4 in.
Electrical: 208V 60Hz 3-Phase **Weight:** 428 lbs.
Elect Notes: **Refer to Steris site planning information.**
Plumb Notes: **Refer to Steris site planning information.** < 125 ppm with water quality and purity tested. 30 to 70 psi (2.0 to 5.0 Bar). 3 to 8 gal/min hot and cold. Cold +41 to 86 deg F. Hot +122 to 176 deg F. 3/4" BSP male thread rubber gasket is required. Do not use tape or any sealant, 3/4" NPT facility connections required. Hose connections will not work. Hot/Cold within 3 feet of proposed unit location. Drain connection 3/4" hose tail outlet from unit. Drain must be fitted with suitable traps. No loops in the drain hose, cut the hose to length to required. Floor sink or floor drain is preferred. Standpipe and wall drains are options for connection to drain. Adhere to local code. Capacity 8 gal/min maximum discharge to drain including overflow. Air tight seal of overflow to drain may cause incorrect unit operation. Air gap must be fitted if required by code. Effluent temperture up to +140 deg F.
HVAC Notes: **Refer to Steris site planning information.** Ambient operating temperature range +41 to 104 deg F. 80% relative humidity for up to +88 deg F decreasing linearly to 50% relative humidity at +104 deg F. Heat output during operation 205 W (700 BTU/hr) during wash cycle.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Dirty

Department: ASC Sterile Processing

Room #: A209A

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Instrument Tracking System

AE #: INTS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Censis Technologics, Inc.	CensiTrac		Wall	OF/VI	Project

Cloud-based surgical instrument and asset management system that tracks down to the instrument, procedure and patient level.

View Cutsheet 202583

1 by each sink and 4th by sterilizers

Network: Networked
Electrical: 120V 60Hz

Room: Dirty **Department:** ASC Sterile Processing

Room #: A209A

Pass Through, Window — AE #: PATW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	PTWAMDR1100		Wall	OF/CI/VI	Project

Automated pass through window for MDR/CSSD. Shelf extends 25in on each side of window (304 stainless steel shelf, brushed finish). Dual microwave sensor actuation from interior and exterior side. View Cutsheet 162476

W x D x H: 28 x N/A x 45 in. **Clearance:** Rear 25 in.; Front 25 in.
Electrical: 120V 60Hz **Weight:** 270 lbs.
Struct Notes: Finished opening 28-1/4" x 45-1/4". 12" strapping on load and unload sides required under wall opening for counter support.

Pump, Detergent — AE #: PUDE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Steris Corporation	Acu-sInQ		Sink Backsplash	OF/CI/VI	Project

Chemistry dosing system is a cleaning aid designed to provide detergent dosing capabilities at the sink with temperature monitoring and process documentation. View Cutsheet 211332

Two per sink by first basin. Mount on sink backsplash.

W x D x H: 7 x 6.25 x 5.25 in.
Electrical: 120V 60Hz 1A **Weight:** 4.3 lbs.

Rack, Washer — AE #: RAWA-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Steris Corporation	FD107		Washer	OF/VI	Project

3-level instrument washing rack manages instrument load during processing in the 7053I washer/disinfector View Cutsheet 160928

Prefer FD74 series. Confirm w/Steris when equipment preferences finalized.

W x D x H: 25.5 x 31.5 x 22 in.

Rack, Washer — AE #: RAWA-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Steris Corporation	FD105		Washer	OF/VI	Project

Two level manifold rack - long. Used to hold loaded instrument trays, general, and special purpose racks during processing in washer/disinfector. View Cutsheet 211124

Prefer FD74 series. Confirm w/Steris when equipment preferences finalized. Pat to send info on models.

W x D x H: 25.5 x 31.5 x 22 in.
Weight: 33 lbs.

Room: Dirty
Room #: A209A

Department: ASC Sterile Processing

Scope, Flusher

AE #: SCFL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Pure Processing	Flexipump		Sink Backsplash	OF/CI/VI	Project

The FlexiPump™ Independent Flushing System is a hands-free automatic flushing pump that replaces syringes and spray guns for manual cleaning. It can clean up to three instruments at once and has pre-programmed flush cycles for consistent and standardized flushing. View Cutsheet 211331

Mount above middle sink.

W x D x H: 11 x 7.25 x 7 in.
Electrical: 120V 60Hz

Sink, Processing, Triple

AE #: SIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Steris Corporation	AMSCO 50 Series	SINK50106	Floor	OF/CI/VI	Project

Freestanding triple bay sink constructed of 304 stainless steel. Bays 24"W x 10"D x 17"H. Height adjustable 33"-41". Automatically monitors temperature and displays on control screen. Temperature is stored in memory for data retention. Automated chemistry dosing through integrated flow meters, also stored in memory. View Cutsheet 211044

One sink left to right orientation, other 2 sinks right to left.

W x D x H: 106 x 28 x 52.6 in.
Electrical: 120V 60Hz 10A 1-Phase **Weight:** 445 lbs.
Elect Notes: ***Refer to manufacturer cut sheet information.***
Plumb Notes: ***Refer to manufacturer cut sheet information.***
Water: Hot, cold, and pure; 1/2" female NPT.
Compressed air: 1/4" female NPT.
Drain: 1-1/2" ABS.
HVAC Notes: ***Refer to manufacturer cut sheet information.***
Struct Notes: ***Refer to manufacturer cut sheet information.***

Table, Utility

AE #: TAUT-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LTSM30UIS / 5MPBGSA		Floor	OF/VI	Project

Mobile-ready worktable with type 304 stainless steel top and 3-sided frame. Casters to be ordered with table (5MPBGSA) with brakes for maximum stability. Load rated at 50 lbs. per square foot to a maximum of 600 lbs. View Cutsheet 211381

To support small tabletop ultrasonic cleaner

W x D x H: 30 x 30 x 34 in.

Room: Dirty **Department: ASC Sterile Processing**

Room #: A209A

Washer, Cart — AE #: WACA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Steris Corporation	VISION 1327		Floor Pit	OF/CI/VI	Project

High Capacity Mechanical Washer for Cleaning, Steam Heated. Low-Level Disinfecting, and Drying of Case Carts, Containers, Utensils, and Beds. View Cutsheet 208932

Includes Sumpless Solution Delivery System, Spraying System, Horizontal Sliding Doors, and Interior Lights.

W x D x H: 120 x 130 x 113 in.
Network: Networked
Electrical: 480V 60Hz 13.5A 3-Phase **Weight:** 7483 lbs.
Elect Notes: See Attached Specification Drawings and Utility Requirements Chart. 460-480V, 60Hz, 3-Ph. 13.5 Amps. Recommended current of 20 Amps.
Plumb Notes: Steam Heated Units. See Attached Specification Drawings and Utility Requirements Chart with regards to Drain, Steam Inlet, Condensate Return, Hot, Cold, and Pure Water Requirements.
HVAC Notes: See Attached Specification Drawings and Utility Requirements Chart on Ventilation Exhaust.
Struct Notes: See Attached Specification Drawings and Utility Requirements Chart on Walls, Ceiling, and Floor Requirements. Includes Pit Dimensions.

Washer/ Disinfector — AE #: WADI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Steris Corporation	7053HP		Floor	OF/CI/VI	Project

Cabinet-type mechanical washer that includes: Color touch screen control system and visual progress indicator. Audible warning system with adjustable volume. View Cutsheet 171926

power vertical sliding door. Eight factory-loaded (Instruments, Orthopedic

Instruments, Utensils, Plastic Goods, Rigid M.I.S., Anesthesia / Respiratory Goods, Gentle and Decontamination) and up to 20 Custom cycles. LED status indicator lighting.

To be model 7053RAS to accommodate da Vinci robot components

W x D x H: 42 x 38 x 80.8 in. **Clearance:** Top 10 in.
Network: Wired
Electrical: 480V 60Hz 34.5A 3-Phase **Weight:** 1543 lbs.
Elect Notes: Recommended Circuit 50A. See Attached Reference Drawings
Plumb Notes: See Attached Reference Drawings; requires hospital-provided steam
HVAC Notes: See Attached Reference Drawings
Struct Notes: See Attached Reference Drawings

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Auto Docking Tc Adapter	FD209	2	6
Robotic Assisted Surgery (RAS) Cycle		1	3

Room: Dirty **Department:** ASC Sterile Processing

Room #: A209A

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: Anteroom (Dirty) **Department:** ASC Sterile Processing

Room #: A209A1

Room Notes: PPE will be stored in casework, do not need a cart

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Anteroom (Dirty) **Department:** ASC Sterile Processing

Room #: A209A1

Room Notes: PPE will be stored in casework, do not need a cart

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office

Department: ASC Sterile Processing

Room #: A209B

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Vendor Workroom **Department:** ASC Sterile Processing

Room #: B207E

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Cart, Supply

AE #: CASU-79

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	SUPER ERECTA SOLID SHELVING		Floor	OF/VI	Project

Mobile cart with 3 each solid stainless steel shelves 60"w x 18"d and 4 each stainless steel posts 73-7/8"h with casters - 2 locking and 2 swivel View Cutsheet 172735

W x D x H: 60 x 18 x 79 in.

Cart, Supply

AE #: CASU-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	METROMAX		Floor	OF/VI	Project

48"w x 18"d x 69"h metromax mobile unit; polymer cart with 4 open grid shelves and 1 solid bottom shelf; 4 each metromax i mobile post (mx63up), 2 each cstr w/max bmpr (5mpx), 2 each cstr w/max bmpr (5mpbx), 4 each metromax i grid shelf (mx1848g), 1 each metromax i solid shelf (mx1848f) View Cutsheet 108876

W x D x H: 48 x 18 x 69 in.

Instrument Tracking System

AE #: INTS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Censis Technologics, Inc.	CensiTrac		Wall	OF/VI	Project

Cloud-based surgical instrument and asset management system that tracks down to the instrument, procedure and patient level. View Cutsheet 202583

Network: Networked
Electrical: 120V 60Hz

Room: Vendor Workroom **Department:** ASC Sterile Processing

Room #: B207E

Table, Work

AE #: TAWO-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	MWTS2436FS		Floor	OF/VI	Project

Space saver mobile stainless steel work table with solid bottom shelf, 600 lb load rating. View Cutsheet 207729

W x D x H: 36 x 24 x 34 in.

Weight: 64 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Break Room
Room #: B205B

Department: Lab - Ambulatory

Coffee Brewer

AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Break Room
Room #: B205B

Department: Lab - Ambulatory

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in.
Clearance: Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A
Weight: 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in.
Clearance: Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Break Room **Department: Lab - Ambulatory**

Room #: B205B

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers — No Cutsheet 141809

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required — View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Refrigerator Freezer, Upright — AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant. — View Cutsheet 208926

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. — View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Break Room

Department: Lab - Ambulatory

Room #: B205B

Waste Receptacle, Recycling w/ Lid/Sign

AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Cytology Lab **Department:** Lab - Ambulatory

Room #: B205C

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Microscope

AE #: LAMI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX43TF		Countertop	OF/VI	Project

Microscope with led illumination. Includes 10x, 40x, 50x, 100x objectives. With phase contrast components. View Cutsheet 160019

Single-head scope. Quote 2023-JAD-2992 - 15 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 10.8 x 17.9 x 16.1 in.
Electrical: 120V 60Hz 4W **Weight:** 28.7 lbs.

Room: Cytology Lab **Department:** Lab - Ambulatory

Room #: B205C

Lab Microscope, Multi-Head

AE #: LAMM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX53		Countertop	OF/VI	Project

Linear 5 headed BX53 microscope with DP28 camera

View Cutsheet 208472

5-head configuration confirmed. Unable to get 4-heads on a smaller footprint. Quote 2023-JAD-2946 - 15 provided 08/15/2024. Rep Jacob Dunkerson suggesting XAPO objectives (versus basic) and DP75 (versus DP 28). Rep Jacob has started with best configurations and UK can change configuration as needed. **Will need to review configurations with users

W x D x H: 63 x 18.3 x 18.1 in.
Electrical: 120V 60Hz 6A 100W **Weight:** 30 lbs.

Monitor, Humidity

AE #: MOHU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sensoscientific Inc.	Humidity and Temperature Sensor	B13-200-OTA	Wall	OF/CI/VI	Project

Monitor ambient temperature and humidity up to 125°C and 100% RH. Price includes humidity probe.

View Cutsheet 208486

W x D x H: 3.88 x 1.38 x 4.25 in.
Electrical: 120V 60Hz 0.5A
Elect Notes: Battery operated. Optional AC/DC power supply (UL Certified). AC Adapter: Input: 100-240V-50/60hz 0.5A Max, Output: 5V at 3.1A

Shelving, Wire

AE #: SHWI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	45TW17		Floor	OF/OI	Project

Corrosion-resistant, stainless steel mobile wire shelving unit The shelves can be removed and the sleeves can be repositioned to raise or lower the shelves on the posts. Load capacity: 800 lb

View Cutsheet 209117

W x D x H: 36 x 18 x 39 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Cytology Wet Specimen Area **Department: Lab - Ambulatory**

Room #: B205C1

Room Notes: (1) Clean, (1) Dirty sink

Cabinet, Safety, Flammable Storage — AE #: CASF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Uline	H-4177M-Y		Floor	OF/OI	Project

Undercounter Flammable Storage Cabinet - Manual Doors, Yellow, 22 Gallon — View Cutsheet 209113

Under cabinet/counter

W x D x H: 35 x 22 x 35 in.

Weight: 190 lbs.

Cart, Utility — AE #: CAUT-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Offex	OF-STC111-G		Floor	OF/OI	Project

Multi-purpose utility cart made from High-density Polyethelyne (HDPE) shelves and PVC legs that never rust, dent, scratch, or stain. Max weight capacity 300lb. Shelves 24"x18". Tub depth 2.75". Clearance between shelves 12" — View Cutsheet 209115

(2) for FNA with microscope on each and (1) for Mikroscan microscope system

W x D x H: 24 x 18 x 39.3 in.

Weight: 24.1 lbs.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black — View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Cytology Wet Specimen Area

Department: Lab - Ambulatory

Room #: B205C1

Room Notes: (1) Clean, (1) Dirty sink

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Lab Microscope System

AE #: LAMS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Mikron Instruments, Inc.	L5 System w/LiveQ Software		Cart	OF/VI	Project

L5 Real-time telemicroscopy system is remotely controlled microscope that allows traditional microscope evaluations of glass slide specimens from any network-accessible location. Includes computer, monitor, 10 slide holders, and one year of annual remote access software license package (5 users). Two objective configurations available: 2x, 4x, 10x, 20x, &40x OR 1.25x, 2x, 4x, 10x, &20x. View Cutsheet 210687

Added per Amy G request per Jennifer Ratner email 3/20/2024. Confirmed placement on 3rd utility cart.

Network: Wired

Electrical: 115V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Laptop upgrade	COMP-222-L5	1	1

Lab Microscope, Dual Head

AE #: LADH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Olympus America, Inc.	BX43		Cart	OF/VI	Project

Dual head lab microscope frame with transmitted 1 arm, led ilium; objectives include 2x, 4x, 10x, 20x, 40x, and 100x oil; oriented for front facing users w/led pointer; 6 position nosepiece; 10x eyepiece View Cutsheet 209116

To go on Cytology Wet Specimen utility carts, (1) per cart. -Per email from Dana Richards / Amy Gerwirtz 3/22/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. Quote No: 2023-JAD-2991 - 13 obtained 8/15/24. **Will need to review configurations with users.

W x D x H: 10.8 x 21.5 x 16.1 in.

Electrical: 120V 60Hz 4A

Room: Cytology Wet Specimen Area **Department:** Lab - Ambulatory

Room #: B205C1

Room Notes: (1) Clean, (1) Dirty sink

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Rack, Dunnage — AE #: RADU-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	New Age Industrial	2029		Floor	OF/OI	Project

Heavy-duty, aluminum construction; open design for air circulation and reduces dust buildup; 3,200 lb. Weight capacity. View Cutsheet 168115

For raising up refrigerator under the counter.

W x D x H: 24 x 18 x 12 in.

Weight: 7.2 lbs.

Refrigerator, Undercounter — AE #: REUC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Danby Products Inc	DAR016A1BSLDB	804LG4	Floor	OF/OI	Project

1.6 cu. ft. (45 L) Capacity Compact Refrigerator View Cutsheet 209114

Under cabinet/counter. Can go directly on floor.

W x D x H: 17.7 x 17.7 x 19.8 in. **Clearance:** Rear 5 in.; Left 2 in.; Right 2 in.; Top 2 in.

Electrical: 120V 60Hz **Weight:** 34.2 lbs.

Elect Notes: This appliance must be grounded. Grounding reduces the risk of electrical shock by providing an escape wire for the electrical current. This appliance has a cord that has a grounding wire with a 3-prong plug. The power cord must be plugged into an outlet that is properly grounded. If the outlet is a 2-prong wall outlet, it must be replaced with a properly grounded 3-prong wall
outlet. The serial rating plate indicates the voltage and frequency the appliance is designed for.

Room: Cytology Wet Specimen Area **Department:** Lab - Ambulatory

Room #: B205C1

Room Notes: (1) Clean, (1) Dirty sink

UPS

AE #: UPSS-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	APC	BE900G3		Cart	OF/OI	Project

UPS battery backup with (6) NEMA 5-15R and (2) NEMA 5-15R surge outlets, USB type A and C ports. Typical recharge time 8 hours. Not rack mountable. View Cutsheet 210939

For Mikroscan microscope cart

W x D x H: 6.57 x 12.5 x 3.54 in.
Electrical: 120V 60Hz 540W **Weight:** 9.04 lbs.
Elect Notes: NEMA 5-15P plug with 5' cord

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Cytology, Private Office **Department:** Lab - Ambulatory

Room #: B205C2, B205C3

Room Notes: Pathologist

Lab Microscope

AE #: LAMI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX43TF		Countertop	OF/VI	Project

Microscope with led illumination. Includes 10x, 40x, 50x, 100x objectives. With phase contrast components. View Cutsheet 160019

Quote No: 2023-JAD-2992 - 15 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 10.8 x 17.9 x 16.1 in.
Electrical: 120V 60Hz 4W **Weight:** 28.7 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Cytology, Private Office (Attending) **Department:** Lab - Ambulatory

Room #: B205C4

Room Notes: Pathologist

Lab Microscope, Dual Head

AE #: LMDH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX46F3		Countertop	OF/VI	Project

Dual head microscope with side-by-side configuration. With the following objectives: 2, 4, 10, 20, 40. View Cutsheet 209272

Quote No: 2023-JAD-3031 - 11 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 33.2 x 14.3 x 21.6 in.
Electrical: 115V 60Hz

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Clinical Lab (Frzs + Ref) **Department:** Lab - Ambulatory

Room #: B206

Lab Freezer — AE #: LAFR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Fisher Scientific - Thermo	TSX3030FA		Floor	OF/VI	Project

Thermo Scientific™ TSX Series high-performance -30°C auto defrost freezers are designed with features that support sample protection and sustainability objectives for the storage reagents, pharmaceuticals, vaccines, biological and other commonly used laboratory and clinical materials such as primers, siRNA molecules and fetal bovine serum (FBS) requiring -30°C. The Series' V-drive technology is designed to provide temperature uniformity that continually adapts to user patterns, offering significant energy savings without compromising protection. Capacity: 29.2 cu ft.

View Cutsheet 209053

W x D x H: 34 x 37.9 x 78.5 in.
Electrical: 115V 60Hz **Weight:** 371 lbs.
Elect Notes: 15-amp dedicated ground circuit. Nema 5-15 hospital grade plug (115v).

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Room: Clinical Lab (Frzs + Ref) **Department:** Lab - Ambulatory

Room #: B206

Refrigerator, Upright, Pharmacy

AE #: RUPH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF25-PH-R0000G		Floor	OF/VI	Project

Laboratory and Pharmacy refrigerator with 24.6 cu ft capacity, glass door, right hinge, and 4 swivel locking casters. Includes (6) full extension epoxy-coated baskets. View Cutsheet 207375

W x D x H: 29.8 x 36.5 x 79.5 in.
Clearance: Rear 2 in.; Top 10 in.; Front 26 in.
Electrical: 115V 60Hz 10.6A 1-Phase
Weight: 415 lbs.
Elect Notes: NEMA 5-15P hospital grade plug and 9' cord. Maximum size of branch circuit overcurrent device - 15A dedicated circuit.
HVAC Notes: Integral top-mounted refrigeration module with 1/3 hp compressor and air-cooled condenser. Non-CFC R134a refrigerant (11.4 oz). BTU/hr normal heat rejection 1060 BTU/hr; maximum heat rejection continuous operation 3210 BTU/hr.
Struct Notes: 10" top clearance needed

Room: Cold Room **Department: Lab - Ambulatory**

Room #: B206A

Room Notes: Panelized system with insulation b/w metal, water cooled condenser and stainless steel evaporator preferred,

Cart, Supply, 48x24x68

AE #: CASU-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Intermetro Industries	Super Adjustable Super Erecta	5A556BC	Floor	OF/VI	Project

Supply Cart, 5-Shelf Wire Shelving Stem Caster Cart, Chrome, 5" wheel size with 600lb load capacity View Cutsheet 208682

W x D x H: 50 x 26.2 x 67.9 in.

Weight: 92 lbs.

Cart, Utility

AE #: CAUT-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	311C		Floor	OF/OI	Project

Cart, utility, three shelves, 22 gauge stainless steel capacity of 200 lbs., 4" swivel casters, option available 2 with brakes, shelves of 15-1/2"; shelf clearance of 11-3/4". View Cutsheet 165092

W x D x H: 27.5 x 16.3 x 32.1 in.

Weight: 29 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
4" Casters, 2 With Brake		1	1

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Cold Room **Department: Lab - Ambulatory**

Room #: B206A

Room Notes: Panelized system with insulation b/w metal, water cooled condenser and stainless steel evaporator preferred,

Refrigerator, Walk-In

AE #: REWI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nor-Lake, Inc.	Enviroline		Ceiling/Floor/Wall	OF/CI/VI	Project

Clinical Lab Cold Room. 10' x 10'6 x 8'7'. This full size walk-in contains 727 internal cubic feet to assure maximum storage capacity. 4C Cooler (+/-) 1C temperature uniformity. Floor walk-in recessed in 4" pit. Stainless steel with a smooth aluminum door. Water cooled with condensers mounted on top of refrigeration unit.

View Cutsheet 210442

Electrical: 208V 60Hz

Elect Notes: **please reference cutsheet planning drawings** Electrical System Requirements:
1) A dedicated circuit to the condensing unit running at 208-230/60/1 with a 20 Amp Breaker to be supplied and installed by electrical contractor
2) A dedicated circuit to the chamber Control/electrical Panel running at 115/60/1 with a 15 Amp Breaker to be supplied and installed by electrical contractor

Plumb Notes: **please reference cutsheet planning drawings**

HVAC Notes: **please reference cutsheet planning drawings**

Struct Notes: **please reference cutsheet planning drawings**

Room: Bone Marrow Processing **Department: Lab - Ambulatory**

Room #: B206C

Room Notes: Clean sink with eye wash. Plan for large 72" x 36" workbench

Allowance, Certification, Hood

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - Allowance				OF/OI	Project

No Cutsheet 167826

Cart, Procedure

AE #: CAPR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	FLEXLINE		Floor	OF/VI	Project

Standard width cart with 24" of vertical drawer space. To include (3) 3" drawers, (1) 6" drawer and (1) 9" drawer. Top drawer to have key lock. View Cutsheet 172947

For Bone Marrow Biopsies

W x D x H: 32.3 x 22.4 x 38.1 in.

Container, Sharps

AE #: COSH-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-02RES-0203SB		Countertop	OF/OI	Service Agreement

Two gallon container with vertical drop lid with beige stabiilty base. Does not lock container to base. Mounts to counter or other flat horizontal surface with semi-permanent adhesive strips or screws.. View Cutsheet 162279

W x D x H: 12.5 x 7 x 15.1 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Bone Marrow Processing **Department: Lab - Ambulatory**

Room #: B206C

Room Notes: Clean sink with eye wash. Plan for large 72" x 36" workbench

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Bone Marrow Processing **Department: Lab - Ambulatory**

Room #: B206C

Room Notes: Clean sink with eye wash. Plan for large 72" x 36" workbench

Hood, Fume, Green — AE #: HOFG-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Labconco Corp.	Protector Echo		Floor	OF/CI/VI	Project

The Protector Echo Filtered Fume Hood requires no ducting and is available in 4', 5', 6' and 8' widths. Neutrodine® Unisorb Filtration Technology offers comprehensive molecular filtration. Benchtop models include a fiberglass panelized liner with optional side windows, or with optional side and back windows. Models are available for carbon-only, carbon with acid sensor, carbon with formaldehyde sensor, or HEPA-only filtration. View Cutsheet 207999

W x D x H: 48 x 37.7 x 66.2 in.
Electrical: 115V 60Hz 10A **Weight:** 540 lbs.
Elect Notes: Power Cord & Plug: 11.75' power cord with plug
HVAC Notes: Requires Chemical Evaluation of space prior to purchase. See sample form in cutsheet.

Lab Workbench — AE #: LAWO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30668		Floor	OF/VI	Project

BONE MARROW BENCH: Heavy-Duty Workstation. Mobile 36"D x 72"L x 30" to 37"H (Adjustable). Black Phenolic Resin Top. Standard Powder-Coat Finish TBD. View Cutsheet 208773

Base/Leg Color: Oyster

W x D x H: 72 x 36 x 37 in.
Electrical: 120V 60Hz

Waste Container, Biohazard — AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.
Weight: 10.9 lbs.

Room: Bone Marrow Processing

Department: Lab - Ambulatory

Room #: B206C

Room Notes: Clean sink with eye wash. Plan for large 72" x 36" workbench

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Storage, Bulk **Department:** Lab - Ambulatory

Room #: B206D

Cabinet, Safety, Flammable Storage

AE #: CASF-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eagle Manufacturing Co.	4510X		Floor	OF/OI	Project

45 Gallon, self-closing, Flammable Liquid Safety Cabinet is constructed of 18-gauge (1 mm) steel. The sides, top, bottom, and doors are double-walled with a 1-1/2 in (3.8 cm) air space between walls. Includes two vents, each have 2 in (5.1 cm) threaded fittings and a fire baffle and cap. View Cutsheet 209032

W x D x H: 43 x 18 x 65 in.

Weight: 267 lbs.

Cabinet, Slide Storage

AE #: CASS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Epredia	141000		Countertop	OF/OI	Project

Hold up to 5000 standard 3 × 1 in. (75 × 26mm) microscope slides in the Epredia™ Stackable Slide Storage Cabinet. Finished in beige baked enamel and complete with drawers. Cabinets lock together when stacked. View Cutsheet 209048

W x D x H: 16.5 x 20.5 x 6 in.

Cabinet, Slide Storage

AE #: CASS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Epredia	14-100-1		Countertop	OF/OI	Project

Metal base for use with storage cabinet 141000. Base is mounted on four rubber feet to protect bench surfaces and floors. Foam dividers for slide drawers (Cat. No. B1000152) available in packs of 12. Cabinet and base are sold separately View Cutsheet 209049

W x D x H: 15.7 x 18.7 x 2.75 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Room: Storage, Bulk

Department: Lab - Ambulatory

Room #: B206D

Pallet

AE #: PALL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	3VAT5		Floor	OF/OI	Project

Stackable pallet. Four way entry. 2000 lb load capacity. View Cutsheet 158718

W x D x H: 48.9 x 48.8 x 5.5 in.

Rack, Dunnage

AE #: RADU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	HP2236PDMB		Floor	OF/OI	Project

Polymer dunnage rack with built-in antimicrobial product protection. Weight capacity 3000 pounds. Separate polymer tie provided for joining racks in "end-to-end" and "back-to-back" configurations. NSF listed. View Cutsheet 129036

W x D x H: 36 x 22 x 12 in.

Shelf, Cabinet

AE #: SHCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Justrite Manufacturing Co.	29937		Cabinet	OF/OI	Project

Expand storage, add new convenience to existing cabinets, or customize your new cabinet with additional shelves to meet specific workflow needs. View Cutsheet 209034

Galvanized steel shelves hold up to 350 lb (159 kg) and adjust on 3" (76-mm) increments for versatile storage.

W x D x H: 39.4 x 14 x N/A in.

Shelving System, Top Track

AE #: SSTT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Top Track		Floor	OF/VI	Project

Metromax I top-track shelving system consisting of two stationary end units and sliding center units; each unit to feature 5-tiers of Metromax-I shelving View Cutsheet 204383

W x D x H: N/A x 60 x 87 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Storage, Bulk

Department: Lab - Ambulatory

Room #: B206D

Waste Receptacle, Recycling Can/ Bottle

AE #: WRCB-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	Project

Green slim jim recycling with venting channels; 23 gallon

View Cutsheet 124391

W x D x H: 11 x 22 x 30 in.

Room: Office, Cubes

Department: Lab - Ambulatory

Room #: B206E, B206G

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Office, Private

Department: Lab - Ambulatory

Room #: B206H

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Urinalysis **Department: Lab - Ambulatory**

Room #: B206J

Room Notes: Dirty sink in this area

Analyzer, Urinalysis — AE #: ANUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sysmex America Inc	UN-3000	Benchtop	Floor	OF/CI/VI	Project

The Sysmex UN-Series Automated Urinalysis Solution is a fully scalable urinalysis solution, delivering a comprehensive assessment of urinalysis results. With fluorescent flow cytometry technology at its core, the Sysmex UN-Series offers an innovative solution for any laboratory. System includes each of the following: Clinitek Novus (1), UF-5000 (1), UD-10 (1), and BCQM (1). Pricing and sizing for Benchtop model

View Cutsheet 208003

W x D x H: 77 x 36 x 61 in.
Clearance: Rear 20 in.; Left 20 in.; Right 20 in.; Top 46 in.
Network: Wired
Electrical: 117V 60Hz 20A 1-Phase
Weight: 1033 lbs.
Elect Notes: **See Manual Template**
Plumb Notes: **See Manual Template**
Struct Notes: **See Manual Template**

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Urinalysis **Department: Lab - Ambulatory**

Room #: B206J

Room Notes: Dirty sink in this area

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Analyzer, Urine — AE #: LAUR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	ADVANTUS		Countertop	OF/VI	Project

Urine dipstick reader. Semi-automated urine chemistry analyzer measures: leukocyte, nitrite, protein, blood, glucose, ketone, bilirubin, urobilinogen, ph, specific gravity, creatinine and protein-to-creatinine ratio. Automatically measures urine color. Sample id entry via manual, bar code or download methods. Calibration automatic with every strip. Memory: 500 patient results and 200 controls. Lcd touch screen display. Onboard thermal printer. Bar code scanner included, mounting clip optional. View Cutsheet 85039

W x D x H: 15.8 x 13.8 x 12.8 in.

Network: Wired

Network Notes: Ethernet connection: 10/100 mbit bidirectional. Keyboard: external pc keyboard option/ps2 connection. External printer interface: parallel port connector (25 pin).

Electrical: 120V 60Hz

Weight: 16 lbs.

Elect Notes: 72 va

Lab Centrifuge, Counter Top — AE #: LACC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Hemocue, Inc.	HEMOCUE STATSPIN EXRPESS 4	SSH4	Countertop	OF/OI	Project

High speed horizontal centrifuge. Adaptors for 7 and 10 ml tubes come with the unit. It can accommodate 1.5ml to 10ml. Adaptors sold separately. View Cutsheet 159663

Placeholder until preferred model provided

W x D x H: 13 x 16 x 8 in.

Electrical: 120V 60Hz 2.5A

Weight: 22 lbs.

Room: Urinalysis **Department: Lab - Ambulatory**

Room #: B206J

Room Notes: Dirty sink in this area

Lab Microscope — AE #: LAMI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX46		Countertop	OF/VI	Project

Microscope; BX46 w/ pln4x 4x objective, pln10x 10x objective, pln40x 40x objective, pln50xoi 50x o/i, pln100xo 100x oil objective; with dustcover. View Cutsheet 142868

BX45 is discontinued. Quote 2024-JAD-3217 - 8 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 10.8 x 17.9 x 16.1 in.
Electrical: 120V 60Hz 4A **Weight:** 28.7 lbs.

Lab Refrigerator, Undercounter — AE #: LARU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	TSX505SAVK		Undercounter	OF/VI	Project

5.5 cu. Ft. Undercounter lab refrigerator. Automatic defrost. Solid door. Three shelves. Full color tft-lcd; 4:3"; 480 x 272 display. View Cutsheet 164935

W x D x H: 23.6 x 26 x 31.8 in.
Electrical: 115V 60Hz 5A
Elect Notes: Plug type: nema 5-15p. 100-240v, 50-60hz. 10 amps max / 3 amp steady state.

Lab Workbench — AE #: LAWO-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30672		Floor	OF/VI	Project

URINE BENCH (C-30672): Direct Drive™ Height Adjustable Workstation. Mobile 30"D x 96"L x 30.5" to 43"H (Adjustable). Black Phenolic Resin Top. View Cutsheet 208777

Standard Powder-Coat Finish TBD. With 7 Duplex power strip

Base/Leg Color: Oyster

W x D x H: 96 x 30 x 43 in.
Electrical: 120V 60Hz 15A

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Urinalysis **Department: Lab - Ambulatory**

Room #: B206J

Room Notes: Dirty sink in this area

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red

View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Hematology **Department: Lab - Ambulatory**

Room #: B206K

Room Notes: Plan for large 72" x 36" Differential Workbench

Allowance, License

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Cellavision, Inc.				OF/OI	Project

No Cutsheet 210224

Amy to confirm

Cart, Utility

AE #: CAUT-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	311C		Floor	OF/OI	Project

Cart, utility, three shelves, 22 gauge stainless steel capacity of 200 lbs., 4" swivel casters, option available 2 with brakes, shelves of 15-1/2"; shelf clearance of 11-3/4". View Cutsheet 165092

Place next to CMAX table closest to Urinalysis. What is this used for? Does any specific equipment sit on this particular cart?

W x D x H: 27.5 x 16.3 x 32.1 in.

Weight: 29 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
4" Casters, 2 With Brake		1	1

Cart, Utility

AE #: CAUT-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	743		Floor	OF/OI	Project

Stainless steel 2 shelf utility cart;650 lb load capacity; two 5" diameter swivel casters and two 8" fixed wheels; clearance between shelves is 21"; shelf size is 21" x 33". View Cutsheet 46492

Place Hematek on top

W x D x H: 22.4 x 38.6 x 37.1 in.

Weight: 64 lbs.

Room: Hematology **Department: Lab - Ambulatory**

Room #: B206K

Room Notes: Plan for large 72" x 36" Differential Workbench

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Analyzer, Coagulation, Automated — AE #: LACA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stago / Diagnostica Stago, Inc.	COMPACT MAX		Countertop	OF/CI/VI	Project

Mechanical clot detection. Large color touch screen. Standardization of methodology, reagents and consumables. Comprehensive reagent offering/on-board management. Random access, true stat sample management. Integration of the all new expert module. At-a-glance status. Comprehensive qc system. Standardized sample reporting with expert rules (basic and advanced). Electronic lot conversion. Electronic log manager. On-board video tutorials View Cutsheet 139783

W x D x H: 38.2 x 28.7 x 27.8 in.

Network: Wired **Network Notes:** Netowrk - rj45 port (ethernet 10/100mbps) lis - rs232 port

Electrical: 115V 60Hz 12A **Weight:** 309 lbs.

Plumb Notes: Confirmed w/vendor - no plumbing needed

Room: Hematology **Department: Lab - Ambulatory**

Room #: B206K

Room Notes: Plan for large 72" x 36" Differential Workbench

Lab Analyzer, Hematology, Automated — AE #: LAHA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sysmex America Inc	XN-3100 (DI-60)		Floor	OF/CI/VI	Project

Automated Hematology analyzer with smart sampler testing, slidemaker/stainer, and DI-60 cell image analyzer. Throughput capacity: up to 200 CBCs/hour, 75 smears/hour. View Cutsheet 206269

W x D x H: 112 x 46.5 x 64 in.
Clearance: Rear 20 in.; Left 20 in.; Right 20 in.; Front 28.5 in.
Network: Wired
Network Notes: LIS, Refer to installation/technical sheets
Electrical: 117V 60Hz
Weight: 1644 lbs.
Elect Notes: Refer to installation/technical information sheets
Plumb Notes: Refer to installation/technical information sheets
HVAC Notes: Refer to installation/technical information sheets

Lab Microscope — AE #: LAMI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Olympus America, Inc.	BX46		Countertop	OF/VI	Project

Microscope; BX46 w/ pln4x 4x objective, pln10x 10x objective, pln40x 40x objective, pln50xoi 50x o/i, pln100xo 100x oil objective; with dustcover. View Cutsheet 142868

BX45 is discontinued. Quote 2024-JAD-3217 - 8 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 10.8 x 17.9 x 16.1 in.
Electrical: 120V 60Hz 4A
Weight: 28.7 lbs.

Lab Pipette, Repeating — AE #: LARE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	30568171		Stand	OF/OI	Project

Single channel with charging cable. Dispense aliquots as low as 100 nL. Increments: 1/10,000th tip size. Full range 100 nL – 50 mL. Up to 1,000 aliquots from one aspiration. No Touch Off™ dispenser. Includes: NanoRep™, 10 mL syringe tip, wall charger, hang-up and Quick Reference Guide. View Cutsheet 209160

W x D x H: N/A x N/A x 9 in.
Network Notes: Connectivity USB: charge, fimware update
Electrical: 120V 60Hz
Weight: 0.5 lbs.
Elect Notes: Battery operated with charging cable

Room: Hematology **Department: Lab - Ambulatory**

Room #: B206K

Room Notes: Plan for large 72" x 36" Differential Workbench

Lab Rocker, Tube — AE #: LART-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Scientific Products/Vwr	GTR-2-FS		Countertop	OF/OI	Project

Fixed Speed of 24 rpm and an Angle of ±25°, Tube Size from 1.5 to 50 ml on the Unit. View Cutsheet 207618

W x D x H: 13.6 x 7 x 7 in.
Electrical: 120V 60Hz

Lab Stainer — AE #: LAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	HEMATEK 3000		Cart	OF/VI	Project

Semi automated slide stainer with dryer View Cutsheet 164328

Place on Utility Cart: Lakeside 743

W x D x H: 21.3 x 18.1 x 8.7 in.
Electrical: 120V 60Hz **Weight:** 44 lbs.

Lab Workbench — AE #: LAWO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30670		Floor	OF/VI	Project

CMAX TABLE (C-30670): Cabinet Workstation. Mobile 42D X 72L X 36H. Black Phenolic Resin Top. Standard Powder-Coat Finish TBD View Cutsheet 208775

Base/Leg Color: Oyster

W x D x H: 72 x 42 x 36 in.
Electrical: 120V 60Hz

Lab Workbench — AE #: LAWO-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30671		Floor	OF/VI	Project

DIFF BENCH (C-30671): Direct Drive™ Height Adjustable Workstation. Mobile 36"D x 96"L x 30.5" to 43"H (Adjustable). Black Phenolic Resin Top. View Cutsheet 208776

Standard Powder-Coat Finish TBD. With 7 Duplex power strip.

Base/Leg Color: Oyster

W x D x H: 96 x 36 x 43 in.
Electrical: 120V 60Hz 15A

Room: Hematology **Department: Lab - Ambulatory**

Room #: B206K

Room Notes: Plan for large 72" x 36" Differential Workbench

Lab Workbench — AE #: LAWO-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30669		Floor	OF/VI	Project

CMAX TABLE (C-30669): Cabinet Workstation. Mobile 42D X 72L X 36H. Black Phenolic Resin Top. Standard Powder-Coat Finish TBD — View Cutsheet 208774

Base/Leg Color: Oyster

W x D x H: 72 x 42 x 36 in.
Electrical: 120V 60Hz

Lab, Pipette — AE #: LAPI-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+50, 100	17015233	Rack	OF/OI	Project

Fixed Volume XLS+ Pipete with UNV Tip, volume: 50ul or 100ul — View Cutsheet 210257

W x D x H: N/A x N/A x 9.6 in.
Weight: 2.3 lbs.

Lab, Pipette — AE #: LAPI-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 200	17015234	Rack	OF/OI	Project

Fixed Volume XLS+ Pipette with UNV Tip, volume: 200ul — View Cutsheet 210259

W x D x H: N/A x N/A x 9.7 in.
Weight: 0.23 lbs.

Lab, Pipette — AE #: LAPI-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 100-1000	17014407	Rack	OF/OI	Project

The Rainin LiteTouch System Pipette XLS+ with UNV Tip: Volume range 100ul - 1000ul — View Cutsheet 210260

W x D x H: N/A x N/A x 10.7 in.
Weight: 0.26 lbs.

Room: Hematology **Department: Lab - Ambulatory**

Room #: B206K

Room Notes: Plan for large 72" x 36" Differential Workbench

Lab, Pipette — AE #: LAPI-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 400, 500, 1000	17015235	Rack	OF/OI	Project

UNV Fixed Volume XLS+ Pipette, volume: 201 - 1000ul View Cutsheet 210261

W x D x H: N/A x N/A x 10.7 in.

Weight: 0.26 lbs.

Lab, Pipette — AE #: LAPI-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+, 2-20ul	17014412	Rack	OF/OI	Project

The Rainin Lite XLS+ System Pipette with UNV Tip: Volume range 2ul - 20ul View Cutsheet 210258

W x D x H: N/A x N/A x 8.8 in.

Weight: 0.45 lbs.

Rack, Pipette — AE #: RAPI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Poltex	PIPRK6		Countertop	OF/OI	Project

6 position pipette (pipettor) rack. Fits most popular brands of pipettes. View Cutsheet 209043

Super durable and cleanable (alcohol resistant) PETG construction. Rubber bumpons on base for a non-slip surface.

W x D x H: 11.4 x 6 x 8.6 in.

Waste Container, Biohazard — AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA View Cutsheet 150156

standards. Liner retainer band holds bags in place. Color: Red

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Room: Hematology **Department: Lab - Ambulatory**

Room #: B206K

Room Notes: Plan for large 72" x 36" Differential Workbench

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Accessioning / Processing **Department: Lab - Ambulatory**

Room #: B206L

Room Notes: Clean Sink w/ eye wash in this area. Plan for large 72" x 36" Processing, Blood Gas, and Centrifuge workbenches

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Cart, Utility — AE #: CAUT-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	311C		Floor	OF/OI	Project

Cart, utility, three shelves, 22 gauge stainless steel capacity of 200 lbs., 4" swivel casters, option available 2 with brakes, shelves of 15-1/2"; shelf clearance of 11-3/4". View Cutsheet 165092

W x D x H: 27.5 x 16.3 x 32.1 in.

Weight: 29 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
4" Casters, 2 With Brake		1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Accessioning / Processing **Department:** Lab - Ambulatory

Room #: B206L

Room Notes: Clean Sink w/ eye wash in this area. Plan for large 72" x 36" Processing, Blood Gas, and Centrifuge workbenches

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Freezer, Undercounter

AE #: FRLA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Helmer, Inc.	iLF105-GX		Undercounter	OF/VI	Project

Lab freezer. 5.3 cu ft. -15°c to -30°c. ADA compliant.

View Cutsheet 209341

W x D x H: 24.3 x 28.4 x 31.9 in. **Clearance:** Rear 3 in.
Network: Networked
Electrical: 115V 60Hz 4.1A **Weight:** 179 lbs.
Elect Notes: NEMA 5-15 hospital-grade | 115V 60Hz, 8 to 10 ft (2.4-3.0m)

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Accessioning / Processing **Department:** Lab - Ambulatory

Room #: B206L

Room Notes: Clean Sink w/ eye wash in this area. Plan for large 72" x 36" Processing, Blood Gas, and Centrifuge workbenches

Ice Maker

AE #: ICMA-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-SI		Countertop	OF/CI	Project

Ice-only dispenser automatic load in countertop configuration, with 12 lb (5.4 kg) of storage. 24 hour production capacity of approximately 425 lb (193.0 kg) of Chewblet compressed nugget ice at water temp. of 70 F (21 C); air temp. of 50 F (10 C). Equipped with automatic self-flushing and Quiet Night sleep mode. Automatic bin level control to start and stop ice machine. NSF and ETL listed.

*Countertop model

View Cutsheet 208923

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase **Weight:** 144 lbs.
Elect Notes: 8.5' cord w/NEMA 5-15P 90 degree hospital grade plug
Plumb Notes: Potable water inlet 3/8" FPT; Drain 3/4" MPT. Water temperature 45-90 degrees F. Water pressure 10-70 psi.
HVAC Notes: Air cooled; heat rejection 5000 BTU/hr
Struct Notes: Refrigerant R404a

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator.

View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Accessioning / Processing **Department:** Lab - Ambulatory

Room #: B206L

Room Notes: Clean Sink w/ eye wash in this area. Plan for large 72" x 36" Processing, Blood Gas, and Centrifuge workbenches

Lab Analyzer, Blood Gas — AE #: LABG-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Radiometer America, Inc.	ABL90 FLEX	393-090	Countertop	OF/VI	Project

Abl90 flex series analyzer, parameters include ph, pco2, hct, cl-, ca++, k+, na+, glucose, lactate, chb, so2, fo2hb, fmethb, and fhhb. Sensor cassette chosen will determine the parameters that will be reported. View Cutsheet 114514

Place on workbench 779

W x D x H: 9.8 x 11.4 x 17.7 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 24 lbs.

Lab Centrifuge, Counter Top — AE #: LACC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hettich Lab Technology	ROTINA 380	C8621-6347	Countertop	OF/OI	Project

Benchtop centrifuge with digital display and control panel View Cutsheet 103907

Blood tube package specified by Chad via email from Jennifer Ratner 3/22/2024. See accessories.

W x D x H: 18 x 23.6 x 16.5 in.
Electrical: 120V 60Hz **Weight:** 116.8 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Rotina 380 Blood Tube Package - 4	380BLOOD4	1	3

Lab Refrigerator, Undercounter — AE #: LARU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	TSX505SAVK		Floor	OF/VI	Project

5.5 cu. Ft. Undercounter lab refrigerator. Automatic defrost. Solid door. Three shelves. Full color tft-lcd; 4:3"; 480 x 272 display. View Cutsheet 164935

W x D x H: 23.6 x 26 x 31.8 in.
Electrical: 115V 60Hz 5A
Elect Notes: Plug type: nema 5-15p. 100-240v, 50-60hz. 10 amps max / 3 amp steady state.

Room: Accessioning / Processing **Department:** Lab - Ambulatory

Room #: B206L

Room Notes: Clean Sink w/ eye wash in this area. Plan for large 72" x 36" Processing, Blood Gas, and Centrifuge workbenches

Lab Splash Shield

AE #: LASS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Fisher Scientific - Thermo	14-293-38		Table	OF/OI	Project

Nalgene polycarbonate safety splash shield with 14" flexible arm. Shield is 0.12" thick. Magnetic base grips to magnetic surfaces. Provides UV protection from 200-360 nm. Do not use with radioisotopes. View Cutsheet 210685

W x D x H: 12 x 8.5 x 15 in.

Lab Workbench

AE #: LAWO-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30673		Floor	OF/VI	Project

CENTRIFUGE TABLE (C-30673): Mass Spectrometer Workstation. Mobile 31"D x 72"L x 36"H (Fixed). Black Phenolic Resin Top. Standard Powder-Coat Finish TBD View Cutsheet 208778

Base/Leg Color: Oyster

W x D x H: 72 x 31 x 36 in.
Electrical: 120V 60Hz

Lab Workbench

AE #: LAWO-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30674		Floor	OF/VI	Project

ABG TABLE (C-30674): Mass Spectrometer Workstation. Mobile 31"D x 72"L x 36"H (Fixed). Black Phenolic Resin Top. Standard Powder-Coat Finish TBD View Cutsheet 208779

Base/Leg Color: Oyster

W x D x H: 72 x 31 x 36 in.
Electrical: 120V 60Hz

Room: Accessioning / Processing **Department:** Lab - Ambulatory

Room #: B206L

Room Notes: Clean Sink w/ eye wash in this area. Plan for large 72" x 36" Processing, Blood Gas, and Centrifuge workbenches

Lab Workbench — AE #: LAWO-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30677		Floor	OF/VI	Project

PROCESSING MANUAL BENCH (C-30677): Direct Drive™ Height Adjustable Workstation. Mobile 36"D x 72"L x 30.5" to 43"H (Adjustable). Black Phenolic Resin Top. Standard. Powder-Coat Finish TBD

View Cutsheet 208782

Base/Leg Color: Oyster

W x D x H: 72 x 36 x 43 in.
Electrical: 120V 60Hz 15A

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Waste Container, Biohazard — AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red

View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.
Weight: 10.9 lbs.

Room: Accessioning / Processing

Department: Lab - Ambulatory

Room #: B206L

Room Notes: Clean Sink w/ eye wash in this area. Plan for large 72" x 36" Processing, Blood Gas, and Centrifuge workbenches

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Chemistry / Biomarkers

Department: Lab - Ambulatory

Room #: B206M

Room Notes: Plan for large 72" x 36" manual and file workbenches

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Chemistry / Biomarkers **Department:** Lab - Ambulatory

Room #: B206M

Room Notes: Plan for large 72" x 36" manual and file workbenches

Lab Analyzer, Chemistry, Immuno

AE #: LACI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Roche Diagnostics	Cobas Pro		Floor	OF/CI/VI	Project

Designed to meet your mid- to high-volume clinical chemistry and immunochemistry testing needs, cobas® pro integrated solutions is the latest innovation in the Roche cobas® family of analyzers. The state-of-the-art solution offers a range of advanced features that help you optimize workflow, improve productivity, and enhance reliability and turnaround times to support patient care.

View Cutsheet 208000

W x D x H: 188 x 46.7 x 56.3 in.
Network: Wired
Electrical: 208V 60Hz 1-Phase **Weight:** 4278 lbs.
Elect Notes: Power Consumption: Whole system: 5.5 kVA
• Sample supply unit and Sample buffers: < 0.8 kVA
• ISE: < 0.4 kVA
• cobas c 503 analytical unit: < 2.4 kVA
• cobas e 801 analytical unit: < 2.4 kVA
• Single phase
Plumb Notes: Deionized water consumption (avg): <64 L/h. Max liquid waste volume: Concentrated: <9 L/h. Normal: <52 L/h.

Lab Refrigerator, Undercounter

AE #: LARU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	TSX505SAVK		Undercounter	OF/VI	Project

5.5 cu. Ft. Undercounter lab refrigerator. Automatic defrost. Solid door. Three shelves. Full color tft-lcd; 4:3"; 480 x 272 display.

View Cutsheet 164935

W x D x H: 23.6 x 26 x 31.8 in.
Electrical: 115V 60Hz 5A
Elect Notes: Plug type: nema 5-15p. 100-240v, 50-60hz. 10 amps max / 3 amp steady state.

Lab Workbench

AE #: LAWO-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30675		Floor	OF/VI	Project

CHEM FILE BENCH (C-30675): Direct Drive™ Height Adjustable Workstation. Mobile 36"D x 72"L x 30.5" to 43"H (Adjustable). Black Phenolic Resin Top.

View Cutsheet 208780

Standard Powder-Coat Finish TBD

Base/Leg Color: Oyster

W x D x H: 72 x 36 x 43 in.
Electrical: 120V 60Hz 15A

Room: Chemistry / Biomarkers

Department: Lab - Ambulatory

Room #: B206M

Room Notes: Plan for large 72" x 36" manual and file workbenches

Lab Workbench

AE #: LAWO-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Workplace Modular Systems, Inc	C-30676		Floor	OF/VI	Project

CHEM MANUAL BENCH (C-30676): Mass Spectrometer Workstation. Mobile 31"D x 72"L x 36"H (Fixed). Black Phenolic Resin Top. Standard Powder-Coat Finish TBD

Base/Leg Color: Oyster

View Cutsheet 208781

W x D x H: 72 x 31 x 36 in.
Electrical: 120V 60Hz

Lab, Pipette

AE #: LAPI-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 400, 500, 1000	17015235	Rack	OF/OI	Project

UNV Fixed Volume XLS+ Pipette, volume: 201 - 1000ul

View Cutsheet 210261

W x D x H: N/A x N/A x 10.7 in.
Weight: 0.26 lbs.

Lab, Pipette

AE #: LAPI-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+, 2-20ul	17014412	Rack	OF/OI	Project

The Rainin Lite XLS+ System Pipette with UNV Tip: Volume range 2ul - 20ul

View Cutsheet 210258

W x D x H: N/A x N/A x 8.8 in.
Weight: 0.45 lbs.

Lab, Pipette

AE #: LAPI-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 100-1000	17014407	Rack	OF/OI	Project

The Rainin LiteTouch System Pipette XLS+ with UNV Tip: Volume range 100ul - 1000ul

View Cutsheet 210260

W x D x H: N/A x N/A x 10.7 in.
Weight: 0.26 lbs.

Room: Chemistry / Biomarkers **Department:** Lab - Ambulatory

Room #: B206M

Room Notes: Plan for large 72" x 36" manual and file workbenches

Lab, Pipette — AE #: LAPI-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+ 200	17015234	Rack	OF/OI	Project

Fixed Volume XLS+ Pipette with UNV Tip, volume: 200ul — View Cutsheet 210259

W x D x H: N/A x N/A x 9.7 in.

Weight: 0.23 lbs.

Lab, Pipette — AE #: LAPI-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rainin	UNV XLS+50, 100	17015233	Rack	OF/OI	Project

Fixed Volume XLS+ Pipete with UNV Tip, volume: 50ul or 100ul — View Cutsheet 210257

W x D x H: N/A x N/A x 9.6 in.

Weight: 2.3 lbs.

Monitor, Humidity — AE #: MOHU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Ceiling / Wall	CF/CI	Project

Centralized humidity monitoring system — No Cutsheet 209164

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Network: Wired

Room: Chemistry / Biomarkers **Department:** Lab - Ambulatory

Room #: B206M

Room Notes: Plan for large 72" x 36" manual and file workbenches

Rack, Pipette — AE #: RAPI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Poltex	PIPRK6		Countertop	OF/OI	Project

6 position pipette (pipettor) rack. Fits most popular brands of pipettes. View Cutsheet 209043

Super durable and cleanable (alcohol resistant) PETG construction. Rubber bumpons on base for a non-slip surface.

W x D x H: 11.4 x 6 x 8.6 in.

Waste Container, Biohazard — AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin — AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Storage

Department: Lab - Ambulatory

Room #: B206N

Room Notes: Previous R.O. Water room for purification system for Cobas Pro

Cart, Supply, 72x24x79

AE #: CASU-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA 2472FS		Floor	OF/VI	Project

6ft supply cart with solid, flat, stainless steel shelves and mobile casters with brakes.

View Cutsheet 211578

W x D x H: 72 x 24 x 74 in.

Room: Corridor

Department: Imaging (3rd Floor)

Room #: A301, A301F, A301G

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Dress

Department: Imaging (3rd Floor)

Room #: A301E1, A301E2, A301G3, A301F5, A301G5, A301F6, A301G6, A301F8, A301G8, A301F9

Room Notes: Assumes hamper will be in common space.

Room: EOS **Department: Imaging (3rd Floor)**

Room #: A301E3

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure — View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Confirm style and sizes of aprons desired, various sizes TBD

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	5

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. — View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black — View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: EOS

Department: Imaging (3rd Floor)

Room #: A301E3

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: EOS **Department: Imaging (3rd Floor)**

Room #: A301E3

Imaging, Radiographic System, Low Dose — AE #: IRSL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eos Imaging Inc.	EDGE		Floor	OF/CI/VI	Project

Intended for use in general radiographic examinations and applications, excluding the evaluation of lung nodules and exams involving fluoroscopy, angiography and mammography. Eos captures simultaneous frontal and lateral head-to-toe images of patients in the upright, weight bearing position using two perpendicular x-ray beams collimated in two thin, horizontal, fan-shaped beams and two detectors. Fan-beam x-rays and detectors are mounted on a c-arm and scan all or part of a patient's body. Digital images are immediately available on the 2d workstation. Includes system, workstation and patient positioning accessory package.

View Cutsheet 170183

Per quote 00000740 dated 3/8/2024 from Eric Howard, bone density can be done on this machine. Need software included if desired. Not available yet so cannot price it but will be available in 2025.

Supplemental Info

W x D x H: 102 x 102 x 97.6 in.
Network: Networked
Electrical: 480V 60Hz 164A 3-Phase **Weight:** 4420 lbs.
Elect Notes: Refer to vendor planning guide
Plumb Notes: Refer to vendor planning guide
HVAC Notes: Refer to vendor planning guide
Struct Notes: Refer to vendor planning guide

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Bone Density Software		1	1

Patient Lift, Ceiling Mount — AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Room: EOS

Department: Imaging (3rd Floor)

Room #: A301E3

Rack, Apron

AE #: RAAP-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eljay Medical	722025	520	Wall	OF/CI	Project

This lead apron and glove rack will hold five aprons and four gloves. The body is heavy gauge steel finished in gray baked enamel and the apron arms and glove supports are anodized aluminum. The unit is designed so that weight is supported by the floor which minimizes wall stress and simplifies installation. Specifications Dimensions: 30" wide x 69" high. Shipping Weight: 25 lbs. Body made of heavy gauge steel finished in grey enamel. Glove brackets and apron support rods are made from anodized aluminum.

View Cutsheet 209350

W x D x H: 30 x N/A x 69 in.

Weight: 25 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301F1

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Confirm type and sizes of aprons desired, various sizes TBD

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	5

Block, Finger — AE #: BLFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Infab Corporation	INF-NCAA		Countertop	OF/OI	Project

Adult oblique finger block. Coated Sponges feature a patented medical grade, fluid-resistant coated surface that is easy to clean with any medical grade disinfectant wipe or spray. View Cutsheet 210514

all items need to be Coated foam

W x D x H: 10.5 x 6 x 3 in.

Board, Transfer — AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory — AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Struct Notes: Wall backing may be required

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301F1

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301F1

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Digital Radiographic Unit — AE #: IMDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Del Medical / Umg	OTC18T		Floor/Ceiling	OF/CI/VI	Project

System includes overhead tube crane with vertical tracking and automatic collimator (manual version available); ev800 four way elevating float top table; vt300 tilting wall stand optional; high frequency generator; Delworks DR system; table capacity 800 lbs. View Cutsheet 168139

Supplemental Info

Network: Wired
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Imaging, Positioning Device — AE #: IMPC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7117-EF-B		Cabinet	OF/OI	Project

45 Degree Spinal Wedge. Coated, extra firm. View Cutsheet 209931

W x D x H: 7 x 24 x 7 in.

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301F1

Imaging, Positioning Device

AE #: IMPD-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7187-EF-B		Cabinet	OF/OI	Project

4 inch Decubitus Block, coated, extra firm. View Cutsheet 209930

W x D x H: 24 x 18 x 4 in.

Imaging, Positioning Device

AE #: IMPD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7100EFB		Cabinet	OF/OI	Project

Extra firm coated torso block 15.5” x 12” x 7” View Cutsheet 123251

Pad, Table

AE #: PATA-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Penn Jersey X-Ray	TPADHD8		Table	OF/OI	Project

Vinyl x-ray table pad with 8 double-stitched handles. Liquid and stain-proof. Radiolucent. Cleans with mild cleaner or germicide. Color: black. View Cutsheet 211246

Spec provided by Sierha Phillips.

W x D x H: 23.3 x 72 x 1 in.

Rack, Apron

AE #: RAAP-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eljay Medical	722025	520	Wall	OF/CI	Project

This lead apron and glove rack will hold five aprons and four gloves. The body is heavy gauge steel finished in gray baked enamel and the apron arms and glove supports are anodized aluminum. The unit is designed so that weight is supported by the floor which minimizes wall stress and simplifies installation. Specifications Dimensions: 30" wide x 69" high. Shipping Weight: 25 lbs. Body made of heavy gauge steel finished in grey enamel. Glove brackets and apron support rods are made from anodized aluminum. View Cutsheet 209350

W x D x H: 30 x N/A x 69 in.

Weight: 25 lbs.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301F1

Sandbag — AE #: SAND-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide, Inc.	SBK-CB		Cabinet	OF/OI	Project

Set includes two 10lb 11" x 11" sandbags; choose color when ordering

View Cutsheet 122392

W x D x H: 11 x N/A x 11 in.

Shield, Lead Free — AE #: SHLF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide	LPSG-T2424S		Floor	OF/OI	Project

Lead free mobile shield 24x24

View Cutsheet 208753

W x D x H: 24 x N/A x 24 in.

Stool, Foot, With Handrail — AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Walker — AE #: WALK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS864104BA		Floor	OF/OI	Project

Assembled Basic Walker, 2-Button, Folding, Adult, 400 lb. Easy-to-use, push-button mechanisms let walkers fold easily. Each side folds independently to allow easy movement through narrow spaces. Side cross braces provide extra durability. Push-button, height-adjustable legs. Height adjusts from approx. 32" to 39".

View Cutsheet 210028

W x D x H: 18 x 21 x 39 in.

Weight: 8 lbs.

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301F1

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Toilet (Patient)

Department: Imaging (3rd Floor)

Room #: A301F2

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Imaging (3rd Floor)

Room #: A301F2

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301F7

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Confirm type and sizes of aprons desired, various sizes TBD

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	5

Block, Finger — AE #: BLFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Infab Corporation	INF-NCAA		Countertop	OF/OI	Project

Adult oblique finger block. Coated Sponges feature a patented medical grade, fluid-resistant coated surface that is easy to clean with any medical grade disinfectant wipe or spray. View Cutsheet 210514

all items need to be Coated foam

W x D x H: 10.5 x 6 x 3 in.

Board, Transfer — AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory — AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Struct Notes: Wall backing may be required

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301F7

Chair, X-Ray

AE #: CHXR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Vela	Turn+ Thorax	70031	Floor	OF/OI	Project

Patient chair designed for thoracic X-rays, where the patient must be stabilized to obtain correct images. Lockable seat rotation (45°/90° right and left) and fold-down armrests allow easy access to capture X-ray images from multiple angles. The patient is placed at the apparatus and the armrests are folded down.

View Cutsheet 210044

W x D x H: 21.7 x 21.7 x 35.8 in.
Electrical: 120V 60Hz

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301F7

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Glove, Lead

AE #: GLLE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	69303		Countertop	OF/OI	Project

Pair of vinyl handcoverings covered with soft urethane materials for rugged durability. Breathable nylon liner keeps hands cool during procedures. View Cutsheet 146882

0.5mm protection. Navy blue.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301F7

Imaging, Digital Radiographic Unit

AE #: IMDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Del Medical / Umg	OTC18T		Floor/Ceiling	OF/CI/VI	Project

System includes overhead tube crane with vertical tracking and automatic collimator (manual version available); ev800 four way elevating float top table; vt300 tilting wall stand optional; high frequency generator; Delworks DR system; table capacity 800 lbs.

View Cutsheet 168139

Supplemental Info

Network: Wired
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Imaging, Positioning Device

AE #: IMPC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7117-EF-B		Cabinet	OF/OI	Project

45 Degree Spinal Wedge. Coated, extra firm.

View Cutsheet 209931

W x D x H: 7 x 24 x 7 in.

Imaging, Positioning Device

AE #: IMPD-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7187-EF-B		Cabinet	OF/OI	Project

4 inch Decubitus Block, coated, extra firm.

View Cutsheet 209930

W x D x H: 24 x 18 x 4 in.

Imaging, Positioning Device

AE #: IMPD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7100EFB		Cabinet	OF/OI	Project

Extra firm coated torso block 15.5” x 12” x 7”

View Cutsheet 123251

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301F7

Pad, Table

AE #: PATA-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Penn Jersey X-Ray	TPADHD8		Table	OF/OI	Project

Vinyl x-ray table pad with 8 double-stitched handles. Liquid and stain-proof. Radiolucent. Cleans with mild cleaner or germicide. Color: black. View Cutsheet 211246

Spec provided by Sierha Phillips.

W x D x H: 23.3 x 72 x 1 in.

Rack, Apron

AE #: RAAP-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eljay Medical	722025	520	Wall	OF/CI	Project

This lead apron and glove rack will hold five aprons and four gloves. The body is heavy gauge steel finished in gray baked enamel and the apron arms and glove supports are anodized aluminum. The unit is designed so that weight is supported by the floor which minimizes wall stress and simplifies installation. Specifications Dimensions: 30" wide x 69" high. Shipping Weight: 25 lbs. Body made of heavy gauge steel finished in grey enamel. Glove brackets and apron support rods are made from anodized aluminum. View Cutsheet 209350

W x D x H: 30 x N/A x 69 in.

Weight: 25 lbs.

Sandbag

AE #: SAND-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide, Inc.	SBK-CB		Cabinet	OF/OI	Project

Set includes two 10lb 11" x 11" sandbags; choose color when ordering View Cutsheet 122392

W x D x H: 11 x N/A x 11 in.

Shield, Lead Free

AE #: SHLF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide	LPSG-T2424S		Floor	OF/OI	Project

Lead free mobile shield 24x24 View Cutsheet 208753

W x D x H: 24 x N/A x 24 in.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301F7

Step, Platform Positioning Device — AE #: SPPD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radon Medical Imaging	CD-24305-C55		Floor	OF/OI	Project

One step patient positioner for CR and DR x-ray systems; mobile. View Cutsheet 211350

W x D x H: 19.5 x 17 x 51 in.

Stool, Foot, With Handrail — AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Walker — AE #: WALK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS864104BA		Floor	OF/OI	Project

Assembled Basic Walker, 2-Button, Folding, Adult, 400 lb. Easy-to-use, push-button mechanisms let walkers fold easily. Each side folds independently to allow easy movement through narrow spaces. Side cross braces provide extra durability. Push-button, height-adjustable legs. Height adjusts from approx. 32" to 39". View Cutsheet 210028

W x D x H: 18 x 21 x 39 in.

Weight: 8 lbs.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: X-Ray (with LLI) **Department:** Imaging (3rd Floor)

Room #: A301G1

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure [View Cutsheet 209349]

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Confirm type and sizes of aprons desired, various sizes TBD

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	5

Block, Finger — AE #: BLFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Infab Corporation	INF-NCAA		Countertop	OF/OI	Project

Adult oblique finger block. Coated Sponges feature a patented medical grade, fluid-resistant coated surface that is easy to clean with any medical grade disinfectant wipe or spray. [View Cutsheet 210514]

all items need to be Coated foam

W x D x H: 10.5 x 6 x 3 in.

Board, Transfer — AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white [View Cutsheet 148914]

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory — AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. [View Cutsheet 142325]

W x D x H: 32 x 1 x 5.5 in.

Struct Notes: Wall backing may be required

Room: X-Ray (with LLI)

Department: Imaging (3rd Floor)

Room #: A301G1

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: X-Ray (with LLI) **Department:** Imaging (3rd Floor)

Room #: A301G1

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Digital Radiographic Unit — AE #: IMDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Del Medical / Umg	OTC18T		Floor/Ceiling	OF/CI/VI	Project

System includes overhead tube crane with vertical tracking and automatic collimator (manual version available); ev800 four way elevating float top View Cutsheet 168139

table; vt300 tilting wall stand optional; high frequency generator; Delworks DR system; table capacity 800 lbs.

With the LLI system, quote provided by Karsten Colwell. Quote 6776 dated 4/22/2024. Supplemental Info

Network: Wired
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Room: X-Ray (with LLI) **Department:** Imaging (3rd Floor)

Room #: A301G1

Imaging, Digital Radiographic Unit, Accessory — AE #: IDRA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Del Medical / Umg	LLI DR System		Wall	OF/VI	Project

DelWorks LLI DR system w/(1) 17"x42" wireless cesium detector and EDR workstation. Includes long length wall stand (approximate dimensions noted), license, software, and other components. View Cutsheet 211248

W x D x H: 19.1 x 7.59 x 78.4 in.

Weight: 200 lbs.

Imaging, Positioning Device — AE #: IMPC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7117-EF-B		Cabinet	OF/OI	Project

45 Degree Spinal Wedge. Coated, extra firm. View Cutsheet 209931

W x D x H: 7 x 24 x 7 in.

Imaging, Positioning Device — AE #: IMPD-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7187-EF-B		Cabinet	OF/OI	Project

4 inch Decubitus Block, coated, extra firm. View Cutsheet 209930

W x D x H: 24 x 18 x 4 in.

Imaging, Positioning Device — AE #: IMPD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7100EFB		Cabinet	OF/OI	Project

Extra firm coated torso block 15.5” x 12” x 7” View Cutsheet 123251

Lead Glasses — AE #: LEGL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Burlington Medical, Inc.	ES90/91		Cabinet	OF/OI	Project

Radiation protection leaded eye frames are designed to fit over your current prescription lenses, providing side shields to protect from lateral exposure. View Cutsheet 209380

An excellent selection for easy and affordable protection without sacrificing the convenience of your own RX glasses. Best suited for medium width faces. Anti-fog, plano non-Rx.

Room: X-Ray (with LLI) **Department:** Imaging (3rd Floor)

Room #: A301G1

Lead Glasses — AE #: LEGL-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	ES30 Radiation Protection Leaded Eyewear		Countertop	OF/OI	Project

Radiation Protection lead glasses best suited for narrow faces

View Cutsheet 211242

Lead Glasses — AE #: LEGL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	ES82 Radiation Protection Leaded Eyewear		Countertop	OF/OI	Project

Radiation Protection Glasses best suited for wide faces

View Cutsheet 211243

Pad, Table — AE #: PATA-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Penn Jersey X-Ray	TPADHD8		Table	OF/OI	Project

Vinyl x-ray table pad with 8 double-stitched handles. Liquid and stain-proof. Radiolucent. Cleans with mild cleaner or germicide. Color: black.

View Cutsheet 211246

Spec provided by Sierha Phillips.

W x D x H: 23.3 x 72 x 1 in.

Rack, Apron — AE #: RAAP-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eljay Medical	722025	520	Wall	OF/CI	Project

This lead apron and glove rack will hold five aprons and four gloves. The body is heavy gauge steel finished in gray baked enamel and the apron arms and glove supports are anodized aluminum. The unit is designed so that weight is supported by the floor which minimizes wall stress and simplifies installation. Specifications Dimensions: 30" wide x 69" high. Shipping Weight: 25 lbs. Body made of heavy gauge steel finished in grey enamel. Glove brackets and apron support rods are made from anodized aluminum.

View Cutsheet 209350

W x D x H: 30 x N/A x 69 in.

Weight: 25 lbs.

Room: X-Ray (with LLI) **Department:** Imaging (3rd Floor)

Room #: A301G1

Sandbag — AE #: SAND-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide, Inc.	SBK-CB		Cabinet	OF/OI	Project

Set includes two 10lb 11" x 11" sandbags; choose color when ordering View Cutsheet 122392

W x D x H: 11 x N/A x 11 in.

Shield, Lead Free — AE #: SHLF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide	LPSG-T2424S		Floor	OF/OI	Project

Lead free mobile shield 24x24 View Cutsheet 208753

W x D x H: 24 x N/A x 24 in.

Stool, Foot, With Handrail — AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Walker — AE #: WALK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS864104BA		Floor	OF/OI	Project

Assembled Basic Walker, 2-Button, Folding, Adult, 400 lb. Easy-to-use, push-button mechanisms let walkers fold easily. Each side folds independently to allow easy movement through narrow spaces. Side cross braces provide extra durability. Push-button, height-adjustable legs. Height adjusts from approx. 32" to 39". View Cutsheet 210028

W x D x H: 18 x 21 x 39 in.

Weight: 8 lbs.

Room: X-Ray (with LLI)

Department: Imaging (3rd Floor)

Room #: A301G1

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301G7

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Confirm type and sizes of aprons desired, various sizes TBD

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	5

Block, Finger — AE #: BLFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Infab Corporation	INF-NCAA		Countertop	OF/OI	Project

Adult oblique finger block. Coated Sponges feature a patented medical grade, fluid-resistant coated surface that is easy to clean with any medical grade disinfectant wipe or spray. View Cutsheet 210514

all items need to be Coated foam

W x D x H: 10.5 x 6 x 3 in.

Board, Transfer — AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory — AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Struct Notes: Wall backing may be required

Room: X-Ray
Room #: A301G7

Department: Imaging (3rd Floor)

Chair, X-Ray

AE #: CHXR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Vela	Turn+ Thorax	70031	Floor	OF/OI	Project

Patient chair designed for thoracic X-rays, where the patient must be stabilized to obtain correct images. Lockable seat rotation (45°/90° right and left) and fold-down armrests allow easy access to capture X-ray images from multiple angles. The patient is placed at the apparatus and the armrests are folded down.

View Cutsheet 210044

W x D x H: 21.7 x 21.7 x 35.8 in.
Electrical: 120V 60Hz

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301G7

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Glove, Lead — AE #: GLLE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	69303		Countertop	OF/OI	Project

Pair of vinyl handcoverings covered with soft urethane materials for rugged durability. Breathable nylon liner keeps hands cool during procedures. View Cutsheet 146882

0.5mm protection. Navy blue.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301G7

Imaging, Digital Radiographic Unit

AE #: IMDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Del Medical / Umg	OTC18T		Floor/Ceiling	OF/CI/VI	Project

System includes overhead tube crane with vertical tracking and automatic collimator (manual version available); ev800 four way elevating float top table; vt300 tilting wall stand optional; high frequency generator; Delworks DR system; table capacity 800 lbs.

View Cutsheet 168139

Supplemental Info

Network: Wired
Elect Notes: **Refer to manufacturer's site planning information.**
Plumb Notes: **Refer to manufacturer's site planning information.**
HVAC Notes: **Refer to manufacturer's site planning information.**
Struct Notes: **Refer to manufacturer's site planning information.**

Imaging, Positioning Device

AE #: IMPD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7100EFB		Cabinet	OF/OI	Project

Extra firm coated torso block 15.5” x 12” x 7”

View Cutsheet 123251

Imaging, Positioning Device

AE #: IMPD-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7187-EF-B		Cabinet	OF/OI	Project

4 inch Decubitus Block, coated, extra firm.

View Cutsheet 209930

W x D x H: 24 x 18 x 4 in.

Imaging, Positioning Device

AE #: IMPC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	7117-EF-B		Cabinet	OF/OI	Project

45 Degree Spinal Wedge. Coated, extra firm.

View Cutsheet 209931

W x D x H: 7 x 24 x 7 in.

Room: X-Ray

Department: Imaging (3rd Floor)

Room #: A301G7

Pad, Table

AE #: PATA-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Penn Jersey X-Ray	TPADHD8		Table	OF/OI	Project

Vinyl x-ray table pad with 8 double-stitched handles. Liquid and stain-proof. Radiolucent. Cleans with mild cleaner or germicide. Color: black. View Cutsheet 211246

Spec provided by Sierha Phillips.

W x D x H: 23.3 x 72 x 1 in.

Rack, Apron

AE #: RAAP-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eljay Medical	722025	520	Wall	OF/CI	Project

This lead apron and glove rack will hold five aprons and four gloves. The body is heavy gauge steel finished in gray baked enamel and the apron arms and glove supports are anodized aluminum. The unit is designed so that weight is supported by the floor which minimizes wall stress and simplifies installation. Specifications Dimensions: 30" wide x 69" high. Shipping Weight: 25 lbs. Body made of heavy gauge steel finished in grey enamel. Glove brackets and apron support rods are made from anodized aluminum. View Cutsheet 209350

W x D x H: 30 x N/A x 69 in.

Weight: 25 lbs.

Sandbag

AE #: SAND-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide, Inc.	SBK-CB		Cabinet	OF/OI	Project

Set includes two 10lb 11" x 11" sandbags; choose color when ordering View Cutsheet 122392

W x D x H: 11 x N/A x 11 in.

Shield, Lead Free

AE #: SHLF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Techno-Aide	LPSG-T2424S		Floor	OF/OI	Project

Lead free mobile shield 24x24 View Cutsheet 208753

W x D x H: 24 x N/A x 24 in.

Room: X-Ray **Department:** Imaging (3rd Floor)

Room #: A301G7

Step, Platform Positioning Device — AE #: SPPD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radon Medical Imaging	CD-24305-C55		Floor	OF/OI	Project

One step patient positioner for CR and DR x-ray systems; mobile. View Cutsheet 211350

W x D x H: 19.5 x 17 x 51 in.

Stool, Foot, With Handrail — AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Walker — AE #: WALK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS864104BA		Floor	OF/OI	Project

Assembled Basic Walker, 2-Button, Folding, Adult, 400 lb. Easy-to-use, push-button mechanisms let walkers fold easily. Each side folds independently to allow easy movement through narrow spaces. Side cross braces provide extra durability. Push-button, height-adjustable legs. Height adjusts from approx. 32" to 39". View Cutsheet 210028

W x D x H: 18 x 21 x 39 in.

Weight: 8 lbs.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Radiologist Work **Department:** Imaging (3rd Floor)

Room #: B301D

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883552		Floor	OF/OI	Project

Slim jim step-on 90l/24 gal resin front waste container. Quiet, controlled lid closure minimizes noise. Internal hinge design to prevent wall damage. View Cutsheet 148391

Factory mutual certified ensures fire safety. Meets osha and obra standards for worker and environmental safety. Color: beige.

other available colors include: yellow, green, black, red, white, blue and gray.

W x D x H: 22.4 x 13.9 x 32.5 in.

Clearance: Top 13.9 in.

Weight: 16.8 lbs.

Room: Tech Work **Department: Imaging (3rd Floor)**

Room #: B301F

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Exam

Department: Interventional Pain Clinic

Room #: B303C, B303E, B303F, B303G, B303H, B303L, B303M, B303N, B304C, B304D, B304E, B304F, B304G, B304H, B304K, B304L, B304M

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam **Department: Interventional Pain Clinic**

Room #: B303C, B303E, B303F, B303G, B303H, B303L, B303M, B303N, B304C, B304D, B304E, B304F, B304G, B304H, B304K, B304L, B304M

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Exam, Power

AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.*** View Cutsheet 209180

W x D x H: 32 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Pain / Psych

Department: Interventional Pain Clinic

Room #: B303D

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: On-Stage Team Work

Department: Interventional Pain Clinic

Room #: B303J, B304J

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient)

Department: Interventional Pain Clinic

Room #: B303K, B304B

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Interventional Pain Clinic

Room #: B303K, B304B

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult

Department: Interventional Pain Clinic

Room #: B304A

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Treat

Department: Interventional Pain Clinic

Room #: B304N, B304P

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treat

Department: Interventional Pain Clinic

Room #: B304N, B304P

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation. View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz
Weight: 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Room: Treat

Department: Interventional Pain Clinic

Room #: B304N, B304P

Monitor, Physiological

AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.
Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: Treat

Department: Interventional Pain Clinic

Room #: B304N, B304P

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Room: Treat **Department: Interventional Pain Clinic**

Room #: B304N, B304P

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Exam, Power — AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.*** View Cutsheet 209180

W x D x H: 32 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Equipment **Department:** Interventional Pain Clinic

Room #: B304P1

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock. 2 per hallway, do not need in every room.

W x D x H: 27 x 18 x 33 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz
Struct Notes: Wall mount: wall channel is 19"h. Basket is 12.75"w x 7.75"d x 5.9"h. Pivot arm is 8"d.
Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	2

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Equipment
Room #: B304P1

Department: Interventional Pain Clinic

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Ultrasound, Portable

AE #: ULPO-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	PX		Stand	OF/VI	Project

15.6 monitor; (3) Transducer ports total; horizontal to vertical work surface; Adjustable height (max 65", min 42"); IPX-7 rated for immersion; Drop-tested to 1 meter; SonoADAPT Imaging Technology; Wifi, Ethernet port View Cutsheet 209960

Per quote 844474 dated 7/5/2023 provided by Jennifer Ratner 5/17/2024, Jantzen provided quote for Dr. Marrs preferred transducer.

W x D x H: 28.3 x 28.3 x 65 in.
Network: Networked
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
L12-3 Transducer	L22916	1	1

Room: Off-Stage Work Space

Department: Interventional Pain Clinic

Room #: B307B1, B307E1, B307F1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Workroom **Department:** Interventional Pain Clinic

Room #: B307C

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Wall	OF/CI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket. View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.*** View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Sharps

AE #: COSH-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004LR		Floor	OF/OI	Supply Agreement

8-gallon red bin (19.7”h x 13.0”d x 11.3 “w) for biohazard waste with wire step-on dolly. View Cutsheet 164306

Jessica spoke with Pam Lee Miller. Will need red sharps for vacutainer urine cups. Keep this item for now.

W x D x H: 14.3 x 16.5 x 23 in.

Room: Soiled Workroom

Department: Interventional Pain Clinic

Room #: B307C

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

Jessica spoke with Pam Lee Miller: red sharps container for vacutainer cups, may shift to these.

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Workroom

Department: Interventional Pain Clinic

Room #: B307C

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supplies **Department: Interventional Pain Clinic**

Room #: B307D

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67 AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Room: Clean Supplies **Department:** Interventional Pain Clinic

Room #: B307D

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Light, Exam/ Treatment

AE #: LIET-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	48810/48950		Floor	OF/OI	Project

Designed for specialties that requre very focused light in specific areas. 3x the typical light output and feautures flexible light pipe. Touchless auto on/off controls; can be used with welch allyn disposable sheaths to reduce risk of infection. (1) white LED light with 50,000 life hours. View Cutsheet 103310

Model approved by Dr. Harned.

W x D x H: 20.9 x 20.9 x 60.2 in.

Electrical: 120V 60Hz 0.3A **Weight:** 12.4 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Mobile Floor Stand	48950	1	1

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Room: Clean Supplies **Department:** Interventional Pain Clinic

Room #: B307D

Sphygmomanometer, Aneroid, Mobile — AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

Add reusable cuffs here and to all W/A monitors in clinic and procedure: small adult, large adult, large adult long,

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Suction Machine — AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Clean Supplies

Department: Interventional Pain Clinic

Room #: B307D

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Private Phone / Huddle

Department: Interventional Pain Clinic

Room #: B307E

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Medication Room

Department: Interventional Pain Clinic

Room #: B307F

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Medication Room **Department:** Interventional Pain Clinic

Room #: B307F

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Medication Room
Room #: B307F

Department: Interventional Pain Clinic

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

W x D x H: 24 x 29 x 32 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 1.4A
Weight: 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Intake

Department: Interventional Pain Procedure

Room #: B301A, B301B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration.

View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz
Struct Notes: Wall mount: wall channel is 19"h. Basket is 12.75"w x 7.75"d x 5.9"h. Pivot arm is 8"d.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor.

View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Room: Intake

Department: Interventional Pain Procedure

Room #: B301A, B301B

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug. View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz

Weight: 61 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stadiometer		1	1

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Intake

Department: Interventional Pain Procedure

Room #: B301A, B301B

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Team Work
Room #: B303A

Department: Interventional Pain Procedure

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Vein Illuminator

AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz.

View Cutsheet 168583

To be positioned on west wall between B303B7 and B303B8

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Bay, Stretcher

Department: Interventional Pain Procedure

Room #: B303A1, B303A2

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white.

View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Room: Bay, Stretcher

Department: Interventional Pain Procedure

Room #: B303A1, B303A2

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Room: Bay, Stretcher

Department: Interventional Pain Procedure

Room #: B303A1, B303A2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: Bay, Stretcher

Department: Interventional Pain Procedure

Room #: B303A1, B303A2

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

Model and pricing per UK, change in model across system due to lead times.

View Cutsheet 211777

W x D x H: 39 x 19 x 45.4 in.
Weight: 25 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Team Work

Department: Interventional Pain Procedure

Room #: B303B

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Lab Analyzer, Coagulation, Downloader

AE #: LACD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Roche Diagnostics	COAGUCHEK	08832366001	Countertop	OF/OI	Project

Features: LED, charging contacts, IR port, RJ45 Ethernet, USB type B, and 54 to 90 °F operating temperature. For use with CoaguChek XS Plus and CoaguChek XS Pro meters.

View Cutsheet 165401

W x D x H: 4.72 x 8.97 x 3.22 in.

Network: Wired

Network Notes: Usb connection to workstation

Electrical: 120V 60Hz 15W

Room: Team Work **Department:** Interventional Pain Procedure

Room #: B303B

Lab Analyzer, Coagulation, Handheld

AE #: LACH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Roche Diagnostics	COAGUCHEK XS PLUS	05021537001	Countertop	OF/OI	Project

Coaguchek xs plus systems provides rapid pt/inr results at the point of care. Full graphical screen. View Cutsheet 114667

W x D x H: 4 x 2 x 7 in.
Electrical: 120V 60Hz 1.7A **Weight:** 0.7 lbs.
Elect Notes: Optional 4 x 1.5v aa batteries (alkali-manganese) or optional rechargeable battery pack

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Toilet- Patient

Department: Interventional Pain Procedure

Room #: B303B1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet- Patient

Department: Interventional Pain Procedure

Room #: B303B1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Bay, Chair **Department:** Interventional Pain Procedure

Room #: B303B2, B303B3, B303A4, B303A5, B303A6, B303A7, B303A8, B303B8, B303A9

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Chair, Recliner

AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

W x D x H: 34 x 73 x 61 in.

Electrical: 120V 60Hz 4A

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Bay, Chair

Department: Interventional Pain Procedure

Room #: B303B2, B303B3, B303A4, B303A5, B303A6, B303A7, B303A8, B303B8, B303A9

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Bay, Chair **Department:** Interventional Pain Procedure

Room #: B303B2, B303B3, B303A4, B303A5, B303A6, B303A7, B303A8, B303B8, B303A9

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Table, Overbed — AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1). View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Bay, Stretcher w/Ceiling Lift

Department: Interventional Pain Procedure

Room #: B303B5, B303B6, B303B7

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white.

View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Room: Bay, Stretcher w/Ceiling Lift

Department: Interventional Pain Procedure

Room #: B303B5, B303B6, B303B7

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Room: Bay, Stretcher w/Ceiling Lift

Department: Interventional Pain Procedure

Room #: B303B5, B303B6, B303B7

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available weight capacity of 550#. Lift to span the 3 adjacent bays: B303B5, B303B6, and B303B7.

View Cutsheet 172960

Supplemental Info

Electrical: 115V 60Hz 2.5A

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Room: Bay, Stretcher w/Ceiling Lift

Department: Interventional Pain Procedure

Room #: B303B5, B303B6, B303B7

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

Model and pricing per UK, change in model across system due to lead times.

View Cutsheet 211777

W x D x H: 39 x 19 x 45.4 in.
Weight: 25 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Corridor (Alcove, Equipment) **Department: Interventional Pain Procedure**

Room #: B305

Allowance, Lead Aprons

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
20	ZZZ - To Be Determined			Rack	OF/OI	Project

No Cutsheet 54638

Need for nurses and other provider staff. Assumes (10) tailored F17 frontal aprons w/tethered thyroid shield (thyroidshield8) at $800 each.

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

View Cutsheet 208817

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

View Cutsheet 203982

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Room: Corridor (Alcove, Equipment) **Department:** Interventional Pain Procedure

Room #: B305

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Drug Dispensing Unit

AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit

View Cutsheet 150404

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A
Elect Notes: Must be located within 6' of the electrical outlet. Fuse: 6.3a. Power and data connections are made to frames at the back right of the computer (53-57" a.f.f.). Power cord length is 15'.
HVAC Notes: 200-600 btu/hr.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Rack, Apron

AE #: RAAP-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Burlington Medical, Inc.	MR4-AH3		Floor	OF/OI	Project

Heavy duty mobile, nesting Z style rack that offers stability for lead apron storage, With (10) AH3 Hangers.

View Cutsheet 210323

W x D x H: 51 x 23 x 55 in.

Room: Corridor (Alcove, Equipment) **Department:** Interventional Pain Procedure

Room #: B305

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

W x D x H: 24 x 29 x 32 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 1.4A
Weight: 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A
Weight: 6.3 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Team Work

Department: Interventional Pain Procedure

Room #: B305A

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean

Department: Interventional Pain Procedure

Room #: B305B

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system

No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired

Network Notes: One data outlet needed per wall

Electrical: 120V 60Hz

Room: Nourish **Department: Interventional Pain Procedure**

Room #: B305B1

Room Notes: No coffee maker needed here per DD meeting 4/23/2024

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser — AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Room: Nourish **Department:** Interventional Pain Procedure

Room #: B305B1

Room Notes: No coffee maker needed here per DD meeting 4/23/2024

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter — AE #: REUN-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF4P-KP-00		Undercounter	OF/VI	Project

3.9 cu ft capacity; stainless steel refrigerator with keypad lock; automatic defrost. Fits below 34" ada countertops without casters. Depth of cabinet is 25.6"d. Depth with façade is 27". View Cutsheet 139827

For patient nourishment. Lock requested to deter unauthorized access.

W x D x H: 23.8 x 27 x 31.4 in. **Clearance:** Rear 3 in.; Top 1 in.
Electrical: 115V 60Hz 4.1A 1-Phase **Weight:** 205 lbs.
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Left Hand Door Hinge	LH	1	1

Room: Nourish

Department: Interventional Pain Procedure

Room #: B305B1

Room Notes: No coffee maker needed here per DD meeting 4/23/2024

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Boom, Dual Lights

AE #: BODL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212216

Quote Q-91751-6 received from Scott Campbell on 9-30-2024. Supplemental Info

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Boom, Monitor

AE #: BOMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212217

Quote Q-91751-6 received from Scott Campbell on 9-30-2024.

Supplemental Info

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Wall	OF/CI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket.

View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook.

View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart For red bin

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Cart, Supply

AE #: CASU-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	STARSYS DOUBLE		Floor	OF/VI	Project

View Cutsheet 172084

W x D x H: 42.5 x 24.9 x 78.4 in.

Cart, Utility

AE #: CAUT-46

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1066BE		Floor	OF/OI	Project

Tough structural foam won't rust, chip or dent. Two 2-5/8" deep trays are 18 7/8" apart. Non-marking 5" casters: 2 swivel, 2 rigid

View Cutsheet 159705

W x D x H: 26 x 46 x 33 in.

Cart, Utility

AE #: CAUT-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3424-88		Floor	OF/VI	Project

Utility cart with 3 shelves and 4" swivel casters. Handles on both ends. Shelf weight capacity: 67 lbs. Total weight capacity 200 lbs. Shelf colors available: red, platinum, black or off white.

View Cutsheet 141070

To hold radiofrequency generator

W x D x H: 18.6 x 33.6 x 37.8 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Generator, Radiofrequency

AE #: GERA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	COOLIEF		Cart	OF/VI	Project

View Cutsheet 171766

Per Avanos quote 23689 dated 7/31/2023 provided by Jantzen via email from Jennifer Ratner 5/17/2024.

W x D x H: 12.8 x 17 x 13 in.

Electrical: 115V 60Hz 3.5A **Weight:** 23.5 lbs.

Elect Notes: Surge protector recommended

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Coolief Multi-Colored RF Therapy Cable	CRX-CRG-MCRF	1	1
Multi-RF Therapy Cable	SRX-CRG-MRF	1	1

Generator, Radiofrequency, Component

AE #: GERC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	QUAD PUMP	CRA-QPU-1	Cart	OF/VI	Project

No Cutsheet 171767

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Generator, Radiofrequency, Component

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	Probes - See Accessories		Cart	OF/VI	Project

Probes for use with Avanos RFA system. See accessories for model numbers and quantities needed. No Cutsheet 211345

Accessories:

Description	Catalog	Qty/Item	Ext Qty
RF Probe, Curved-16-100-White	PMP-16-100C	10	10
RF Probe, Curved-18-100 Black (Pink Stylet...)	PMP-18-100C	9	9
RF Probe, Curved-20-100-Yellow	PMP-20-100C	9	9
RF Probe, Curved-20-145-Yellow	PMP-20-145C	6	6
RF Probe, Curved-22-54-Black	PMP-22-54C	2	2

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Pain Procedure, w/ Ceiling Lift **Department: Interventional Pain Procedure**

Room #: B305C

Imaging, Portable C-Arm

AE #: IMPC-31

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC Elite CFD 31		Floor	OF/VI	Project

OEC Elite CFD Super C-arm with 31 cm digital mobile Ergo c-arm. Efficient positioning with 90°/180° flip flop. Additional range of motion and positioning flexibility with smartview pivot joint. Productive with low lateral height and small ap/lat offset. Max orbital rotation 178° (9") and 181° (12").

View Cutsheet 206509

Software: PMCare

Detector: 31 cm

** Workstation specified separately (34.1"w x 25.8"d x 68.1"h)

Per GE quote 2011152679.2 dated 8/13/2024. Includes wireless DICOM and OEC touch tableside with RUI.

W x D x H: 33.2 x 78.7 x 78.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 654 lbs.
Elect Notes: Refer to vendor specifications

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wireless DICOM		1	1

Imaging, Portable C-Arm, Component

AE #: IPCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC ELITE CFD WORKSTATION		Floor	OF/VI	Project

Workstation with 4k display; used in coordination with c-arm for system control and image monitoring

View Cutsheet 165014

W x D x H: 34.1 x 25.8 x 68.1 in.
Electrical: 120V 60Hz **Weight:** 428 lbs.

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Imaging, Table, Fluoroscopy

AE #: IMTF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Image Diagnostics, Inc.	Aspect ISR		Floor	OF/VI	Project

Mobile imaging table. Low attenuation carbon fiber 24" x 84" table top and pad. Trendelenburg approximately 12 degrees. Height range 32"-44". Patient weight capacity 600 lbs. Emergency stop button at base of table. Battery backup power. View Cutsheet 211342

Table spec from Jantzen via email from Jennifer Ratner. GE Quote 2011152679.2 dated 8/13/2024 from Winny Wearren.

W x D x H: 30 x 84 x 44 in.
Electrical: 120V 60Hz 10A **Weight:** 605 lbs.
Elect Notes: Floor outlet requested

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Foot Control	A100-2071	1	1
Headrest with Mini Rails, Articulating, Removable	A100-2317	1	1
Radiation Shield, Articulating, Rail Mounted	A610-051	1	1

Monitor, Display

AE #: MODI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	NEC Display Solutions	V554		Wall	OF/VI	Project

Commercial 55" lcd display. 1920 x 1080 resolution. 16:9 ratio. Hdmi and vga inputs. View Cutsheet 168143

For displaying fluoroscopic images. To be provided by Stryker.

W x D x H: 49 x 2.5 x 28.1 in.
Electrical: 120V 60Hz 1.4A **Weight:** 54.2 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls.

View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning.

View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Patient Lift, Ceiling Mount

AE #: PLCM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GH3+		Ceiling	OF/CI/VI	Project

Gh3+ lifting motor is available in models with lifting capabilities of 440, 550, 600, 660, 770, 825, & 880 lbs. Optional scale module available

View Cutsheet 172960

Stretcher has 700 lb capacity, but table has less. Weight capacity to be approximately 550 lbs.

Supplemental Info

Electrical: 115V 60Hz 2.5A

Rack, Vial

AE #: RAVI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	2970013413		Table	OF/OI	Project

Accu-Draw vial holder with clamp to mount to table or mayo stand. Holds multiple vials horizontally at once to allow hands-free access for drawing up medications. Features (3) slots for multi-dose vials and (4) slots for single-dose vials, which click and lock into place.

View Cutsheet 210666

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Shield, Lead

AE #: SHLE-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf X-Ray Corporation	56606-W		Floor	OF/OI	Project

OptiClear lead acrylic mobile x-ray barrier provides full body shield with 0.5mm lead equivalent protection. Clear panel 30"W x 48"H. Shatter-resistant. Locking casters.

View Cutsheet 210656

W x D x H: 31 x 25 x 75 in.

Weight: 320 lbs.

Shield, Lead, Table Mounted

AE #: SLTM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	DRAPE		Table	OF/OI	Project

Table-mounted shield/drape. To mount to IDI Aspect ISR imaging table on side of table that does not come from manufacturer with a protective drape attached.

No Cutsheet 211347

Quote 1120708 dated 6/5/2024 from Burlington Medical provided by Jantzen Merriman 6/10/2024.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

Specified by Robyn/Jennifer

W x D x H: 20 x 25 x 62 in.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Table, Instrument

AE #: TAIN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	HOWARD 7835SS		Floor	OF/OI	Project

4' x 2' stainless steel back table; with shelf with a clearance of 16" from top shelf; on 2" ballbearing casters. View Cutsheet 11052

Specified by Robyn/Jennifer

W x D x H: 48 x 24 x 34 in.

Weight: 130 lbs.

Ultrasound, Portable

AE #: ULPO-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	PX		Stand	OF/VI	Project

15.6 monitor; (3) Transducer ports total; horizontal to vertical work surface; Adjustable height (max 65", min 42"); IPX-7 rated for immersion; Drop-tested to 1 meter; SonoADAPT Imaging Technology; Wifi, Ethernet port View Cutsheet 209960

Per quote 844474 dated 7/5/2023 provided by Jennifer Ratner 5/17/2024, Jantzen provided quote for Dr. Marrs preferred transducer.

W x D x H: 28.3 x 28.3 x 65 in.
Network: Networked
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
L12-3 Transducer	L22916	1	1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Pain Procedure, w/ Ceiling Lift

Department: Interventional Pain Procedure

Room #: B305C

Workstation, Documentation

AE #: WODO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	6215		Floor	OF/VI	Project

Mobile workstation with height adjustable from 23" to 49". Two 4" locking casters in front. Base dimensions 20.5"W x 19.5"D. Weight limit 20 lbs. View Cutsheet 210659

Select finish when ordering.

List of probes forthcoming, multiply x4.

W x D x H: 26 x 21 x 49 in.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305D

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Needle driver that gets reprocessed in SPD. Have 35 now at South for 2 rooms. Plan 70 here. Forceps.

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Boom, Dual Lights

AE #: BODL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212216

Quote Q-91751-6 received from Scott Campbell on 9-30-2024. Supplemental Info

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305D

Boom, Monitor

AE #: BOMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212217

Quote Q-91751-6 received from Scott Campbell on 9-30-2024.

Supplemental Info

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Wall	OF/CI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket.

View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42" tall Metro starsys cart with 3 – 3", 2 – 6", and 1 – 9" deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3" and 1 – 6" egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19" and 1 – 28" peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook.

View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart For red bin

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305D

Cart, Supply

AE #: CASU-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	STARSYS DOUBLE		Floor	OF/VI	Project

View Cutsheet 172084

W x D x H: 42.5 x 24.9 x 78.4 in.

Cart, Utility

AE #: CAUT-46

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1066BE		Floor	OF/OI	Project

Tough structural foam won't rust, chip or dent. Two 2-5/8" deep trays are 18 7/8" apart. Non-marking 5" casters: 2 swivel, 2 rigid

View Cutsheet 159705

W x D x H: 26 x 46 x 33 in.

Cart, Utility

AE #: CAUT-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3424-88		Floor	OF/VI	Project

Utility cart with 3 shelves and 4" swivel casters. Handles on both ends. Shelf weight capacity: 67 lbs. Total weight capacity 200 lbs. Shelf colors available: red, platinum, black or off white.

View Cutsheet 141070

To hold radiofrequency generator

W x D x H: 18.6 x 33.6 x 37.8 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305D

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Generator, Radiofrequency

AE #: GERA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	COOLIEF		Cart	OF/VI	Project

View Cutsheet 171766

Per Avanos quote 23689 dated 7/31/2023 provided by Jantzen via email from Jennifer Ratner 5/17/2024.

W x D x H: 12.8 x 17 x 13 in.
Electrical: 115V 60Hz 3.5A **Weight:** 23.5 lbs.
Elect Notes: Surge protector recommended

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Coolief Multi-Colored RF Therapy Cable	CRX-CRG-MCRF	1	1
Multi-RF Therapy Cable	SRX-CRG-MRF	1	1

Generator, Radiofrequency, Component

AE #: GERC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	QUAD PUMP	CRA-QPU-1	Cart	OF/VI	Project

No Cutsheet 171767

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305D

Generator, Radiofrequency, Component

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	Probes - See Accessories		Cart	OF/VI	Project

Probes for use with Avanos RFA system. See accessories for model numbers and quantities needed. No Cutsheet 211345

Accessories:

Description	Catalog	Qty/Item	Ext Qty
RF Probe, Curved-16-100-White	PMP-16-100C	10	10
RF Probe, Curved-18-100 Black (Pink Stylet...)	PMP-18-100C	9	9
RF Probe, Curved-20-100-Yellow	PMP-20-100C	9	9
RF Probe, Curved-20-145-Yellow	PMP-20-145C	6	6
RF Probe, Curved-22-54-Black	PMP-22-54C	2	2

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Pain Procedure **Department: Interventional Pain Procedure**

Room #: B305D

Imaging, Portable C-Arm

AE #: IMPC-31

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC Elite CFD 31		Floor	OF/VI	Project

OEC Elite CFD Super C-arm with 31 cm digital mobile Ergo c-arm. Efficient positioning with 90°/180° flip flop. Additional range of motion and positioning flexibility with smartview pivot joint. Productive with low lateral height and small ap/lat offset. Max orbital rotation 178° (9") and 181° (12"). View Cutsheet 206509

Software: PMCare

Detector: 31 cm

** Workstation specified separately (34.1"w x 25.8"d x 68.1"h)

Per GE quote 2011152679.2 dated 8/13/2024. Includes wireless DICOM and OEC touch tableside with RUI.

W x D x H: 33.2 x 78.7 x 78.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 654 lbs.
Elect Notes: Refer to vendor specifications

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wireless DICOM		1	1

Imaging, Portable C-Arm, Component

AE #: IPCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC ELITE CFD WORKSTATION		Floor	OF/VI	Project

Workstation with 4k display; used in coordination with c-arm for system control and image monitoring View Cutsheet 165014

W x D x H: 34.1 x 25.8 x 68.1 in.
Electrical: 120V 60Hz **Weight:** 428 lbs.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305D

Imaging, Table, Fluoroscopy

AE #: IMTF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Image Diagnostics, Inc.	Aspect ISR		Floor	OF/VI	Project

Mobile imaging table. Low attenuation carbon fiber 24" x 84" table top and pad. Trendelenburg approximately 12 degrees. Height range 32"-44". Patient weight capacity 600 lbs. Emergency stop button at base of table. Battery backup power. View Cutsheet 211342

Table spec from Jantzen via email from Jennifer Ratner. GE Quote 2011152679.2 dated 8/13/2024 from Winny Wearren.

W x D x H: 30 x 84 x 44 in.
Electrical: 120V 60Hz 10A **Weight:** 605 lbs.
Elect Notes: Floor outlet requested

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Foot Control	A100-2071	1	1
Headrest with Mini Rails, Articulating, Removable	A100-2317	1	1
Radiation Shield, Articulating, Rail Mounted	A610-051	1	1

Monitor, Display

AE #: MODI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	NEC Display Solutions	V554		Wall	OF/VI	Project

Commercial 55" lcd display. 1920 x 1080 resolution. 16:9 ratio. Hdmi and vga inputs. View Cutsheet 168143

For displaying fluoroscopic images. To be provided by Stryker.

W x D x H: 49 x 2.5 x 28.1 in.
Electrical: 120V 60Hz 1.4A **Weight:** 54.2 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305D

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls.

View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning.

View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Rack, Vial

AE #: RAVI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	2970013413		Table	OF/OI	Project

Accu-Draw vial holder with clamp to mount to table or mayo stand. Holds multiple vials horizontally at once to allow hands-free access for drawing up medications. Features (3) slots for multi-dose vials and (4) slots for single-dose vials, which click and lock into place.

View Cutsheet 210666

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305D

Shield, Lead

AE #: SHLE-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf X-Ray Corporation	56606-W		Floor	OF/OI	Project

OptiClear lead acrylic mobile x-ray barrier provides full body shield with 0.5mm lead equivalent protection. Clear panel 30"W x 48"H. Shatter-resistant. View Cutsheet 210656

Locking casters.

W x D x H: 31 x 25 x 75 in.

Weight: 320 lbs.

Shield, Lead, Table Mounted

AE #: SLTM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	DRAPE		Table	OF/OI	Project

Table-mounted shield/drape. To mount to IDI Aspect ISR imaging table on side of table that does not come from manufacturer with a protective drape attached. No Cutsheet 211347

Quote 1120708 dated 6/5/2024 from Burlington Medical provided by Jantzen Merriman 6/10/2024.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305D

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

Specified by Robyn/Jennifer

W x D x H: 20 x 25 x 62 in.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Instrument

AE #: TAIN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	HOWARD 7835SS		Floor	OF/OI	Project

4' x 2' stainless steel back table; with shelf with a clearance of 16" from top shelf; on 2" ballbearing casters. View Cutsheet 11052

Specified by Robyn/Jennifer

W x D x H: 48 x 24 x 34 in.

Weight: 130 lbs.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305D

Ultrasound, Portable

AE #: ULPO-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	PX		Stand	OF/VI	Project

15.6 monitor; (3) Transducer ports total; horizontal to vertical work surface; Adjustable height (max 65", min 42"); IPX-7 rated for immersion; Drop-tested to 1 meter; SonoADAPT Imaging Technology; Wifi, Ethernet port

View Cutsheet 209960

Per quote 844474 dated 7/5/2023 provided by Jennifer Ratner 5/17/2024, Jantzen provided quote for Dr. Marrs preferred transducer.

W x D x H: 28.3 x 28.3 x 65 in.
Network: Networked
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
L12-3 Transducer	L22916	1	1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Workstation, Documentation

AE #: WODO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	6215		Floor	OF/VI	Project

Mobile workstation with height adjustable from 23" to 49". Two 4" locking casters in front. Base dimensions 20.5"W x 19.5"D. Weight limit 20 lbs.

View Cutsheet 210659

Select finish when ordering.

W x D x H: 26 x 21 x 49 in.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305E

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Needle driver that gets reprocessed in SPD. Have 35 now at South for 2 rooms. Plan 70 here. Forceps.

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Boom, Dual Lights

AE #: BODL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212216

Quote Q-91751-6 received from Scott Campbell on 9-30-2024. Supplemental Info

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305E

Boom, Monitor

AE #: BOMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212217

Quote Q-91751-6 received from Scott Campbell on 9-30-2024.

Supplemental Info

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Wall	OF/CI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket.

View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook.

View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart For red bin

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305E

Cart, Supply

AE #: CASU-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	STARSYS DOUBLE		Floor	OF/VI	Project

View Cutsheet 172084

W x D x H: 42.5 x 24.9 x 78.4 in.

Cart, Utility

AE #: CAUT-46

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1066BE		Floor	OF/OI	Project

Tough structural foam won't rust, chip or dent. Two 2-5/8" deep trays are 18 7/8" apart. Non-marking 5" casters: 2 swivel, 2 rigid

View Cutsheet 159705

W x D x H: 26 x 46 x 33 in.

Cart, Utility

AE #: CAUT-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3424-88		Floor	OF/VI	Project

Utility cart with 3 shelves and 4" swivel casters. Handles on both ends. Shelf weight capacity: 67 lbs. Total weight capacity 200 lbs. Shelf colors available: red, platinum, black or off white.

View Cutsheet 141070

To hold radiofrequency generator

W x D x H: 18.6 x 33.6 x 37.8 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Room: Pain Procedure **Department: Interventional Pain Procedure**

Room #: B305E

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Generator, Radiofrequency

AE #: GERA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	COOLIEF		Cart	OF/VI	Project

View Cutsheet 171766

Per Avanos quote 23689 dated 7/31/2023 provided by Jantzen via email from Jennifer Ratner 5/17/2024.

W x D x H: 12.8 x 17 x 13 in.
Electrical: 115V 60Hz 3.5A **Weight:** 23.5 lbs.
Elect Notes: Surge protector recommended

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Coolief Multi-Colored RF Therapy Cable	CRX-CRG-MCRF	1	1
Multi-RF Therapy Cable	SRX-CRG-MRF	1	1

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305E

Generator, Radiofrequency, Component

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	Probes - See Accessories		Cart	OF/VI	Project

Probes for use with Avanos RFA system. See accessories for model numbers and quantities needed. No Cutsheet 211345

Accessories:

Description	Catalog	Qty/Item	Ext Qty
RF Probe, Curved-16-100-White	PMP-16-100C	10	10
RF Probe, Curved-18-100 Black (Pink Stylet...)	PMP-18-100C	9	9
RF Probe, Curved-20-100-Yellow	PMP-20-100C	9	9
RF Probe, Curved-20-145-Yellow	PMP-20-145C	6	6
RF Probe, Curved-22-54-Black	PMP-22-54C	2	2

Generator, Radiofrequency, Component — AE #: GERC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	QUAD PUMP	CRA-QPU-1	Cart	OF/VI	Project

No Cutsheet 171767

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Pain Procedure **Department: Interventional Pain Procedure**

Room #: B305E

Imaging, Portable C-Arm

AE #: IMPC-31

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC Elite CFD 31		Floor	OF/VI	Project

OEC Elite CFD Super C-arm with 31 cm digital mobile Ergo c-arm. Efficient positioning with 90°/180° flip flop. Additional range of motion and positioning flexibility with smartview pivot joint. Productive with low lateral height and small ap/lat offset. Max orbital rotation 178° (9") and 181° (12").

View Cutsheet 206509

Software: PMCare

Detector: 31 cm

** Workstation specified separately (34.1"w x 25.8"d x 68.1"h)

Per GE quote 2011152679.2 dated 8/13/2024. Includes wireless DICOM and OEC touch tableside with RUI.

W x D x H: 33.2 x 78.7 x 78.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 654 lbs.
Elect Notes: Refer to vendor specifications

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wireless DICOM		1	1

Imaging, Portable C-Arm, Component

AE #: IPCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC ELITE CFD WORKSTATION		Floor	OF/VI	Project

Workstation with 4k display; used in coordination with c-arm for system control and image monitoring

View Cutsheet 165014

W x D x H: 34.1 x 25.8 x 68.1 in.
Electrical: 120V 60Hz **Weight:** 428 lbs.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305E

Imaging, Table, Fluoroscopy

AE #: IMTF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Image Diagnostics, Inc.	Aspect ISR		Floor	OF/VI	Project

Mobile imaging table. Low attenuation carbon fiber 24" x 84" table top and pad. Trendelenburg approximately 12 degrees. Height range 32"-44". Patient weight capacity 600 lbs. Emergency stop button at base of table. Battery backup power. View Cutsheet 211342

Table spec from Jantzen via email from Jennifer Ratner. GE Quote 2011152679.2 dated 8/13/2024 from Winny Wearren.

W x D x H: 30 x 84 x 44 in.
Electrical: 120V 60Hz 10A **Weight:** 605 lbs.
Elect Notes: Floor outlet requested

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Foot Control	A100-2071	1	1
Headrest with Mini Rails, Articulating, Removable	A100-2317	1	1
Radiation Shield, Articulating, Rail Mounted	A610-051	1	1

Monitor, Display

AE #: MODI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	NEC Display Solutions	V554		Wall	OF/VI	Project

Commercial 55" lcd display. 1920 x 1080 resolution. 16:9 ratio. Hdmi and vga inputs. View Cutsheet 168143

For displaying fluoroscopic images. To be provided by Stryker.

W x D x H: 49 x 2.5 x 28.1 in.
Electrical: 120V 60Hz 1.4A **Weight:** 54.2 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305E

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Rack, Vial

AE #: RAVI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	2970013413		Table	OF/OI	Project

Accu-Draw vial holder with clamp to mount to table or mayo stand. Holds multiple vials horizontally at once to allow hands-free access for drawing up medications. Features (3) slots for multi-dose vials and (4) slots for single-dose vials, which click and lock into place. View Cutsheet 210666

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305E

Shield, Lead

AE #: SHLE-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf X-Ray Corporation	56606-W		Floor	OF/OI	Project

OptiClear lead acrylic mobile x-ray barrier provides full body shield with 0.5mm lead equivalent protection. Clear panel 30"W x 48"H. Shatter-resistant. View Cutsheet 210656

Locking casters.

W x D x H: 31 x 25 x 75 in.

Weight: 320 lbs.

Shield, Lead, Table Mounted

AE #: SLTM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	DRAPE		Table	OF/OI	Project

Table-mounted shield/drape. To mount to IDI Aspect ISR imaging table on side of table that does not come from manufacturer with a protective drape attached. No Cutsheet 211347

Quote 1120708 dated 6/5/2024 from Burlington Medical provided by Jantzen Merriman 6/10/2024.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305E

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

Specified by Robyn/Jennifer

W x D x H: 20 x 25 x 62 in.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Instrument

AE #: TAIN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	HOWARD 7835SS		Floor	OF/OI	Project

4' x 2' stainless steel back table; with shelf with a clearance of 16" from top shelf; on 2" ballbearing casters. View Cutsheet 11052

Specified by Robyn/Jennifer

W x D x H: 48 x 24 x 34 in.

Weight: 130 lbs.

Room: Pain Procedure
Room #: B305E

Department: Interventional Pain Procedure

Ultrasound, Portable

AE #: ULPO-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	PX		Stand	OF/VI	Project

15.6 monitor; (3) Transducer ports total; horizontal to vertical work surface; Adjustable height (max 65", min 42"); IPX-7 rated for immersion; Drop-tested to 1 meter; SonoADAPT Imaging Technology; Wifi, Ethernet port

View Cutsheet 209960

Per quote 844474 dated 7/5/2023 provided by Jennifer Ratner 5/17/2024, Jantzen provided quote for Dr. Marrs preferred transducer.

W x D x H: 28.3 x 28.3 x 65 in.
Network: Networked
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
L12-3 Transducer	L22916	1	1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Workstation, Documentation

AE #: WODO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	6215		Floor	OF/VI	Project

Mobile workstation with height adjustable from 23" to 49". Two 4" locking casters in front. Base dimensions 20.5"W x 19.5"D. Weight limit 20 lbs.

View Cutsheet 210659

Select finish when ordering.

W x D x H: 26 x 21 x 49 in.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305F

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cart	OF/OI	Project

No Cutsheet 10789

Needle driver that gets reprocessed in SPD. Have 35 now at South for 2 rooms. Plan 70 here. Forceps.

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Board, Transfer

AE #: BOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	9-719		Wall	OF/OI	Project

Anti-static standard patient shifter, white View Cutsheet 148914

W x D x H: 22 x 0.25 x 72 in.

Board, Transfer, Accessory

AE #: BOTA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ali Med	75134		Wall	OF/CI	Project

Wall hanger for patient shifter, horizontal. 2" long adjustable width pegs accommodate most shifters. Solid oak, clear finish. Mounting hardware included. View Cutsheet 142325

W x D x H: 32 x 1 x 5.5 in.

Boom, Dual Lights

AE #: BODL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212216

Quote Q-91751-6 received from Scott Campbell on 9-30-2024. Supplemental Info

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305F

Boom, Monitor

AE #: BOMO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron			Ceiling	OF/CI/VI	Project

No Cutsheet 212217

Quote Q-91751-6 received from Scott Campbell on 9-30-2024.

Supplemental Info

Bracket, Controlled Substance Disposal Container

AE #: BRCS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	CSRXBKT		Wall	OF/CI	Service Agreement

Bracket holds 1-gallon (XCRX1G) and 3-gallon (CSRX3G) controlled substance medication disposal containers. Dimensions are approximate and reflect disposal container in bracket.

View Cutsheet 208855

W x D x H: 12 x 6 x 10 in.

Cart, Anesthesia

AE #: CAAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

42” tall Metro starsys cart with 3 – 3”, 2 – 6”, and 1 – 9” deep drawers with the blue drawer pulls. Cart has an overbridge with 2 shelves above. Cart will have a key lock and also 2 – 3” and 1 – 6” egg crate divider kits. There are 2 accessory brackets for left side and 1 – 19” and 1 – 28” peel pouch/catheter holder (that goes on the accessory brackets) and 1 - universal clamp and 1 – short utility hook.

View Cutsheet 211228

**Assembly (which is not included) is required for accessories onto the cart. The hospital assembled all their own carts the last time they purchased.

W x D x H: 22.8 x 25 x 62.5 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart For red bin

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305F

Cart, Supply

AE #: CASU-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	STARSYS DOUBLE		Floor	OF/VI	Project

View Cutsheet 172084

W x D x H: 42.5 x 24.9 x 78.4 in.

Cart, Utility

AE #: CAUT-46

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1066BE		Floor	OF/OI	Project

Tough structural foam won't rust, chip or dent. Two 2-5/8" deep trays are 18 7/8" apart. Non-marking 5" casters: 2 swivel, 2 rigid

View Cutsheet 159705

W x D x H: 26 x 46 x 33 in.

Cart, Utility

AE #: CAUT-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3424-88		Floor	OF/VI	Project

Utility cart with 3 shelves and 4" swivel casters. Handles on both ends. Shelf weight capacity: 67 lbs. Total weight capacity 200 lbs. Shelf colors available: red, platinum, black or off white.

View Cutsheet 141070

To hold radiofrequency generator

W x D x H: 18.6 x 33.6 x 37.8 in.

Container, Sharps

AE #: COSH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	LH-17 / DWSH-17		Floor	OF/OI	Service Agreement

17-gallon sharps container with hamper top lid and step on dolly

View Cutsheet 125932

W x D x H: 14.5 x 22.5 x 29.8 in.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305F

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Generator, Radiofrequency — AE #: GERA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	COOLIEF		Cart	OF/VI	Project

View Cutsheet 171766

Per Avanos quote 23689 dated 7/31/2023 provided by Jantzen via email from Jennifer Ratner 5/17/2024.

W x D x H: 12.8 x 17 x 13 in.
Electrical: 115V 60Hz 3.5A **Weight:** 23.5 lbs.
Elect Notes: Surge protector recommended

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Coolief Multi-Colored RF Therapy Cable	CRX-CRG-MCRF	1	1
Multi-RF Therapy Cable	SRX-CRG-MRF	1	1

Generator, Radiofrequency, Component — AE #: GERC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	QUAD PUMP	CRA-QPU-1	Cart	OF/VI	Project

No Cutsheet 171767

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305F

Generator, Radiofrequency, Component

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Avanos	Probes - See Accessories		Cart	OF/VI	Project

Probes for use with Avanos RFA system. See accessories for model numbers and quantities needed. No Cutsheet 211345

Accessories:

Description	Catalog	Qty/Item	Ext Qty
RF Probe, Curved-16-100-White	PMP-16-100C	10	10
RF Probe, Curved-18-100 Black (Pink Stylet...)	PMP-18-100C	9	9
RF Probe, Curved-20-100-Yellow	PMP-20-100C	9	9
RF Probe, Curved-20-145-Yellow	PMP-20-145C	6	6
RF Probe, Curved-22-54-Black	PMP-22-54C	2	2

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Pain Procedure **Department: Interventional Pain Procedure**

Room #: B305F

Imaging, Portable C-Arm

AE #: IMPC-31

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC Elite CFD 31		Floor	OF/VI	Project

OEC Elite CFD Super C-arm with 31 cm digital mobile Ergo c-arm. Efficient positioning with 90°/180° flip flop. Additional range of motion and positioning flexibility with smartview pivot joint. Productive with low lateral height and small ap/lat offset. Max orbital rotation 178° (9") and 181° (12").

View Cutsheet 206509

Software: PMCare

Detector: 31 cm

** Workstation specified separately (34.1"w x 25.8"d x 68.1"h)

Per GE quote 2011152679.2 dated 8/13/2024. Includes wireless DICOM and OEC touch tableside with RUI.

W x D x H: 33.2 x 78.7 x 78.7 in.
Network: Networked
Electrical: 120V 60Hz 15A **Weight:** 654 lbs.
Elect Notes: Refer to vendor specifications

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wireless DICOM		1	1

Imaging, Portable C-Arm, Component

AE #: IPCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	OEC ELITE CFD WORKSTATION		Floor	OF/VI	Project

Workstation with 4k display; used in coordination with c-arm for system control and image monitoring

View Cutsheet 165014

W x D x H: 34.1 x 25.8 x 68.1 in.
Electrical: 120V 60Hz **Weight:** 428 lbs.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305F

Imaging, Table, Fluoroscopy

AE #: IMTF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Image Diagnostics, Inc.	Aspect ISR		Floor	OF/VI	Project

Mobile imaging table. Low attenuation carbon fiber 24" x 84" table top and pad. Trendelenburg approximately 12 degrees. Height range 32"-44". Patient weight capacity 600 lbs. Emergency stop button at base of table. Battery backup power. View Cutsheet 211342

Table spec from Jantzen via email from Jennifer Ratner. GE Quote 2011152679.2 dated 8/13/2024 from Winny Wearren.

W x D x H: 30 x 84 x 44 in.
Electrical: 120V 60Hz 10A **Weight:** 605 lbs.
Elect Notes: Floor outlet requested

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Foot Control	A100-2071	1	1
Headrest with Mini Rails, Articulating, Removable	A100-2317	1	1
Radiation Shield, Articulating, Rail Mounted	A610-051	1	1

Monitor, Display

AE #: MODI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	NEC Display Solutions	V554		Wall	OF/VI	Project

Commercial 55" lcd display. 1920 x 1080 resolution. 16:9 ratio. Hdmi and vga inputs. View Cutsheet 168143

For displaying fluoroscopic images. To be provided by Stryker.

W x D x H: 49 x 2.5 x 28.1 in.
Electrical: 120V 60Hz 1.4A **Weight:** 54.2 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305F

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls.

View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning.

View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Rack, Vial

AE #: RAVI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Alimed, Inc.	2970013413		Table	OF/OI	Project

Accu-Draw vial holder with clamp to mount to table or mayo stand. Holds multiple vials horizontally at once to allow hands-free access for drawing up medications. Features (3) slots for multi-dose vials and (4) slots for single-dose vials, which click and lock into place.

View Cutsheet 210666

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305F

Shield, Lead

AE #: SHLE-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wolf X-Ray Corporation	56606-W		Floor	OF/OI	Project

OptiClear lead acrylic mobile x-ray barrier provides full body shield with 0.5mm lead equivalent protection. Clear panel 30"W x 48"H. Shatter-resistant. View Cutsheet 210656

Locking casters.

W x D x H: 31 x 25 x 75 in.

Weight: 320 lbs.

Shield, Lead, Table Mounted

AE #: SLTM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	DRAPE		Table	OF/OI	Project

Table-mounted shield/drape. To mount to IDI Aspect ISR imaging table on side of table that does not come from manufacturer with a protective drape attached. No Cutsheet 211347

Quote 1120708 dated 6/5/2024 from Burlington Medical provided by Jantzen Merriman 6/10/2024.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Pain Procedure

Department: Interventional Pain Procedure

Room #: B305F

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62"

View Cutsheet 46599

Specified by Robyn/Jennifer

W x D x H: 20 x 25 x 62 in.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5"

View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Instrument

AE #: TAIN-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	HOWARD 7835SS		Floor	OF/OI	Project

4' x 2' stainless steel back table; with shelf with a clearance of 16" from top shelf; on 2" ballbearing casters.

View Cutsheet 11052

Specified by Robyn/Jennifer

W x D x H: 48 x 24 x 34 in.

Weight: 130 lbs.

Room: Pain Procedure **Department:** Interventional Pain Procedure

Room #: B305F

Ultrasound, Portable

AE #: ULPO-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	PX		Stand	OF/VI	Project

15.6 monitor; (3) Transducer ports total; horizontal to vertical work surface; Adjustable height (max 65", min 42"); IPX-7 rated for immersion; Drop-tested to 1 meter; SonoADAPT Imaging Technology; Wifi, Ethernet port

View Cutsheet 209960

Per quote 844474 dated 7/5/2023 provided by Jennifer Ratner 5/17/2024, Jantzen provided quote for Dr. Marrs preferred transducer.

W x D x H: 28.3 x 28.3 x 65 in.
Network: Networked
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
L12-3 Transducer	L22916	1	1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Workstation, Documentation

AE #: WODO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	6215		Floor	OF/VI	Project

Mobile workstation with height adjustable from 23" to 49". Two 4" locking casters in front. Base dimensions 20.5"W x 19.5"D. Weight limit 20 lbs.

View Cutsheet 210659

Select finish when ordering.

W x D x H: 26 x 21 x 49 in.

Room: MD Work

Department: Interventional Pain Procedure

Room #: B305G

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Clean Linen

Department: Interventional Pain Procedure

Room #: B305H

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Room: Soiled Utility

Department: Interventional Pain Procedure

Room #: B305J

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Soiled Utility

Department: Interventional Pain Procedure

Room #: B305J

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Height / Weight

Department: Interventional Pain Procedure

Room #: B306K

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h.

View Cutsheet 206457

See accessory for stadiometer and hand rail

W x D x H: 35 x 30 x N/A in.

Electrical: 120V 60Hz 15W **Weight:** 107 lbs.

Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Hand Rail		1	1
Height Gauge		1	1

Room: Toilet (Patient)

Department: Physical Medicine & Rehab

Room #: A302A, A304E

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Physical Medicine & Rehab

Room #: A302A, A304E

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: EMG

Department: Physical Medicine & Rehab

Room #: A302B, A302D, A302F

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

Cart does need to lock.

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: EMG

Department: Physical Medicine & Rehab

Room #: A302B, A302D, A302F

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Electromyograph

AE #: EMYO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cadwell Laboratories	Sierra Summit		Cart	OF/VI	Project

EMG cart configured for EMG/NCS and Ultrasound includes: Sierra Summit 3-12 channel amplifier, Sierra NMUS1 ultrasound, swivel amplifier arm w/SlimTroller Plus and needle holder, high performance mini PC, 24" monitor, keyboard and mouse trays, footswitch and bracket, lower storage shelf, rear supply bin, and ultrasound probe and gel on work tray. View Cutsheet 211106

Stay with Cadwell. Include ultrasound capability. Make sure to include Isolation Transformer in quote*.

W x D x H: 24 x 24 x 48 in.
Network: Wired
Electrical: 115V 60Hz
Elect Notes: ***Requires 110V outlet with isolated ground to prevent interference with testing. Requires separate UPS to prevent loss of test data in the event of any power loss.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hook, Multipurpose

AE #: HOOK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Wall	CF/CI	Project

Hook for holding spine model. To have minimum 25 lbs. weight capacity. To be specified, provided, and installed by contractor. No Cutsheet 211274

Room: EMG **Department:** Physical Medicine & Rehab

Room #: A302B, A302D, A302F

Lamp — AE #: LAMP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pibbs	DL 957		Floor	OF/OI	Project

Two headed Processing Lamp with flexible chrome arms, adjustable stand, five star base with industrial strength casters. 550 Total Watts (250/Bulb), 1 year warranty View Cutsheet 211270

W x D x H: 31 x 26 x 69 in.
Electrical: 125V 500W

Model, Anatomy — AE #: MOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Universal Medical	Highly Flexible Spine Model	A59-1	Wall	OF/OI	Project

Specially mounted on flexible core. Complete pelvis and occipital plate. Full flexible mounting. L3-L4 disc prolapsed. Spinal nerve exits. Cervical vertebral artery. Male pelvis. Stand sold separately. View Cutsheet 207361

W x D x H: 29.1 x N/A x N/A in.
Weight: 4.3 lbs.

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Treatment, Hi/Lo — AE #: TTHL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	Performa 300		Floor	OF/VI	Project

500 lb weight capacity, center section rises 30 degrees View Cutsheet 211408

W x D x H: 27 x 76 x 18 in.
Clearance: Top 19 in.
Electrical: 120V 60Hz 1.8A

Room: EMG **Department: Physical Medicine & Rehab**

Room #: A302B, A302D, A302F

Transformer-Isolation — AE #: TRIS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Powertronix	P1BTWFHBOC9			OF/OI	Project

Provides medical isolation from main electricity supply, limiting leakage current and providing patient and operator protection. Power: 600 VA. UL listed. View Cutsheet 211878

Can mount to floor, rack, wall, cart, or other location. Inlet type C-14. Number of outlets: 6. Outlet type IEC 320.

W x D x H: 8.3 x 6.2 x 3.2 in.
Electrical: 120V 60Hz **Weight:** 17 lbs.
Elect Notes: 600 VA

UPS — AE #: UPSS-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	APC	BE900G3		Wall	OF/CI	Project

UPS battery backup with (6) NEMA 5-15R and (2) NEMA 5-15R surge outlets, USB type A and C ports. Typical recharge time 8 hours. Not rack mountable. View Cutsheet 210939

For Cadwell EMG cart.

W x D x H: 6.57 x 12.5 x 3.54 in.
Electrical: 120V 60Hz 540W **Weight:** 9.04 lbs.
Elect Notes: NEMA 5-15P plug with 5' cord

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: EMG W/ large table

Department: Physical Medicine & Rehab

Room #: A302E

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

Cart does need to lock.

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: EMG W/ large table

Department: Physical Medicine & Rehab

Room #: A302E

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Electromyograph

AE #: EMYO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cadwell Laboratories	Sierra Summit		Cart	OF/VI	Project

EMG cart configured for EMG/NCS and Ultrasound includes: Sierra Summit 3-12 channel amplifier, Sierra NMUS1 ultrasound, swivel amplifier arm w/SlimTroller Plus and needle holder, high performance mini PC, 24" monitor, keyboard and mouse trays, footswitch and bracket, lower storage shelf, rear supply bin, and ultrasound probe and gel on work tray. View Cutsheet 211106

Stay with Cadwell. Include ultrasound capability. Make sure to include Isolation Transformer in quote*.

W x D x H: 24 x 24 x 48 in.
Network: Wired
Electrical: 115V 60Hz
Elect Notes: ***Requires 110V outlet with isolated ground to prevent interference with testing. Requires separate UPS to prevent loss of test data in the event of any power loss.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hook, Multipurpose

AE #: HOOK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Wall	CF/CI	Project

Hook for holding spine model. To have minimum 25 lbs. weight capacity. To be specified, provided, and installed by contractor. No Cutsheet 211274

Room: EMG W/ large table **Department:** Physical Medicine & Rehab

Room #: A302E

Lamp

AE #: LAMP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pibbs	DL 957		Floor	OF/OI	Project

Two headed Processing Lamp with flexible chrome arms, adjustable stand, five star base with industrial strength casters. 550 Total Watts (250/Bulb), 1 year warranty

View Cutsheet 211270

W x D x H: 31 x 26 x 69 in.
Electrical: 125V 500W

Model, Anatomy

AE #: MOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Universal Medical	Highly Flexible Spine Model	A59-1	Wall	OF/OI	Project

Specially mounted on flexible core. Complete pelvis and occipital plate. Full flexible mounting. L3-L4 disc prolapsed. Spinal nerve exits. Cervical vertebral artery. Male pelvis. Stand sold separately.

View Cutsheet 207361

W x D x H: 29.1 x N/A x N/A in.
Weight: 4.3 lbs.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5"

View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Treatment, Hi/Lo

AE #: TTHL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	PHS Medical	PT3613		Floor	OF/VI	Project

650 lb lifting capacity, back rest raises up to 65 degrees

View Cutsheet 211410

W x D x H: 36 x 77 x 17 in.
Clearance: Top 18 in.
Electrical: 120V 60Hz 10A

Room: EMG W/ large table **Department:** Physical Medicine & Rehab

Room #: A302E

Transformer-Isolation — AE #: TRIS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Powertronix	P1BTWFHBOC9			OF/OI	Project

Provides medical isolation from main electricity supply, limiting leakage current and providing patient and operator protection. Power: 600 VA. UL listed. View Cutsheet 211878

Can mount to floor, rack, wall, cart, or other location. Inlet type C-14. Number of outlets: 6. Outlet type IEC 320.

W x D x H: 8.3 x 6.2 x 3.2 in.
Electrical: 120V 60Hz **Weight:** 17 lbs.
Elect Notes: 600 VA

Transformer-Isolation — AE #: TRIS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Powertronix	M-Series	X1FMWFINOE3Cart		OF/OI	Project

Isolation station to provide medical isolation from main electricity supply. May be mounted to floor, rack, wall, cart, and other custom solutions. View Cutsheet 212326

W x D x H: 15.8 x 11.7 x 3.48 in.
Weight: 45 lbs.

UPS — AE #: UPSS-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	APC	BE900G3		Wall	OF/CI	Project

UPS battery backup with (6) NEMA 5-15R and (2) NEMA 5-15R surge outlets, USB type A and C ports. Typical recharge time 8 hours. Not rack mountable. View Cutsheet 210939

For Cadwell EMG cart.

W x D x H: 6.57 x 12.5 x 3.54 in.
Electrical: 120V 60Hz 540W **Weight:** 9.04 lbs.
Elect Notes: NEMA 5-15P plug with 5' cord

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Equipment **Department:** Physical Medicine & Rehab

Room #: A302E1

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Ultrasound Scanner

AE #: IMUS-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	LX	L28354	Floor	OF/VI	Project

Multipurpose imaging ultrasound system. Features: 11 lbs. storage bin capacity, 19.45 in. W x 15.31 in. H clinical monitor with 1600 x 1200 px resolution, (32 to 104 degrees F operating temperature, 15 to 95 percent R.H. humidity, and 700 to 1060 hPa atmospheric pressure. Imaging modes: 2D (256 gray shades), Color Power Doppler (CPD) (256 colors), Color Doppler (Color) (256 colors), M Mode, Continuous wave (CW) Doppler, Tissue Doppler Imaging (TDI), and Tissue Harmonic Imaging (THI). View Cutsheet 207216

Includes mobile stand

W x D x H: 23 x 23 x 68 in.
Network: Networked
Electrical: 120V 60Hz 6A **Weight:** 152 lbs.

Room: On-Stage Team Work

Department: Physical Medicine & Rehab

Room #: A303, A305

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Soiled Linen

Department: Physical Medicine & Rehab

Room #: A304

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Intake

Department: Physical Medicine & Rehab

Room #: A304C, A304D

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration.

View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz
Struct Notes: Wall mount: wall channel is 19"h. Basket is 12.75"w x 7.75"d x 5.9"h. Pivot arm is 8"d.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor.

View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Room: Intake

Department: Physical Medicine & Rehab

Room #: A304C, A304D

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug. View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz

Weight: 61 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stadiometer		1	1

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Intake

Department: Physical Medicine & Rehab

Room #: A304C, A304D

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Height / Weight **Department:** Physical Medicine & Rehab

Room #: A304D1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

See accessory for stadiometer and hand rail

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Hand Rail		1	1
Height Gauge		1	1

Room: Exam (PMR) **Department: Physical Medicine & Rehab**

Room #: A304F, A304H, A304K, A306H, A306J, A306K, A306L, A306N, A306P, A306Q, A306R, A306S, A306T

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock w/autolocking feature. Want cart for each exam room + 2 per hallway for meds and other procedural items.

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam (PMR) **Department:** Physical Medicine & Rehab

Room #: A304F, A304H, A304K, A306H, A306J, A306K, A306L, A306N, A306P, A306Q, A306R, A306S, A306T

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hook, Multipurpose — AE #: HOOK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Wall	CF/CI	Project

Hook for holding spine model. To have minimum 25 lbs. weight capacity. To be specified, provided, and installed by contractor. No Cutsheet 211274

Model, Anatomy — AE #: MOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Universal Medical	Highly Flexible Spine Model	A59-1	Wall	OF/OI	Project

Specially mounted on flexible core. Complete pelvis and occipital plate. Full flexible mounting. L3-L4 disc prolapsed. Spinal nerve exits. Cervical vertebral artery. Male pelvis. Stand sold separately. View Cutsheet 207361

W x D x H: 29.1 x N/A x N/A in.

Weight: 4.3 lbs.

Room: Exam (PMR) **Department: Physical Medicine & Rehab**

Room #: A304F, A304H, A304K, A306H, A306J, A306K, A306L, A306N, A306P, A306Q, A306R, A306S, A306T

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department. With casters.

W x D x H: 20 x 20 x 24.5 in.

Table, Treatment, Hi/Lo

AE #: TTHL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	Performa 300		Floor	OF/VI	Project

500 lb weight capacity, center section rises 30 degrees View Cutsheet 211408

W x D x H: 27 x 76 x 18 in. **Clearance:** Top 19 in.
Electrical: 120V 60Hz 1.8A

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam (PMR)

Department: Physical Medicine & Rehab

Room #: A304G

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock w/autolocking feature. Want cart for each exam room + 2 per hallway for meds and other procedural items.

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam (PMR)

Department: Physical Medicine & Rehab

Room #: A304G

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hook, Multipurpose

AE #: HOOK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Wall	CF/CI	Project

Hook for holding spine model. To have minimum 25 lbs. weight capacity. To be specified, provided, and installed by contractor. No Cutsheet 211274

Model, Anatomy

AE #: MOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Universal Medical	Highly Flexible Spine Model	A59-1	Wall	OF/OI	Project

Specially mounted on flexible core. Complete pelvis and occipital plate. Full flexible mounting. L3-L4 disc prolapsed. Spinal nerve exits. Cervical vertebral artery. Male pelvis. Stand sold separately. View Cutsheet 207361

W x D x H: 29.1 x N/A x N/A in.

Weight: 4.3 lbs.

Room: Exam (PMR) **Department:** Physical Medicine & Rehab

Room #: A304G

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department. With casters.

W x D x H: 20 x 20 x 24.5 in.

Table, Treatment, Hi/Lo

AE #: TTHL-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	7023144		Floor	OF/VI	Project

650 lb weight capacity, View Cutsheet 211411

W x D x H: 40 x 77 x 17 in. **Clearance:** Top 18 in.

Electrical: 120V 60Hz

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam (PMR)

Department: Physical Medicine & Rehab

Room #: A304J, A304L, A304M

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock w/autolocking feature. Want cart for each exam room + 2 per hallway for meds and other procedural items.

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam (PMR)

Department: Physical Medicine & Rehab

Room #: A304J, A304L, A304M

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hook, Multipurpose

AE #: HOOK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Wall	CF/CI	Project

Hook for holding spine model. To have minimum 25 lbs. weight capacity. To be specified, provided, and installed by contractor. No Cutsheet 211274

Model, Anatomy

AE #: MOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Universal Medical	Highly Flexible Spine Model	A59-1	Wall	OF/OI	Project

Specially mounted on flexible core. Complete pelvis and occipital plate. Full flexible mounting. L3-L4 disc prolapsed. Spinal nerve exits. Cervical vertebral artery. Male pelvis. Stand sold separately. View Cutsheet 207361

W x D x H: 29.1 x N/A x N/A in.

Weight: 4.3 lbs.

Room: Exam (PMR) **Department:** Physical Medicine & Rehab

Room #: A304J, A304L, A304M

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department. With casters.

W x D x H: 20 x 20 x 24.5 in.

Table, Treatment, Hi/Lo

AE #: TTHL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	PHS Medical	PT3613		Floor	OF/VI	Project

650 lb lifting capacity, back rest raises up to 65 degrees View Cutsheet 211410

W x D x H: 36 x 77 x 17 in. **Clearance:** Top 18 in.

Electrical: 120V 60Hz 10A

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Equipment
Room #: A304M1

Department: Physical Medicine & Rehab

Imaging, Ultrasound Scanner

AE #: IMUS-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	LX	L28354	Floor	OF/VI	Project

Multipurpose imaging ultrasound system. Features: 11 lbs. storage bin capacity, 19.45 in. W x 15.31 in. H clinical monitor with 1600 x 1200 px resolution, (32 to 104 degrees F operating temperature, 15 to 95 percent R.H. humidity, and 700 to 1060 hPa atmospheric pressure. Imaging modes: 2D (256 gray shades), Color Power Doppler (CPD) (256 colors), Color Doppler (Color) (256 colors), M Mode, Continuous wave (CW) Doppler, Tissue Doppler Imaging (TDI), and Tissue Harmonic Imaging (THI).

View Cutsheet 207216

Includes mobile stand

W x D x H: 23 x 23 x 68 in.
Network: Networked
Electrical: 120V 60Hz 6A
Weight: 152 lbs.

Room: Consult

Department: Physical Medicine & Rehab

Room #: A306A, A306C

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Equipment **Department:** Physical Medicine & Rehab

Room #: A306F

Imaging, Ultrasound Scanner

AE #: IMUS-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sonosite, Inc.	LX	L28354	Floor	OF/VI	Project

Multipurpose imaging ultrasound system. Features: 11 lbs. storage bin capacity, 19.45 in. W x 15.31 in. H clinical monitor with 1600 x 1200 px resolution, (32 to 104 degrees F operating temperature, 15 to 95 percent R.H. humidity, and 700 to 1060 hPa atmospheric pressure. Imaging modes: 2D (256 gray shades), Color Power Doppler (CPD) (256 colors), Color Doppler (Color) (256 colors), M Mode, Continuous wave (CW) Doppler, Tissue Doppler Imaging (TDI), and Tissue Harmonic Imaging (THI). View Cutsheet 207216

Includes mobile stand

W x D x H: 23 x 23 x 68 in.
Network: Networked
Electrical: 120V 60Hz 6A **Weight:** 152 lbs.

Lifter, Patient

AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor. View Cutsheet 208837

This is the single mobile lifter designated for the entire floor.

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Room: Equipment

Department: Physical Medicine & Rehab

Room #: A306G

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock w/autolocking feature. Want cart for each exam room + 2 per hallway for meds and other procedural items.

W x D x H: 27 x 18 x 33 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Alcove, Linen

Department: Physical Medicine & Rehab

Room #: A306T1

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Team Work

Department: Physical Medicine & Rehab

Room #: A307H

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Medication Room

Department: Physical Medicine & Rehab

Room #: A308D

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Medication Room **Department:** Physical Medicine & Rehab

Room #: A308D

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Medication Room
Room #: A308D

Department: Physical Medicine & Rehab

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

W x D x H: 24 x 29 x 32 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 1.4A
Weight: 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Toilet (Staff)

Department: Physical Medicine & Rehab

Room #: A308E

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supplies / Linen

Department: Physical Medicine & Rehab

Room #: A308F

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system

No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired

Network Notes: One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position.

View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures.

View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z)

View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Room: Clean Supplies / Linen

Department: Physical Medicine & Rehab

Room #: A308F

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement. One vitals monitor for use in rooms as needed.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz
Struct Notes: Wall mount: wall channel is 19"h. Basket is 12.75"w x 7.75"d x 5.9"h. Pivot arm is 8"d.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Clean Supplies / Linen

Department: Physical Medicine & Rehab

Room #: A308F

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

Need two for the clinic.

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Clean Supplies / Linen

Department: Physical Medicine & Rehab

Room #: A308F

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Hold

Department: Physical Medicine & Rehab

Room #: A308G

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Sharps

AE #: COSH-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004LR		Floor	OF/OI	Supply Agreement

8-gallon red bin (19.7”h x 13.0”d x 11.3 “w) for biohazard waste with wire step-on dolly.

View Cutsheet 164306

W x D x H: 14.3 x 16.5 x 23 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Hold

Department: Physical Medicine & Rehab

Room #: A308G

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage Work Space **Department: Physical Medicine & Rehab**

Room #: PMR052

Room Notes: Enclosed space for (8) x 5' desk.

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder Unable to provide larger Tote Bin per UK recycling.

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Accessories

AE #: ACCE-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Beyond Balance	PSSE Extension Poles		Cabinet	OF/OI	Project

Physiotherapeutic scoliosis specific exercise poles 1.25" diameter, one pair of 2 male/2 female each. Made of poplar wood. Assembled length 82". View Cutsheet 210945

W x D x H: 1.25 x 1.25 x 41 in.

Accessories

AE #: ACCE-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Reaxing	3D Mat	RE 1043	Floor	OF/OI	Project

3D mat for use alone or with Reaxing Board. View Cutsheet 210931

W x D x H: 39.4 x 39.4 x 2.36 in.

Allowance, Equipment

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - Allowance			Cabinet	OF/OI	Project

No Cutsheet 62508

Allowance for sporting equipment (tennis, golf, etc.)

Allowance, Free Weights and Barbell

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - Allowance			Rack	OF/OI	Project

No Cutsheet 211389

For Free Weights and barbell(45lbs) for squat rack

Allowance, Positioning Device

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cabinet	OF/OI	Project

Positioning device allowance. No Cutsheet 75402

Allowance for bolsters, wedges, etc.

Room: Physical Therapy **Department:** Physical Therapy

Room #: A307A

Balance Disc

AE #: BADI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081432418	969131	Cabinet	OF/OI	Project

Balance disc 60cm. One side is tactile for stimulation. Inflates with standard pump. View Cutsheet 172902

W x D x H: 23.6 x 23.6 x 3.1 in.

Balance Pad

AE #: BAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081068089		Floor	OF/OI	Project

Elite balance pad, soft foam construction for barefoot training and proprioception, Non-slip, durable tear-resistant surface helps prevent falls, For improving stability and mobility while strengthening joints View Cutsheet 207195

W x D x H: 20 x 16 x 2.5 in.

Balance Trainer

AE #: BATR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Korebalance	19 Professional		Floor	OF/VI	Project

Offers balance assessment and training. Interactive 3D games. Professional version has 2" hardened steel, adjustable safety arms. Weight limit 500 lbs. View Cutsheet 210533

W x D x H: 44 x 58 x 80 in.
Electrical: 115V 60Hz **Weight:** 500 lbs.

Balance Trainer

AE #: BATR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Korebalance	KoreSway Mobile		Floor	OF/OI	Project

Includes a force plate platform with carry bag, touch screen laptop computer, and foam mat for perturbed surface activities. Step up height 2.75". View Cutsheet 210535

Patient weight capacity 330 lbs.

W x D x H: 23 x 23 x 2.75 in.
Electrical: 120V 60Hz **Weight:** 31 lbs.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Balance Trainer

AE #: BATR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081247295	929244	Cabinet	OF/OI	Project

Theraband stability trainer is soft, oval-shaped, color-coded pad. Color blue, density soft.

View Cutsheet 210924

Ball, Exercise

AE #: BAEX-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	FitBALL	FBMINI	665272330387	Rack	OF/OI	Project

Blue ball 9" round anti-burst ball.

View Cutsheet 210712

W x D x H: 9 x 9 x 9 in.

Ball, Exercise

AE #: BAEX-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	553466		Rack	OF/OI	Project

Exercise ball. 30 inch blue.

View Cutsheet 158868

W x D x H: 30 x 30 x 30 in.

Ball, Exercise

AE #: BAEX-26

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	553465		Rack	OF/OI	Project

Exercise ball. 26 inch 65 cm green.

View Cutsheet 158867

W x D x H: 26 x 26 x 26 in.

Ball, Exercise

AE #: BAEX-21

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	553464		Stand	OF/VI	Project

21" / 55cm red exercise ball, includes 2 ball plugs and an inflation adapter. Tested to 600 lbs of static weight.

View Cutsheet 156722

W x D x H: 21 x 21 x 21 in.

Room: Physical Therapy **Department:** Physical Therapy

Room #: A307A

Band, Resistance

AE #: BARE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Myosource Kinetic Bands	Acceleration Speed Cord		Cabinet	OF/OI	Project

Acceleration Speed Cord kit includes resistance band (speed cord), adjustable large size belt, assistant hand strap, anchor strap, and carrying bag. View Cutsheet 210926

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Add Medium Belt		1	1
Add Small Belt		1	1
Extra Cord		1	1

Bar, Weighted

AE #: BAWE-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cando - Fabrication Enterprises	10-1604		Rack	OF/VI	Project

3 lb. weighted bar View Cutsheet 207714

W x D x H: 36 x 2 x 2 in.

Weight: 3 lbs.

Bar, Weighted

AE #: BAWE-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cando - Fabrication Enterprises	10-1608		Rack	OF/VI	Project

5 lb. weight bar. View Cutsheet 207715

W x D x H: 36 x 2 x 2 in.

Weight: 5 lbs.

Bars, Parallel

AE #: BAPA-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tri W-G Group	TG1006		Floor	OF/VI	Project

Motorized height and width adjustable parallel bars, 16' in length. Weight capacity 600 lbs. Fingertip controls, individual or simultaneous operation. Steel frame. Height adjustable bars with range from 25.5"H to 39.75"H. Horizontal inside dimension 15.5"-24.5". Non-skid black mat. Color: Pearl Gray standard, Porcelain optional color. View Cutsheet 210557

W x D x H: 53.5 x 216 x 39.8 in.
Electrical: 115V 60Hz 6.8A 782W
Struct Notes: Platform 16' long. Ramps add 12" to each end of platform.

Room: Physical Therapy **Department:** Physical Therapy

Room #: A307A

Board, Balance

AE #: BOBA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Reaxing	Reax Board Pro1 250		Floor	OF/VI	Project

View Cutsheet 210696

W x D x H: 49.2 x 98.4 x 13 in.
Electrical: 115V 60Hz **Weight:** 970 lbs.

Board, BAPS

AE #: BOPS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	C6400-0		Floor	OF/VI	Project

Biomechanical ankle platform; produces controlled, calibrated and predictable stress on the lower leg, ankle and foot; lightweight, durable platform with permanent indices to assure proper foot placement, latex free; platform is reversible to accommodate right or left foot; system includes 5 hemispherical attachments, 2 weight rods, 4 weight plates (2.5 lbs. Ea.), wall mount, clinical manual

View Cutsheet 39753

Board, Rocker & Wobble

AE #: BORW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081559848	550131	Shelf	OF/OI	Project

Softboards functional balance system features compression legs to give user sense of floating. Intermediate model.

View Cutsheet 172903

W x D x H: 32 x 25 x 17 in.
Weight: 4.5 lbs.

Board, Slant

AE #: BOSL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	7025974		Floor	OF/OI	Project

Hardwood plywood construction adjusts to 4 different angles: 10, 20, 30, and 40 degrees.

View Cutsheet 210933

W x D x H: 17 x 13 x 12 in.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Board, Wobble

AE #: BOWO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thera-Band	ROCKER BOARD		Floor	OF/OI	Project

Wooden uniplane rocker, offers sensory motor challenges in two planes. Restricts lateral movement. View Cutsheet 145098

straight dowel under

Struct Notes: All-wood construction with non-slip strips
maximum angle of 34 degrees, supports up to 400lbs

Bolster, Therapy

AE #: BOTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	2794G		Rack	OF/OI	Project

Tumble forms 2 therapy bolster; solid core; 36" long; 8" diameter; with strap for carrying and hanging on rack. View Cutsheet 158877

W x D x H: 8 x 8 x 36 in.

Bolster, Therapy

AE #: BOTH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	2794H		Rack	OF/OI	Project

Tumbleforms 2 rolls for use in rehabilitation, fitness, and neurobehavioral training for patients with special needs. View Cutsheet 172680

W x D x H: 12 x 12 x 48 in.

Weight: 22 lbs.

Bolster, Therapy

AE #: BOTH-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Tumble Forms Inc/Patterson Medical/Sammons Preston	Bolster 8" x 24"		Rack	OF/OI	Project

Bolster roll, 8" round x 24" long. Molded from soft foam with rounded corners makes it soft yet firm. Rigid core prevents collapsing. Seamless body fluid resistant coating. Carry/storage handle. View Cutsheet 210923

W x D x H: 8 x 24 x 8 in.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Cart, Cold Compression

AE #: CACC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Hausmann Industries, Inc.	A9023		Floor	OF/VI	Project

Cart designed to hold two cold compression units or one cold compression unit and modality. Top surface measures 23"W x 21.5"D. One 4"H drawer measures 21.5"W x 14.5"D. Bottom pull out features 4 drying racks for cold compression sleeves. Total weight capacity 180 lbs. Color options: Black or Natural Oak.

View Cutsheet 210548

W x D x H: 24.5 x 22.8 x 38.5 in.

Cart, Therapy

AE #: CATH-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MJM Intl	Universal Therapy Cart	081627488	Floor	OF/VI	Project

Made of healthcare grade PVC pipe and fittings with rustproof casters. Holds multiple exercise balls and up to 8 weighted bars.

View Cutsheet 210538

W x D x H: 44 x 19 x 58 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic.

View Cutsheet 207611

Requested for use in cleaning space

W x D x H: 42 x 20 x 37.5 in.

Cervical Spine Assessment System

AE #: CSAS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	BTE Technologies	MCU		Floor	OF/VI	Project

Multi Cervical Unit for assessing and treating chronic neck pain.

View Cutsheet 210537

Confirm if laptop, printer, and cart come with device or if they are provided by customer.

W x D x H: 31 x 47 x 77 in.
Electrical: 120V 60Hz 14A
Elect Notes: Dedicated circuit required

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Chair, Recliner

AE #: CHRE-89

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Svago	Lite 2		Floor	OF/VI	Project

Zero gravity recliner with 21"W seat. Weight capacity 275 lbs. View Cutsheet 210530

W x D x H: 29.1 x 63 x 46.1 in.
Electrical: 120V 60Hz **Weight:** 88.4 lbs.
Elect Notes: cord length 9'

Cold Therapy Unit

AE #: COTU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Game Ready (Coolsystems, Inc.)	Pro 2.1		Cart	OF/OI	Project

Ice machine cold and compression therapy unit. Includes control unit, connector hose, power cord, and AD adapter. View Cutsheet 210701

W x D x H: 7.5 x 16 x 7.75 in.
Electrical: 120V 60Hz **Weight:** 7.3 lbs.

Cone

AE #: CONE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Power Systems, Inc	12"H		Cabinet	OF/OI	Project

Agility cone; 12" high; orange, stackable View Cutsheet 172099

W x D x H: 6 x 6 x 12 in.

Cupping Set

AE #: CUSE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	Silicone Cupping Set	7101507	Cabinet	OF/OI	Project

Silicone cupping set includes varying sized transparent cups. Comes with 4 sizes: 1.2", 1.7", 2.0", and 2.5". View Cutsheet 210713

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dynamometer

AE #: DYNA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	JAMAR PLUS+	563213	Drawer	OF/VI	Project

Jamar plus+ digital hand dynamometer has electronic load sensors. Aluminum body with scratch-resistant uv coating. Readout displays isometric grip force from 0-200 lbs (90 kg). Comes in reusable storage container. 1 year warranty. View Cutsheet 150801

Elect Notes: Requires (2) aaa batteries, included

Electrotherapy System

AE #: ELSY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Chattanooga Group	Vectra Genisys		Floor	OF/VI	Project

Combination 4-channel system for ultrasound, electrotherapy, and EMG. View Cutsheet 210547

W x D x H: 17 x 16.3 x 42.5 in.

Electrical: 115V 60Hz **Weight:** 34 lbs.

Exercise Cable Machine, Portable

AE #: ECMP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	MaxPro	SC Portable Cable Machine		Floor	OF/OI	Project

Portable cable machine, folds up when not in use. View Cutsheet 210932

W x D x H: 3.6 x 32.3 x 4.1 in.

Room: Physical Therapy
Room #: A307A

Department: Physical Therapy

Exercise Unit, Bicycle, Upright

AE #: EUBU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Matrix Fitness	Endurance		Floor	OF/VI	Project

Upright bicycle, self-powered, multiple program options. Maximum user weight 400 lbs. View Cutsheet 210525

W x D x H: 25.7 x 51.5 x 60.5 in.
Weight: 149 lbs.

Exercise Unit, Body Blade

AE #: EUBB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bodyblade	Starter Bundle		Cabinet	OF/OI	Project

Starter bundle includes 1 Bodyblade Pro(60" length, 2.5 lbs), 1 Bodyblade Classic(48" length, 1.75lbs) , and 1 Bodyblade CxT(40" length, 1.5 lbs). View Cutsheet 210707

W x D x H: N/A x N/A x 60 in.
Weight: 5.75 lbs.

Exercise Unit, Drive Sled

AE #: EUDS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Perform Better	DRIVE SLED II	2670	Floor	OF/OI	Project

Drive sled ii. Flat bottom and solid steel feet. Includes sled, heavy-duty h-harness, and two vertical push handles. View Cutsheet 158955

W x D x H: 30 x 46 x 36 in.

Exercise Unit, Elliptical

AE #: EXUE-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Life Fitness	Integrity Series		Floor	OF/VI	Project

Integrity series elliptical exerciser. Max user weight 400 lbs. Stride length 20". View Cutsheet 207606

W x D x H: 29 x 86 x 64 in.
Electrical: 120V 60Hz 20A
Weight: 301 lbs.
Elect Notes: Dedicated 20A circuit

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Exercise Unit, Ergometer

AE #: EUER-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Scifit Systems Inc.	PRO 2	PRO230-INT	Floor	OF/VI	Project

Pro2 offers upper body, lower body (recumbent bike), or total body exercise; the upper and lower cranks are dependent, allowing individuals to use passive assistance - using strong limbs to drive weaker limbs through the range of motion; adjustable upper and lower cranks provide a greater range of movement, exercise variety, and custom fit; therapy assist pedal (only available on the shown seat model) provides easy seat adjustment, eliminating risk due to compromised body position; all seats easily remove for wheelchair access. Three seating options are available : tall back, fixed height seat - (shown) oversized, height adjustable swivel seat featuring therapy assist pedal - oversized, fixed height bariatric seat

View Cutsheet 123077

W x D x H: 31 x 64 x 57 in.

Exercise Unit, Functional Trainer

AE #: EUFT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081571389	565323	Floor	OF/VI	Project

Link Series Functional Trainer provides free cable and bodyweight training as well as total body stretching. Allows squats, curls, rows, and other exercises.

View Cutsheet 210522

W x D x H: 85 x 33 x 89 in.

Weight: 979 lbs.

Exercise Unit, NuStep

AE #: EUNS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Nustep, Inc.	T6 Pro	7102850	Floor	OF/VI	Project

T6 Pro has 2 adjustable straps on each oversized foot pedal to keep feet stable. Arms adjust up to 18" and hand grips rotate 40 degrees. Low step-through design for individuals with physical limitations. Reclining 360-degree swivel seat. Touch screen display. Weight limit 500 lbs.

View Cutsheet 210520

W x D x H: 30 x 73 x 52 in.

Electrical: 115V 60Hz

Exercise Unit, Pilates

AE #: PILA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Faittd	Foldable Pilates Machine		Floor	OF/VI	Project

Foldable Pilates machine & equipment with reformer accessories, reformer box, padded jump board. Weight capacity 300 lbs.

View Cutsheet 210930

W x D x H: 30 x 97 x 16 in.

Weight: 145 lbs.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Exercise Unit, Pilates

AE #: PILA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Optp	AEROPILATES RING		Rack	OF/OI	Project

Purple pilates ring. Diameter: 14.75"

View Cutsheet 170057

W x D x H: 14.8 x N/A x N/A in.

Exercise Unit, Prowler Sled

AE #: EUPS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Torque Fitness	Tank M4		Floor	OF/VI	Project

Sled with ergonomic handles, dual adjustable and frictionless magnetic brake system that increases resistance with speed.

View Cutsheet 210528

W x D x H: 31.9 x 52.4 x 37.1 in.

Weight: 198 lbs.

Exercise Unit, Recumbent Bicycle

AE #: EURB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Spirit Fitness	XBR95		Floor	OF/VI	Project

Recumbent bike constructed of professional grade equipment features wipe clean surface. Adjustable cooling fans. Self-generating, no power cord needed. Weight capacity 350 lbs. 10 built-in programs and 20 resistance levels.

View Cutsheet 210523

W x D x H: 30 x 50 x 57 in.

Weight: 147 lbs.

Exercise Unit, Shuttle

AE #: EUSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shuttle Systems	MVP PRO	3200	Floor	OF/VI	Project

Plyometric training; supine leg press; 12 elasticords; maximum 500 lb. Resistance.

View Cutsheet 169787

W x D x H: 31 x 109 x 30 in.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Exercise Unit, Smith Machine

AE #: ESMI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Best Fitness	Smith Machine	BFSM250	Floor	OF/VI	Project

Weight machine can be used without a spotter due to safety catches. Solid steel, knurled Olympic barbell slides on carriage. Weight capacity 300 lbs. View Cutsheet 210518

W x D x H: 66 x 50 x 79 in.

Weight: 114 lbs.

Exercise Unit, Squat Rack

AE #: EUSR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sorinex	XL Series Half Rack		Floor	OF/VI	Project

Half rack with 3" x 3" tubing. Multiple options and configurations. View Cutsheet 210519

W x D x H: 47 x 64 x 95.4 in.

Weight: 423 lbs.

Exercise Unit, Suspension Training

AE #: EUST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	TRX Training Center	TRX PRO4		Rack	OF/OI	Project

Includes suspension trainer, one year free TRX app access, adjustable foot cradles, theft-resistant carabiner, industrial-grade reinforcement stitching, View Cutsheet 172752

barrel lock adjusters, suspension anchor, door anchor, TRX Xtender and mesh carry bag.

To be mounted to squat rack. This does not need to be wall mounted.

Exercise Unit, Treadmill, Anti-Gravity

AE #: ETAG-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Boost Treadmills	Boost 2 Core		Floor	OF/VI	Project

Core model with maximum speed 12 mph, color white. User height range 4'6" - 7'0". Allow 24" clearance from ceiling to top height of tallest user. View Cutsheet 210521

W x D x H: 42 x 82 x 77 in.

Clearance: Rear 30 in.; Left 12 in.; Right 12 in.; Front 12 in.

Electrical: 120V 60Hz 20A 1-Phase

Elect Notes: 20A single phase dedicated circuit required.

Struct Notes: Requires 44"W door to room. Room size recommended 10.5' x 5.5'.

Room: Physical Therapy **Department: Physical Therapy**

Room #: A307A

Exercise Unit, Wall Rail — AE #: EUWR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thera-Band	CLX Wall Station and Anchor	081706779	Wall	OF/CI	Project

Vertical, wall-mounted slide track. Comes with step-by-step exercise poster and 7 CLX progressive resistance bands. View Cutsheet 210526

W x D x H: 4 x 2 x 84 in.

Exerciser, Balance Device — AE #: EXBD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bosu	BOSU PRO BALANCE TRAINER		Floor	OF/OI	Project

Balance exerciser. Dome shape with flat bed base. Used for training balance, building strength, and enhancing flexibility. Can be used dome or platform side down. Includes foot pump. Maximum user weight limit is 350 lbs. View Cutsheet 164566

W x D x H: 26 x 26 x 10 in.

Gait and Safety System — AE #: GASS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Aretech	ZeroG 3D		Ceiling	OF/CI/VI	Project

Robotic body weight support system that automatically tracks patients as they move freely in any direction. Dynamic body weight support offloads a percentage of the patient's weight as they perform activities in a 3-dimensional workspace with customizable boundaries up to 500 SF while fall protection provides safety. Dynamic support up to 200 lbs. Static support up to 450 lbs. View Cutsheet 211107

Price $360,500 for 300 SF system with 2-phase installation (phase 1 ceiling pendants/structure and phase 2 tracks/robot). Additional 200' in length included in cost above. Per email from Teddy O'Connell 4/23/2024.

W x D x H: 120 x 600 x N/A in.
Network: Wired **Network Notes:** Data and power for user interface: Windows touchscreen PC and wireless remote
Electrical: 120V 60Hz 10A
Elect Notes: Electrical control box requires 208-230VAC / 60 Hz / 10A. This is noted as a separate item in the database (item 211141)
Struct Notes: Minimum ceiling height 9'4"

Room: Physical Therapy **Department: Physical Therapy**

Room #: A307A

Gait and Safety System Component — AE #: GSSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Aretech	ZeroG Control Box		Wall	OF/CI	Project

Electronics control box contains power conditioning components, including an isolation transformer, circuit breaker, and solid state relays for the ZeroG 3D system. Box contains the system's main power switch as well as the emergency stop button. Key locked box.

View Cutsheet 211141

To be mounted on wall of treatment room at corner by staff workroom. Price is included in the ZeroG system.

W x D x H: 15 x 9 x 15 in.
Electrical: 208V 60Hz 20A **Weight:** 74 lbs.
Elect Notes: Dedicated wall outlet.
Struct Notes: Mount 3/4" plywood to wall and then the electronics box is secured to the plywood.

Gait and Safety System Component — AE #: GSSC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Aretech	Harness Rack		Wall	OF/CI	Project

Rack for holding ZeroG system harnesses. Cost included with system purchase.

View Cutsheet 211165

W x D x H: 48 x 3 x 3 in.
Struct Notes: Recommended mounting height 60" AFF

Gauge, Pinch — AE #: GAPI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081296656		Handheld	OF/OI	Project

Measures in pounds and kilograms. 0-60 lb gauge

View Cutsheet 206807

Weight: 0.53 lbs.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Goniometer

AE #: GONI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Performance Health	7541		Drawer	OF/OI	Project

<<large>> 12-1/2" standard goniometer

View Cutsheet 158999

Goniometer

AE #: GONI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Performance Health	081187665	7540	Drawer	OF/OI	Project

EZ Read goniometer, 8" size.

View Cutsheet 210910

Goniometer

AE #: GONI-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	Arthrodial Goniometer	926625	Drawer	OF/OI	Project

Arthrodial goniometer for measuring cervical rotation, lateral flexion of the head, and anterior -posterior cervical flexion. Bubble level ensures measurement is accurate on the horizontal plane.

View Cutsheet 210911

Goniometer

AE #: GONI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Performance Health	081187657	7539	Drawer	OF/OI	Project

Jamar EZ Read goniometer 6" size

View Cutsheet 210912

Hammer, Reflex

AE #: HARE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Performance Health	081441609	566683	Drawer	OF/OI	Project

Used for reflex testing, the triangular-shaped rubber head is connected to a long, solid chrome steel handle designed for sure grip. Latex Free option.

View Cutsheet 165454

W x D x H: 7.5 x N/A x N/A in.

Weight: 0.02 lbs.

Room: Physical Therapy **Department:** Physical Therapy

Room #: A307A

Heat Therapy Device — AE #: HETD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hyperice	Venom 2 Back		Cabinet	OF/OI	Project

Heat and massage wrap for the back. View Cutsheet 210918

Heat Therapy Device — AE #: HETD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hyperice	Venom 2 Leg		Cabinet	OF/OI	Project

Heat and massage therapy wrap for the leg. View Cutsheet 210921

Heat Therapy Device — AE #: HETD-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hyperice	Venom 2 Shoulder		Cabinet	OF/OI	Project

Heat and massage therapy wrap for the shoulder View Cutsheet 210922

Hydrocollator — AE #: HYDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rich-Mar Corporation	HYDRATHERM DELUXE HT-R12-DW		Floor	OF/OI	Project

Mobile moist heat therapy unit. Includes drainage pump, divider system, 3 standard, 3 universal, 3 cervical, and 3 oversize hydrheat packs. Features composite tub, digital low water sensor, composite dividers, temperature range from 120 degrees fahrenheit to 160 degrees fahrenheit and digital thermostat control. 18 gallon water capacity without heat packs. View Cutsheet 164538

W x D x H: 30 x 20 x 33 in.
Electrical: 120V 60Hz 8.3A 1000W 1-Phase **Weight:** 75 lbs.

Inclinometer — AE #: INCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Performance Health	081275643	A44130	Cabinet	OF/OI	Project

Measures users flexion, extension, abduction, and adduction. Also measures small and large joints, and the spine's ability to rotate. Gives 1" increments of measurement. Pocket size. View Cutsheet 210705

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Iontophoresis Machine

AE #: IOMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ActivaTek	ActivaDose II	568747	Cabinet	OF/OI	Project

Dose delivery device with 2 controls that operate dose and current.

View Cutsheet 210704

W x D x H: 6 x 10 x 4 in.

Weight: 1.5 lbs.

Ladder, Agility

AE #: LAGI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	SMART AGILITY LADDER	568796	Floor	OF/OI	Project

15 ft. Ladder consisting of two 7.5 foot segments; flat, hard plastic rungs

View Cutsheet 158562

W x D x H: 20 x 180 x N/A in.

Laser Therapy Unit

AE #: LATU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	TheraTouch	LX2		Stand	OF/VI	Project

Laser therapy touch unit to treat acute and chronic conditions. Dimensions approximated.

View Cutsheet 210555

W x D x H: 32 x 24 x 44 in.

Electrical: 115V 60Hz

Massager

AE #: MASS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Hyperice	Hypervolt 2 Pro		Shelf	OF/OI	Project

View Cutsheet 207182

W x D x H: 2.5 x 8 x 10.4 in.

Weight: 2.6 lbs.

Elect Notes: Battery operated

Room: Physical Therapy **Department:** Physical Therapy

Room #: A307A

Mat, Floor — AE #: MAFL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	081008549	2210A	Floor	OF/VI	Project

Folding therapy mat 2' x 4'. View Cutsheet 210720

W x D x H: 24 x 48 x 2 in.

Mirror — AE #: MIPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	5350		Floor	OF/VI	Project

Freestanding single section mirror on casters; heavy plate glass with electroplated copper produces bright, distortion-free images; oak laminate frame View Cutsheet 70720

W x D x H: 27 x 4 x 72 in.

Model, Anatomy — AE #: MOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Universal Medical	Highly Flexible Spine Model	A59-1	Shelf	OF/OI	Project

Specially mounted on flexible core. Complete pelvis and occipital plate. Full flexible mounting. L3-L4 disc prolapsed. Spinal nerve exits. Cervical vertebral artery. Male pelvis. Stand sold separately. View Cutsheet 207361

W x D x H: 29.1 x N/A x N/A in.

Weight: 4.3 lbs.

Monitor, Pulse Oximeter — AE #: MOPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	CME Corp.	CESS-98708-00		Countertop	OF/OI	Project

Fingertip Pulse Oximeter with SpO2 value display, pulse rate value display, bar graph display, pulse waveform display. Battery-powered device. View Cutsheet 206072

W x D x H: 1.22 x 2.24 x 1.26 in.

Positioning Device — AE #: PODE-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Amazon	DMI Wedge Pillow 8"		Cabinet	OF/OI	Project

Leg pillow wedge View Cutsheet 210925

W x D x H: 20 x 24 x 8 in.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Rack, Kettle Bell

AE #: RAKB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Body Solid Inc	GDKR100		Floor	OF/OI	Project

Dual dumbbell and kettlebell rack - configurable platforms flip to hold either dumbbells or kettle bells. Heavy gauge steel construction with powder coat finish. View Cutsheet 210710

W x D x H: 45 x 23 x 33 in.

Weight: 79 lbs.

Rack, Weight Storage

AE #: RAWS-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sammons Preston / Patterson	C5161		Floor	OF/VI	Project

Cuff weight and dumbbell storage rack, holds up to 500#.features front and back pegboards with 24 movable hooks, and two built-in racks to hold 20 dumbbells. Heavy-duty , dual wheel casters make moving a fully loaded rack easy. Partial assembly required, shipped directly from manufacturer. Latex-free. Accessory: exercise band storage cap. View Cutsheet 62284

May decrease to 1 if space is limited

W x D x H: 24 x 24 x 53 in.

Roller, Exercise

AE #: ROEX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	OPTP	Pro-Roller		Cabinet	OF/OI	Project

Pro-Roller blue marble color, 6" round x 36" long View Cutsheet 210928

W x D x H: 6 x 6 x 36 in.

Roller, Exercise

AE #: ROEX-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	OPTP	Pro-Roller Soft		Cabinet	OF/OI	Project

Pro-Roller Soft, color blue. Round 36"L x 6" round. View Cutsheet 210929

W x D x H: 6 x 6 x 36 in.

Room: Physical Therapy **Department: Physical Therapy**

Room #: A307A

Sphygmomanometer, Aneroid, Handheld — AE #: SPAH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Platinum Series DS58		Cabinet	OF/OI	Project

With gear-free DuraShock technology, you can count on the DS58 aneroid to remain in calibration longer than traditional aneroids, providing more accurate readings over time and a lower lifetime cost, helping to improve practice efficiencies and your bottom line. View Cutsheet 209186

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stick, Massage — AE #: STMG-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	ZZZ - To Be Determined	Massage Stick		Cabinet	OF/OI	Project

Model / size to be determined View Cutsheet 210703

Room: Physical Therapy **Department: Physical Therapy**

Room #: A307A

Stool, Nesting — AE #: STNE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	552398		Cabinet	OF/VI	Project

Therapy steps. The four steps can be nested when not in use. Each step has a 300 lb. Weight capacity. The top surface is covered with a low pile, foot friendly, carpet to make patients feel secure when performing mobility and balance exercises. Step 1 measures 10"w x 12"l x 2"h. Step 2, 12" w x 14" l x 4"h. Step 3, 14"w x 18"l x 6"h. Step 4, 16"w x 20"l x 8"h. View Cutsheet 159044

2 sets

W x D x H: 16 x 20 x 8 in.

Stool, Without Back — AE #: STNB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
11	Armedica Mfg Corp	AM-844		Floor	OF/OI	Project

Mobile stool with square 14" seat and four 2.5" casters. Seat height 18". Welded steel frame. Weight capacity 225 lb. View Cutsheet 167099

W x D x H: 16 x 16 x 18 in.

Table, Traction — AE #: TATR-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Chattanooga Group	Triton DTS Traction	7102937	Floor	OF/VI	Project

Table with traction unit that features 5 unique, fully programmable pull patters. Allows isolation of all phases of pull with independent timing. Advanced accessory kit with DTS Triton traction unit, Saunders cervical traction unit, Quickwrap DTS belt set, and knee bolsters. Table upholstery color: Imperial Blue. View Cutsheet 210517

W x D x H: 110 x 31 x 37 in.
Electrical: 115V 60Hz **Weight:** 428 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
DTS Advanced Accessory Kit		1	2

Table, Treatment, Hi/Lo — AE #: TATH-27

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Performance Health	7023770		Floor	OF/VI	Project

Electric 3-section treatment table with lifting capacity of 500 lbs. Height adjustable with foot pedal from 17" to 35". Individual locking casters. View Cutsheet 210515

W x D x H: 77 x 27 x 35 in.
Electrical: 120V 60Hz **Weight:** 350 lbs.

Room: Physical Therapy **Department:** Physical Therapy

Room #: A307A

Table, Treatment, Hi/Lo — AE #: TATH-98

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Performance Health	7023133		Floor	OF/VI	Project

Pivotal Health Solutions Essential Thera-P Bobath 5-section electric treatment table with 2" high density foam; height adjustable with foot pedal 17"-35". View Cutsheet 210516

ADA compliant. Lifting capacity 500 lbs.

W x D x H: 40 x 77 x 35 in.
Electrical: 115V 60Hz **Weight:** 350 lbs.

Therapy Unit — AE #: THUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Game Ready (Coolsystems, Inc.)	Med4 Elite		Floor	OF/VI	Project

Multi-modality therapy unit dual user recovery system integrates iceless cold, controllable heat, rapid contrast, and active compression therapies. Hose connections: 2 ports, 2 holsters. Specific wraps available for each body part being treated. View Cutsheet 210554

W x D x H: 24.8 x 32.5 x 43 in.
Electrical: 115V 60Hz **Weight:** 172 lbs.

Therapy Unit — AE #: THUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Game Ready (Coolsystems, Inc.)	Med4 Elite		Floor	OF/VI	Project

Multi-modality therapy unit dual user recovery system integrates iceless cold, controllable heat, rapid contrast, and active compression therapies. Hose connections: 2 ports, 2 holsters. Specific wraps available for each body part being treated. View Cutsheet 210554

W x D x H: 24.8 x 32.5 x 43 in.
Electrical: 115V 60Hz **Weight:** 172 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Ankle Wrap Large	590330	4	4
Back Wrap	590500	2	2
C-T Spine Wrap	590502	2	2
Hip-Groin Wrap - Left	590604	4	4
Hip-Groin Wrap - Right	590602	4	4
Hose Dual Connector 5'	570302	2	2
Hose Replacement 6'	570300	2	2
Knee Wrap - Straight	590100	4	4
Shoulder Wrap - Large Left	590434	4	4
Shoulder Wrap - Large Right	590432	4	4

Room: Physical Therapy **Department:** Physical Therapy

Room #: A307A

Therapy Unit — AE #: THUN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	NecksLevel	Sports Bundle		Cabinet	OF/OI	Project

Neck evaluation and therapy kit includes 1 NecksLevel Pro, travel case, Zoom tutorial for staff, 5 strength headbands, full resistance package, and 1 replacement band set. View Cutsheet 210927

Tool, Therapy — AE #: TOTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sound Assisted Soft Tissue Mobilization	Eight Instrument Set		Cabinet	OF/OI	Project

Set contains: all 8 SASTM instruments, 1 oz. jar of SASTM emollient, hard carrying case, protocols, manual, online certification, and HD treatment videos. View Cutsheet 210946

W x D x H: 15 x 10 x 4.25 in.

Tourniquet, Automatic — AE #: TOAU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Delfi	9-2200-200BFR		Stand	OF/OI	Project

Personalized blood flow restriction; cuff pressure range 50-350mmHg; BFR Pressure application timer 1-30min; advanced pressure regulation; 12 preset protocols; interval timer; REPS indicator; intuitive user interface. Set includes (1) each of the following: PTS BFR system, 18", 24", and 34" Easi-Fit BFR cuffs, and PTS transport bag. View Cutsheet 200401

W x D x H: 4.7 x 4.3 x 7 in.

Weight: 2.4 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
PTS Roll Stand w/Basket	9-2200-550	1	2

Treadmill, Electric — AE #: TREL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Reaxing	Reax Run Pro1		Floor	OF/VI	Project

Proprioceptive treadmill performs sudden and unpredictable inclinations while running. View Cutsheet 210695

W x D x H: 46.1 x 95.3 x 65.4 in.

Electrical: 110V 60Hz **Weight:** 1323 lbs.

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Weight, Bar

AE #: WEBA-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	540014		Cart	OF/OI	Project

Gray bars with color labels to indicate weight. Vinyl grip area in center of each bar facilitates single extremity exercise. Set of 1,2,3,4, and 5 lb weights. View Cutsheet 158841

Weight, Cuff

AE #: WECU-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	081031707	517050	Rack	OF/VI	Project

Ankle / wrist cuff weight, 0.5 lb. Color pink. Velcro closure. View Cutsheet 210711

Weight, Cuff

AE #: WECU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sammons Preston / Patterson	081430016	969107	Rack	OF/VI	Project

Deluxe cuff weight, 7 piece set (1, 2, 3, 4, 5, 7.5 & 10 lb weights) View Cutsheet 114950

Weight, Dumbbell

AE #: WEDU-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	CanDo Standard Weight Dumbbell Set		Rack	OF/VI	Project

Set of 20 dumbbells, one pair each from 1 lb. to 10 lbs. Each weight is a different color. Wipe-clean vinyl coating allows user to sanitize for shared use. View Cutsheet 207401

Room: Physical Therapy

Department: Physical Therapy

Room #: A307A

Weight, Kettle Bell

AE #: WEKB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Body Solid Inc	KBVS295		Rack	OF/OI	Project

Set of vinyl dipped kettle bells in the following weights (lbs.): 5, 8, 10, 12, 15, 20, 25, 30, 35, 40, 45, and 50. View Cutsheet 210709

Workstation, Documentation

AE #: WODO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
8	Midmark Corporation	6215		Floor	OF/VI	Project

Mobile workstation with height adjustable from 23" to 49". Two 4" locking casters in front. Base dimensions 20.5"W x 19.5"D. Weight limit 20 lbs. View Cutsheet 210659

Select finish when ordering.

W x D x H: 26 x 21 x 49 in.

Room: Reception **Department: Physical Therapy**

Room #: A307A1

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Clean Supplies **Department: Physical Therapy**

Room #: A307A2

Cane — AE #: CANE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081561828		Rack	OF/OI	Project

Standard size. Supports up to 500 lbs

View Cutsheet 211395

Cane — AE #: CANE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081561836		Rack	OF/OI	Project

Size tall. Supports up to 500lbs

View Cutsheet 211396

Crutches — AE #: CRUT-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	7100181		Rack	OF/OI	Project

ADULT SIZE CRUTCHES. ADJUSTABLE HEIGHT FROM 45 TO 53 INCHES.

View Cutsheet 200178

Crutches — AE #: CRUT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	7100182		Rack	OF/OI	Project

YOUTH SIZE CRUTCHES. HEIGHT ADJUSTABLE FROM 37 TO 45 INCHES.

View Cutsheet 200180

Crutches — AE #: CRUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	7100180		Rack	OF/OI	Project

TALL SIZE CRUTCHES. HEIGHT ADJUSTABLE FROM 53-61 INCHES.

View Cutsheet 200179

Crutches, Bariatric — AE #: CRUT-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081160498	562103	Rack	OF/OI	Project

Adult Tall Heavy Duty Steel Crutches, 55"-63", supports up to 550lbs

View Cutsheet 211393

Room: Clean Supplies **Department: Physical Therapy**

Room #: A307A2

Crutches, Forearm — AE #: CRFO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081561802		Rack	OF/OI	Project

size: adult

View Cutsheet 211394

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility

View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Clean Supplies **Department: Physical Therapy**

Room #: A307A2

Rack, Crutch — AE #: RACR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sammons Preston / Patterson	081186501		Wall	OF/CI	Project

Wall mounted storage rack for storing up to 12 canes, crutches and/or walkers. Designed to hold up to 30 lbs of weight. The rack comes with 2 bases each 33"L x 5.25"H to provide a combined 66" of storage space. Hangers extend 16.5" from the wall. View Cutsheet 207964

W x D x H: 66 x 16.5 x 5.25 in.

Walker, Bariatric — AE #: WABA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081561653		Floor	OF/OI	Project

BARIATRIC WALKER WITH DOUBLE 5 INCH WHEELS. VINYL CONTOURED HAND GRIPS. ALUMINUM FRAME SUPPORTS UP TO 700 LBS. View Cutsheet 200171

Walker with double 5" wheels

W x D x H: 20 x 24 x 43 in.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Alcove, Equipment

Department: Physical Therapy

Room #: A307A3

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Cold / Hot Pack, Reusable

AE #: CHPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Performance Health	081017771	3548B	Freezer	OF/OI	Project

Conforming cryotherapy cold pack, quarter size 5.5" x 6.5", blue View Cutsheet 167069

Cold / Hot Pack, Reusable

AE #: CHPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sammons Preston / Patterson	3548A		Freezer	OF/OI	Project

Soft pliable cold pack half size 7.5" x 11". Remains cold for up to 30 minutes. Latex free. View Cutsheet 100392

W x D x H: 7.5 x 11 x N/A in.

Cold / Hot Pack, Reusable

AE #: CHPR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sammons Preston / Patterson	3547		Freezer	OF/OI	Project

Soft pliable cold pack neck contour 23" long. Remains cold for up to 30 minutes. Latex free. View Cutsheet 100393

W x D x H: 23 x N/A x N/A in.

Freezer, Undercounter

AE #: FRUN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Summit Appliance Div / Felix Storch	FS24L		Undercounter	OF/OI	Project

Compact all-freezer with temp range up -20 degrees celsius. 1.4 cu. Ft. With manual defrost, removable wire shelf, seamless interior liner, interior dial thermostat, factory installed lock and reversible door. Flat door liner designed to comply with cdc guidelines. View Cutsheet 165552

W x D x H: 18.5 x 17.8 x 20 in.
Electrical: 115V 60Hz 0.8A 92W

Room: Alcove, Equipment **Department:** Physical Therapy

Room #: A307A3

Ice Maker

AE #: ICMA-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-SI		Stand	OF/CI	Project

Ice-only dispenser automatic load in countertop configuration, with 12 lb (5.4 kg) of storage. 24 hour production capacity of approximately 425 lb (193.0 kg) of Chewblet compressed nugget ice at water temp. of 70 F (21 C); air temp. of 50 F (10 C). Equipped with automatic self-flushing and Quiet Night sleep mode. Automatic bin level control to start and stop ice machine. NSF and ETL listed.

View Cutsheet 208923

For ice packs, no water dispenser

W x D x H: 16.1 x 23.5 x 32.5 in.
Clearance: Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase
Weight: 144 lbs.
Elect Notes: 8.5' cord w/NEMA 5-15P 90 degree hospital grade plug
Plumb Notes: Potable water inlet 3/8" FPT; Drain 3/4" MPT. Water temperature 45-90 degrees F. Water pressure 10-70 psi.
HVAC Notes: Air cooled; heat rejection 5000 BTU/hr
Struct Notes: Refrigerant R404a

Ice Maker / Water Dispenser, Component

AE #: ICMW-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12BASE-CL		Floor	OF/CI	Project

Stainless steel base stand for ice maker/water dispenser model 12CI425A. Includes stainless legs with adjustable flanged feet and high capacity carbonless filter (3,000 gallons). Pre-plumbed and ready for external connections.

View Cutsheet 208924

W x D x H: 17.5 x 22 x 33 in.
Weight: 80 lbs.

Rack, Dunnage

AE #: RADU-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	New Age Industrial	2029		Floor	OF/OI	Project

Heavy-duty, aluminum construction; open design for air circulation and reduces dust buildup; 3,200 lb. Weight capacity.

View Cutsheet 168115

For raising up freezer under the counter.

W x D x H: 24 x 18 x 12 in.
Weight: 7.2 lbs.

Room: Soiled Hold

Department: Physical Therapy

Room #: A307B

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Treat

Department: Physical Therapy

Room #: A307C, A307D

Allowance, Positioning Device

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cabinet	OF/OI	Project

Positioning device allowance. No Cutsheet 75402

Allowance for bolsters, wedges, etc.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock w/autolocking feature

W x D x H: 27 x 18 x 33 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treat

Department: Physical Therapy

Room #: A307C, A307D

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Electro-Acupuncture Device

AE #: ELAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lhasa OMS, Inc.	ITO ES-160	ITO.ES.160	Desk	OF/OI	Project

6-channel electro-acupuncture device from Japan provides 8 stimulation modes. View Cutsheet 210702

W x D x H: 9.4 x 6.8 x 2 in.

Weight: 1.23 lbs.

Elect Notes: Powered by (4) standard 1.5 V C Batteries

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Stool, Without Back

AE #: STNB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Armedica Mfg Corp	AM-844		Floor	OF/OI	Project

Mobile stool with square 14" seat and four 2.5" casters. Seat height 18". Welded steel frame. Weight capacity 225 lb. View Cutsheet 167099

W x D x H: 16 x 16 x 18 in.

Room: Treat **Department: Physical Therapy**

Room #: A307C, A307D

Table, Treatment, Hi/Lo — AE #: TATH-98

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	7023133		Floor	OF/VI	Project

Pivotal Health Solutions Essential Thera-P Bobath 5-section electric treatment table with 2" high density foam; height adjustable with foot pedal 17"-35". View Cutsheet 210516

ADA compliant. Lifting capacity 500 lbs.

W x D x H: 40 x 77 x 35 in.
Electrical: 115V 60Hz **Weight:** 350 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Therapy Workroom **Department: Physical Therapy**

Room #: A307E

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Office

Department: Physical Therapy

Room #: A307J

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Height / Weight **Department:** Spine

Room #: A301A1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

See accessory for stadiometer

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Height Gauge		1	1

Room: Intake **Department:** Spine

Room #: A301A, A301B, A301C, A301D

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Electrical: 120V 60Hz
Struct Notes: Wall mount: wall channel is 19"h. Basket is 12.75"w x 7.75"d x 5.9"h. Pivot arm is 8"d.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component — AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Intake **Department:** Spine

Room #: A301A, A301B, A301C, A301D

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug. View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz **Weight:** 61 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stadiometer		1	1

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Intake

Department: Spine

Room #: A301A, A301B, A301C, A301D

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: On-Stage Team Work **Department:** Spine

Room #: A301J, B301H, A310G, A310H

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam **Department: Spine**

Room #: A301K, A301L, A301M, A301N, A301P, B301G, B301J, B301L, B301M, A302G, A302H, A302J, A302K, A302L, A302M, A302N, A302P, A310A, A310B, A310C, A310D, A310E, A310F

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam **Department:** Spine

Room #: A301K, A301L, A301M, A301N, A301P, B301G, B301J, B301L, B301M, A302G, A302H, A302J, A302K, A302L, A302M, A302N, A302P, A310A, A310B, A310C, A310D, A310E, A310F

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hook, Multipurpose — AE #: HOOK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	TBD		Wall	CF/CI	Project

Hook for holding spine model. To have minimum 25 lbs. weight capacity. To be specified, provided, and installed by contractor. No Cutsheet 211274

Model, Anatomy — AE #: MOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Universal Medical	Highly Flexible Spine Model	A59-1	Wall	OF/OI	Project

Specially mounted on flexible core. Complete pelvis and occipital plate. Full flexible mounting. L3-L4 disc prolapsed. Spinal nerve exits. Cervical vertebral artery. Male pelvis. Stand sold separately. View Cutsheet 207361

W x D x H: 29.1 x N/A x N/A in.

Weight: 4.3 lbs.

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Room: Exam **Department:** Spine

Room #: A301K, A301L, A301M, A301N, A301P, B301G, B301J, B301L, B301M, A302G, A302H, A302J, A302K, A302L, A302M, A302N, A302P, A310A, A310B, A310C, A310D, A310E, A310F

Table, Exam, Power

AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.***

View Cutsheet 209180

W x D x H: 32 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Equipment **Department:** Spine

Room #: A301P1

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

To be used for pre-op screenings.

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	2

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Equipment
Room #: A301P1

Department: Spine

Ophthalmoscope/ Otoscope

AE #: OPOT-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710-71M/7670-12/713263		Floor Stand	OF/OI	Project

Ophthalmoscope/otoscope on mobile stand. Configuration includes: 77710 - green series wall transformer, 11720 - coaxial ophthalmoscope, 23810 - diagnostic macroview otoscope, 7670-12 - mobile stand with basket and 713263 - domestic power adapter.

View Cutsheet 123343

W x D x H: 21 x 21 x 43 in.
Electrical: 120V 60Hz 0.3A

Scanner, Bladder

AE #: SCBL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Verathon Inc. - Medical	i10	0270-1014	Stand	OF/VI	Project

Bladder scanner i10 system; on rolling stand.

View Cutsheet 200466

Electrical: 120V 60Hz 1.4A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand	0800-0631	1	1

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Room: Equipment **Department:** Spine

Room #: A301P1

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Alcove, Equipment

Department: Spine

Room #: A302P1

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

W x D x H: 27 x 18 x 33 in.

Room: Wellness

Department: Spine

Room #: A306B, A306D, A306E

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Wellness **Department:** Spine

Room #: A306B, A306D, A306E

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Office **Department:** Spine

Room #: A307K, A307L, A307M, A307N, A307P, A307Q, A308A, A308B

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Meeting Workroom **Department: Spine**

Room #: A307R

Room Notes: To be shared by 3rd floor departments

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle, Recycling Combination — AE #: WARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Max-R	P-RO-STT10D		Floor	OF/OI	Project

10-gallon Top Load Waste & Recycling Bins. View Cutsheet 209397

W x D x H: 28 x 15 x 30 in.

Room: Faculty Work

Department: Spine

Room #: A308C

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage Work Space **Department:** Spine

Room #: A308C1

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder Disperse evenly throughout Off-Stage work area

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

1 in each 6-person pod on north end of building

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
8	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

Disperse evenly throughout open Off-Stage work area

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Staff)

Department: Spine

Room #: A308J, A309F

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Corridor

Department: Spine

Room #: A309

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

To be placed in the middle of the floor

W x D x H: 20.5 x 16 x 36 in.

Room: Clean Supplies **Department: Spine**

Room #: A309B

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67 AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Room: Clean Supplies **Department:** Spine

Room #: A309B

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Room: Clean Supplies **Department:** Spine

Room #: A309B

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Hold **Department:** Spine

Room #: A309C

Bin, Biohazard Waste — AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Soiled Linen — AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.*** View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Sharps — AE #: COSH-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004LR		Floor	OF/OI	Supply Agreement

8-gallon red bin (19.7”h x 13.0”d x 11.3 “w) for biohazard waste with wire step-on dolly. View Cutsheet 164306

W x D x H: 14.3 x 16.5 x 23 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Hold **Department:** Spine

Room #: A309C

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube — AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult **Department:** Spine

Room #: B301C, A304A, A304B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Toilet (Patient)

Department: Spine

Room #: B301E, B301K

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Spine

Room #: B301E, B301K

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Equipment

Department: Spine

Room #: B301M1

Room Notes: No MEQ currently assigned to this space.

Room: Private Phone / Huddle

Department: Spine

Room #: B307B, A308K, A309D

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Reception

Department: Administration

Room #: A406A

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Waiting

Department: Administration

Room #: A406A1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle, Recycle Bin

AE #: WARB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Global Industrial	35 Gal	T9F641439RBL	Cabinet	OF/OI	Project

35-gallon, square plastic recycle container.

View Cutsheet 210122

To go in built-in waste/recycling counter-cabinets

W x D x H: 19.5 x 19.5 x 27.8 in.

Weight: 9 lbs.

Room: Nourishment **Department:** Administration

Room #: A406A3

Coffee Brewer — AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Refrigerator, Drawer — AE #: REDR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	True Food Service Equipment	TURADA-24-D-A~O		Undercounter	OF/CI	Project

Overlay panel-ready ADA-height undercounter refrigerator with 2 drawers. Capacity 5 cu. ft. Maintains 33-41 degree F temperature. Concealed digital temperature controls. View Cutsheet 211277

Custom panels purchased separately.

W x D x H: 23.9 x 23.1 x 31.9 in. **Clearance:** Front 21 in.
Electrical: 115V 60Hz 0.8A 1-Phase **Weight:** 190 lbs.
Elect Notes: Power cord 10' long. NEMA-5-15 plug.
HVAC Notes: Energy Star rated. Refrigerant R600a. Annual energy consumption (kWh): 273.
Struct Notes: Cutout dimensions: 24"W x 24"D x 32"H

Refrigerator, Undercounter, Component — AE #: REUC-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	ZZZ - To Be Determined	Refrigerator Drawer Panel		Refrigerator	OF/CI	Project

Panel for True ADA-height undercounter two drawer panel-ready refrigerator (model . Two panels needed for refrigerator. Panel dimensions: 23-11/16"W x 0.75"D x 13-27/32"H. View Cutsheet 211278

Confirm panel color / finish with design team prior to purchase.

W x D x H: 23.7 x 0.75 x 13.8 in.

Room: Nourishment

Department: Administration

Room #: A406A3

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Workstations **Department:** Administration

Room #: A406B

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Office, Mngr

Department: Administration

Room #: A406C, A406D, A406E, A406F, A406G, A407J, A407K, A407L, A407M, A407N, A407P

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Workstations **Department:** Administration

Room #: A406H

Room Notes: Space for 21 workstations

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
21	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
21	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Toilet (Staff)

Department: Administration

Room #: A406J1, A406J3

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Storage

Department: Administration

Room #: A406J2

Room Notes: Assumes no medical equipment required for this area. Built-in shelving: Millwork vs Furniture

Room: Office, CMO

Department: Administration

Room #: A407A

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Work / Copy

Department: Administration

Room #: A407B

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. One dispenser needed by each door.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office, Faculty Director

Department: Administration

Room #: A407C

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Office, Director

Department: Administration

Room #: A407D, A407E

Room Notes: Assoc. Dir. Admin., Amb OP.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Conference Room

Department: Administration

Room #: A407F

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Office, Deputy Director

Department: Administration

Room #: A407G

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Kitchen **Department:** Administration

Room #: A407H

Coffee Brewer — AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately. View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Kitchen **Department:** Administration

Room #: A407H

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Kitchen **Department:** Administration

Room #: A407H

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers — No Cutsheet 141809

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required — View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Refrigerator Freezer, Upright — AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant. — View Cutsheet 208926

Left hinge preferred if available in Energy Star model. Otherwise, right hinge is OK.

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. — View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Kitchen

Department: Administration

Room #: A407H

Waste Receptacle, Recycling w/ Lid/Sign

AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: LL Office, Chair

Department: Administration

Room #: B002A

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: LL Reception, Faculty

Department: Administration

Room #: B002B, B002C

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: LL Office, Faculty **Department: Administration**

Room #: B002D, B002E, B002F, B002G, B002H, B002J, B002K, B002L, B002M, B002N, B002P, B002Q, B002R, B002S, B002T, B002U

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: LL Admin Faculty **Department:** Administration

Room #: B002V

Room Notes: 2 workstations

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Equipment Storage A **Department:** Apheresis

Room #: A502S

Room Notes: Located in and shared with Infusion. Apheresis has it's own designated equipment in pink.

Cart, Supply

AE #: CASU-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Super erecta model with chrome finish to include (3) wire shelves, (1) solid bottom shelf, (2) braking casters, (2) swivel casters, and (4) 63" posts View Cutsheet 160459

W x D x H: 48 x 24 x 68 in.

Commode

AE #: COMM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Guardian / Medline	G1-200LX4		Floor	OF/OI	Project

Three In One Elongated Steel Folding Bedside Commode is designed to provide assistance with toileting needs. It features a folding frame design that assembles in seconds without tools. It has an elongated seat for added maneuverability and comfort. Wt capacity: 350lb. View Cutsheet 209395

W x D x H: 22 x 18 x N/A in.

Weight: 56 lbs.

Commode, Bariatric

AE #: COBA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	G1-201LBX1		Floor	OF/OI	Project

Bariatric steel commode. Comes with pail, lid, splash guard, and solid seat. 650 lb. weight capacity, 17"-20.5" adjustable seat height, 18.5" seat depth, 24" wide between arms, 29.5" wide overall. View Cutsheet 209396

W x D x H: 29.5 x 27 x N/A in.

Room: Equipment Storage A **Department:** Apheresis

Room #: A502S

Room Notes: Located in and shared with Infusion. Apheresis has it's own designated equipment in pink.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Photopheresis Machine

AE #: PHMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Therakos	CELLEX		Floor	OF/VI	Project

Integrated, closed photophoresis system for cell collection, photoactivation and reinfusion. Allows for single-operator management of treatment. Touch screen operator interface. View Cutsheet 127222

W x D x H: 23 x 31 x 84 in.
Clearance: Rear 10 in.; Left 10 in.; Right 10 in.; Front 10 in.
Electrical: 120V 60Hz
Weight: 341 lbs.
Struct Notes: 10" clearance on all sides is manufacturer recommended operating space.

Room: Equipment Storage A **Department:** Apheresis

Room #: A502S

Room Notes: Located in and shared with Infusion. Apheresis has it's own designated equipment in pink.

Sphygmomanometer, Aneroid, Handheld — AE #: SPAH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Platinum Series DS58		Cabinet	OF/OI	Project

With gear-free DuraShock technology, you can count on the DS58 aneroid to remain in calibration longer than traditional aneroids, providing more accurate readings over time and a lower lifetime cost, helping to improve practice efficiencies and your bottom line.

Handheld preferred/confirmed.

View Cutsheet 209186

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Cabinet	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: Equipment Storage A **Department:** Apheresis

Room #: A502S

Room Notes: Located in and shared with Infusion. Apheresis has it's own designated equipment in pink.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Cabinet	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Cabinet	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Vein Illuminator

AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz. View Cutsheet 168583

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A
Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	1

Room: Corridor

Department: Apheresis

Room #: A509

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Patient Room **Department:** Apheresis

Room #: A509A, A509B, A509C, A509D, A509F, A509H

Bed, Electric — AE #: BEEL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	S3 EX	3005S3EX	Floor	OF/VI	Project

Med / surg bed. Siderails designed with one-hand operation and an intermediate position for patient assistance during bed entry and exit. Open architecture platform. Centrally located brake pedal. 500 lb weight capacity. Capable of linking to hospital network via wireless or wired connection. View Cutsheet 149049

W x D x H: 41.5 x 93 x 30 in.
Network: Networked
Electrical: 120V 60Hz 8A

Bed, Electric, Component — AE #: BEEC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	AIR PUMP	2861000025	Bed	OF/VI	Project

Air pump for use with isoflex lal 2860 surface View Cutsheet 165842

W x D x H: 8 x 5 x 8.5 in.
Electrical: 120V 60Hz 0.25A **Weight:** 5.5 lbs.

Bracket, Sharps Container — AE #: BRSC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	FL584		Cart	OF/VI	Project

Sharps container bracket for Flexline and Starsys overbridge systems. Sharps containers sold separately. Bracket also mounts to universal clamp in addition to overbridge hanger rail. View Cutsheet 209427

W x D x H: 9.12 x 6.75 x 8 in.

Cart, Procedure — AE #: CAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

Polymer cart on caster; with (1) 3", (3) 6" and (1) 9" drawer; Electronic PIN locking; Pull handles. View Cutsheet 200197

Drawer configuration to be determined by dept. Include automatic locking mechanism

W x D x H: 22.7 x 24.9 x 44.7 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad-includes auto locking	SXRX412	1	1

Room: Patient Room

Department: Apheresis

Room #: A509A, A509B, A509C, A509D, A509F, A509H

Container, Sharps

AE #: COSH-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203		Cart	OF/OI	Service Agreement

Red 3-gallon sharps container with vertical drop lid

View Cutsheet 211070

Mount to Starsys Cart with Bracket FL584

W x D x H: 12.5 x 4.7 x 21.1 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Patient Room

Department: Apheresis

Room #: A509A, A509B, A509C, A509D, A509F, A509H

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Patient Room **Department:** Apheresis

Room #: A509A, A509B, A509C, A509D, A509F, A509H

Monitor, Accessory Basket — AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Room: Patient Room **Department:** Apheresis

Room #: A509A, A509B, A509C, A509D, A509F, A509H

Pheresis System

AE #: PHSY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Terumo BCT / Cobe BCT	OPTIA		Floor	OF/VI	Project

Removes targeted blood components via optical detection system. View Cutsheet 146475

W x D x H: 20.8 x 32 x 68.5 in. **Clearance:** Rear 11.8 in.; Left 11.8 in.; Right 11.8 in.; Front 11.8 in.
Electrical: 120V 60Hz **Weight:** 220 lbs.

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Patient Room **Department:** Apheresis

Room #: A509A, A509B, A509C, A509D, A509F, A509H

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Patient Room **Department:** Apheresis

Room #: A509A, A509B, A509C, A509D, A509F, A509H

Stool, With Back

AE #: STWB-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	425		Floor	OF/VI	Project

Air lift stool, hand operated, contoured seat, with back rest. Wt capacity: 225 lbs. Height adjustable 17.5" - 24.5", with back rest: 25" - 31.5" View Cutsheet 209428

Model preferred by users in DD2

W x D x H: 23 x 23 x 31.5 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1). View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Warmer, Blood/ Fluid

AE #: WABF-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gentherm	Astotherm plus	AP220NA	Cart	OF/OI	Project

Warmer for blood, IV fluids, and irrigation fluids. View Cutsheet 209704

Mounts on the apheresis machine. Model confirmed by Jennie Lamb via email 12/19/2023.

W x D x H: 5.31 x 11.6 x 5.71 in.

Electrical: 115V 60Hz 450W **Weight:** 6.39 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area **Department:** Apheresis

Room #: A509E

Room Notes: Assumes space for 6-8 people. No glucometer in Apheresis per staff.

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: On-Stage Team Work Area **Department:** Apheresis

Room #: A509E

Room Notes: Assumes space for 6-8 people. No glucometer in Apheresis per staff.

Ice Maker / Water Dispenser — AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Hold **Department:** Apheresis

Room #: A509E1

Room Notes: Shared with Precision Med, hold space for hopper. Soiled linen cart for shared linen disposal.

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Soiled Hold **Department:** Apheresis

Room #: A509E1

Room Notes: Shared with Precision Med, hold space for hopper. Soiled linen cart for shared linen disposal.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Truck, Cube — AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Room: Soiled Hold **Department:** Apheresis

Room #: A509E1

Room Notes: Shared with Precision Med, hold space for hopper. Soiled linen cart for shared linen disposal.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supply / Linen / Meds **Department:** Apheresis

Room #: A509G

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.
Weight: 6 lbs.

Room: Clean Supply / Linen / Meds

Department: Apheresis

Room #: A509G

Cart, Linen

AE #: CALI-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAXI		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 36" x 24". Two solid (mx2436f) and two grid shelves (mx2436g); on 5" casters - one set swivel (5mdxa) and one set braking (5mdbxa); side and back enclosure panels (mep57e & mep37e); to include blue coated cover with velcro closures (24x36x74vcmb). View Cutsheet 167067

Department requested smaller linen cart.

W x D x H: 36 x 24 x 80.1 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Clean Supply / Linen / Meds

Department: Apheresis

Room #: A509G

Drug Dispensing Unit

AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit

View Cutsheet 150404

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A

Drug Dispensing Unit, Auxiliary

AE #: DDUA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES HALF HEIGHT COLUMN		Floor	OF/VI	Lease

Half height column auxiliary

View Cutsheet 158539

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 31 x 28 x 43 in.
Electrical: 120V 60Hz 0.9A

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Network: Wired

Room: Clean Supply / Linen / Meds **Department:** Apheresis

Room #: A509G

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient)

Department: Apheresis

Room #: A509J

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Apheresis

Room #: A509J

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Reception **Department:** Infusion

Room #: A500W1

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight **Department:** Infusion

Room #: A501A1

Room Notes: Located near entry and Vitals / Triage rooms

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

See accessory for stadiometer

W x D x H: 35 x 30 x N/A in.

Electrical: 120V 60Hz 15W **Weight:** 107 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Height Gauge		1	1

Room: Alcove, Height / Weight **Department:** Infusion

Room #: A501A1

Room Notes: Located near entry and Vitals / Triage rooms

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Infusion Bay **Department: Infusion**

Room #: A501B, A501C, A501D, A501E, A501H, A501K, A502N, A502Q, A503L, A503M, A504A, A504B, A504C, A504D, A504F, A504G, A504H, A505C, A505E, A505J, A505K, A505L, A505M, A505S, A505T, A506A, A506C, A507B, A507C, A507D, A507F, A507G, A507H, A507K, A507N, A507Q, A508B, A508C, A508E, A508G, A508H, A508J, A508K, A508L, A508M, A508N, A508P, A508Q

Room Notes: Assumes recliner, furnished by Furniture

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Room: Infusion Bay **Department: Infusion**

Room #: A501B, A501C, A501D, A501E, A501H, A501K, A502N, A502Q, A503L, A503M, A504A, A504B, A504C, A504D, A504F, A504G, A504H, A505C, A505E, A505J, A505K, A505L, A505M, A505S, A505T, A506A, A506C, A507B, A507C, A507D, A507F, A507G, A507H, A507K, A507N, A507Q, A508B, A508C, A508E, A508G, A508H, A508J, A508K, A508L, A508M, A508N, A508P, A508Q

Room Notes: Assumes recliner, furnished by Furniture

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

Glove box holders are NOT in cabinet in these open infusion bays.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Accessory Basket — AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Infusion Bay **Department: Infusion**

Room #: A501B, A501C, A501D, A501E, A501H, A501K, A502N, A502Q, A503L, A503M, A504A, A504B, A504C, A504D, A504F, A504G, A504H, A505C, A505E, A505J, A505K, A505L, A505M, A505S, A505T, A506A, A506C, A507B, A507C, A507D, A507F, A507G, A507H, A507K, A507N, A507Q, A508B, A508C, A508E, A508G, A508H, A508J, A508K, A508L, A508M, A508N, A508P, A508Q

Room Notes: Assumes recliner, furnished by Furniture

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Pump, I.V. — AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Room: Infusion Bay **Department:** Infusion

Room #: A501B, A501C, A501D, A501E, A501H, A501K, A502N, A502Q, A503L, A503M, A504A, A504B, A504C, A504D, A504F, A504G, A504H, A505C, A505E, A505J, A505K, A505L, A505M, A505S, A505T, A506A, A506C, A507B, A507C, A507D, A507F, A507G, A507H, A507K, A507N, A507Q, A508B, A508C, A508E, A508G, A508H, A508J, A508K, A508L, A508M, A508N, A508P, A508Q

Room Notes: Assumes recliner, furnished by Furniture

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Infusion Bay **Department: Infusion**

Room #: A501B, A501C, A501D, A501E, A501H, A501K, A502N, A502Q, A503L, A503M, A504A, A504B, A504C, A504D, A504F, A504G, A504H, A505C, A505E, A505J, A505K, A505L, A505M, A505S, A505T, A506A, A506C, A507B, A507C, A507D, A507F, A507G, A507H, A507K, A507N, A507Q, A508B, A508C, A508E, A508G, A508H, A508J, A508K, A508L, A508M, A508N, A508P, A508Q

Room Notes: Assumes recliner, furnished by Furniture

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: Infusion Bay **Department: Infusion**

Room #: A501B, A501C, A501D, A501E, A501H, A501K, A502N, A502Q, A503L, A503M, A504A, A504B, A504C, A504D, A504F, A504G, A504H, A505C, A505E, A505J, A505K, A505L, A505M, A505S, A505T, A506A, A506C, A507B, A507C, A507D, A507F, A507G, A507H, A507K, A507N, A507Q, A508B, A508C, A508E, A508G, A508H, A508J, A508K, A508L, A508M, A508N, A508P, A508Q

Room Notes: Assumes recliner, furnished by Furniture

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient) **Department: Infusion**

Room #: A501F, A502J, A502P, A502R, A503N, A505B, A505D, A505P, A507E, A507J, A507L, A507P, A508D, A508F

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient) **Department: Infusion**

Room #: A501F, A502J, A502P, A502R, A503N, A505B, A505D, A505P, A507E, A507J, A507L, A507P, A508D, A508F

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Medication Alcove **Department:** Infusion

Room #: A501G1, A502L1, A504K1, A505V1, A507S1

Container, Sharps

AE #: COSH-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-02RES-0203SB		Countertop	OF/OI	Service Agreement

Two gallon container with vertical drop lid with beige stabiilty base. Does not lock container to base. Mounts to counter or other flat horizontal surface with semi-permanent adhesive strips or screws..

View Cutsheet 162279

W x D x H: 12.5 x 7 x 15.1 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Medication Alcove **Department: Infusion**

Room #: A501G1, A502L1, A504K1, A505V1, A507S1

Drug Dispensing Unit — AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit — View Cutsheet 150404

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A
Elect Notes: Must be located within 6' of the electrical outlet. Fuse: 6.3a. Power and data connections are made to frames at the back right of the computer (53-57" a.f.f.). Power cord length is 15'.
HVAC Notes: 200-600 btu/hr.

Drug Dispensing Unit, Auxiliary — AE #: DDUA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES HALF HEIGHT COLUMN		Floor	OF/VI	Lease

Half height column auxiliary — View Cutsheet 158539

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 31 x 28 x 43 in.
Electrical: 120V 60Hz 0.9A

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. — View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Network: Wired

Room: Medication Alcove **Department:** Infusion

Room #: A501G1, A502L1, A504K1, A505V1, A507S1

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: On-Stage Team Work Area **Department: Infusion**

Room #: A501G, A502L, A504E, A507S

Room Notes: On-Stage work areas/pods and MEQ split between (2) room numbers. All MEQ listed in these room#s

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Cart, Procedure — AE #: CAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Intermetro Industries	Starsys		Floor	OF/VI	Project

Polymer cart on caster; with (1) 3", (3) 6" and (1) 9" drawer; Electronic PIN locking; Pull handles. View Cutsheet 200197

**Drawer configuration to be determined by dept. Include automatic locking mechanism **

W x D x H: 22.7 x 24.9 x 44.7 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Basic Keyless Entry Touchpad-includes auto locking	SXRX412	1	5

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Room: On-Stage Team Work Area **Department: Infusion**

Room #: A501G, A502L, A504E, A507S

Room Notes: On-Stage work areas/pods and MEQ split between (2) room numbers. All MEQ listed in these room#s

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter

View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Ophthalmoscope/ Otoscope

AE #: OPOT-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	71-SM2NDX		Countertop	OF/OI	Project

MacroView Basic Otoscope offers focus-free design and 3x wider viewing area. Coaxial Ophthalmoscope for reduced glare with long lasting LED. Metal power handles with NiCad battery and desktop charging base stand.

View Cutsheet 207767

Electrical: 120V 60Hz

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Infusion Private Room **Department:** Infusion

Room #: A501J, A502M, A503P, A504J, A505A, A505R, A505U, A506D, A507R

Bed, Electric

AE #: BEEL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	S3 EX	3005S3EX	Floor	OF/VI	Project

Med / surg bed. Siderails designed with one-hand operation and an intermediate position for patient assistance during bed entry and exit. Open architecture platform. Centrally located brake pedal. 500 lb weight capacity. Capable of linking to hospital network via wireless or wired connection.

View Cutsheet 149049

W x D x H: 41.5 x 93 x 30 in.
Network: Networked
Electrical: 120V 60Hz 8A

Bed, Electric, Component

AE #: BEEC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	AIR PUMP	2861000025	Bed	OF/VI	Project

Air pump for use with isoflex lal 2860 surface

View Cutsheet 165842

W x D x H: 8 x 5 x 8.5 in.
Electrical: 120V 60Hz 0.25A **Weight:** 5.5 lbs.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: Infusion Private Room **Department:** Infusion

Room #: A501J, A502M, A503P, A504J, A505A, A505R, A505U, A506D, A507R

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Infusion Private Room **Department:** Infusion

Room #: A501J, A502M, A503P, A504J, A505A, A505R, A505U, A506D, A507R

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Monitor, Accessory Basket — AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Infusion Private Room **Department:** Infusion

Room #: A501J, A502M, A503P, A504J, A505A, A505R, A505U, A506D, A507R

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls.

View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning.

View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Room: Infusion Private Room **Department:** Infusion

Room #: A501J, A502M, A503P, A504J, A505A, A505R, A505U, A506D, A507R

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Infusion Private Room **Department:** Infusion

Room #: A501J, A502M, A503P, A504J, A505A, A505R, A505U, A506D, A507R

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet View Cutsheet 211777

Holder (1), Hanging Shelf (1).

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Room: Infusion Private Room

Department: Infusion

Room #: A501J, A502M, A503P, A504J, A505A, A505R, A505U, A506D, A507R

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Vitals / Triage Room **Department:** Infusion

Room #: A502A, A502B, A502C, A507M

Room Notes: Assumes recliner by furniture

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Vitals / Triage Room

Department: Infusion

Room #: A502A, A502B, A502C, A507M

Room Notes: Assumes recliner by furniture

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Room: Vitals / Triage Room **Department:** Infusion

Room #: A502A, A502B, A502C, A507M

Room Notes: Assumes recliner by furniture

Monitor, Accessory Basket — AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz
Struct Notes: Wall mount: wall channel is 19"h. Basket is 12.75"w x 7.75"d x 5.9"h. Pivot arm is 8"d.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: Vitals / Triage Room **Department:** Infusion

Room #: A502A, A502B, A502C, A507M

Room Notes: Assumes recliner by furniture

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Vitals / Triage Room **Department:** Infusion

Room #: A502A, A502B, A502C, A507M

Room Notes: Assumes recliner by furniture

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office, Private

Department: Infusion

Room #: A502E, A503A, A505G, A505H

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Infusion Private Room / Apheresis Flex **Department:** Infusion

Room #: A502F, A502H, A502K

Room Notes: Same MEQ as infusion private room, but can flex as Apheresis

Bed, Electric

AE #: BEEL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	S3 EX	3005S3EX	Floor	OF/VI	Project

Med / surg bed. Siderails designed with one-hand operation and an intermediate position for patient assistance during bed entry and exit. Open architecture platform. Centrally located brake pedal. 500 lb weight capacity. Capable of linking to hospital network via wireless or wired connection.

View Cutsheet 149049

W x D x H: 41.5 x 93 x 30 in.
Network: Networked
Electrical: 120V 60Hz 8A

Bed, Electric, Component

AE #: BEEC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	AIR PUMP	2861000025	Bed	OF/VI	Project

Air pump for use with isoflex lal 2860 surface

View Cutsheet 165842

W x D x H: 8 x 5 x 8.5 in.
Electrical: 120V 60Hz 0.25A **Weight:** 5.5 lbs.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: Infusion Private Room / Apheresis Flex **Department:** Infusion

Room #: A502F, A502H, A502K

Room Notes: Same MEQ as infusion private room, but can flex as Apheresis

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Infusion Private Room / Apheresis Flex **Department: Infusion**

Room #: A502F, A502H, A502K

Room Notes: Same MEQ as infusion private room, but can flex as Apheresis

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Monitor, Accessory Basket — AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Infusion Private Room / Apheresis Flex **Department:** Infusion

Room #: A502F, A502H, A502K

Room Notes: Same MEQ as infusion private room, but can flex as Apheresis

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Pump, I.V. — AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Room: Infusion Private Room / Apheresis Flex **Department:** Infusion

Room #: A502F, A502H, A502K

Room Notes: Same MEQ as infusion private room, but can flex as Apheresis

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Infusion Private Room / Apheresis Flex **Department:** Infusion

Room #: A502F, A502H, A502K

Room Notes: Same MEQ as infusion private room, but can flex as Apheresis

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet View Cutsheet 211777

Holder (1), Hanging Shelf (1).

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Room: Infusion Private Room / Apheresis Flex

Department: Infusion

Room #: A502F, A502H, A502K

Room Notes: Same MEQ as infusion private room, but can flex as Apheresis

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Hold **Department:** Infusion

Room #: A502G, A503J, A505F, A505N, A506H1

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Hold **Department:** Infusion

Room #: A502G, A503J, A505F, A505N, A506H1

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Crash Cart **Department:** Infusion

Room #: A502L2

Room Notes: One crash cart approved by leadership.

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Alcove, Crash Cart **Department:** Infusion

Room #: A502L2

Room Notes: One crash cart approved by leadership.

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Equipment Storage A **Department:** Infusion

Room #: A502S1

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Equipment Storage A **Department:** Infusion

Room #: A502S1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.

Network: Wireless

Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Equipment Storage A **Department:** Infusion

Room #: A502S1

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff.

View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: Equipment Storage A **Department:** Infusion

Room #: A502S1

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Vein Illuminator

AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz. View Cutsheet 168583

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	1

Room: Toilet (Staff)

Department: Infusion

Room #: A503B, A503C, A503D

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Private Phone / Respite

Department: Infusion

Room #: A503E, A503G

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Off-Stage, Team Work Area

Department: Infusion

Room #: A503F

Room Notes: Assumes space for 16 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Nourishment (Ref) **Department:** Infusion

Room #: A503G1

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Refrigerator, Upright

AE #: REUP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Whirlpool Corp.	WSR57R18DM		Floor	OF/OI	Project

All refrigerator with 18 cu ft capacity. Stainless steel. Adjustable door bins, one fixed shelf and 4 slide out shelves. Frost-free. Door right hinge and is not reversible. View Cutsheet 156613

W x D x H: 30.3 x 31.3 x 66.8 in. **Clearance:** Rear 1 in.; Left 0.25 in.; Right 3 in.; Front 24.5 in.
Electrical: 115V 60Hz **Weight:** 198 lbs.
Elect Notes: Energy star qualified. 15- or 20-amp fused, grounded electrical supply is required. Separate circuit recommended.

Room: Clean Supply (A) **Department: Infusion**

Room #: A503K

Room Notes: With Haemobank

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67 AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Room: Clean Supply (A) **Department:** Infusion

Room #: A503K

Room Notes: With Haemobank

Dispensing Unit, Blood Bank — AE #: DUBB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Haemonetics Corp.	HAEMOBANK 20		Countertop	OF/VI	Project

Dispensing system features refrigerator, workstation kiosk and printer; undercounter model includes 20 secure access compartments; add-on configuration includes hardware and allowance for configuration software and services **annual software support not included**

View Cutsheet 161501

For Platelets. Wireless temperature monitoring is built into the Haemobank equipment. No additional temperature monitoring needed.

W x D x H: 30.3 x 31.3 x 35 in.
Clearance: Rear 2 in.; Left 2 in.; Right 2 in.
Network: Wired
Electrical: 120V 60Hz 7A
Weight: 425 lbs.
Struct Notes: Allow 2" depth clearance for connections if power & data are located behind unit

Dispensing Unit, Blood Bank, Component — AE #: DBBC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Haemonetics Corp.	BLOODTRACK V5 KIOSK		Wall	OF/CI/VI	Project

Kiosk workstation interfaces with bloodtrack system network and dispensing refrigerator; standard configuration: wall mount; desktop or vesa mounting brackets are optional

View Cutsheet 161502

W x D x H: 12.6 x 7.8 x 11.6 in.
Network: Wired
Electrical: 120V 60Hz 35W

Dispensing Unit, Blood Bank, Component — AE #: DBBC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Haemonetics Corp.	CG408		Countertop	OF/VI	Project

Printer supports haemobank bloodtrack system; connects to kiosk workstation; <<requires countertop or shelf for support>>

View Cutsheet 161503

W x D x H: 7.04 x 9.37 x 6.81 in.
Network Notes: Usb connection to kiosk component
Electrical: 120V 60Hz 3A

Room: Clean Supply (A) **Department:** Infusion

Room #: A503K

Room Notes: With Haemobank

Ophthalmoscope/ Otoscope

AE #: OPOT-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710-71M/7670-12/713263		Floor Stand	OF/OI	Project

Ophthalmoscope/otoscope on mobile stand. Configuration includes: 77710 - green series wall transformer, 11720 - coaxial ophthalmoscope, 23810 - diagnostic macroview otoscope, 7670-12 - mobile stand with basket and 713263 - domestic power adapter.

View Cutsheet 123343

W x D x H: 21 x 21 x 43 in.
Electrical: 120V 60Hz 0.3A

Refrigerator, Blood Bank, Component

AE #: RBBC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Haemonetics Corp.	HAEMOBANK consumable cart		Floor	OF/VI	Project

Consumable cart. Two adjustable shelves. One trash compartment.

View Cutsheet 171375

W x D x H: 14.2 x 21.6 x 27.8 in.
Weight: 63 lbs.

Refrigerator, Blood Bank, Component

AE #: RBBC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Haemonetics Corp.	HAEMOBANK access console		Cart	OF/VI	Project

Access console with 10.5" color LCD touchscreen.

View Cutsheet 171373

W x D x H: 14 x 23.6 x 51.5 in.
Clearance: Rear 1.25 in.; Top 8 in.
Network: Wired
Network Notes: (1) rs232, (1) usb port, (2) ethernet ports
Electrical: 115V 60Hz 4A
Weight: 108 lbs.

Room: Clean Supply (A) **Department:** Infusion

Room #: A503K

Room Notes: With Haemobank

Refrigerator, Blood Bank, Single Door

AE #: REBS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Haemonetics Corp.	HAEMOBANK		Floor	OF/VI	Project

80 tray capacity blood bank refrigerator. 7" lcd touchscreen interface. Storage of blood products or other medical and scientific products. Temperature range of 2 c to 10 c. Standard, swivel locking casters.

View Cutsheet 171372

Includes software, implementation services, and variable services. Wireless temperature monitoring is built into the Haemobank equipment. No additional temperature monitoring needed.

W x D x H: 29 x 38.1 x 79.7 in. **Clearance:** Rear 3 in.; Top 8 in.
Network: Wired
Electrical: 115V 60Hz 11.9A **Weight:** 747 lbs.

Room: Nourishment **Department: Infusion**

Room #: A504B1, A508K1

Room Notes: Keep microwave.

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Coffee Brewer

AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately. View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Nourishment **Department:** Infusion

Room #: A504B1, A508K1

Room Notes: Keep microwave.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser — AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Room: Nourishment **Department:** Infusion

Room #: A504B1, A508K1

Room Notes: Keep microwave.

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.

Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.

Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Nourishment **Department:** Infusion

Room #: A504B1, A508K1

Room Notes: Keep microwave.

Waste Receptacle, Recycling w/ Lid/Sign

AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: On-Stage Team Work Area

Department: Infusion

Room #: A504K, A505V, A506E

Room Notes: Some on-stage work areas/pods and MEQ split between (2) room numbers. All MEQ listed in other room#

Room: Clean Supply (B) **Department: Infusion**

Room #: A506F

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Room: Equipment Storage B **Department: Infusion**

Room #: A506G

Room Notes: With mobile Pt lift

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cold Cap

AE #: COCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Dignitana	DigniCap Delta		Floor	OF/OI	Lease

The DigniCap Scalp Cooling System is indicated to reduce the likelihood of chemotherapy-induced alopecia in cancer patients with solid tumors. View Cutsheet 211844

Placeholder. Qty confirmed 9/13/24 with Jennifer Ratner.

W x D x H: 15 x 20 x 37.5 in.
Electrical: 120V 60Hz 20A **Weight:** 143 lbs.
Elect Notes: Input voltage: 100 – 240 VAC, 47-63 Hz. Input current maximum: 17 amp. Recommendation from sales rep: A dedicated, red/emergency power outlet, 20 amp.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Room: Equipment Storage B **Department:** Infusion

Room #: A506G

Room Notes: With mobile Pt lift

Lifter, Patient

AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor. View Cutsheet 208837

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Network Notes: Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Equipment Storage B **Department:** Infusion

Room #: A506G

Room Notes: With mobile Pt lift

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A
Weight: 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	2

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Becton Dickinson	Alaris 8100	8100	Shelf	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	4

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.
Weight: 13 lbs.

Room: Equipment Storage B

Department: Infusion

Room #: A506G

Room Notes: With mobile Pt lift

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Equipment Storage B **Department:** Infusion

Room #: A506G

Room Notes: With mobile Pt lift

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Vein Illuminator

AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz. View Cutsheet 168583

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	2

Room: Lounge **Department:** Infusion

Room #: A507A, A508A

Coffee Brewer — AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Audiology Booth	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Lounge **Department:** Infusion

Room #: A507A, A508A

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Lounge **Department:** Infusion

Room #: A507A, A508A

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers — No Cutsheet 141809

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required — View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. — View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling w/ Lid/Sign — AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. — View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Alcove, Stretcher

Department: Infusion

Room #: IN00136

Room Notes: Not shown on floor plan

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Room: Alcove, Sink / Pharm Bin

Department: Infusion

Room #: IN0137

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
21	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
21	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
21	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
21	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Alcove, Linen **Department:** Infusion

Room #: IN0138

Room Notes: 3 alcoves throughout infusion dept. (1) linen hamper per alcove

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Accessioning / Processing

Department: Lab - Cell Therapy

Room #: B505A

Allowance, Certification, Hood

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - Allowance				OF/OI	Project

No Cutsheet 167826

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Accessioning / Processing

Department: Lab - Cell Therapy

Room #: B505A

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Freezer, Controlled Rate

AE #: FRCR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Custom Biogenic Systems (Cbs)	2101		Countertop	OF/VI	Project

The 2101 Controlled Rate Freezer from Custom Biogenic Systems ensures samples are frozen at a precise, optimal rate to prevent lethal intracellular freezing for increased viability with reproducible, traceable results. Ideal for freezing of cell culture and Biobank samples prior to long-term storage in LN2 freezers or PHCbi -150°C ULT freezers. 7.4 gallon capacity View Cutsheet 209119

W x D x H: 19 x 25.5 x 30.3 in.

Electrical: 120V 60Hz 10A **Weight:** 76.5 lbs.

Freezer, Ultra-Low

AE #: FRUL-03E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Panasonic Healthcare	MDF-C8V1-PA		Floor	EX/OI	Existing

The MDF-C8V1 VIP Ultra Low Temperature Freezer is ideal -80°C freezing environment using VIP PLUS technology maximizes storage capacity. The newly developed single-compressor system achieves higher energy efficiency and space saving construction. View Cutsheet 210216

Current model, purchased in 2023.

W x D x H: 21.6 x 27 x 37.2 in.

Electrical: 115V 60Hz 330W **Weight:** 154 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Accessioning / Processing **Department:** Lab - Cell Therapy

Room #: B505A

Hood, Safety Biological

AE #: HOSB-77

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Nu Aire, Inc.	NU-540-600		Floor	OF/VI	Project

6ft BSC. The LabGard ES (Energy Saver) model NU-540 is a Class II, Type A2 Biological Safety Cabinet providing Personnel, Product, and Environmental Protection that can be either exhausted back into the room or connected to a facility HVAC system to minimize cross-contamination of low to moderate risk biologicals in the absence of volatile toxic chemicals. View Cutsheet 209447

No venting, recirculates air in the room. See accessories for telescoping base at 27" per Giovi, arm rests, and IV pole with hooks.

W x D x H: 77.6 x 31.4 x 61.9 in.
Electrical: 115V 60Hz **Weight:** 620 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Elbow rest		1	2
Foam arm rest		1	2
IV bar with hooks		1	2
Telescoping Base		1	2

Hood, Safety Biological

AE #: HOSB-53

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nu Aire, Inc.	NU-540-400		Floor	OF/VI	Project

4ft BSC. The LabGard ES (Energy Saver) model NU-540 is a Class II, Type A2 Biological Safety Cabinet providing Personnel, Product, and Environmental Protection that can be either exhausted back into the room or connected to a facility HVAC system to minimize cross-contamination of low to moderate risk biologicals in the absence of volatile toxic chemicals. View Cutsheet 211673

No venting, recirculates air in the room. See accessories for telescoping base at 27" per Giovi, arm rests, and IV pole with hooks.

W x D x H: 53.6 x 31.4 x 61.9 in.
Electrical: 115V 60Hz **Weight:** 465 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Elbow rest		1	1
Foam arm rest		1	1
IV bar with hooks		1	1
Telescoping Base		1	1

Room: Accessioning / Processing **Department:** Lab - Cell Therapy

Room #: B505A

Lab Analyzer, Hematology, Automated

AE #: LAHA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sysmex America Inc	XN450		Countertop	OF/CI/VI	Project

Automated compact 6-part differential hematology analyzer. Has a fully integrated IPU (information-processing unit) including an LCD color touchscreen – so you do not need a separate computer to operate the analyzer. It incorporates the proven Sysmex technologies of fluorescence flow cytometry, hydrodynamic focusing and our cyanide-free SLS method for determining hemoglobin.

Include HP laser jet printer; 6" clearance between analyzer and printer, plus 15" for printer. Keep as net New for now. May relocate existing closer to procurement.

View Cutsheet 208802

W x D x H: 17.7 x 18.1 x 17.3 in.

Network: Wired

Network Notes: There must be access to Internet via a high speed broadband connection (DSL or better). Jacks: Two Ethernet (RJ45 Jack) connection from the instrument and BCQM laptop(If Applicable) to LAN (including patch cables) must exist. IP Address: Two routable IP address for the instrument and BCQM laptop(If Applicable) must exist. If the instrument is already interfaced to a host for demographics and results, the connection is TCP/IP, and is on the network, the same address / connection can be used for SNCS.

Electrical: 115V 60Hz 15A

Weight: 77.2 lbs.

Elect Notes: **See cutsheet**

Plumb Notes: Requires Drain. **See cutsheet**

Struct Notes: **See cutsheet**

Lab Centrifuge, Counter Top

AE #: LACC-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Clay Adams / Becton Dickinson Diagnostics	Serofuge 2002		Countertop	OF/OI	Project

Features that include locking lid, digital controls and displays, gasket seal, and dual speed operation, (2400rpm/500xG or 3400rpm/1049xG). An unbreakable 12 place plastic rotor for 12 x 75mm tubes is also available within. The device also includes a plastic rotor, having a capacity for accommodating blood tubes up to 12.7 dia. X 75 mm long.

View Cutsheet 210189

W x D x H: 13 x 17 x 12 in.

Electrical: 115V 60Hz

Weight: 28 lbs.

Room: Accessioning / Processing **Department:** Lab - Cell Therapy

Room #: B505A

Lab Centrifuge, Refrigerated, Component — AE #: LCRC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Beckman Coulter, Inc	JS-4.2	339080	Refrigerator	OF/VI	Project

Swinging bucket rotor for the Beckman Coulter J-HC refrigerated centrifuge. JS-4.2 Swinging-Bucket Rotor (Windshielded). Windshielded, six-place rotor with aluminum rotor yoke and removable aluminum swinging buckets. Buckets are interchangeable with Microplate Carriers 358682 for spinning microtiter plates and MiniTube Racks. Holds up to six liters, six blood bags, or six microtiter plate carriers. View Cutsheet 210197

Compatible with the Avanti J-HC Centrifuge, see accessories for tube and bottle adapters

Accessories:

Description	Catalog	Qty/Item	Ext Qty
15ml tube adapter	339102	1	1
250ml bottle adapter	339108	1	1
500ml bottle adapter	339109	1	1
50ml tube adapter	339103	1	1

Lab Centrifuge, Refrigerated, Floor Model — AE #: LCRF-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Beckman Coulter, Inc	Avanti J-HC		Floor	OF/VI	Project

The Avanti J-HC High Capacity Centrifuge provides you with a complete solution for batch bioprocessing. A maximum of 9 liters can be spun quickly. This allows processing of up to 36 liters per hour when harvesting bacteria. Enhanced operator safety is pro vided with disposable HarvestLine System Liners. The Avanti J-HC's Friction Reduction System (FRS) allows for quicker, quieter, and cooler runs. View Cutsheet 208273

J6-MI recently discontinued, this is the replacement

W x D x H: 28 x 34 x 34 in.
Electrical: 208V 60Hz 24A **Weight:** 660 lbs.
Elect Notes: Maximum Heat Dissipation to Room: 2.0 kW (6 900 BTU/hr)

Lab Differential Counter — AE #: LADC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Modulus Data Systems	DIFFCOUNT III 10-308		Countertop	OF/OI	Project

Microprocessor-controlled differential cell counter designed specifically for hematology laboratory. 8-channel cell counter; with LCD display; alarm actuates after 100 counts; with percentage, count and clear buttons; 3 digits. View Cutsheet 210192

To sit next to microscope, can both be next to each other.

W x D x H: 6 x 9 x 2.25 in.
Electrical: 120V 60Hz

Room: Accessioning / Processing **Department:** Lab - Cell Therapy

Room #: B505A

Lab Microscope — AE #: LAMI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX46		Countertop	OF/VI	Project

Microscope; BX46 w/ pln4x 4x objective, pln10x 10x objective, pln40x 40x objective, pln50xoi 50x o/i, pln100xo 100x oil objective; with dustcover. View Cutsheet 142868

BX45 is discontinued. Quote 2024-JAD-3217 - 8 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 10.8 x 17.9 x 16.1 in.
Electrical: 120V 60Hz 4A **Weight:** 28.7 lbs.

Lab Pipette Holder — AE #: LAPH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Eppendorf	Pipette Carousel 2	31-160-00015	Countertop	OF/OI	Project

Carries up to six manual single or multi-channel Eppendorf pipettes. Includes rotatable stand with completely new design that holds all current manual pipettes including Eppendorf Research®, Research® plus, Reference®, Reference® 2 or Biomaster® and most of their predecessors. Pipette holders are interchangeable, no tools required. Robust design that securely holds and protects pipettes. Handle for easy transport from bench to bench. View Cutsheet 206942

1 in 4ft hood, 1 by Sysmex

Weight: 3.66 lbs.

Lab Pipetter — AE #: LAPI-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Eppendorf	20-200ul, EPPR3055		Rack	OF/OI	Project

Eppendorf Reference 2 Adjustable Volume, Single Channel Pipette, 20 - 200 uL View Cutsheet 209184

Lab Pipetter — AE #: LAPI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Eppendorf	2-20ul, 3123000039		Rack	OF/OI	Project

Eppendorf Research® Plus Single Channel Pipette, adjustable, 2 - 20 µL, yellow operating button, includes epT.I.PS. box View Cutsheet 209182

Room: Accessioning / Processing **Department:** Lab - Cell Therapy

Room #: B505A

Lab Pipetter — AE #: LAPI-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rainin	200ul - 1ml, 17015235		Rack	OF/OI	Project

Eppendorf Research® Plus Single Channel Pipette, adjustable, 200 µL - 1ml, yellow operating button, includes epT.I.PS. box View Cutsheet 210220

Lab Rocker, Bag / Platform — AE #: LRBP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fisher Scientific - Thermo	3D Platform Rocker	88-861-045	Countertop	OF/OI	Project

This platform rotator provides a smooth orbital motion for mixing in culture flasks, dishes, plates and tubes. Includes a dimpled rubber mat and 6 tube securing bands. Tray dimensions: 12" x 10.5" View Cutsheet 209175

W x D x H: 16.3 x 11.6 x 6.7 in.
Electrical: 120V 60Hz 0.8A **Weight:** 16.1 lbs.

Lab Rocker, Tube — AE #: LART-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Scientific Products/Vwr	GTR-2-FS		Countertop	OF/OI	Project

Fixed Speed of 24 rpm and an Angle of ±25°, Tube Size from 1.5 to 50 ml on the Unit. View Cutsheet 207618

W x D x H: 13.6 x 7 x 7 in.
Electrical: 120V 60Hz

Lab Shaker — AE #: LASH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	20215		Hood	OF/OI	Project

Digital orbital shaker with vial stands. Speed range 20-300 rpm. Platform 11" x 11". View Cutsheet 208661

Place holder for blood bank bag rocker

W x D x H: 12.4 x 12.3 x 7.8 in.
Electrical: 115V 60Hz

Room: Accessioning / Processing

Department: Lab - Cell Therapy

Room #: B505A

Mixer, Vortex

AE #: MIVO-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Fisher Scientific - Thermo	12-815-50		Countertop	OF/OI	Project

Vortex mixer; simultaneous vortexing of up to 4 test tubes; variable mixing action by adjusting pressure of test tube against foam rubber top; white plastic top is acid and alkaline resistant; cast aluminum base; 3000rpm motor; top-mounted push-button on/off switch; suction cup feet; ball bearing drive

View Cutsheet 156736

Place near 4' hood and (1) 6' hood. Model confirmed with UK, Giovi

W x D x H: 5.5 x 5.5 x 4.2 in.
Electrical: 120V 60Hz 0.4A

Monitor, Humidity

AE #: MOHU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Ceiling / Wall	CF/CI	Project

Centralized humidity monitoring system

No Cutsheet 209164

Monitor, Oxygen Room

AE #: MOOR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Analox	Safe-Ox+		Wall	OF/CI	Project

An ambient oxygen enrichment and depletion monitor which is simple to use and easy to maintain. Dimensions listed are for Central Unit. Repeater Unit: 3" x 1.7" x 5.1

View Cutsheet 209176

W x D x H: 6.9 x 2.6 x 4 in.
Electrical: 110V
Elect Notes: Mains powered Ax O2NE+TM/Safe-Ox+TM's are pre-wired with a mains cable, fitted with a plug suited to the destination country. Where internal plug fuses are fitted, these are 3 amp. Ensure that the unit is connected to the correct supply voltage (i.e. 110 or 230V AC). Where no fuse is fitted in the plug, the instrument should be powered from a 3 amp fused outlet. The Ax O2NE+TM/Safe-Ox+TM is fitted with an internal fuse, which is rated at 500mA.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Elect Notes: Loop Voltage/Current: 0-5V, 0-10V, 4-20mA, Power Supply: (4) 1.5V AA Lithium Batteries. Any AA 1.5V batteries can be used (lithium or alkaline) Optional - External AC/DC Power Supply - UL certied Universal input: 100Vac to 240Vac

Room: Accessioning / Processing **Department:** Lab - Cell Therapy

Room #: B505A

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Refrigerator, Blood Bank

AE #: REBB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Helmer, Inc.	iBR120-GX		Floor	OF/VI	Project

High performance storage of blood and other medical and scientific products. Storage volume: 20.2 cu ft. View Cutsheet 209123

W x D x H: 29 x 28.2 x 79.6 in.
Electrical: 120V 60Hz 15A **Weight:** 507 lbs.
Elect Notes: NEMA 5-15 hospital-grade | 115V 60Hz, 8 to 10 ft (2.4-3.0m)
Inquire about additional plug/cord options
Facility Supply Rating: Branch circuit with earth ground, meeting plug/cord ratings as well as local electrical safety codes and requirements
110-120V AC: 15 A (minimum)
220-240V AC: 10 A (minimum)

Scale, Gram

AE #: SCGR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Mettler-Toledo, Inc.	ICS439, PBD659		Countertop	OF/OI	Project

Compact gram scale with front mounted digital interface display. Scale can read weights from 0.5g - 3000g. Platform is 9.5" x 11.8". View Cutsheet 210433

W x D x H: 11.8 x 14.6 x 403 in.
Network: Networked **Network Notes:** Scale interface (Analog, IDNet or SICSpro), RS232 data interface
Electrical: 120V 60Hz

Room: Accessioning / Processing

Department: Lab - Cell Therapy

Room #: B505A

Sealer, Tube

AE #: SETU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Fresenius Kabi	CompoSeal Mobilea II		Cabinet	OF/OI	Project

CompoSeal® Mobilea II is used for mobile sealing in donation teams or at processing departments with its light weight Lithium Polymer battery delivering optimal sealing performance. Transport case includes all items: CompoSeal Mobilea II set, power pack, hand-held sealer, charger, cable.

View Cutsheet 211590

W x D x H: 15.3 x 4.3 x 11.8 in.

Weight: 10.46 lbs.

Elect Notes: Battery powered

Waste Container, Biohazard

AE #: WARE-21

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	1883564 RED		Floor	OF/OI	Project

Step-on rectangular waste; 8 gallon.

View Cutsheet 163730

W x D x H: 16.7 x 10.6 x 21 in.

Weight: 6 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Storage

Department: Lab - Cell Therapy

Room #: B505A1

Cart, Supply

AE #: CASU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Super Erecta		Floor	OF/VI	Project

Custom supply cart, 4-tier. (4x)A1836NC/(4x)63UP/5MP/5MPB — No Cutsheet 208758

Supplemental info- cut sheet includes 1 solid stainless bottom shelf and 4 upper wire shelves, 74” posts instead of the 63”, to match a standard build for UK. Shelves are adjustable. — Supplemental Info

W x D x H: 36 x 18 x 69 in.

Cart, Supply

AE #: CASU-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Super erecta model with chrome finish to include (3) wire shelves, (1) solid bottom shelf, (2) braking casters, (2) swivel casters, and (4) 63" posts — View Cutsheet 160459

W x D x H: 48 x 24 x 68 in.

Cart, Wire

AE #: CAWI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Global Industrial	40912		Floor	OF/OI	Project

Top basket 30-3/4"L x 17-1/2"W x 7"H. Bottom basket 30-3/4"L x 17-1/2"W x 7"H. Heavy-duty steel wire and tubing frame. Wt capacity: 200lb. Color: Chrome; Caster/Glide/Wheel: Four 4" Front Swivel Casters, 10" Rear Wheels. — View Cutsheet 209172

W x D x H: 21.5 x 37.5 x 39.3 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. — View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Storage

Department: Lab - Cell Therapy

Room #: B505A1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Stand	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser.

View Cutsheet 141564

Used for calibrations and water baths

W x D x H: 16.1 x 23.5 x 32.5 in.
Clearance: Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A
Weight: 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Room: Storage
Room #: B505A1

Department: Lab - Cell Therapy

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in.
Clearance: Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component

AE #: ICMW-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12BASE-CL		Floor	OF/CI	Project

Stainless steel base stand for ice maker/water dispenser model 12CI425A. Includes stainless legs with adjustable flanged feet and high capacity carbonless filter (3,000 gallons). Pre-plumbed and ready for external connections. View Cutsheet 208924

W x D x H: 17.5 x 22 x 33 in.
Weight: 80 lbs.

Monitor, Humidity

AE #: MOHU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sensoscientific Inc.	Humidity and Temperature Sensor	B13-200-OTA	Wall	OF/CI/VI	Project

Monitor ambient temperature and humidity up to 125°C and 100% RH. Price includes humidity probe. View Cutsheet 208486

W x D x H: 3.88 x 1.38 x 4.25 in.
Electrical: 120V 60Hz 0.5A
Elect Notes: Battery operated. Optional AC/DC power supply (UL Certified). AC Adapter: Input: 100-240V-50/60hz 0.5A Max, Output: 5V at 3.1A

Room: Storage

Department: Lab - Cell Therapy

Room #: B505A1

Monitor, Oxygen Room

AE #: MOOR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Analox	Safe-Ox+		Wall	OF/CI	Project

An ambient oxygen enrichment and depletion monitor which is simple to use and easy to maintain. Dimensions listed are for Central Unit. Repeater Unit: 3" x 1.7" x 5.1

View Cutsheet 209176

W x D x H: 6.9 x 2.6 x 4 in.

Electrical: 110V

Elect Notes: Mains powered Ax O2NE+TM/Safe-Ox+TM's are pre-wired with a mains cable, fitted with a plug suited to the destination country. Where internal plug fuses are fitted, these are 3 amp. Ensure that the unit is connected to the correct supply voltage (i.e. 110 or 230V AC). Where no fuse is fitted in the plug, the instrument should be powered from a 3 amp fused outlet. The Ax O2NE+TM/Safe-Ox+TM is fitted with an internal fuse, which is rated at 500mA.

Room: Biorespository **Department: Lab - Cell Therapy**

Room #: B505B

Allowance, Relocation of Existing Equipment

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GenVault Transport Services	MVE Cryo Freezers			OF/VI	Project

For relocation and installation of MVE Cryogenic freezers. **Pricing is for relocation services, ~$7500 is the day rate to relocate all (4) freezers.** View Cutsheet 213098

Battery, Backup AE #: BABA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Power Sonic	PS-1290		Freezer	OF/VI	Project

12 V, 9.00 AH external, sealed lead acid battery. Offers excellent performance in a wide range of applications including security and fire systems, medical devices, emergency lighting, and UPS systems. View Cutsheet 210185

Battery will be installed by MVE at their factory.

W x D x H: 5.95 x 2.56 x 4.15 in. **Weight:** 6 lbs.

Elect Notes: External battery. 12V, 9.00AH,

Canister, Frame AE #: CAFR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4800	BioLife Solutions, Inc	ZC021		Freezer	OF/VI	Project

Custom canister / cassette to hold cryogenic bags for Baxter Fenwal, Cryomacs, Origen and CharterMed. (4) Canisters can fit in a frame. View Cutsheet 211591

Per Giovi, 4 canisters per frame, 200 frames per MVE freezer

W x D x H: 7.55 x 0.44 x 6 in.

Cart, Utility AE #: CAUT-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Lakeside Mfg. Co.	947		Floor	OF/OI	Project

Rugged Angled Stainless Steel U-Frame For Added Strength. Shelves are 14-gauge stainless steel with reinforced edges front and back. Heavy-duty wide tread 8” fixed wheels and 5” swivel casters View Cutsheet 209179

W x D x H: 42 x 25.9 x 37.4 in.

Room: Biorespository

Department: Lab - Cell Therapy

Room #: B505B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Frame, 4-Place

AE #: FRAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1200	BioLife Solutions, Inc	ZF4-ZC021		Freezer	OF/VI	Project

4-PLACE FRAME FOR ZC021 CANISTER

View Cutsheet 211592

Per Giovi, 4 canisters per frame, 200 frames per MVE freezer

W x D x H: 0.56 x N/A x 6.38 in.

Room: Biorespository **Department: Lab - Cell Therapy**

Room #: B505B

Freezer, Cryogenic — AE #: FRCR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	MVE Biomedical Div. / Chart Industries	MVE 1536P-190 / TEC3000		Floor	OF/CI/VI	Project

The MVE 1500 Series -190°C freezers provide cryogenic storage [View Cutsheet 209127]

for up to 36,400 1.2 / 2.0 ml vials. Height with lift over. Wt empty: 690 lb, Wt full: 2037 lb. Step adds 7.9in to front. Use with TEC3000 component

Battery will be installed by MVE at their factory. (6) will be net new, (4) will be existing. Pricing from quote #Q008769, 8/22/24.

W x D x H: 53 x 62 x 61.3 in. **Clearance:** Top 37.1 in.
Electrical: 110V 60Hz 3A 30W **Weight:** 2037 lbs.
Elect Notes: TEC 3000 component requires an additional 120 v, 60 htz outlet (2-prong plug/outlet).
Struct Notes: The 1536P-190 has a LN2 Capacity at Vapor Platform L est. of 133

Freezer, Cryogenic — AE #: FRCR-02E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	MVE Biomedical Div. / Chart Industries	MVE 1536P-190 / TEC3000		Floor	EX/VI/CI	Existing

The MVE 1500 Series -190°C freezers provide cryogenic storage [View Cutsheet 209127]

for up to 36,400 1.2 / 2.0 ml vials. Height with lift over. Wt empty: 690 lb, Wt full: 2037 lb. Step adds 7.9in to front. Use with TEC3000 component

Battery will be installed by MVE at their factory. (6) will be net new, (4) will be existing. **See allowance for relocation services** [Supplemental Info]

W x D x H: 53 x 62 x 61.3 in. **Clearance:** Top 37.1 in.
Electrical: 110V 60Hz 3A 30W **Weight:** 2037 lbs.
Elect Notes: TEC 3000 component requires an additional 120 v, 60 htz outlet (2-prong plug/outlet).
Struct Notes: The 1536P-190 has a LN2 Capacity at Vapor Platform L est. of 133

Freezer, Undercounter — AE #: FRUC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Helmer, Inc.	iBF105-GX		Undercounter	OF/VI	Project

Undercounter plasma freezer. Temp range: -15 to -30. Storage capacity 5 cu ft. [View Cutsheet 209121]

Locate under (1) incubator.

W x D x H: 24 x 26.8 x 34 in.
Electrical: 115V 60Hz **Weight:** 221 lbs.
Elect Notes: NEMA 5-15 hospital grade plug (115V)
CEE 7/7 plug (230V 50Hz)
NEMA 6-15 hospital grade plug (230V 60Hz)
8-10 ft (2439-3048 mm)

Room: Biorespository **Department: Lab - Cell Therapy**

Room #: B505B

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Differential Counter — AE #: LADC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Modulus Data Systems	DIFFCOUNT III 10-308		Countertop	OF/OI	Project

Microprocessor-controlled differential cell counter designed specifically for hematology laboratory. 8-channel cell counter; with LCD display; alarm actuates after 100 counts; with percentage, count and clear buttons; 3 digits. View Cutsheet 210192

To sit next to microscope

W x D x H: 6 x 9 x 2.25 in.
Electrical: 120V 60Hz

Lab Incubator, CO2 — AE #: LAIC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Thermo Fisher Scientific	380		Countertop	OF/VI	Project

Thermo Scientific™ Forma™ Steri-Cycle CO Incubators offer ISO Class 5 HEPA filtration and 140° C on-demand high temperature sterilization. With IR sensor. View Cutsheet 210198

Same as model currently used. With IR Sensor.

W x D x H: 26.1 x 25 x 39.5 in.
Electrical: 115V 60Hz **Weight:** 260 lbs.
Elect Notes: 115V, 50/60 Hz, 9.6 FLA (operating range 90-125V) NEMA 5-15P plug
Circuit breaker, power switch: 12 Amps, 2 Pole
Convenience receptacle: 75 Watts max. (matches cabinet voltage)
Alarm contacts: Deviation of temp, CO2, RH; power failure; customer connections through jack on back of unit
Access port, CO2 inlet: 1.3" (3.3cm) with removable silicone plug, 1/4" barbed hose
Unit heat load: 341 BTUH (100 Watts), 85 kcal per hour

Room: Biorespository **Department: Lab - Cell Therapy**

Room #: B505B

Lab Microscope — AE #: LAMI-01E

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX45		Countertop	EX/OI	Existing

Olympus BX45 Binocular Microscope comes with ergonomic concerns which flexibility helps the operator maintain an upright, comfortable posture, especially beneficial for prolonged observation periods. Includes: 5 Position Nosepiece with slider inlet. Plan 4x/0.10na,19mm Working Distance Objective. Plan 10x/0.25na,10.5mm Working Distance Objective. Plan 40x/0.65na,0.60mm Working Distance Objective. Plan 100x/1.25na Oil,0.15mm Working Distance Objective. 6V 30Watt Halogen Light Source.

View Cutsheet 163852

Include inverted phase for cell culture plates Use Existing microscope here.

W x D x H: 10.8 x 17.9 x 16.1 in.
Electrical: 120V 60Hz 0.85A

Monitor, Humidity — AE #: MOHU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sensoscientific Inc.	Humidity and Temperature Sensor	B13-200-OTA	Wall	OF/CI/VI	Project

Monitor ambient temperature and humidity up to 125°C and 100% RH. Price includes humidity probe.

View Cutsheet 208486

W x D x H: 3.88 x 1.38 x 4.25 in.
Electrical: 120V 60Hz 0.5A
Elect Notes: Battery operated. Optional AC/DC power supply (UL Certified). AC Adapter: Input: 100-240V-50/60hz 0.5A Max, Output: 5V at 3.1A

Monitor, Oxygen Room — AE #: MOOR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Analox	Safe-Ox+		Wall	OF/CI	Project

An ambient oxygen enrichment and depletion monitor which is simple to use and easy to maintain. Dimensions listed are for Central Unit. Repeater Unit: 3" x 1.7" x 5.1

View Cutsheet 209176

W x D x H: 6.9 x 2.6 x 4 in.
Electrical: 110V
Elect Notes: Mains powered Ax O2NE+TM/Safe-Ox+TM's are pre-wired with a mains cable, fitted with a plug suited to the destination country. Where internal plug fuses are fitted, these are 3 amp. Ensure that the unit is connected to the correct supply voltage (i.e. 110 or 230V AC). Where no fuse is fitted in the plug, the instrument should be powered from a 3 amp fused outlet. The Ax O2NE+TM/Safe-Ox+TM is fitted with an internal fuse, which is rated at 500mA.

Room: Biorespository **Department: Lab - Cell Therapy**

Room #: B505B

Tank, CO2

AE #: TACO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	ZZZ - To Be Determined	50 lb		Stand	OF/OI	Service Agreement

High pressure CO2 tank, 50 lb. Diameter 8.6". See accessories for base, nut, nipple, and yoke

View Cutsheet 209181

W x D x H: N/A x 8.6 x 47 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
CGA 320 Nut and Nipple	WESM1-320-PG	1	2
Cylinder Base	HUD4045	1	2
WESM1-940-PG	CGA 940 Yoke	1	2

Room: Liquid Nitrogen **Department:** Lab - Cell Therapy

Room #: B505B1

Room Notes: Assumes 180L LN tanks. Assume space for (12) tanks with caster base.

Caster Base

AE #: CABA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
12	Saft Cart	CRYO-8860		Floor	OF/OI	Project

Caster base for cylinder gas tanks. Ex: Liquid Nitrogen

View Cutsheet 209456

W x D x H: 31 x 21.5 x 5 in.

Monitor, Humidity

AE #: MOHU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sensoscientific Inc.	Humidity and Temperature Sensor	B13-200-OTA	Wall	OF/CI/VI	Project

Monitor ambient temperature and humidity up to 125°C and 100% RH. Price includes humidity probe.

View Cutsheet 208486

W x D x H: 3.88 x 1.38 x 4.25 in.
Electrical: 120V 60Hz 0.5A
Elect Notes: Battery operated. Optional AC/DC power supply (UL Certified). AC Adapter: Input: 100-240V-50/60hz 0.5A Max, Output: 5V at 3.1A

Monitor, Oxygen Room

AE #: MOOR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Analox	Safe-Ox+		Wall	OF/CI	Project

An ambient oxygen enrichment and depletion monitor which is simple to use and easy to maintain. Dimensions listed are for Central Unit. Repeater Unit:

View Cutsheet 209176

3" x 1.7" x 5.1

W x D x H: 6.9 x 2.6 x 4 in.
Electrical: 110V
Elect Notes: Mains powered Ax O2NE+TM/Safe-Ox+TM's are pre-wired with a mains cable, fitted with a plug suited to the destination country. Where internal plug fuses are fitted, these are 3 amp. Ensure that the unit is connected to the correct supply voltage (i.e. 110 or 230V AC). Where no fuse is fitted in the plug, the instrument should be powered from a 3 amp fused outlet. The Ax O2NE+TM/Safe-Ox+TM is fitted with an internal fuse, which is rated at 500mA.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
12	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Room: Toilet (Staff)

Department: Lab - Cell Therapy

Room #: B507A1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Storage (Admin) **Department:** Lab - Cell Therapy

Room #: B507A2

Room Notes: Includes FDA paperwork & binders

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Shelving, Wire

AE #: SHWI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	SUPER ERECTA - SUPER ADJUSTABLE 60X24X74		Floor	OF/VI	Project

Chrome wire shelving with 5 shelves. 60"w x 24"d x 74"h. Corner release system for repositioning of shelves during initial assembly. Siteselect posts View Cutsheet 164501 enable tool-free adjustment at 1" (25mm) increments along entire height of the post. Maximum weight capacity 2000 lbs (600lb per shelf).

W x D x H: 60 x 24 x 74 in.

Room: Team Work Area

Department: Lab - Cell Therapy

Room #: B507A4, B507A5, B507A6, B507A7

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Office, Private

Department: Lab - Cell Therapy

Room #: B507A8

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Corridor

Department: Pharmacy (Infusion)

Room #: B503

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Work Area

Department: Pharmacy (Infusion)

Room #: B503A, B503H

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Work Area (IDS)

Department: Pharmacy (Infusion)

Room #: B503B

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: IDS Protocol Storage

Department: Pharmacy (Infusion)

Room #: B503B1

Room Notes: Assumes no medical equipment in this area.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Conference Room

Department: Pharmacy (Infusion)

Room #: B503C

Waste Receptacle, Recycling Combination

AE #: WARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Max-R	P-RO-STT10D		Floor	OF/OI	Project

10-gallon Top Load Waste & Recycling Bins.

View Cutsheet 209397

W x D x H: 28 x 15 x 30 in.

Room: Work Area

Department: Pharmacy (Infusion)

Room #: B503D1

Cart, Sharps Container

AE #: CASC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	8 Gallon Sharps Container	108SRCL	Floor	OF/VI	Service Agreement

Disposable container designed for the collection of sharps waste. Large, hinged lid and port opening allow for 2 disposal options. Gasketed lid ensures leak resistance. Large container for use on floor or cart. Optional Bemis Cart (sku: 430030) available.

View Cutsheet 208721

For red container

W x D x H: 11.5 x 16 x 16.5 in.

Cart, Supply, 60x24x68

AE #: CASU-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	2460FS		Floor	OF/VI	Project

24x60 solid s/s shelf (2460FS) 6 each; 63" post with cap only (63UPS) 4 each; 5" polyurethane caster s/s swivel (5MPGSA) 2 each and 5" polyurethane caster s/s brake (5MPBGSA) 2 each.

View Cutsheet 208660

W x D x H: 60 x 24 x 68 in.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly.

View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Work Area (Open) **Department: Pharmacy (Infusion)**

Room #: B503D2

Room Notes: Assumes space for 12 people

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. To be placed across corridor by door to Anteroom.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container — AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled View Cutsheet 100085

resin will not rust and resists chips and dents

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Office, Pharmacist

Department: Pharmacy (Infusion)

Room #: B503D, B503F

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Anteroom **Department: Pharmacy (Infusion)**

Room #: B503E

Room Notes: Scrub sink to be specified by architect and provided by contractor.

Bench

AE #: BENC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Eagle Group	CRB1848		Floor	OF/CI	Project

Solid 300 series stainless steel gowning bench with standard undershelf. May be bolted to floor if desired. View Cutsheet 208670

W x D x H: 48 x 18 x 19 in.

Weight: 43 lbs.

Cart, Supply, 60x24x68

AE #: CASU-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	2460FS		Floor	OF/VI	Project

24x60 solid s/s shelf (2460FS) 6 each; 63" post with cap only (63UPS) 4 each; 5" polyurethane caster s/s swivel (5MPGSA) 2 each and 5" polyurethane caster s/s brake (5MPBGSA) 2 each. View Cutsheet 208660

W x D x H: 60 x 24 x 68 in.

Cart, Transfer

AE #: CATR-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	1424FS / 33UPS		Floor	OF/VI	Project

14x24 solid s/s shelf (1424fs) 3 each; 33-3/4" post with cap only (33ups) 4 each; 5" caster s/s swivel (2) and brake (2). View Cutsheet 168390

W x D x H: 14 x 24 x 36 in.

Dispenser, Paper Towel

AE #: DIPT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Contec Healthcare	9451		Wall	OF/CI	Project

Stainless steel dispenser for low-lint disposable hand drying wipes. View Cutsheet 208769

One to be placed one either side of sink.

W x D x H: 10 x 4.75 x 9 in.

Room: Anteroom **Department: Pharmacy (Infusion)**

Room #: B503E

Room Notes: Scrub sink to be specified by architect and provided by contractor.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

Automatic model confirmed

W x D x H: 12 x 7 x 8 in.

Table, Work

AE #: TAWO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	TWS2460FS-316-S		Floor	OF/VI	Project

316 ALL-STAINLESS WORKTABLE with bottom shelf. Height adjustable 34"-39". View Cutsheet 208668

PPE to be kept on bottom shelf

W x D x H: 60 x 24 x 35 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Clean Hoods (Non-HD Compounding) **Department: Pharmacy (Infusion)**

Room #: B503E1

Room Notes: Pass thru Clean Hoods to Work Area

Cart, Supply, 60x24x68

AE #: CASU-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	2460FS		Floor	OF/VI	Project

24x60 solid s/s shelf (2460FS) 6 each; 63" post with cap only (63UPS) 4 each; 5" polyurethane caster s/s swivel (5MPGSA) 2 each and 5" polyurethane caster s/s brake (5MPBGSA) 2 each. View Cutsheet 208660

W x D x H: 60 x 24 x 68 in.

Cart, Transfer

AE #: CATR-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	1424FS / 33UPS		Floor	OF/VI	Project

14x24 solid s/s shelf (1424fs) 3 each; 33-3/4" post with cap only (33ups) 4 each; 5" caster s/s swivel (2) and brake (2). View Cutsheet 168390

W x D x H: 14 x 24 x 36 in.

Container, Pharmacy Waste - Blue

AE #: COPW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Stericycle	DWS-08/C-08-2004		Floor	OF/VI	Service Agreement

8-gallon blue bin for medication waste with wire step-on dolly. View Cutsheet 164305

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Stericycle	DWS-08/C-08-2004LR		Floor	OF/OI	Supply Agreement

8-gallon red bin (19.7”h x 13.0”d x 11.3 “w) for biohazard waste with wire step-on dolly. View Cutsheet 164306

W x D x H: 14.3 x 16.5 x 23 in.

Room: Clean Hoods (Non-HD Compounding) **Department: Pharmacy (Infusion)**

Room #: B503E1

Room Notes: Pass thru Clean Hoods to Work Area

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

Automatic model confirmed

W x D x H: 12 x 7 x 8 in.

Hood, Laminar Flow

AE #: HOLF-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baker Company, The	EG4252		Floor	OF/VI	Project

Horizontal laminar flow clean bench, 4 foot; hepa supply filter 99.99% minimum efficiency in capturing 0.3 micrometer particles; interior width 46.5"w x 20-3/16"d x 28-1/8"h; removable stainless steel iv bar; caster wheel base View Cutsheet 164968

W x D x H: 50 x 35.9 x 71 in.

Electrical: 115V 60Hz 20A 1-Phase **Weight:** 440 lbs.

Elect Notes: 11 ft external length power cord with 20 amp nema 5-20 plug.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Caster Wheels		1	3
Motorized Base Stand		1	3

Room: Clean Hoods (Non-HD Compounding) **Department:** Pharmacy (Infusion)

Room #: B503E1

Room Notes: Pass thru Clean Hoods to Work Area

Hood, Safety Biological

AE #: HOSB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baker Company, The	SG404		Floor	OF/VI	Project

Sterilegard e3; class ii type A2 biosafety cabinet; 4-foot; interior dimension 46"w x 24-9/16"d x 27-7/16"h — View Cutsheet 165704

Not exhausted.

W x D x H: 53.8 x 30.6 x 111 in.
Electrical: 115V 60Hz 20A 1-Phase **Weight:** 655 lbs.
Elect Notes: **refer to manufacturer's specifications.** power cord 14 ft external length with 20 amp nema 5-20 plug.
Plumb Notes: **refer to manufacturer's specifications.**
HVAC Notes: **refer to manufacturer's specifications.**
Struct Notes: **refer to manufacturer's specifications.**

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Base stand w/hydraulic lift		1	1
Casters (set of 4)		1	1
Standard 8" Sash		1	1

Lab Shaker

AE #: LASH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	20215		Table	OF/OI	Project

Digital orbital shaker with vial stands. Speed range 20-300 rpm. Platform 11" x 11". — View Cutsheet 208661

W x D x H: 12.4 x 12.3 x 7.8 in.
Electrical: 115V 60Hz

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Network: Wired

Room: Clean Hoods (Non-HD Compounding) **Department: Pharmacy (Infusion)**

Room #: B503E1

Room Notes: Pass thru Clean Hoods to Work Area

Refrigerator, Double Door Glass — AE #: RPDD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Follett Corporation	REF45-BB-00000G		Floor	OF/VI	Project

Double dual-pane glass door refrigerator with 45 cu ft capacity; outer hinges; frost-free and auto evaporating condensate; 12 solid stainless steel baskets; on 6 heavy-duty casters; audible and visual alarms

View Cutsheet 167618

W x D x H: 59.8 x 33.6 x 79.5 in. **Clearance:** Rear 2 in.; Top 16 in.
Electrical: 115V 60Hz 12A 1-Phase **Weight:** 610 lbs.
Elect Notes: Max fuse 20 amps; dedicated circuit; NEMA hospital grade 90 degree 5-20P plug; 9' cord
HVAC Notes: Non-CFC refrigerant R134a; normal operation heat rejection 1480 BTU / hr.; max heat rejection with continuous operation 5240 BTU / hr.

Table, Prep — AE #: TAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Intermetro Industries	4824FS		Floor	OF/VI	Project

48x24 solid s/s shelf (2448FS) 3 each; 33" post (33UPS) 4 each; 5" caster s/s swivel (2) and brake (2).

View Cutsheet 208664

W x D x H: 48 x 24 x 33 in.

Table, Work — AE #: TAWO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	TWS2460FS-316-S		Floor	OF/VI	Project

316 ALL-STAINLESS WORKTABLE with bottom shelf. Height adjustable 34"-39".

View Cutsheet 208668

W x D x H: 60 x 24 x 35 in.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Clean Hoods (Non-HD Compounding) **Department: Pharmacy (Infusion)**

Room #: B503E1

Room Notes: Pass thru Clean Hoods to Work Area

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

For collecting HDPE #2 plastic

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Hazardous Hoods (HD Compounding) **Department: Pharmacy (Infusion)**

Room #: B503E2

Cart, Supply, 60x24x68

AE #: CASU-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Intermetro Industries	2460FS		Floor	OF/VI	Project

24x60 solid s/s shelf (2460FS) 6 each; 63" post with cap only (63UPS) 4 each; 5" polyurethane caster s/s swivel (5MPGSA) 2 each and 5" polyurethane caster s/s brake (5MPBGSA) 2 each. View Cutsheet 208660

W x D x H: 60 x 24 x 68 in.

Cart, Transfer

AE #: CATR-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	1424FS / 33UPS		Floor	OF/VI	Project

14x24 solid s/s shelf (1424fs) 3 each; 33-3/4" post with cap only (33ups) 4 each; 5" caster s/s swivel (2) and brake (2). View Cutsheet 168390

W x D x H: 14 x 24 x 36 in.

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Stericycle	H18B		Floor	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid View Cutsheet 209270

Supply item provided by warehouse

W x D x H: 12.5 x 17.3 x 24 in.

Container, Sharps

AE #: COSH-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004LR		Floor	OF/OI	Supply Agreement

8-gallon red bin (19.7”h x 13.0”d x 11.3 “w) for biohazard waste with wire step-on dolly. View Cutsheet 164306

W x D x H: 14.3 x 16.5 x 23 in.

Room: Hazardous Hoods (HD Compounding) **Department:** Pharmacy (Infusion)

Room #: B503E2

Dispenser, Sterillium

AE #: DIST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	LXT10AUTO		Wall	OF/CI	Project

Automatic sterillium dispenser. View Cutsheet 161507

Automatic model confirmed

W x D x H: 12 x 7 x 8 in.

Hood, Safety Biological

AE #: HOSB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Baker Company, The	SG404		Floor	OF/CI/VI	Project

Sterilegard e3; class ii type A2 biosafety cabinet; 4-foot; interior dimension 46"w x 24-9/16"d x 27-7/16"h View Cutsheet 165704

Clearance of 18" in back and 24" on sides for cleaning. Hood exhausted, fixed height, not on casters. Standard 8" sash and optional FlexAIR Canopy

Exhaust Connect required.

W x D x H: 53.8 x 30.6 x 111 in.
Electrical: 115V 60Hz 20A 1-Phase **Weight:** 655 lbs.
Elect Notes: **refer to manufacturer's specifications.** power cord 14 ft external length with 20 amp nema 5-20 plug.
Plumb Notes: **refer to manufacturer's specifications.**
HVAC Notes: **refer to manufacturer's specifications.** externally exhausted. 12" diameter air tight damper.
Struct Notes: **refer to manufacturer's specifications.**

Accessories:

Description	Catalog	Qty/Item	Ext Qty
FlexAIR Canopy Exhaust Connect		1	5
Standard 8" Sash		1	5

Lab Shaker

AE #: LASH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	20215		Table	OF/OI	Project

Digital orbital shaker with vial stands. Speed range 20-300 rpm. Platform 11" x 11". View Cutsheet 208661

W x D x H: 12.4 x 12.3 x 7.8 in.
Electrical: 115V 60Hz

Room: Hazardous Hoods (HD Compounding) **Department: Pharmacy (Infusion)**

Room #: B503E2

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Blood Bank, Single Door — AE #: REBB-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF25i-BB		Floor	OF/VI	Project

Upright 24.6 ft. capacity refrigerator with 6 full-extension stainless steel drawers, dual pane glass door with full length handle w/cylinder lock, and (4) swiveling dual wheel casters with toe locks. Full stainless steel cabinet interior and exterior. Audible and visual high/low temperature, door open, power failure, and low battery alarms. Energy star rated View Cutsheet 211193

model: REF25i-BB-R-00-00-G

W x D x H: 29.8 x 36.5 x 79.5 in. **Clearance:** Rear 2 in.; Top 10 in.
Electrical: 115V 60Hz 2.5A **Weight:** 427 lbs.
Elect Notes: NEMA 5-15P hospital grade plug and 9' cord. Maximum size of branch circuit overcurrent device - 15A dedicated circuit.
HVAC Notes: Integral top-mounted refrigeration module with 1/3 hp compressor and air-cooled condenser. Non-CFC R134a refrigerant (11.4 oz). BTU/hr normal heat rejection 1060 BTU/hr; maximum heat rejection continuous operation 3210 BTU/hr.
Struct Notes: 10" top clearance needed

Refrigerator, Double Door Glass — AE #: RPDD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF45-BB-00000G		Floor	OF/VI	Project

Double dual-pane glass door refrigerator with 45 cu ft capacity; outer hinges; frost-free and auto evaporating condensate; 12 solid stainless steel baskets; on 6 heavy-duty casters; audible and visual alarms View Cutsheet 167618

W x D x H: 59.8 x 33.6 x 79.5 in. **Clearance:** Rear 2 in.; Top 16 in.
Electrical: 115V 60Hz 12A 1-Phase **Weight:** 610 lbs.
Elect Notes: Max fuse 20 amps; dedicated circuit; NEMA hospital grade 90 degree 5-20P plug; 9' cord
HVAC Notes: Non-CFC refrigerant R134a; normal operation heat rejection 1480 BTU / hr.; max heat rejection with continuous operation 5240 BTU / hr.

Room: Hazardous Hoods (HD Compounding) **Department: Pharmacy (Infusion)**

Room #: B503E2

Table, Prep — AE #: TAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Intermetro Industries	4824FS		Floor	OF/VI	Project

48x24 solid s/s shelf (2448FS) 3 each; 33" post (33UPS) 4 each; 5" caster s/s swivel (2) and brake (2). View Cutsheet 208664

W x D x H: 48 x 24 x 33 in.

Table, Work — AE #: TAWO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	TWS2460FS-316-S		Floor	OF/VI	Project

316 ALL-STAINLESS WORKTABLE with bottom shelf. Height adjustable 34"-39". View Cutsheet 208668

W x D x H: 60 x 24 x 35 in.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Waste Receptacle, Recycle Bin — AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

For collecting HDPE #2 plastic

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Gene Therapy **Department: Pharmacy (Infusion)**

Room #: B503E3

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	H18B		Floor	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid

View Cutsheet 209270

Supply item provided by warehouse

W x D x H: 12.5 x 17.3 x 24 in.

Hood, Safety Biological

AE #: HOSB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baker Company, The	BCG401		Floor	OF/CI/VI	Project

4ft class ii, type b2 biological safety cabinet provides 100% exhausted hepa filtered air; standard features: air bypass armrest, (1) cable port, stediflow motor controller, readysafe low-flow mode, unipressure plenum airflow system. Specifications include -12" diameter exhaust collar; options to include: iv bar

View Cutsheet 167661

Clearance of 18" in back and 24" on sides for cleaning. Hood exhausted, fixed height, not on casters.

W x D x H: 53.9 x 33.6 x 94.5 in.
Electrical: 115V 60Hz 20A **Weight:** 720 lbs.
Elect Notes: Refer to manufacturer drawing document
Plumb Notes: Refer to manufacturer drawing document
HVAC Notes: Refer to manufacturer drawing document

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Iv Bar		1	1

Table, Prep

AE #: TAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	4824FS		Floor	OF/VI	Project

48x24 solid s/s shelf (2448FS) 3 each; 33" post (33UPS) 4 each; 5" caster s/s swivel (2) and brake (2).

View Cutsheet 208664

W x D x H: 48 x 24 x 33 in.

Room: Gene Therapy

Department: Pharmacy (Infusion)

Room #: B503E3

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

For collecting HDPE #2 plastic

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Work Area

Department: Pharmacy (Infusion)

Room #: B503F1

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Cart, Supply, 60x24x68

AE #: CASU-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	2460FS		Floor	OF/VI	Project

24x60 solid s/s shelf (2460FS) 6 each; 63" post with cap only (63UPS) 4 each; 5" polyurethane caster s/s swivel (5MPGSA) 2 each and 5" polyurethane caster s/s brake (5MPBGSA) 2 each.

View Cutsheet 208660

W x D x H: 60 x 24 x 68 in.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Work Area **Department: Pharmacy (Infusion)**

Room #: B503F1

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Blood Bank, Single Door — AE #: REBB-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF25i-BB		Floor	OF/VI	Project

Upright 24.6 ft. capacity refrigerator with 6 full-extension stainless steel drawers, dual pane glass door with full length handle w/cylinder lock, and (4) swiveling dual wheel casters with toe locks. Full stainless steel cabinet interior and exterior. Audible and visual high/low temperature, door open, power failure, and low battery alarms. Energy star rated View Cutsheet 211193

model: REF25i-BB-R-00-00-G

W x D x H: 29.8 x 36.5 x 79.5 in. **Clearance:** Rear 2 in.; Top 10 in.
Electrical: 115V 60Hz 2.5A **Weight:** 427 lbs.
Elect Notes: NEMA 5-15P hospital grade plug and 9' cord. Maximum size of branch circuit overcurrent device - 15A dedicated circuit.
HVAC Notes: Integral top-mounted refrigeration module with 1/3 hp compressor and air-cooled condenser. Non-CFC R134a refrigerant (11.4 oz). BTU/hr normal heat rejection 1060 BTU/hr; maximum heat rejection continuous operation 3210 BTU/hr.
Struct Notes: 10" top clearance needed

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Work Area

Department: Pharmacy (Infusion)

Room #: B503G

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Staff Lockers **Department: Pharmacy (Infusion)**

Room #: B503J

Room Notes: No hamper needed. Used scrubs go back into scrub receiver on level 2,

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Floor	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

For collecting HDPE #2 plastic

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Toilet (Staff)

Department: Pharmacy (Infusion)

Room #: B503J1, B503J2

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Non-HD Storage / Home Infusion **Department: Pharmacy (Infusion)**

Room #: B503K

Carousel System

AE #: CASY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	White	MiniVert 60		Floor	OF/CI/VI	Project

Vertical mobile carousel. Host computer interface provides for direct integration with software. Clean room - ISO3-ISO8. Pans 60"W x 9. Weight capacity 300 lbs. per pan x 9 pans = 2700 lbs. of available product storage. Must be used with either BD or Swisslog software. View Cutsheet 208413

Confirm with department if carousel will be leased from BD or purchased. Confirm if it is wanted with or without casters.

W x D x H: 88 x 49 x 78 in.
Clearance: Left 30 in.
Network: Wired
Network Notes: (4) Ethernet connections required: (1) for carousel, (1) for hospital-provided PC, and (2) for vendor-provided barcode scanner and Zebra printer.
Electrical: 115V 60Hz 15A 1-Phase
Weight: 1800 lbs.
Elect Notes: A total of (5) 115V power outlets needed for this system: (1) EM power outlet recommended for carousel. Normal or EM power for PC, monitor, Zebra printer, and barcode scanner.
Struct Notes: Weight of carousel empty = 1,800 lbs. Max product weight = 2,700 lbs. Total maximum weight = 4,500 lbs. Width noted does not include handle on left side. Desk recommended to right of carousel to support vendor-provided barcode scanner and Zebra printer and the hospital-provided PC. Subtract 8" from width if casters are not desired/used.

Cart, Drug Dispensing Unit

AE #: CDDU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	MFG-59140 CUSTOM TABLE		Floor	OF/OI	Project

Stainless steel mobile table w/4 locking swivel casters for holding a 250 lb pyxis machine. Ships assembled. View Cutsheet 171845

Confirm this option for supporting Pyxis 2-drawer unit vs. requested 3rd worktable.

W x D x H: 30 x 25 x 30 in.

Cart, Supply, 60x24x68

AE #: CASU-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Intermetro Industries	2460FS		Floor	OF/VI	Project

24x60 solid s/s shelf (2460FS) 6 each; 63" post with cap only (63UPS) 4 each; 5" polyurethane caster s/s swivel (5MPGSA) 2 each and 5" polyurethane caster s/s brake (5MPBGSA) 2 each. View Cutsheet 208660

2 for Infusion, 2 for Clinic, 2 for home infusion pumps. Four in room and two just outside room. Carts to have 4 solid stainless steel shelves.

W x D x H: 60 x 24 x 68 in.

Room: Non-HD Storage / Home Infusion

Department: Pharmacy (Infusion)

Room #: B503K

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 2-Drawer Main		Cart	OF/VI	Lease

ES platform: 2-drawer main unit View Cutsheet 150403

W x D x H: 22.8 x 27 x 27.8 in.
Network: Wired
Electrical: 120V 60Hz 3A **Weight:** 300 lbs.
Struct Notes: Counter height recommended 24" max to provide good ergonomics. Countertop depth required 30" to accommodate unit and provide stability. Raised edge countertop recommended.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Printer

AE #: PRIN-00

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	TBD		Desk	OF/VI	Lease

Provided by BD for Carousel. Specifications to be determined. No Cutsheet 209249

To sit on shelf on front of carousel or mounted to carousel.

W x D x H: 7 x 30 x 30 in.
Network: Wired
Electrical: 115V 60Hz

Room: Non-HD Storage / Home Infusion **Department: Pharmacy (Infusion)**

Room #: B503K

Rack, Dunnage — AE #: RADU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Logiquip Healthcare Storage Solutions	AL2448		Floor	OF/OI	Project

Lqs dunnage rack; aluminum; 48"w x 24"d x 12"h View Cutsheet 122977

W x D x H: 48 x 24 x 12 in.

Refrigerator, Blood Bank, Single Door — AE #: REBB-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Follett Corporation	REF25i-BB		Floor	OF/VI	Project

Upright 24.6 ft. capacity refrigerator with 6 full-extension stainless steel drawers, dual pane glass door with full length handle w/cylinder lock, and (4) swiveling dual wheel casters with toe locks. Full stainless steel cabinet interior and exterior. Audible and visual high/low temperature, door open, power failure, and low battery alarms. Energy star rated View Cutsheet 211193

model: REF25i-BB-R-00-00-G

W x D x H: 29.8 x 36.5 x 79.5 in. **Clearance:** Rear 2 in.; Top 10 in.
Electrical: 115V 60Hz 2.5A **Weight:** 427 lbs.
Elect Notes: NEMA 5-15P hospital grade plug and 9' cord. Maximum size of branch circuit overcurrent device - 15A dedicated circuit.
HVAC Notes: Integral top-mounted refrigeration module with 1/3 hp compressor and air-cooled condenser. Non-CFC R134a refrigerant (11.4 oz). BTU/hr normal heat rejection 1060 BTU/hr; maximum heat rejection continuous operation 3210 BTU/hr.
Struct Notes: 10" top clearance needed

Refrigerator, Pyxis, Undercounter — AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit. View Cutsheet 170325

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
Elect Notes: 15a dedicated ground circuit; nema 5-15 hospital grade plug 8-10 ft. Battery backup.
HVAC Notes: Variable speed compressor-based forced air refrigeration system; r600a, isobutane, epa snap compliant refrigerant charge

Room: Non-HD Storage / Home Infusion

Department: Pharmacy (Infusion)

Room #: B503K

Scanner, Barcode

AE #: SCBA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	TBD		Desk	OF/VI	Lease

Provided by BD for use with Carousel. Specifications to be determined. No Cutsheet 209250

W x D x H: 4 x 4 x 6 in.
Electrical: 115V 60Hz

Shelving, High Density

AE #: SHHD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Spacesaver Corp.	Custom		Floor	OF/CI/VI	Project

Custom high density shelving system with surface mounted steel rail and mechanical assist drive. Each unit is 42"W x 18"D. View Cutsheet 209361

W x D x H: 204 x 100 x 82.3 in.
Struct Notes: Designed to be used on normal industrial floors with no leveling required provided the floor flatness meets these specifications: 3/16" over any 2' run of rail, 1/4" over any 10' run of rail, and 1/4" from perpendicular points on adjacent rails.

Table, Work

AE #: TAWO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	TWS2460FS-316-S		Floor	OF/VI	Project

316 ALL-STAINLESS WORKTABLE with bottom shelf. Height adjustable 34"-39". View Cutsheet 208668

One is for 2-drawer Pyxis. May consider smaller, lower cart instead. Confirm height requirements.

W x D x H: 60 x 24 x 35 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Floor	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Hazardous Storage

Department: Pharmacy (Infusion)

Room #: B503K1

Room Notes: Pass-thru Haz Storage to Haz Hoods

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Cabinet, Safety, Flammable Storage

AE #: CASF-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Eagle Manufacturing Co.	2310X		Floor	OF/OI	Project

24 Gallon, self-closing, Space Saver Flammable Liquid Safety Cabinet is constructed of 18-gauge (1 mm) steel. The sides, top, bottom, and doors are double-walled with a 1-1/2 in (3.8 cm) air space between walls. Includes two vents, each have 2 in (5.1 cm) threaded fittings and a fire baffle and cap. Cabinets have a high gloss powder coat finish with red trilingual warning, plus grounding attachment, 3-point latch system, and 2-in (5.1 cm) raised, leakproof door sill. Each shelf is adjustable on 3 in (7.6 cm) centers, supported by 4 brackets, with a 350 lbs (159 kg) safe allowable load. Cabinets are FM-Approved and meet NFPA Code 30 and OSHA requirements.

View Cutsheet 208770

W x D x H: 23.3 x 18 x 65 in.

Weight: 178 lbs.

Cart, Supply, 60x24x68

AE #: CASU-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	2460FS		Floor	OF/VI	Project

24x60 solid s/s shelf (2460FS) 6 each; 63" post with cap only (63UPS) 4 each; 5" polyurethane caster s/s swivel (5MPGSA) 2 each and 5" polyurethane caster s/s brake (5MPBGSA) 2 each.

View Cutsheet 208660

W x D x H: 60 x 24 x 68 in.

Room: Hazardous Storage **Department: Pharmacy (Infusion)**

Room #: B503K1

Room Notes: Pass-thru Haz Storage to Haz Hoods

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Drug Dispensing Unit, Auxiliary

AE #: DDUA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pyxis / Becton Dickinson & Co.	ES DOUBLE COLUMN AUXILIARY		Floor	OF/VI	Lease

Double column auxiliary (8 doors) View Cutsheet 158541

W x D x H: 52 x 28 x 79.5 in.
Electrical: 120V 60Hz 3A

Room: Hazardous Storage **Department:** Pharmacy (Infusion)

Room #: B503K1

Room Notes: Pass-thru Haz Storage to Haz Hoods

Freezer, Upright

AE #: FRUP-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	FZR25-LB		Floor	OF/VI	Project

Full stainless steel interior and exterior; heavy-duty dual locking casters; four shelves; right hinged solid 2.6" thick insulated stainless steel door with ada-compliant full length locking handle; lcd displays temperature; audible and visual high / low temperature, door open, power failure, low battery alarms; rs-485 port and dry contacts for data streaming and remote alarming. 24.6 cu ft capacity. View Cutsheet 156594

W x D x H: 29.8 x 36.5 x 79.5 in. **Clearance:** Rear 2 in.; Left 9 in.; Top 16 in.
Electrical: 115V 60Hz 12A 1-Phase **Weight:** 370 lbs.
Elect Notes: Nema 5-20 90 degree hospital-grade plug. Max fuse 20a. Cord 9' long
HVAC Notes: Max heat rejection: 2400 btu/hr. Maximum ambient temperature 86 f / 30 c. **requires 9" clearance on left side only if ambient temperature is >86 degrees f.

Lab Freezer, Ultralow

AE #: LAFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	TSX500		Floor	OF/VI	Project

24.1 CU Ft Ultra Low Freezer. Temperature Range -50°C to -86°C. Three Shelves. 500 Box Capacity. View Cutsheet 207287

W x D x H: 34 x 37.6 x 78 in.
Electrical: 115V 60Hz 9.5A **Weight:** 627 lbs.
Elect Notes: NEMA 5-15

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
8	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Room: Hazardous Storage **Department: Pharmacy (Infusion)**

Room #: B503K1

Room Notes: Pass-thru Haz Storage to Haz Hoods

Refrigerator, Blood Bank, Single Door

AE #: REBB-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
8	Follett Corporation	REF25i-BB		Floor	OF/VI	Project

Upright 24.6 ft. capacity refrigerator with 6 full-extension stainless steel drawers, dual pane glass door with full length handle w/cylinder lock, and (4) swiveling dual wheel casters with toe locks. Full stainless steel cabinet interior and exterior. Audible and visual high/low temperature, door open, power failure, and low battery alarms. Energy star rated

View Cutsheet 211193

model: REF25i-BB-R-00-00-G

W x D x H: 29.8 x 36.5 x 79.5 in. **Clearance:** Rear 2 in.; Top 10 in.
Electrical: 115V 60Hz 2.5A **Weight:** 427 lbs.
Elect Notes: NEMA 5-15P hospital grade plug and 9' cord. Maximum size of branch circuit overcurrent device - 15A dedicated circuit.
HVAC Notes: Integral top-mounted refrigeration module with 1/3 hp compressor and air-cooled condenser. Non-CFC R134a refrigerant (11.4 oz). BTU/hr normal heat rejection 1060 BTU/hr; maximum heat rejection continuous operation 3210 BTU/hr.
Struct Notes: 10" top clearance needed

Table, Work

AE #: TAWO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	TWS2460FS-316-S		Floor	OF/VI	Project

316 ALL-STAINLESS WORKTABLE with bottom shelf. Height adjustable 34"-39".

View Cutsheet 208668

W x D x H: 60 x 24 x 35 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Receiving

Department: Pharmacy (Infusion)

Room #: B503L

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Rack, Dunnage

AE #: RADU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Logiquip Healthcare Storage Solutions	AL2448		Floor	OF/OI	Project

Lqs dunnage rack; aluminum; 48"w x 24"d x 12"h

View Cutsheet 122977

W x D x H: 48 x 24 x 12 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Breakdown / Waste

Department: Pharmacy (Infusion)

Room #: B503L1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Rack, Dunnage

AE #: RADU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Logiquip Healthcare Storage Solutions	AL2448		Floor	OF/OI	Project

Lqs dunnage rack; aluminum; 48"w x 24"d x 12"h

View Cutsheet 122977

W x D x H: 48 x 24 x 12 in.

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side.

View Cutsheet 209162

One for trash, one for cardboard

W x D x H: 31 x 53 x 38 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue.

View Cutsheet 91514

For cold packs

W x D x H: 31 x 43.8 x 37 in.

Room: Shared Work Area (Off stage) **Department:** Precision Medicine

Room #: A509K, B501Y1

Room Notes: Assumes space for 8 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient)

Department: Precision Medicine

Room #: B501A, B501J, B507F

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Precision Medicine

Room #: B501A, B501J, B507F

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department:** Precision Medicine

Room #: B501B, B501C, B501D, B501E, B501F, B501H, B501S, B501U, B502C, B502E, B502G, B502J

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room **Department:** Precision Medicine

Room #: B501B, B501C, B501D, B501E, B501F, B501H, B501S, B501U, B502C, B502E, B502G, B502J

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Room: Exam Room **Department:** Precision Medicine

Room #: B501B, B501C, B501D, B501E, B501F, B501H, B501S, B501U, B502C, B502E, B502G, B502J

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Sphygmomanometer, Aneroid, Wall Mount

AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Room: Exam Room **Department:** Precision Medicine

Room #: B501B, B501C, B501D, B501E, B501F, B501H, B501S, B501U, B502C, B502E, B502G, B502J

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power — AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Room: Exam Room **Department:** Precision Medicine

Room #: B501B, B501C, B501D, B501E, B501F, B501H, B501S, B501U, B502C, B502E, B502G, B502J

Thermometer, Electronic, Oral

AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius

View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area

Department: Precision Medicine

Room #: B501G

Room Notes: Closed, space for 12 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder Unable to provide larger Tote Bin per UK recycling.

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area (Central) **Department:** Precision Medicine

Room #: B501G1

Room Notes: Open/half-wall for 12 people

Bin, Plastic — AE #: BIPL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Akro-Mils / Myers Industries	AKROBIN	30270BLUE	Countertop	OF/OI	Project

Heavy-duty plastic akrobin in blue; can sit on counter or hang from louvered racks and panels, rail racks, and louvered carts for high-density storage; corrosion-proof. View Cutsheet 167300

For chemo drop off

W x D x H: 16.5 x 18 x 11 in.

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder Unable to provide larger Tote Bin per UK recycling.

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Room: On-Stage Team Work Area (Central) **Department:** Precision Medicine

Room #: B501G1

Room Notes: Open/half-wall for 12 people

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Infusion (Bed) **Department:** Precision Medicine

Room #: B501K, B501M, B501N, B501P

Basket, Sphygmomanometer — AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Bed, Electric — AE #: BEEL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	S3 EX	3005S3EX	Floor	OF/VI	Project

Med / surg bed. Siderails designed with one-hand operation and an intermediate position for patient assistance during bed entry and exit. Open architecture platform. Centrally located brake pedal. 500 lb weight capacity. Capable of linking to hospital network via wireless or wired connection. View Cutsheet 149049

W x D x H: 41.5 x 93 x 30 in.
Network: Networked
Electrical: 120V 60Hz 8A

Bed, Electric, Component — AE #: BEEC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	AIR PUMP	2861000025	Bed	OF/VI	Project

Air pump for use with isoflex lal 2860 surface View Cutsheet 165842

W x D x H: 8 x 5 x 8.5 in.
Electrical: 120V 60Hz 0.25A **Weight:** 5.5 lbs.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Room: Infusion (Bed) **Department: Precision Medicine**

Room #: B501K, B501M, B501N, B501P

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: Infusion (Bed) **Department:** Precision Medicine

Room #: B501K, B501M, B501N, B501P

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Infusion (Bed) **Department:** Precision Medicine

Room #: B501K, B501M, B501N, B501P

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Accessory Basket

AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: Infusion (Bed) **Department:** Precision Medicine

Room #: B501K, B501M, B501N, B501P

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Ophthalmoscope/ Otoscope — AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Pump, I.V. — AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Room: Infusion (Bed) **Department:** Precision Medicine

Room #: B501K, B501M, B501N, B501P

Pump, I.V., Component — AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Aneroid, Wall Mount — AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Infusion (Bed) **Department:** Precision Medicine

Room #: B501K, B501M, B501N, B501P

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527
pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Table, Overbed — AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet View Cutsheet 211777
Holder (1), Hanging Shelf (1).

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Room: Infusion (Bed)

Department: Precision Medicine

Room #: B501K, B501M, B501N, B501P

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Medication Room **Department:** Precision Medicine

Room #: B501L

Room Notes: Request for sink made by nursing staff.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Medication Room **Department:** Precision Medicine

Room #: B501L

Room Notes: Request for sink made by nursing staff.

Drug Dispensing Unit — AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit — View Cutsheet 150404

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A

Drug Dispensing Unit, Auxiliary — AE #: DDUA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES HALF HEIGHT COLUMN		Floor	OF/VI	Lease

Half height column auxiliary — View Cutsheet 158539

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 31 x 28 x 43 in.
Electrical: 120V 60Hz 0.9A

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. — View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Medication Room **Department:** Precision Medicine

Room #: B501L

Room Notes: Request for sink made by nursing staff.

Ice Maker / Water Dispenser — AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Medication Room **Department:** Precision Medicine

Room #: B501L

Room Notes: Request for sink made by nursing staff.

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 24 x 29 x 32 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 1.4A
Weight: 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient, Lead Lined)

Department: Precision Medicine

Room #: B501Q1, B501R1, B501T1, B501V1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient, Lead Lined)

Department: Precision Medicine

Room #: B501Q1, B501R1, B501T1, B501V1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Equipment / EKG Closet **Department:** Precision Medicine

Room #: B501Q2

Room Notes: Research EKGs here. Only (1) mobile cart needed

Cart, Electrocardiograph

AE #: CAEL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC 2000		Floor	OF/OI	Project

MAC compact trolley is available for add-on if you would like to mount it for easy transportation around your clinical practice. View Cutsheet 209133

W x D x H: 20 x 20 x 37 in.

Electrocardiograph

AE #: ELEC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
7	GE Healthcare	MAC 2000		Shelf	OF/OI	Research

View Cutsheet 168157

Provided by research study.

W x D x H: 28 x 28 x 32 in.

Network: Networked **Network Notes:** Wired or wireless bidirectional communication

Electrical: 120V 60Hz 4A

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Basket, Sphygmomanometer — AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Supply — AE #: CASU-17

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Innerspace Corp / Stanley	Narrow Pace 21	SPN21W4	Floor	OF/VI	Project

The narrow version of the Pace 21 cart accommodates a variety of interior and exterior accessories. It has a lightweight aluminum case, durable and stable bumper and base, seamless work surface with raised edges, 5” medical-grade casters, and keyed lock. View Cutsheet 211771

Changed from Armstrong AMC-4 cart, item 134924

W x D x H: 17 x 24.5 x 33 in.

Weight: 75 lbs.

Container, Pharmacy Waste - Black — AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly. View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Container, Sharps, Lead Lined — AE #: CSLL-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Biodex Medical Systems, Inc	039-325		Floor	OF/OI	Project

Sharps shield constructed of steel with 0.125" lead; accommodates small and medium monoject sharps containers View Cutsheet 52082

W x D x H: 11.8 x 7.5 x 10 in.

Weight: 48 lbs.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Monitor, Accessory Basket — AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Ophthalmoscope/ Otoscope — AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Pump, I.V. — AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.

Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Aneroid, Wall Mount

AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Room: Infusion (Theranostic - Recliner) **Department:** Precision Medicine

Room #: B501Q, B501R, B501T

Room Notes: Plan for recliner (furniture)

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1). View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Infusion (Theranostic - Bed) **Department:** Precision Medicine

Room #: B501V

Basket, Sphygmomanometer — AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Bed, Electric — AE #: BEEL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	S3 EX	3005S3EX	Floor	OF/VI	Project

Med / surg bed. Siderails designed with one-hand operation and an intermediate position for patient assistance during bed entry and exit. Open architecture platform. Centrally located brake pedal. 500 lb weight capacity. Capable of linking to hospital network via wireless or wired connection. View Cutsheet 149049

W x D x H: 41.5 x 93 x 30 in.
Network: Networked
Electrical: 120V 60Hz 8A

Bed, Electric, Component — AE #: BEEC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	AIR PUMP	2861000025	Bed	OF/VI	Project

Air pump for use with isoflex lal 2860 surface View Cutsheet 165842

W x D x H: 8 x 5 x 8.5 in.
Electrical: 120V 60Hz 0.25A **Weight:** 5.5 lbs.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Room: Infusion (Theranostic - Bed) **Department:** Precision Medicine

Room #: B501V

Cart, Supply

AE #: CASU-17

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Innerspace Corp / Stanley	Narrow Pace 21	SPN21W4	Floor	OF/VI	Project

The narrow version of the Pace 21 cart accommodates a variety of interior and exterior accessories. It has a lightweight aluminum case, durable and stable bumper and base, seamless work surface with raised edges, 5” medical-grade casters, and keyed lock. View Cutsheet 211771

Changed from Armstrong AMC-4 cart, item 134924

W x D x H: 17 x 24.5 x 33 in.

Weight: 75 lbs.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly. View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Container, Sharps, Lead Lined

AE #: CSLL-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Biodex Medical Systems, Inc	039-325		Floor	OF/OI	Project

Sharps shield constructed of steel with 0.125" lead; accommodates small and medium monoject sharps containers View Cutsheet 52082

W x D x H: 11.8 x 7.5 x 10 in.

Weight: 48 lbs.

Room: Infusion (Theranostic - Bed)

Department: Precision Medicine

Room #: B501V

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Infusion (Theranostic - Bed) **Department:** Precision Medicine

Room #: B501V

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. Available by the each or in case of 4.

View Cutsheet 209178

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Accessory Basket

AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook

View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration.

View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Infusion (Theranostic - Bed) **Department: Precision Medicine**

Room #: B501V

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Ophthalmoscope/ Otoscope — AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Room: Infusion (Theranostic - Bed) **Department:** Precision Medicine

Room #: B501V

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Room: Infusion (Theranostic - Bed)

Department: Precision Medicine

Room #: B501V

Sphygmomanometer, Aneroid, Wall Mount

AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Infusion (Theranostic - Bed) **Department:** Precision Medicine

Room #: B501V

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Closet, Hot Storage

Department: Precision Medicine

Room #: B501V2

Cabinet, Lead Lined, Decay

AE #: CLLD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Mirion Technologies	244-140		Floor	OF/CI	Project

Lead-lined key-locking decay cabinet with 0.25" lead and 2 adjustable shelves that support up to 100 lbs. each. Stainless steel countertop with 4" backsplash and 1/2" spill resistant lip. Cabinet will accommodate sharps containers and other boxed waste prior to disposal. It can also be used to store flood sources.

View Cutsheet 209537

W x D x H: 30.5 x 24.8 x 40.3 in.

Weight: 1010 lbs.

Cart, Therapy

AE #: CATH-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	FG409500BLA		Floor	OF/OI	Project

Enclosed cart with 2 shelves and 300 lbs. maximum load capacity. Color black. Includes (4) swivel casters.

View Cutsheet 209471

W x D x H: 40.6 x 20.8 x 37.8 in.

Room: Consult / Consent Room

Department: Precision Medicine

Room #: B501W

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Clean Supply / Linen

Department: Precision Medicine

Room #: B501X

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system

No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired

Network Notes: One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position.

View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures.

View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z)

View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Room: Clean Supply / Linen

Department: Precision Medicine

Room #: B501X

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Mask, PAPR

AE #: MAPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	3M Healthcare	VERSAFLO TR-600			OF/OI	Project

Versaflo tr-600 papr with chemical cartridge and double shroud papr hood. Dimensions for all pieces in carrying case. View Cutsheet 168022

W x D x H: 20 x 11 x 12 in.

Electrical: 120V 60Hz 1.5A

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Room: Nourishment, Staff **Department:** Precision Medicine

Room #: B501Y

Coffee Brewer

AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately. View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Nourishment, Staff **Department:** Precision Medicine

Room #: B501Y

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Nourishment, Staff **Department:** Precision Medicine

Room #: B501Y

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers — No Cutsheet 141809

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required — View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. — No Cutsheet 209142

Refrigerator Freezer, Upright — AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant. — View Cutsheet 208926

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Room: Nourishment, Staff

Department: Precision Medicine

Room #: B501Y

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling w/ Lid/Sign

AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign.

View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Alcove, Height / Weight **Department:** Precision Medicine

Room #: B502A

Room Notes: Ht/Wt only

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Wheelchair — AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Stadiometer — AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.
Weight: 3.7 lbs.

Room: Alcove, Height / Weight

Department: Precision Medicine

Room #: B502A

Room Notes: Ht/Wt only

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Mobile Equipment / Crash Cart

Department: Precision Medicine

Room #: B502B

Room Notes: Add crash cart here

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Room: Mobile Equipment / Crash Cart **Department:** Precision Medicine

Room #: B502B

Room Notes: Add crash cart here

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	2

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Mobile Equipment / Crash Cart

Department: Precision Medicine

Room #: B502B

Room Notes: Add crash cart here

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Mobile Equipment / Crash Cart

Department: Precision Medicine

Room #: B502B

Room Notes: Add crash cart here

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Toilet (Staff)

Department: Precision Medicine

Room #: B502H

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Office, Private

Department: Precision Medicine

Room #: B507B, B507C

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: On-Stage Team Work Area

Department: Precision Medicine

Room #: B507D1

Room Notes: Open/half-wall, space for 6 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder Unable to provide larger Tote Bin per UK recycling.

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Infusion (Recliner)

Department: Precision Medicine

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly. View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Room: Infusion (Recliner) **Department:** Precision Medicine

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Infusion (Recliner) **Department:** Precision Medicine

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Accessory Basket

AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Room: Infusion (Recliner) **Department: Precision Medicine**

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor — AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Room: Infusion (Recliner) **Department:** Precision Medicine

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Infusion (Recliner) **Department:** Precision Medicine

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Aneroid, Wall Mount

AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Infusion (Recliner) **Department:** Precision Medicine

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet View Cutsheet 211777

Holder (1), Hanging Shelf (1).

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Room: Infusion (Recliner) **Department: Precision Medicine**

Room #: B507D, B507E, B507G, B507H

Room Notes: Plan for recliner (furniture)

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Blanket Warmer **Department:** Precision Medicine

Room #: B507F1

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Vein Illuminator

AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz. View Cutsheet 168583

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	1

Room: Nourishment **Department:** Precision Medicine

Room #: B507H1

Coffee Brewer

AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately. View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Nourishment **Department:** Precision Medicine

Room #: B507H1

Ice Maker / Water Dispenser — AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Nourishment **Department:** Precision Medicine

Room #: B507H1

Refrigerator Freezer, Upright

AE #: REFU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Frigidaire / Electrolux Home Products	FFTR2045VS		Floor	OF/OI	Project

This 20 cu. ft. top-freezer refrigerator fits in the same sized cutout as a traditional 18 cu. ft. model, but with more capacity. Available with a left or right hinge. Colors: white, stainless steel, or black. View Cutsheet 211623

Left side hinge preferred in this location

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 0.38 in.
Electrical: 120V 60Hz 2A
Elect Notes: *Refer to user manual* 15 A dedicated circuit required.
Plumb Notes: *Refer to user manual* Access to a household cold water line with water pressure between 30 and 100 psi.
HVAC Notes: *Refer to user manual* Not Energy Star certified. Annual energy 427 kWh. Refrigerant R-600a.
Struct Notes: *Refer to user manual*

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Waste Receptacle, Recycling w/ Lid/Sign

AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign. View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Family / Quiet Waiting

Department: Precision Medicine

Room #: B507J

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Research Lab **Department:** Precision Medicine

Room #: B507K

Check Source

AE #: CHSO-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	01-5196		Countertop	OF/OI	Project

Luci 137 cesium check source

View Cutsheet 122361

Confirmed with Bryan Lemieux. Mount to survey meter

W x D x H: 1 x 0.1 x 1 in.

Container, Sharps

AE #: COSH-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203 / 0203SB		Countertop	OF/OI	Supply Agreement

Durable resin countertop stability base affixes a 2 or 3 gallon Vertical Drop Container (or 4 gallon Horizontal Drop Container) to any flat, stable surface.

View Cutsheet 209187

The base can be attached to the surface with semi-permanent adhesive strips or screws.

W x D x H: 12.5 x 7 x 21.1 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Research Lab **Department:** Precision Medicine

Room #: B507K

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Holder, Sample

AE #: HOSA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	180-2	47-1665	Countertop	OF/OI	Project

Sample holder for use with 44-9 detector; indicated use: repeatable geometry counting of wipes, filter paper, or slides. Sample size 5.1 cm diameter maximum. View Cutsheet 209545

Confirmed with Bryan Lemieux. Mount on survey meter with check source.

W x D x H: 3 x 6 x 3.6 in.

Weight: 0.9 lbs.

Room: Research Lab **Department:** Precision Medicine

Room #: B507K

Lab Centrifuge, Refrigerated, Counter Top

AE #: LCRC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Beckman Coulter, Inc	Avanti J-15R IVD		Countertop	OF/VI	Project

The Avanti™ J-15R benchtop centrifuge (refrigerated) leverages the ultra harmonic technology, designed to protect your sample and increase workflow time efficiency. Ultra harmonic technology leverages intelligent acceleration and deceleration profiles, reduces sample disturbances and provides time savings. Ultra harmonic technology, Workflow optimization, Sample protection ,Time efficiency

Multi-dimension imbalance tolerance

One centrifuge needed for radioactive specimen processing. Confirm total quantity needed.

View Cutsheet 208408

W x D x H: 29.8 x 27.7 x 14.5 in. **Clearance:** Rear 3 in.; Left 3 in.; Right 3 in.
Electrical: 120V 60Hz 12A **Weight:** 264.6 lbs.

Lab Freezer

AE #: LAFR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fisher Scientific - Thermo	TSX3030FA		Floor	OF/VI	Project

Thermo Scientific™ TSX Series high-performance -30°C auto defrost freezers are designed with features that support sample protection and sustainability objectives for the storage reagents, pharmaceuticals, vaccines, biological and other commonly used laboratory and clinical materials such as primers, siRNA molecules and fetal bovine serum (FBS) requiring -30°C. The Series' V-drive technology is designed to provide temperature uniformity that continually adapts to user patterns, offering significant energy savings without compromising protection. Capacity: 29.2 cu ft.

View Cutsheet 209053

W x D x H: 34 x 37.9 x 78.5 in.
Electrical: 115V 60Hz **Weight:** 371 lbs.
Elect Notes: 15-amp dedicated ground circuit. Nema 5-15 hospital grade plug (115v).

Lab Freezer, Ultralow

AE #: LAFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Thermo Fisher Scientific	TSX500		Floor	OF/VI	Project

24.1 CU Ft Ultra Low Freezer. Temperature Range -50°C to -86°C. Three Shelves. 500 Box Capacity.

View Cutsheet 207287

W x D x H: 34 x 37.6 x 78 in.
Electrical: 115V 60Hz 9.5A **Weight:** 627 lbs.
Elect Notes: NEMA 5-15

Room: Research Lab **Department:** Precision Medicine

Room #: B507K

Lab Waterbath

AE #: LAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Fisher Scientific - Thermo	22-047-771		Countertop	OF/VI	Project

Microprocessor-controlled heating from ambient to 65°C

View Cutsheet 207303

High contrast background illuminated by a bright LED array provides optimal specimen viewing. Removable glass dish permits easy cleaning

Scratch-, heat- and chemical-resistant plastic housing.

W x D x H: 18.8 x 11.8 x 5.25 in.
Electrical: 120V 60Hz 1.75A

Meter, Survey

AE #: MESU-33

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ludlum Measurements, Inc.	Model 3	48-1605	Countertop	OF/OI	Project

General purpose analog ratemeter supports GM and scintillation detectors.

View Cutsheet 209520

Confirmed with Bryan. Use with check source, probe clip, portable scaler, and check source holder

W x D x H: 3.5 x 8.5 x 6.5 in.

Weight: 3.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Mechanical Check Source Holder	4062-166	1	1
Portable Scaler	4464-114	1	1
Probe Clip	4010-008-01	1	1

Monitor, Humidity

AE #: MOHU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sensoscientific Inc.	Humidity and Temperature Sensor	B13-200-OTA	Wall	OF/CI/VI	Project

Monitor ambient temperature and humidity up to 125°C and 100% RH. Price includes humidity probe.

View Cutsheet 208486

W x D x H: 3.88 x 1.38 x 4.25 in.
Electrical: 120V 60Hz 0.5A
Elect Notes: Battery operated. Optional AC/DC power supply (UL Certified). AC Adapter: Input: 100-240V-50/60hz 0.5A Max, Output: 5V at 3.1A

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tridium			Freezer	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room.

No Cutsheet 209142

Room: Research Lab **Department:** Precision Medicine

Room #: B507K

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Upright, Pharmacy, Single Door — AE #: RPSD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF25-PH		Floor	OF/VI	Project

24.6 cu ft upright refrigerator, 6 epoxy-coated baskets, dual pane glass door, ada compliant, full length handle with integral lock, heavy-duty corrosion resistant stainless steel, (4) dual-wheel swiveling casters with toe lock, left hinged door. View Cutsheet 129363

Specify right hinge

W x D x H: 29.8 x 36.5 x 79.5 in.
Clearance: Rear 2 in.; Top 10 in.
Electrical: 115V 60Hz 8.7A
Weight: 415 lbs.
Elect Notes: 4.8 kwh/day
HVAC Notes: 1050 btu/hr

Waste Container, Lead Lined — AE #: WCLL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Capintec, Inc	039-110		Floor	OF/OI	Project

This Shielded Waste Container is used in facilities that generate low-energy beta and gamma radiation waste. The interior of the container is constructed of .063" aluminum and .25" lead. View Cutsheet 208730

Per Kimyli, depending on cabinetry, we may not need this

W x D x H: 12 x 9 x 22 in.
Weight: 120 lbs.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

Confirm with Bryan Lemieux about radioactive waste bin

W x D x H: 11.3 x 20.4 x 30 in.

Room: Research Lab

Department: Precision Medicine

Room #: B507K

Waste Receptacle, Recycle Bin

AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack

View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Soiled Hold

Department: Precision Medicine

Room #: PM0047

Room Notes: Shared with Apheresis - See Room A509E1

Room: Alcove, Hamper

Department: Precision Medicine

Room #: PM0069

Room Notes: Location TBD

Room: Consult

Department: Head, Neck, RC Clinic

Room #: A601A, A601B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight **Department:** Head, Neck, RC Clinic

Room #: A601B1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Wheelchair — AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Stadiometer — AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.
Weight: 3.7 lbs.

Room: Alcove, Height / Weight

Department: Head, Neck, RC Clinic

Room #: A601B1

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Exam Room **Department: Head, Neck, RC Clinic**

Room #: A601C, A601D, A601E, A601F, A601G, A601H, A601L, A601N, A601P, B601N, B601P, B601Q, B601T, B601U, B601V, B601W, B601Y

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room **Department: Head, Neck, RC Clinic**

Room #: A601C, A601D, A601E, A601F, A601G, A601H, A601L, A601N, A601P, B601N, B601P, B601Q, B601T, B601U, B601V, B601W, B601Y

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Exam Room **Department: Head, Neck, RC Clinic**

Room #: A601C, A601D, A601E, A601F, A601G, A601H, A601L, A601N, A601P, B601N, B601P, B601Q, B601T, B601U, B601V, B601W, B601Y

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended.
Department prefers no arms for procedures, but would like as an option for fall risk. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Room: Exam Room **Department: Head, Neck, RC Clinic**

Room #: A601C, A601D, A601E, A601F, A601G, A601H, A601L, A601N, A601P, B601N, B601P, B601Q, B601T, B601U, B601V, B601W, B601Y

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area

Department: Head, Neck, RC Clinic

Room #: A601J, A601K, B601Z, A610A, A610H

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Treatment

Department: Head, Neck, RC Clinic

Room #: A601M

Cabinet, Exam/ Treatment, E.N.T.

AE #: CAET-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	TC100C		Floor	OF/VI	Project

Sit-down height ENT treatment cabinet. Countertop height 33.5"H with 15"H backwall w/stainless steel shelf, (2) countertop recessed cordless instrument handle charger wells, right hand hose location, (2) application bottles, backwall mouonted glass bead mirror warmer, left side endoscope cold storage tubes (confirm size and mounting), and 4-port LED light source.

View Cutsheet 208941

Review cut sheet and confirm options.Per CME quote 406078-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 35.5 x 21 x 48.5 in.
Electrical: 115V 60Hz 7.5A

Cart, Electrosurgical

AE #: CAES-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	VLFTCRT		Floor	OF/OI	Project

Mobile cart for electrosurgical unit. Three shelves. Dimensions include cart and electrosurgical unit.

View Cutsheet 161483

W x D x H: 24 x 24 x 35 in.

Cart, Procedure

AE #: CAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

Polymer cart on caster; with (1) 3", (3) 6" and (1) 9" drawer; Electronic PIN locking; Pull handles.

View Cutsheet 200197

Drawer configuration to be determined by dept

W x D x H: 22.7 x 24.9 x 44.7 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Treatment

Department: Head, Neck, RC Clinic

Room #: A601M

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Cart	OF/OI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes.

View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Room: Treatment **Department:** Head, Neck, RC Clinic

Room #: A601M

Electrosurgical Unit — AE #: ELUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medtronic / Covidien	FT10	VLFT10GEN	Cart	OF/OI	Project

Electrosurgical unit with monopolar, bipolar, vessel sealing, and tissue sensing technology; fuses vessels up to and including 7mm; automatic instrument recognition; all-in-one unit compatible with all ligasure instruments. View Cutsheet 147652

Model confirmed in signoff meeting 2/5/2024.

W x D x H: 14.5 x 18.2 x 7 in.
Electrical: 120V 60Hz 9A **Weight:** 22.3 lbs.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Treatment **Department:** Head, Neck, RC Clinic

Room #: A601M

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation.

View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz
Weight: 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Monitor, Physiological

AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle.

View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 115V 60Hz 1.8A
Weight: 12.3 lbs.

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Room: Treatment

Department: Head, Neck, RC Clinic

Room #: A601M

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Ophthalmoscope

AE #: OPHT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	11720-L		Cart	OF/OI	Project

3.5v coaxial ophthalmoscope. Long-lasting LED illumination. Works with all Welch Allyn 3.5v power sources. View Cutsheet 205877

W x D x H: 1.77 x 2.95 x 3.15 in.

Otoscope

AE #: OTOS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Hillrom Company, Inc.	250-2		Cart	OF/OI	Project

Diagnostic 3.5V LED otoscope. Wide-angle viewing lens. Works with all Welch Allyn 3.5V power sources. Includes a port for pneumatic otoscopy. View Cutsheet 208578

Room: Treatment
Room #: A601M

Department: Head, Neck, RC Clinic

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A
Weight: 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Rechargeable Handle

AE #: REHA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Hillrom Company, Inc.	719-3		Cart	OF/OI	Project

Lithium Ion Plus Power handle with integrated USB-C charger. Also compatible with Welch Allyn Universal Desk Charger 719-DSK and 71140 chargers.

View Cutsheet 206571

W x D x H: 1.18 x 1.18 x 5.51 in.
Weight: 0.31 lbs.

Room: Treatment **Department:** Head, Neck, RC Clinic

Room #: A601M

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Room: Treatment **Department:** Head, Neck, RC Clinic

Room #: A601M

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

Department prefers no arms for procedures, but would like as an option for fall risk.

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Table, Instrument

AE #: TAIN-99

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7842SS		Floor	OF/OI	Project

Stainless steel instrument table with h-brace base; two inch swivel casters View Cutsheet 14192

Department prefers H-brace table

W x D x H: 36 x 20 x 34 in.

Room: Treatment

Department: Head, Neck, RC Clinic

Room #: A601M

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red

View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Medication Alcove **Department: Head, Neck, RC Clinic**

Room #: A608L

Room Notes: Shared with Heme/BMT

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 6-Drawer Main		Floor	OF/VI	Lease

ES platform: 6-drawer main unit View Cutsheet 150404

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 22.8 x 27 x 55 in.
Network: Wired
Electrical: 120V 60Hz 3A
Elect Notes: Must be located within 6' of the electrical outlet. Fuse: 6.3a. Power and data connections are made to frames at the back right of the computer (53-57" a.f.f.). Power cord length is 15'.
HVAC Notes: 200-600 btu/hr.

Room: Medication Alcove **Department: Head, Neck, RC Clinic**

Room #: A608L

Room Notes: Shared with Heme/BMT

Drug Dispensing Unit, Auxiliary — AE #: DDUA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	PYXIS ES SINGLE COLUMN		Floor	OF/VI	Lease

Single column auxiliary with 4 doors. View Cutsheet 150661

W x D x H: 31 x 28 x 79.5 in.
Electrical: 120V 60Hz 3A
Elect Notes: Powered via connection to main unit

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Medication Alcove **Department: Head, Neck, RC Clinic**

Room #: A608L

Room Notes: Shared with Heme/BMT

Refrigerator, Pyxis, Full Height

AE #: RPFH-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES REFRIGERATOR		Floor	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the pyxis medstation es system. Features secure locking bins that release when remotely accessed by the medstation es system. Medical grade and supports meeting cdc vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 f / 2-10 c. Casters are standard with unit.

Pyxis configuration per Katie Plahn per 9/1/2023 call.

View Cutsheet 171479

W x D x H: 24.3 x 29.5 x 70.5 in. **Clearance:** Top 8 in.
Electrical: 115V 60Hz 1.4A **Weight:** 363 lbs.
Elect Notes: 15 amp dedicated ground circuit; NEMA 5-15 hospital grade plug

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage, Team Work Area

Department: Head, Neck, RC Clinic

Room #: A609A1, A609C1

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Supplies / Linen **Department:** Head, Neck, RC Clinic

Room #: A609B

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Warming AE #: CAWA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7922TG		Countertop	OF/VI	Project

Single compartment warming cabinet with glass door; 9.02 cu. Ft. Capacity; 2 shelves; to be used for heating and storage of fluids or warming blankets; built-in temperature data recorder; keypad for setting internal temperature located above door. View Cutsheet 122436

W x D x H: 30 x 26.6 x 35.5 in.
Electrical: 120V 60Hz 7.5A 750W **Weight:** 325 lbs.
HVAC Notes: 1535 btu/hr.

Cart, Cylinder, Medical Gas AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.
Weight: 6 lbs.

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Room: Supplies / Linen **Department:** Head, Neck, RC Clinic

Room #: A609B

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Room: Supplies / Linen

Department: Head, Neck, RC Clinic

Room #: A609B

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Workroom

Department: Head, Neck, RC Clinic

Room #: A609C

Room Notes: Hold space for Hopper

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Scope

AE #: CASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medivators, Inc.	CLEANASCOPE CART	103631	Floor	OF/OI	Project

10-tray cart transport cart system with 10 trays for endoscopes; minimizes direct handling and contact with airborne contaminants; uses green (clean) and red (contaminated) covers

View Cutsheet 159789

W x D x H: 20.5 x 22.4 x 56.5 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Room: Soiled Workroom

Department: Head, Neck, RC Clinic

Room #: A609C

Room Notes: Hold space for Hopper

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Workroom **Department: Head, Neck, RC Clinic**

Room #: A609C

Room Notes: Hold space for Hopper

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Analyzer, Urine — AE #: LAUR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	CLINITEK STATUS +	BAH1780	Countertop	OF/OI	Project

Point-of-care urinalysis with touch screen user interface. View Cutsheet 103504

W x D x H: 6.7 x 10.7 x 6.2 in.

Network: Wired

Network Notes: Uni-directional via serial port rs232

Electrical: 120V 60Hz 15W

Weight: 3.65 lbs.

Elect Notes: 6 aa batteries, non-rechargeable

Truck, Cube — AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle — AE #: WARE-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883458		Floor	OF/OI	Project

Slim jim step-on 50l/13 gal resin front waste container. Quiet, controlled lid closure minimizes noise. Internal hinge design to prevent wall damage. View Cutsheet 148389

Factory mutual certified ensures fire safety. Meets osha and obra standards for worker and environmental safety. Color: Beige.

other available colors include: yellow, green, black, red, white, blue and gray.

W x D x H: 18 x 11.5 x 28.3 in.

Clearance: Top 11.5 in.

Weight: 10.9 lbs.

Room: Private Phone / Huddle

Department: Head, Neck, RC Clinic

Room #: A609D

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Toilet (Staff)

Department: Head, Neck, RC Clinic

Room #: A609E

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam (ENT/Microscope) **Department: Head, Neck, RC Clinic**

Room #: A610B

Room Notes: ***Email to Dr. Valentino 2/12/2024 to confirm if microscope images are to be displayed on wall mounted monitor.

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Cabinet, Exam/ Treatment, E.N.T. AE #: CAET-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	TC100C		Floor	OF/VI	Project

Sit-down height ENT treatment cabinet. Countertop height 33.5"H with 15"H backwall w/stainless steel shelf, (2) countertop recessed cordless instrument handle charger wells, right hand hose location, (2) application bottles, backwall mouonted glass bead mirror warmer, left side endoscope cold storage tubes (confirm size and mounting), and 4-port LED light source. View Cutsheet 208941

Review cut sheet and confirm options.Per CME quote 406078-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 35.5 x 21 x 48.5 in.
Electrical: 115V 60Hz 7.5A

Cabinet, Storage AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Room: Exam (ENT/Microscope) **Department:** Head, Neck, RC Clinic

Room #: A610B

Room Notes: ***Email to Dr. Valentino 2/12/2024 to confirm if microscope images are to be displayed on wall mounted monitor.

Cart, Video Procedure

AE #: CAVP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	WM-NP3/OEV-262H		Floor	OF/VI	Project

Mobile workstation (K10035366) with 27" high definition LCD monitor (OEV-262H) View Cutsheet 171517

To include the Visera Elite II OTV-S200 all-in-one video processor / light source and ImageStream nCare device and connectivity / licenses. Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

W x D x H: 26.2 x 26.6 x 81.6 in.
Network: Wired
Electrical: 120V 60Hz 15A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Ent Scope Hanger	MAJ-2145	2	2
Lcd Monitor Arm	MAJ-2216	1	1
Mountng Adaptor For Flat Panel	FLP-0002-17C	1	1
Nurses Control Arm	MAJ-2167	1	1
Sliding Keyboard	MAJ-2146	1	1
Videoscope Cable Evis Exera Ii	MAJ-1430	1	1
Visera Elite Keyboard	MAJ-1921	1	1

Chair, Procedure, Bariatric

AE #: CHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	830		Floor	OF/VI	Project

Power procedure chair. ADA compliant. Standard, swivel, or mobile base options. Foot and hand controls. Programable positioning. Oval articulating headrest. 725 lb. weight capacity. If power outlet is planned in floor, 3 ft. power cord (accessory) is needed. View Cutsheet 170372

Per CME quote 406079-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 25 x 73 x 39 in.
Electrical: 120V 60Hz 7A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Accessory rails		1	1
Exam light		1	1
Power Cord, 3 ft.	130-1905	1	1
Rectangular head rest		1	1

Room: Exam (ENT/Microscope) **Department: Head, Neck, RC Clinic**

Room #: A610B

Room Notes: ***Email to Dr. Valentino 2/12/2024 to confirm if microscope images are to be displayed on wall mounted monitor.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam (ENT/Microscope) **Department: Head, Neck, RC Clinic**

Room #: A610B

Room Notes: ***Email to Dr. Valentino 2/12/2024 to confirm if microscope images are to be displayed on wall mounted monitor.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Cart	OF/OI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Exam (ENT/Microscope) **Department: Head, Neck, RC Clinic**

Room #: A610B

Room Notes: ***Email to Dr. Valentino 2/12/2024 to confirm if microscope images are to be displayed on wall mounted monitor.

Microscope, ENT — AE #: MIEN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Jedmed Instrument Company	71-2601		Wall	OF/CI/VI	Project

Anthony Products Inc. / JedMed Kaps V-series wall mounted microscope. Specifications to be determined. Recommended mounting height 50". View Cutsheet 208942

Dr. Valentino requested to route the microscope images through video tower to monitor on wall.

W x D x H: 51.6 x N/A x 23.6 in.
Electrical: 115V 60Hz

Monitor, Display — AE #: MODI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	NEC Display Solutions	E438		Wall	OF/VI	Project

LCD 43Inch Large 4K UHD Display. 3 HDMI. 1 VGA. 1 USB 2.0. 1 USB Typ C. 3840 x 2160 Native Resolution. View Cutsheet 205790

To display images from Olympus video procedure cart. Monitor spec is placeholder only. May be IT item, need to coordinate/confirm.

W x D x H: 38.1 x 2.79 x 22 in.
Electrical: 110V 60Hz

Ophthalmoscope — AE #: OPHT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	11720-L		Cart	OF/OI	Project

3.5v coaxial ophthalmoscope. Long-lasting LED illumination. Works with all Welch Allyn 3.5v power sources. View Cutsheet 205877

W x D x H: 1.77 x 2.95 x 3.15 in.

Otoscope — AE #: OTOS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Hillrom Company, Inc.	250-2		Cart	OF/OI	Project

Diagnostic 3.5V LED otoscope. Wide-angle viewing lens. Works with all Welch Allyn 3.5V power sources. Includes a port for pneumatic otoscopy. View Cutsheet 208578

Room: Exam (ENT/Microscope) **Department:** Head, Neck, RC Clinic

Room #: A610B

Room Notes: ***Email to Dr. Valentino 2/12/2024 to confirm if microscope images are to be displayed on wall mounted monitor.

Rechargeable Handle

AE #: REHA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Hillrom Company, Inc.	719-3		Cart	OF/OI	Project

Lithium Ion Plus Power handle with integrated USB-C charger. Also compatible with Welch Allyn Universal Desk Charger 719-DSK and 71140 chargers. View Cutsheet 206571

W x D x H: 1.18 x 1.18 x 5.51 in.

Weight: 0.31 lbs.

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam (ENT) **Department: Head, Neck, RC Clinic**

Room #: A610C, A610D, A610E, A610G, A610J

Allowance, Instrument

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined				OF/OI	Project

No Cutsheet 10789

Handheld instrument allowance

Cabinet, Exam/ Treatment, E.N.T.

AE #: CAET-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	TC100C		Floor	OF/VI	Project

Sit-down height ENT treatment cabinet. Countertop height 33.5"H with 15"H backwall w/stainless steel shelf, (2) countertop recessed cordless instrument handle charger wells, right hand hose location, (2) application bottles, backwall mouonted glass bead mirror warmer, left side endoscope cold storage tubes (confirm size and mounting), and 4-port LED light source. View Cutsheet 208941

Review cut sheet and confirm options.Per CME quote 406078-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 35.5 x 21 x 48.5 in.
Electrical: 115V 60Hz 7.5A

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Room: Exam (ENT) **Department: Head, Neck, RC Clinic**

Room #: A610C, A610D, A610E, A610G, A610J

Cart, Video Procedure

AE #: CAVP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	WM-NP3/OEV-262H		Floor	OF/VI	Project

Mobile workstation (K10035366) with 27" high definition LCD monitor (OEV-262H) View Cutsheet 171517

To include the Visera Elite II OTV-S200 all-in-one video processor / light source and ImageStream nCare device and connectivity / licenses. Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

W x D x H: 26.2 x 26.6 x 81.6 in.
Network: Wired
Electrical: 120V 60Hz 15A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Ent Scope Hanger	MAJ-2145	2	2
Lcd Monitor Arm	MAJ-2216	1	1
Mountng Adaptor For Flat Panel	FLP-0002-17C	1	1
Nurses Control Arm	MAJ-2167	1	1
Sliding Keyboard	MAJ-2146	1	1
Videoscope Cable Evis Exera Ii	MAJ-1430	1	1
Visera Elite Keyboard	MAJ-1921	1	1

Chair, Procedure, Bariatric

AE #: CHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	830		Floor	OF/VI	Project

Power procedure chair. ADA compliant. Standard, swivel, or mobile base options. Foot and hand controls. Programable positioning. Oval articulating headrest. 725 lb. weight capacity. If power outlet is planned in floor, 3 ft. power cord (accessory) is needed. View Cutsheet 170372

Per CME quote 406079-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 25 x 73 x 39 in.
Electrical: 120V 60Hz 7A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Accessory rails		1	1
Exam light		1	1
Power Cord, 3 ft.	130-1905	1	1
Rectangular head rest		1	1

Room: Exam (ENT) **Department: Head, Neck, RC Clinic**

Room #: A610C, A610D, A610E, A610G, A610J

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam (ENT) **Department:** Head, Neck, RC Clinic

Room #: A610C, A610D, A610E, A610G, A610J

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Cart	OF/OI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Exam (ENT) **Department: Head, Neck, RC Clinic**

Room #: A610C, A610D, A610E, A610G, A610J

Monitor, Display — AE #: MODI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	NEC Display Solutions	E438		Wall	OF/VI	Project

LCD 43Inch Large 4K UHD Display. 3 HDMI. 1 VGA. 1 USB 2.0. 1 USB Typ C. 3840 x 2160 Native Resolution. View Cutsheet 205790

To display images from Olympus video procedure cart. Monitor spec is placeholder only. May be IT item, need to coordinate/confirm.

W x D x H: 38.1 x 2.79 x 22 in.
Electrical: 110V 60Hz

Ophthalmoscope — AE #: OPHT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	11720-L		Cart	OF/OI	Project

3.5v coaxial ophthalmoscope. Long-lasting LED illumination. Works with all Welch Allyn 3.5v power sources. View Cutsheet 205877

W x D x H: 1.77 x 2.95 x 3.15 in.

Otoscope — AE #: OTOS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Hillrom Company, Inc.	250-2		Cart	OF/OI	Project

Diagnostic 3.5V LED otoscope. Wide-angle viewing lens. Works with all Welch Allyn 3.5V power sources. Includes a port for pneumatic otoscopy. View Cutsheet 208578

Rechargeable Handle — AE #: REHA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Hillrom Company, Inc.	719-3		Cart	OF/OI	Project

Lithium Ion Plus Power handle with integrated USB-C charger. Also compatible with Welch Allyn Universal Desk Charger 719-DSK and 71140 chargers. View Cutsheet 206571

W x D x H: 1.18 x 1.18 x 5.51 in.
Weight: 0.31 lbs.

Room: Exam (ENT) **Department: Head, Neck, RC Clinic**

Room #: A610C, A610D, A610E, A610G, A610J

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Work Area (V/S) **Department: Head, Neck, RC Clinic**

Room #: A610K

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter — AE #: REUN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF4P		Undercounter	OF/VI	Project

3.9 cu ft refrigerator fits below ada height counter. Stainless steel interior and exterior. Top-mounted controls. User-selectable product or air temp display. High/low temp alarms. Programmable operating range 2-10 degrees celsius / 36-50 dg fahrenheit (factory preset 4 dg c). Two (2) epoxy-coated wire shelves. Dry contacts. Magnetic gasket, self-closing door. User-selectable temp display in unit c or f. Cabinet-wide temp remains within =/- 1 degree c with frequent door opening. Programmed defrost cycles. Depth of cabinet is 25.6". Depth with façade is 27". View Cutsheet 139889

No keypad lock needed.

W x D x H: 23.8 x 27 x 31.4 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 4.1A
Weight: 205 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle — AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.
Weight: 1 lbs.

Room: Audiology **Department: Head, Neck, RC Clinic**

Room #: A610L

Room Notes: Per DD2 meeting: will see adult patients, no need for VRA equipment for pediatric testing. Need 24" wall mounted monitor provided by UKHC IT to display test results from PC/Audiometer on the Audiologist desk outside booth. Confirmed in MEQ signoff meeting 2/5/2024.

Audiometer

AE #: AUDI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grason-Stadler / Viasys / Cardinal Health	AUDIOSTAR PRO		Desk	OF/VI	Project

Two independent channel audiometer with pediatric settings; air conduction: 125 hz - 20,000 hz, bone conduction: 250 hz - 8,000 hz; sound field 125 hz - 8,000 hz, paired inserts: 125 hz - 8,000 hz, frequency accuracy: ±1% and total harmonic distortion: < 2%; inlcudes special tests - special tests - ablb, sisi, high frequency audiometry, ten test, quicksin, bkb-sin, tone decay, amtas pro; includes wireless keyboard & mouse and gooseneck microphone; transfer data to connected pc with an e-record solution software, print reports directly to owner provided printer or thru usb to printer.

Per quote Q-362093-2 from Ryan Mills dated 2/7/2024. Model 8518226 includes ultrahigh frequency headphones. To sit outside booth on Audiologist desk.

View Cutsheet 166555

W x D x H: 20.1 x 14.6 x 13.2 in.

Network: Networked

Network Notes: Connects to owner provided pc and printer

Electrical: 115V 60Hz 1A 90W

Weight: 17 lbs.

Audiometer, Screening

AE #: AUSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grason-Stadler / Viasys / Cardinal Health	CORTI DPOAE		Countertop	OF/OI	Project

Handheld, portable device for measuring otoacoustic emissions (oae) in infants, children and adults; test up to 12 frequencies; includes unit and cradle, probe, micro-usb charging cablef for charger, database software, micro usb connector,disposable tip kit and tubes.

View Cutsheet 166557

W x D x H: 4.8 x 3.5 x 7 in.

Electrical: 120V 60Hz 1.6A

Weight: 0.5 lbs.

Elect Notes: Powered by 3.6 v rechargeable lithium ion battery
needs 120 v, 60 hz outlet to charge nearby

Struct Notes: Dimensions noted are unit and charging cradle

Room: Audiology **Department: Head, Neck, RC Clinic**

Room #: A610L

Room Notes: Per DD2 meeting: will see adult patients, no need for VRA equipment for pediatric testing. Need 24" wall mounted monitor provided by UKHC IT to display test results from PC/Audiometer on the Audiologist desk outside booth. Confirmed in MEQ signoff meeting 2/5/2024.

Booth, Audiological

AE #: BOAU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ETS-Lindgren / Acoustic Systems	RE-143MC		Floor	OF/CI/VI	Project

Eight foot wide single wall design. Pre-wired jack panel with cable pass-thru. Low-profile, 12 cm (4 3/4") isolated floor system. Switch-activated led illumination system. Acoustically engineered roof and wall-mounted ventilation. Soundsecure patient viewing window. Soundsecure acoustic door with window. Carpeting with cove base trim. Hospital-grade recessed electrical devices. View Cutsheet 168120

Per quote from Ryan Mills (e3 Diagnostics) Q-362093-2 dated 2/7/2024. Door to be in NE corner of booth and to open out. Per MEQ meeting 2/7/2024: Department does not want carpet in booth, design team to provide alternate flooring. Color of booth to be coordinated with Interiors during procurement.

W x D x H: 96 x 92 x 97.6 in.
Network: Wired
Electrical: 120V 60Hz 15A **Weight:** 4650 lbs.
Elect Notes: <<refer to sample drawing>>
HVAC Notes: <<refer to sample drawing>>
Struct Notes: <<refer to sample drawing>>
** note recessed pit**

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Audiology Booth	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

W x D x H: 27 x 18 x 33 in.

Charger Stand

AE #: CHST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	719-DSK		Audiology Booth	OF/OI	Project

Universal desk charger with two wells. Compatible with 71140, 719-3, 71910, 71670 handles. 12800 and 22800 used with 71249 adapter sleeve. View Cutsheet 207032

To sit on top of supply cart in booth.

W x D x H: 7.48 x 4.33 x 3.94 in.
Electrical: 110V 60Hz 0.1A **Weight:** 2.65 lbs.
Elect Notes: Comes with 6' long medical grade detachable cord.

Room: Audiology **Department: Head, Neck, RC Clinic**

Room #: A610L

Room Notes: Per DD2 meeting: will see adult patients, no need for VRA equipment for pediatric testing. Need 24" wall mounted monitor provided by UKHC IT to display test results from PC/Audiometer on the Audiologist desk outside booth. Confirmed in MEQ signoff meeting 2/5/2024.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Audiology Booth	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Audiology **Department:** Head, Neck, RC Clinic

Room #: A610L

Room Notes: Per DD2 meeting: will see adult patients, no need for VRA equipment for pediatric testing. Need 24" wall mounted monitor provided by UKHC IT to display test results from PC/Audiometer on the Audiologist desk outside booth. Confirmed in MEQ signoff meeting 2/5/2024.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Audiology Booth	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Audiology Booth	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Otoscope

AE #: OTOS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Hillrom Company, Inc.	250-2		Audiology Booth	OF/OI	Project

Diagnostic 3.5V LED otoscope. Wide-angle viewing lens. Works with all Welch Allyn 3.5V power sources. Includes a port for pneumatic otoscopy. View Cutsheet 208578

Room: Audiology **Department: Head, Neck, RC Clinic**

Room #: A610L

Room Notes: Per DD2 meeting: will see adult patients, no need for VRA equipment for pediatric testing. Need 24" wall mounted monitor provided by UKHC IT to display test results from PC/Audiometer on the Audiologist desk outside booth. Confirmed in MEQ signoff meeting 2/5/2024.

Rechargeable Handle — AE #: REHA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Hillrom Company, Inc.	719-3		Audiology Booth	OF/OI	Project

Lithium Ion Plus Power handle with integrated USB-C charger. Also compatible with Welch Allyn Universal Desk Charger 719-DSK and 71140 chargers. View Cutsheet 206571

W x D x H: 1.18 x 1.18 x 5.51 in.

Weight: 0.31 lbs.

Speaker — AE #: SPEA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Radioear	S90	8100	Audiology Booth	OF/VI	Project

Audiometric speaker system; ROHS compatible; reduced sound reflection. Includes (2) speakers, 157.5" cable, cable fasteners, mounting brackets/screws and set-up guide. View Cutsheet 167875

Per quote Q-362093-2 from Ryan Mills dated 2/7/2024.

W x D x H: 13.8 x 5.12 x 13.8 in.

Electrical: 80W **Weight:** 10.23 lbs.

Stool — AE #: STOO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Amazon	ELR-15620-GY		Audiology Booth	OF/OI	Project

ECR4Kids wobble stool, color gray. View Cutsheet 210212

Spec per Jennifer Shinn 2/9/2024.

W x D x H: 13 x 13 x 20 in.

Weight: 5.5 lbs.

Room: Audiology **Department: Head, Neck, RC Clinic**

Room #: A610L

Room Notes: Per DD2 meeting: will see adult patients, no need for VRA equipment for pediatric testing. Need 24" wall mounted monitor provided by UKHC IT to display test results from PC/Audiometer on the Audiologist desk outside booth. Confirmed in MEQ signoff meeting 2/5/2024.

Tympanometer — AE #: TYMP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grason-Stadler / Viasys / Cardinal Health	TYMPSTAR PRO		Audiology Booth	OF/VI	Project

Performs range of middle ear measurements on patients of all ages. 12" touch screen monitor. Customizable user tests. Emr/her compatible with gsi suite for reporting and counseling. View Cutsheet 166577

Per quote Q-362093-2 from Ryan Mills dated 2/7/2024. To sit on supply cart in booth.

W x D x H: 16 x 11 x 14.5 in.
Electrical: 115V 60Hz 60W **Weight:** 12 lbs.

Waste Receptacle — AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.
Weight: 1 lbs.

Waste Receptacle, Recycle Bin — AE #: WARR-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2955-73		Floor	OF/OI	Project

Deskside recycling container. Blue with universal recycle symbol. Contains post-consumer recycled resin(pcr). 13 qt. Capacity. Ships 12/pack View Cutsheet 160467

W x D x H: 11.4 x 8.25 x 12.3 in.

Room: Exam (Voice/Swallow - Prosthetic) **Department: Head, Neck, RC Clinic**

Room #: A610M

Room Notes: Goal is to have capability to do video procedures in this room in the future. Provide infrastructure to enable these procedures.

Box, Medication

AE #: BOME-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	20463		Wall	OF/CI	Project

Locking clear polycarbonate wall box with heavy-duty hinges. Includes keyless entry digital lock. View Cutsheet 208854

W x D x H: 10.1 x 5.25 x 3.88 in.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

W x D x H: 27 x 18 x 33 in.

Cart, Supply

AE #: CASU-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	STARSYS DOUBLE		Floor	OF/VI	Project

View Cutsheet 172084

Department needs as much storage as possible due to high amount of different supplies.

W x D x H: 42.5 x 24.9 x 78.4 in.

Room: Exam (Voice/Swallow - Prosthetic) **Department: Head, Neck, RC Clinic**

Room #: A610M

Room Notes: Goal is to have capability to do video procedures in this room in the future. Provide infrastructure to enable these procedures.

Chair, Procedure, Bariatric

AE #: CHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	830		Floor	OF/VI	Project

Power procedure chair. ADA compliant. Standard, swivel, or mobile base options. Foot and hand controls. Programable positioning. Oval articulating headrest. 725 lb. weight capacity. If power outlet is planned in floor, 3 ft. power cord (accessory) is needed.

View Cutsheet 170372

Per CME quote 406079-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 25 x 73 x 39 in.
Electrical: 120V 60Hz 7A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Accessory rails		1	1
Exam light		1	1
Power Cord, 3 ft.	130-1905	1	1
Rectangular head rest		1	1

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: Exam (Voice/Swallow - Prosthetic) **Department: Head, Neck, RC Clinic**

Room #: A610M

Room Notes: Goal is to have capability to do video procedures in this room in the future. Provide infrastructure to enable these procedures.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Exam (Voice/Swallow - Prosthetic) **Department: Head, Neck, RC Clinic**

Room #: A610M

Room Notes: Goal is to have capability to do video procedures in this room in the future. Provide infrastructure to enable these procedures.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Headlight — AE #: HEAD-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	46070R		Cabinet	OF/OI	Project

Welch Allyn Green Series LED portable headlight; one white LED, 40 lumens, 5500 deg K; rigid headband; rechargeable battery View Cutsheet 206638

Electrical: 120V 60Hz

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. View Cutsheet 85906

Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

Increased to quantity 2 based on photos provided

W x D x H: 23 x 23 x 25.5 in.

Room: Exam (Voice/Swallow - Prosthetic) **Department: Head, Neck, RC Clinic**

Room #: A610M

Room Notes: Goal is to have capability to do video procedures in this room in the future. Provide infrastructure to enable these procedures.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance. View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam (Voice/Swallow - Endoscopy) **Department:** Head, Neck, RC Clinic

Room #: A610N

Room Notes: Prefer monitor on wall for patient and/or family to view procedure - assume IT solution. V/S has 9 existing rhinolaryngoscopes.

Box, Medication

AE #: BOME-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Health Care Logistics	20463		Wall	OF/CI	Project

Locking clear polycarbonate wall box with heavy-duty hinges. Includes keyless entry digital lock. View Cutsheet 208854

W x D x H: 10.1 x 5.25 x 3.88 in.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Cart, Video Procedure

AE #: CAVP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	WM-NP2/VISERA ELITE 2		Floor	OF/VI	Project

Stroboscopy video procedure cart to include: mobile endoscopic workstation (wm-np2), visera elite ii all in one 2d processor and led light source (otv-s200), high def led lcd monitor (oev-262h), stroboscopy led light source (cll-s1), ncare medical grade touch panel; visera elite keyboard, full hd 3ccd autoclavable camera head, and 2 rhinolaryngoscopes (enf-v3 & enf-vt3); dimensions are for workstation with monitor at highest position View Cutsheet 169920

Have this model currently per MEQ signoff meeting 2/5/2024. May bring existing carts over to new building and keep in exam rooms for use as needed.

Quote Q-01738835 provided by rep Michael Garvas on 08/29/2024.

W x D x H: 25.6 x 27.6 x 81.5 in.
Network: Wired
Electrical: 120V 60Hz
Elect Notes: 1300va power input

Room: Exam (Voice/Swallow - Endoscopy) **Department: Head, Neck, RC Clinic**

Room #: A610N

Room Notes: Prefer monitor on wall for patient and/or family to view procedure - assume IT solution. V/S has 9 existing rhinolaryngoscopes.

Chair, Procedure, Bariatric

AE #: CHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MTI, Inc.	830		Floor	OF/VI	Project

Power procedure chair. ADA compliant. Standard, swivel, or mobile base options. Foot and hand controls. Programable positioning. Oval articulating headrest. 725 lb. weight capacity. If power outlet is planned in floor, 3 ft. power cord (accessory) is needed.

View Cutsheet 170372

Per CME quote 406079-1 dated 7/17/2023; added dollars for freight and delivery/installation.

W x D x H: 25 x 73 x 39 in.
Electrical: 120V 60Hz 7A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Accessory rails		1	1
Exam light		1	1
Power Cord, 3 ft.	130-1905	1	1
Rectangular head rest		1	1

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: Exam (Voice/Swallow - Endoscopy) **Department: Head, Neck, RC Clinic**

Room #: A610N

Room Notes: Prefer monitor on wall for patient and/or family to view procedure - assume IT solution. V/S has 9 existing rhinolaryngoscopes.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Exam (Voice/Swallow - Endoscopy) **Department: Head, Neck, RC Clinic**

Room #: A610N

Room Notes: Prefer monitor on wall for patient and/or family to view procedure - assume IT solution. V/S has 9 existing rhinolaryngoscopes.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Headlight

AE #: HEAD-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	46070R		Cabinet	OF/OI	Project

Welch Allyn Green Series LED portable headlight; one white LED, 40 lumens, 5500 deg K; rigid headband; rechargeable battery View Cutsheet 206638

Electrical: 120V 60Hz

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. View Cutsheet 85906

Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Room: Exam (Voice/Swallow - Endoscopy) **Department: Head, Neck, RC Clinic**

Room #: A610N

Room Notes: Prefer monitor on wall for patient and/or family to view procedure - assume IT solution. V/S has 9 existing rhinolaryngoscopes.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance. View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Mobile Equipment **Department:** Head, Neck, RC Clinic

Room #: A610N1

Room Notes: Will need portable storage for thoracentesis supplies

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Imaging, Ultrasound Scanner

AE #: IMUS-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Imaging	EPIQ Elite		Floor	OF/VI	Project

EPIQ Elite ultrasound with nSIGHT imaging, FlexVue with orthoganal view, MFI HD and 24" HD display View Cutsheet 207839

This model is place holder for space planning only. For ENT use. To have 3 probes total including (1) high frequency and (1) low frequency. Department to send preferred manufacturer and model.

W x D x H: 23.9 x 43 x 67.5 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 230 lbs.

Room: Mobile Equipment **Department:** Head, Neck, RC Clinic

Room #: A610N1

Room Notes: Will need portable storage for thoracentesis supplies

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Network Notes: Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	10

Monitor, Vital Signs, Component — AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Sphygmomanometer, Aneroid, Mobile — AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
11	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Mobile Equipment **Department:** Head, Neck, RC Clinic

Room #: A610N1

Room Notes: Will need portable storage for thoracentesis supplies

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
11	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
11	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stand, Mayo — AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

Added per email from Dr. Valentino via Jennifer Ratner 12/6/2023.

W x D x H: 21.3 x 16.3 x 39 in.

Suction Machine — AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Mobile Equipment **Department:** Head, Neck, RC Clinic

Room #: A610N1

Room Notes: Will need portable storage for thoracentesis supplies

Ultrasound, Portable

AE #: ULPO-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	VSCAN		Handheld	OF/OI	Project

Pocket-sized ultrasound with transducer attached; available transducers include linear and sector. View Cutsheet 172597

For Pulmonary use

Room: Scope Storage **Department: Head, Neck, RC Clinic**

Room #: A610P

Room Notes: Room needs surface for writing in logs. Confirm w/design team.

Allowance, Scope

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined			Cabinet	OF/VI	Project

No Cutsheet 158668

Per final MEQ review meeting, Sam O'Bryan stated that scope allowance may need to increase to $700 or more if existing scopes need to be replaced with project dollars. This is to be discussed internally.

Cabinet, Scope Storage-Drying

AE #: CASD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Harloff Company, Inc.	SureDry	SC8036DRDP-12-DSS3316	Floor / Wall	OF/CI	Project

Scope cabinet with Dri-Scope Aid features positive pressure fully redundant fan system with 3 intake and 2 exhaust fans. Fan run time is adjustable. View Cutsheet 208798

HEPA filter removes 99.7% of particulates 0.03 microns. Holds 12 scopes. Key locking tempered glass double doors.

Today at Markey, department has 12 scopes. Voice / Swallow has 9 scopes. Need to accommodate 36 scopes here.

W x D x H: 36 x 24 x 93 in.
Electrical: 115V 60Hz

Cart, Scope

AE #: CASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Medivators, Inc.	CLEANASCOPE CART	103631	Floor	OF/OI	Project

10-tray cart transport cart system with 10 trays for endoscopes; minimizes direct handling and contact with airborne contaminants; uses green (clean) and red (contaminated) covers View Cutsheet 159789

W x D x H: 20.5 x 22.4 x 56.5 in.

Cart, Supply

AE #: CASU-69

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	A566BC/A2460BR	Floor	OF/VI	Project

Adjustable super erecta chrome plated wire stem caster cart with 5 shelves, (4) posts; 5" casters (2 swivel, 2 brake). 60"w x 24"d x 69"h. View Cutsheet 62298

For holding instrument trays

W x D x H: 60 x 24 x 69 in.

Room: Scope Storage **Department: Head, Neck, RC Clinic**

Room #: A610P

Room Notes: Room needs surface for writing in logs. Confirm w/design team.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Pathology

Department: Head, Neck, RC Clinic

Room #: A610P1

Bracket, Sharps Container

AE #: BRSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	0203WMA		Wall	OF/CI	Project

Locking wall mount bracket and key for 2 & 3 gallon containers

View Cutsheet 209292

For 2 gallon sharps container

W x D x H: 13 x 5.75 x 2.75 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Alcove, Pathology **Department: Head, Neck, RC Clinic**

Room #: A610P1

Lab Microscope, Dual Head

AE #: LMDH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX46F3		Cart	OF/VI	Project

Dual head microscope with side-by-side configuration. With the following objectives: 2, 4, 10, 20, 40. View Cutsheet 209272

Quote No: 2023-JAD-3031 - 11 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 33.2 x 14.3 x 21.6 in.
Electrical: 115V 60Hz

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.
Weight: 1 lbs.

Room: Toilet (Patient)

Department: Head, Neck, RC Clinic

Room #: B601R, A610F, A610M1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Head, Neck, RC Clinic

Room #: B601R, A610F, A610M1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area

Department: Head, Neck, RC Clinic

Room #: B601S

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case

View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless

Network Notes: Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter

View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room - PFT

Department: Head, Neck, RC Clinic

Room #: B601X

Room Notes: No med gases needed for this room per Jennifer Ratner email 6/13/2024.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room - PFT **Department: Head, Neck, RC Clinic**

Room #: B601X

Room Notes: No med gases needed for this room per Jennifer Ratner email 6/13/2024.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Exam Room - PFT **Department: Head, Neck, RC Clinic**

Room #: B601X

Room Notes: No med gases needed for this room per Jennifer Ratner email 6/13/2024.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Plethysmograph

AE #: PLET-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Vyaire	Vyntus BODY		Floor	OF/VI	Project

Body box for plethysmography; bench with 551 lb weight capacity for patient; sitting height 18.7" and sitting area is 19.9"W x 13"D; Height Step-In: 2.8" View Cutsheet 202584

W x D x H: 36.7 x 31.5 x 72.8 in.
Electrical: 115V 60Hz **Weight:** 385 lbs.
Elect Notes: Two 120V / 60Hz power connections needed: Body box 80 VA max; Workstation cart 690 VA
HVAC Notes: Temperature Sensor: -10 to 50 C
Humidity Sensor: 0 to 100% relative humidity
Air Pressure Sensor: 500 to 1100 hPa (375 to 825 mmHg)

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: Exam Room - PFT **Department: Head, Neck, RC Clinic**

Room #: B601X

Room Notes: No med gases needed for this room per Jennifer Ratner email 6/13/2024.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended.

Department prefers no arms for procedures, but would like as an option for fall risk.

View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Waiting (Transplant) **Department:** Hematology / BMT

Room #: A602A

Coffee Brewer — AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service. View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Waiting (Transplant) **Department:** Hematology / BMT

Room #: A602A

Ice Maker / Water Dispenser — AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in. **Clearance:** Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A **Weight:** 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department: Hematology / BMT**

Room #: A602B, A602C, A602D, A602E, A602F, A602G, A602J, A604C, A604D, A604E, A604F, A604G, A604H, A604J, A604M, A606C, A606D, A606E, A606F, A606G, A606H, A606K, A606M, A606N

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam Room **Department: Hematology / BMT**

Room #: A602B, A602C, A602D, A602E, A602F, A602G, A602J, A604C, A604D, A604E, A604F, A604G, A604H, A604J, A604M, A606C, A606D, A606E, A606F, A606G, A606H, A606K, A606M, A606N

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Ophthalmoscope/ Otoscope — AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Room: Exam Room **Department:** Hematology / BMT

Room #: A602B, A602C, A602D, A602E, A602F, A602G, A602J, A604C, A604D, A604E, A604F, A604G, A604H, A604J, A604M, A606C, A606D, A606E, A606F, A606G, A606H, A606K, A606M, A606N

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.***

View Cutsheet 209180

Wide table top preferred by department.

W x D x H: 32 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area (6)

Department: Hematology / BMT

Room #: A602H, A606J

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Mobile Equipment **Department:** Hematology / BMT

Room #: A602L1

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Lifter, Patient

AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor. View Cutsheet 208837

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Room: Mobile Equipment **Department:** Hematology / BMT

Room #: A602L1

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	4

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Mobile Equipment **Department:** Hematology / BMT

Room #: A602L1

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Treatment (Transplant / Car-T)

Department: Hematology / BMT

Room #: A602L, A602M

Bed, Electric

AE #: BEEL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	S3 EX	3005S3EX	Floor	OF/VI	Project

Med / surg bed. Siderails designed with one-hand operation and an intermediate position for patient assistance during bed entry and exit. Open architecture platform. Centrally located brake pedal. 500 lb weight capacity. Capable of linking to hospital network via wireless or wired connection.

View Cutsheet 149049

W x D x H: 41.5 x 93 x 30 in.
Network: Networked
Electrical: 120V 60Hz 8A

Bed, Electric, Component

AE #: BEEC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	AIR PUMP	2861000025	Bed	OF/VI	Project

Air pump for use with isoflex lal 2860 surface

View Cutsheet 165842

W x D x H: 8 x 5 x 8.5 in.
Electrical: 120V 60Hz 0.25A **Weight:** 5.5 lbs.

Cart, Procedure

AE #: CAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

Polymer cart on caster; with (1) 3", (3) 6" and (1) 9" drawer; Electronic PIN locking; Pull handles.

View Cutsheet 200197

Drawer configuration to be determined by dept LP trays are roughly 18"W x 12"D. Will need to fit in drawers.

W x D x H: 22.7 x 24.9 x 44.7 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Treatment (Transplant / Car-T)

Department: Hematology / BMT

Room #: A602L, A602M

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes.

View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Room: Treatment (Transplant / Car-T) **Department:** Hematology / BMT

Room #: A602L, A602M

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Light, Exam/ Treatment — AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation. View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Room: Treatment (Transplant / Car-T) **Department:** Hematology / BMT

Room #: A602L, A602M

Monitor, Physiological — AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.

Network: Wired **Network Notes:** Required two data ports

Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.

Weight: 3.1 lbs.

Monitor, Physiological, Monitor Arm — AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: Treatment (Transplant / Car-T) **Department:** Hematology / BMT

Room #: A602L, A602M

Ophthalmoscope/ Otoscope

AE #: OPOT-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	71-SM2NDX		Countertop	OF/OI	Project

MacroView Basic Otoscope offers focus-free design and 3x wider viewing area. Coaxial Ophthalmoscope for reduced glare with long lasting LED. Metal power handles with NiCad battery and desktop charging base stand. View Cutsheet 207767

Prefer countertop model so provider does not need to reach over patient.

Electrical: 120V 60Hz

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Room: Treatment (Transplant / Car-T)

Department: Hematology / BMT

Room #: A602L, A602M

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult.

View Cutsheet 160315

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: Treatment (Transplant / Car-T)

Department: Hematology / BMT

Room #: A602L, A602M

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Table, Instrument

AE #: TAIN-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7832SS	0117832000	Floor	OF/OI	Project

Instrument table with shelf; 16" clearance between shelves; 16 gauge, 304 stainless construction; closed top hem; three-inch casters View Cutsheet 75798

W x D x H: 36 x 20 x 34 in.

Weight: 48 lbs.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet View Cutsheet 211777

Holder (1), Hanging Shelf (1).

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Room: Treatment (Transplant / Car-T) **Department:** Hematology / BMT

Room #: A602L, A602M

Thermometer, Electronic, Oral

AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius

View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: On-Stage Team Work Area (12) **Department:** Hematology / BMT

Room #: A603

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult

Department: Hematology / BMT

Room #: A604A, A604B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight (W/C Scale) **Department:** Hematology / BMT

Room #: A604B1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Accessory Basket — AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Alcove, Height / Weight (W/C Scale) **Department:** Hematology / BMT

Room #: A604B1

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning. View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Alcove, Height / Weight (W/C Scale) **Department:** Hematology / BMT

Room #: A604B1

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stadiometer — AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle — AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Toilet (Patient)

Department: Hematology / BMT

Room #: A604K, A602M1, A606L1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Hematology / BMT

Room #: A604K, A602M1, A606L1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Treatment (General) **Department:** Hematology / BMT

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Cart, Procedure — AE #: CAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	Starsys		Floor	OF/VI	Project

Polymer cart on caster; with (1) 3", (3) 6" and (1) 9" drawer; Electronic PIN locking; Pull handles. View Cutsheet 200197

Drawer configuration to be determined by dept LP trays are roughly 18"W x 12"D. Will need to fit in drawers.

W x D x H: 22.7 x 24.9 x 44.7 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treatment (General) **Department:** Hematology / BMT

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Treatment (General) **Department:** Hematology / BMT

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Ladder, Step

AE #: LADS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	6DHF0		Floor	OF/OI	Project

Folding Step: 2 Steps, 18 3/4 in Top Step Ht, 18 1/2 in Bottom Wd, 330 lb Load Capacity View Cutsheet 206472

For use by patients to flex hips during procedures

W x D x H: 18.5 x 21 x 30 in.

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation. View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Room: Treatment (General) **Department:** Hematology / BMT

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Monitor, Physiological — AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Network Notes: Required two data ports
Electrical: 115V 60Hz 1.8A
Weight: 12.3 lbs.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Monitor, Physiological, Monitor Arm — AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.
Weight: 15.4 lbs.

Monitor, Wall Channel — AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Room: Treatment (General) **Department:** Hematology / BMT

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Ophthalmoscope/ Otoscope

AE #: OPOT-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	71-SM2NDX		Countertop	OF/OI	Project

MacroView Basic Otoscope offers focus-free design and 3x wider viewing area. Coaxial Ophthalmoscope for reduced glare with long lasting LED. Metal power handles with NiCad battery and desktop charging base stand. View Cutsheet 207767

Prefer countertop model so provider does not need to reach over patient.

Electrical: 120V 60Hz

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. View Cutsheet 85906

Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Room: Treatment (General) **Department: Hematology / BMT**

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

Wall or ceiling mounted preferred to save floor space.

W x D x H: 24 x 24 x 72 in.

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; View Cutsheet 46527

pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

W x D x H: 23 x 23 x 25.5 in.

Room: Treatment (General) **Department:** Hematology / BMT

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Stretcher

AE #: STRT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	1115000000E	Big Wheel 30"	Floor	OF/VI	Project

Prime Electric Big Wheel, 700 lb weight capacity, Less than 21-inch low height, Litter-mounted oxygen bottle holder, Power-washable design (1105 and 1115 only), Center-locking brake system with dual end activators, Dual, side-mounted foot control hydraulics with uni-lower pedal, Dual end brake/steer controls, Glideaway Siderails, 4 integrated IV receptacles, +/- Trendelenburg, 8-inch Omni Surface Casters with integrated wheel covers, Pneumatic backrest/stationary foot, Thermoformed ABS base, Integrated utility tray, Integrated transfer board

View Cutsheet 205997

W x D x H: 38 x 85 x 43 in.
Electrical: 120V 60Hz

Table, Instrument

AE #: TAIN-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7832SS	0117832000	Floor	OF/OI	Project

Instrument table with shelf; 16" clearance between shelves; 16 gauge, 304 stainless construction; closed top hem; three-inch casters

View Cutsheet 75798

W x D x H: 36 x 20 x 34 in.
Weight: 48 lbs.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.
Weight: 25 lbs.

Room: Treatment (General) **Department:** Hematology / BMT

Room #: A604L, A606L

Room Notes: Procedures will include lumbar punctures, bone marrow aspiration, skin biopsies, Ommaya reservoir access

Thermometer, Electronic, Oral — AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius

View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: On-Stage Team Work Area (12)

Department: Hematology / BMT

Room #: A605

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Height / Weight

Department: Hematology / BMT

Room #: A606A, A606B, A602A1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Accessory Basket

AE #: MOAB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WM-0001-18		Wall	OF/CI	Project

Wire basket mounted to wall channel provides storage for cuffs and misc materials; includes integrated cord wrap and cable hook View Cutsheet 102139

W x D x H: 12 x 8 x 6 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Arm	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Alcove, Height / Weight

Department: Hematology / BMT

Room #: A606A, A606B, A602A1

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls.

View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Mounting Arm, Vital Signs Monitor

AE #: MAVS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	FLP-0009-02 / WA-0015-91		Wall Channel	OF/VI	Project

Channel-mounted 12" pivot arm with VESA mounting plate with optional Connex power supply channel mount (WA-0015-91) for use with Welch Allyn Connex monitor. Pivot point at wall channel for lateral adjustability and swivel adjustment. VESA 75/100 mm compatible. Mount allows tilt and swivel motion for monitor positioning.

View Cutsheet 208927

W x D x H: 4.8 x 15.5 x 8 in.

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug.

View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz

Weight: 61 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: Alcove, Height / Weight

Department: Hematology / BMT

Room #: A606A, A606B, A602A1

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Toilet (Staff)

Department: Hematology / BMT

Room #: A608D, A608J

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Private Phone / Huddle

Department: Hematology / BMT

Room #: A608E, A608K

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Equipment

Department: Hematology / BMT

Room #: A608F

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole. View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Room: Equipment
Room #: A608F

Department: Hematology / BMT

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

One for full and one for empty

View Cutsheet 72313

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability.

View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Equipment **Department:** Hematology / BMT

Room #: A608F

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Crashcart	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Soiled Workroom

Department: Hematology / BMT

Room #: A608G

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly.

View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Workroom

Department: Hematology / BMT

Room #: A608G

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Analyzer, Urine

AE #: LAUR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	CLINITEK STATUS +	BAH1780	Countertop	OF/OI	Project

Point-of-care urinalysis with touch screen user interface.

View Cutsheet 103504

W x D x H: 6.7 x 10.7 x 6.2 in.

Network: Wired

Network Notes: Uni-directional via serial port rs232

Electrical: 120V 60Hz 15W

Weight: 3.65 lbs.

Elect Notes: 6 aa batteries, non-rechargeable

Room: Soiled Workroom **Department:** Hematology / BMT

Room #: A608G

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Undercounter, ADA Height

AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white. View Cutsheet 211261

For Clinitek supplies

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.
HVAC Notes: Refrigerant R600a

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supplies **Department:** Hematology / BMT

Room #: A608H

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Room: Clean Supplies

Department: Hematology / BMT

Room #: A608H

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z)

View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Room: Toilet (Patient)

Department: Multi-Disciplinary Clinic

Room #: B601A, B602L, B603B, B603K, B605M, B601L1, B603N1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient) **Department:** Multi-Disciplinary Clinic

Room #: B601A, B602L, B603B, B603K, B605M, B601L1, B603N1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department:** Multi-Disciplinary Clinic

Room #: B601B, B601C, B601D, B601E, B601F, B601G, B601J, B601K, B601M, B602C, B602E, B602F, B602G, B602H, B602M, B602N, B602P, B603C, B603D, B603E, B603F, B603G, B603H, B603J, B603L, B603M, B605D, B605E, B605F, B605G, B605J

Room Notes: Sani wipes to be kept in cabinet. No linen hamper needed as use paper products in exam rooms.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Emesis Bag — AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room **Department:** Multi-Disciplinary Clinic

Room #: B601B, B601C, B601D, B601E, B601F, B601G, B601J, B601K, B601M, B602C, B602E, B602F, B602G, B602H, B602M, B602N, B602P, B603C, B603D, B603E, B603F, B603G, B603H, B603J, B603L, B603M, B605D, B605E, B605F, B605G, B605J

Room Notes: Sani wipes to be kept in cabinet. No linen hamper needed as use paper products in exam rooms.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes.

View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Room: Exam Room **Department:** Multi-Disciplinary Clinic

Room #: B601B, B601C, B601D, B601E, B601F, B601G, B601J, B601K, B601M, B602C, B602E, B602F, B602G, B602H, B602M, B602N, B602P, B603C, B603D, B603E, B603F, B603G, B603H, B603J, B603L, B603M, B605D, B605E, B605F, B605G, B605J

Room Notes: Sani wipes to be kept in cabinet. No linen hamper needed as use paper products in exam rooms.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Backless preferred by department.

W x D x H: 20 x 20 x 24.5 in.

Room: Exam Room **Department:** Multi-Disciplinary Clinic

Room #: B601B, B601C, B601D, B601E, B601F, B601G, B601J, B601K, B601M, B602C, B602E, B602F, B602G, B602H, B602M, B602N, B602P, B603C, B603D, B603E, B603F, B603G, B603H, B603J, B603L, B603M, B605D, B605E, B605F, B605G, B605J

Room Notes: Sani wipes to be kept in cabinet. No linen hamper needed as use paper products in exam rooms.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended.

View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area **Department:** Multi-Disciplinary Clinic

Room #: B601H, B602A, B602J, B602K, B604, B605C, B605H

Room Notes: Assumes space for 6-12 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Treatment Room - Ostomy Nurse **Department:** Multi-Disciplinary Clinic

Room #: B601L

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treatment Room - Ostomy Nurse **Department:** Multi-Disciplinary Clinic

Room #: B601L

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Treatment Room - Ostomy Nurse **Department:** Multi-Disciplinary Clinic

Room #: B601L

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Light, Exam/ Treatment — AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation. View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Monitor, Physiological — AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Room: Treatment Room - Ostomy Nurse **Department:** Multi-Disciplinary Clinic

Room #: B601L

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.

Electrical: 115V 60Hz

Room: Treatment Room - Ostomy Nurse **Department:** Multi-Disciplinary Clinic

Room #: B601L

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Room: Treatment Room - Ostomy Nurse **Department:** Multi-Disciplinary Clinic

Room #: B601L

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Treatment Room - Ostomy Nurse **Department:** Multi-Disciplinary Clinic

Room #: B601L

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.

Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Patient Support Rails 2ea./Pr.	9A60001	1	1

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Room: Treatment Room - Ostomy Nurse

Department: Multi-Disciplinary Clinic

Room #: B601L

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Mobile Equipment **Department:** Multi-Disciplinary Clinic

Room #: B601M1

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Imaging, Ultrasound Scanner

AE #: ULPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	ST		Floor	OF/VI	Project

With 21" portrait, gray scale, touchscreen display and mobile, adjustable height stand; 2 transducer ports and on-stand storage; In-plane needle visualization. View Cutsheet 209454

** Dimensions noted with Stand

Includes mobile stand May not need, Erin to confirm w/providers.

W x D x H: 25.5 x 23 x 68 in.
Network: Networked
Electrical: 120V 60Hz **Weight:** 110 lbs.

Room: Mobile Equipment **Department:** Multi-Disciplinary Clinic

Room #: B601M1

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	3

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Scanner, Bladder

AE #: SCBL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Verathon Inc. - Medical	i10	0270-1014	Stand	OF/VI	Project

Bladder scanner i10 system; on rolling stand. View Cutsheet 200466

Electrical: 120V 60Hz 1.4A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand	0800-0631	1	1

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Mobile Equipment **Department:** Multi-Disciplinary Clinic

Room #: B601M1

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Corridor **Department:** Multi-Disciplinary Clinic

Room #: B602, B603

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available. View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.

Room: Consult **Department:** Multi-Disciplinary Clinic

Room #: B602B, B602D, B603A, B605B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight **Department:** Multi-Disciplinary Clinic

Room #: B602C1, B605A1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

May want wall mounted hand rails in addition to the rail provided with the scale. Group also discussed recessing scale in floor. This is not standard and would be a larger discussion.

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.
Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.
Weight: 1 lbs.

Room: Mobile Equipment **Department:** Multi-Disciplinary Clinic

Room #: B603M1

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Imaging, Ultrasound Scanner

AE #: ULPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	ST		Floor	OF/VI	Project

With 21" portrait, gray scale, touchscreen display and mobile, adjustable height stand; 2 transducer ports and on-stand storage; In-plane needle visualization. View Cutsheet 209454

** Dimensions noted with Stand

Includes mobile stand May not need, Erin to confirm w/providers.

W x D x H: 25.5 x 23 x 68 in.
Network: Networked
Electrical: 120V 60Hz **Weight:** 110 lbs.

Room: Mobile Equipment **Department:** Multi-Disciplinary Clinic

Room #: B603M1

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Network Notes: Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	4

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Mobile Equipment **Department:** Multi-Disciplinary Clinic

Room #: B603M1

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Vein Illuminator

AE #: VEIL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accuvein Inc.	AV500/HF550		Stand	OF/VI	Project

Vein imaging. Simplified display. Shows dark veins on a green background or green veins on a dark background. Device dimensions without stand is 2" x 2.4" x 7.9", 9.7 oz. View Cutsheet 168583

W x D x H: 24 x 24 x 42 in.
Electrical: 120V 60Hz 1A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand, Powered	HF570	1	1

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Bin, Recycle, Scope

AE #: BIRS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	ZZZ - To Be Determined	Black scope recycling bin		Floor	OF/OI	Project

Bin to collect recyclable scopes; dimensions approximate pending confirmation of specifications — No Cutsheet 209442

W x D x H: 14 x 18 x 23 in.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. — View Cutsheet 208699

W x D x H: 27 x 18 x 33 in.

Cabinet, Ultrasound Transducer

AE #: CAUT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Civco Medical Solutions	610-1327		Wall / Floor	OF/CI	Project

General purpose & endocavity probe cabinet; holds up to six probes; true HEPA filter provides continuous airflow using positive pressure. Airflow specifications: 200 air changes/hour. Filter specifications: 99.97% @ 0.3 µm. Vertical suspension of probes facilitates drying. Includes U.S. power cord. — View Cutsheet 165407

W x D x H: 24 x 10 x 74 in.
Clearance: Right 6 in.; Top 10 in.
Electrical: 120V 60Hz 0.5A
Weight: 100 lbs.
Elect Notes: 15a hospital-grade gfci outlet required

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. — View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Generator, Steam — AE #: GEST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Boston Scientific	Rezum		Table	OF/VI	Project

Steam generator for urologic procedure to shrink the prostate. Requires other owner provided items including but not limited to cart or surface for generator, prep tray, IV pole, rigid cystoscope lens, light source and cord, video camera and display (recorder optional), drain bucket, and hemostat. View Cutsheet 209170

May be existing, Erin verified that the Urology service will need this device.

Electrical: 120V 60Hz

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation.

View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Monitor, Physiological

AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle.

View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp.

View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Probe Cleaner — AE #: PRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON2		Wall	OF/OI	Project

Ultrasound probe high level disinfection system. Captures user id, instrument id, disinfectant information and chemical indicator. Can download data to usb or to hospital network. View Cutsheet 172692

W x D x H: 14.3 x 12.6 x 21.2 in.
Network: Wired
Electrical: 120V 60Hz 5A **Weight:** 48.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount	E8350NG	1	1

Probe Cleaner Accessory, Printer — AE #: PCAP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON PRINTER		Wall	OF/OI	Project

Printer To Accompany Trophon 2. Connected to Trophon2 Unit via USB Cable. Printer is a Traceability Solution, Printing Trophon Disinfection Labels. View Cutsheet 171574

W x D x H: 4.33 x 6.89 x 9.84 in.
Electrical: 120V 60Hz 1.8A

Probe Cleaner, Component — AE #: PRCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	WALL MOUNT	N05009	Wall	OF/CI	Project

Wall mount for probe cleaner. View Cutsheet 172898

W x D x H: 14.2 x 12.8 x 10.8 in. **Clearance:** Left 10 in.; Right 10 in.

Probe Cleaner, Component — AE #: PRCC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	PRINTER WALL MOUNT	N00105	Wall	OF/CI	Project

Printer wall mount for trophon printer. View Cutsheet 172899

W x D x H: 4.33 x 6.89 x 9.84 in.

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Pump, I.V. AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors. View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module. View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Stand, Mayo

AE #: STMA-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1065-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 20" x 25" removable tray, foot pedal operated, friction locks from 36" to 62" View Cutsheet 46599

Increased size of tray to accommodate Ambu disposable cystoscope.

W x D x H: 20 x 25 x 62 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.

Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Patient Support Rails 2ea./Pr.	9A60001	1	1

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Table, Prep

AE #: TAPR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	SG-80-SS		Floor	OF/OI	Project

Stainless steel construction; features table top with rail; single drawer; shelf; 3" double ball bearing casters, rubber wheels. View Cutsheet 141195

For Rezum radiofrequency generator and SpaceOAR device

W x D x H: 20 x 16 x 34 in.

Tissue Protective Treatment Device

AE #: TPTD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Boston Scientific	SpaceOAR		Table	OF/VI	Project

SpaceOAR treatment device for placing hydrogel between prostate and rectum to protect rectum during prostate radiation therapy. Specifications to be confirmed. No Cutsheet 209171

Electrical: 120V 60Hz

Ultrasound System

AE #: ULSY-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	B K Medical	BK3000		Floor	OF/VI	Project

High resolution ultrasound system dedicated to urology. Advanced imaging modes include elastography and contrast imaging. Two hours of plug freee imaging. View Cutsheet 170167

Model confirmed in 8/28/2023 MEQ meeting

W x D x H: 26.4 x 33.5 x 64.6 in.
Network: Networked
Electrical: 115V 60Hz

Room: Treatment Room - Urology **Department:** Multi-Disciplinary Clinic

Room #: B603N

Room Notes: Currently use disposable instruments.

Video Cystoscopy System

AE #: VICS-22

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ambu Inc.	aScope 4 Cysto		Stand	OF/VI	Project

Cystoscope system uses single-use disposable scopes with portable monitor. Mounting monitor to the optional cart is reflected in the approximated dimensions. View Cutsheet 210232

W x D x H: 20 x 24 x 64 in.
Electrical: 115V 60Hz

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.
Weight: 10.9 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Triage / Injections Room **Department:** Multi-Disciplinary Clinic

Room #: B605A

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Chair, Recliner

AE #: CHRE-09

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	TRURIZE	3333-000-000	Floor	OF/VI	Project

Clinical powered reclining chair with dual sided occupant control panel with lockout controls, dual sided caregiver specific control panels, six positions, integrated chair exit alarm system, pivoting armrests, one touch brake, vertical handles for maneuvering, two integrated foley bag hooks, two line management hooks, 3.5" casters, length full flat 73", height 53"-61" weight capacity 350lbs. View Cutsheet 160913

W x D x H: 34 x 73 x 61 in.
Electrical: 120V 60Hz 4A

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Triage / Injections Room **Department:** Multi-Disciplinary Clinic

Room #: B605A

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Room: Triage / Injections Room **Department:** Multi-Disciplinary Clinic

Room #: B605A

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter — View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.
Network: Wired
Network Notes: Rj-45 ethernet jack
Electrical: 120V 60Hz 15W

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. — View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component — AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. — View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. — View Cutsheet 150982

Room: Triage / Injections Room **Department:** Multi-Disciplinary Clinic

Room #: B605A

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Workroom **Department:** Multi-Disciplinary Clinic

Room #: B605L

Room Notes: Confirm intended use for this space

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Workroom **Department:** Multi-Disciplinary Clinic

Room #: B605L

Room Notes: Confirm intended use for this space

Lab Analyzer, Urine

AE #: LAUR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	CLINITEK STATUS +	BAH1780	Countertop	OF/OI	Project

Point-of-care urinalysis with touch screen user interface. View Cutsheet 103504

W x D x H: 6.7 x 10.7 x 6.2 in.
Network: Wired
Network Notes: Uni-directional via serial port rs232
Electrical: 120V 60Hz 15W
Weight: 3.65 lbs.
Elect Notes: 6 aa batteries, non-rechargeable

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Countertop

AE #: RECO-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF1	REF1-00	Countertop	OF/VI	Project

1 cu. Ft. High performance countertop refrigerator. Stainelss steel. Led temperature display on front. Includes cylinder lock with 2 keys. User adjustable operating temperature range from 34°f to 55°f (1.1°c t0 13°c). Right hinged door reverses quickly in field. View Cutsheet 142291

W x D x H: 18.6 x 24 x 17.9 in.
Clearance: Rear 2 in.; Left 2 in.; Right 2 in.; Top 8 in.
Electrical: 115V 60Hz 1.8A 1-Phase
Weight: 73 lbs.
HVAC Notes: Heat rejection: 190 btu/hr.
Struct Notes: Ventilation clearance with 8" or more top clearance: 2" on each side. Ventilation clearance with less than 8" top clearance: 6" on one side. Footprint of refrigerator is 20"d; top is 24"d.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Workroom **Department:** Multi-Disciplinary Clinic

Room #: B605L

Room Notes: Confirm intended use for this space

Workstation, US Infection Control

AE #: WOIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	AuditPro		Countertop	OF/OI	Project

Infection control workflow compliance management in the form of a workstation and mobile unit to be used with the Nanosonic Trophon2. Handheld computer/barcode scanner dimensions: 6.18 x 3.08 x 0.67 in

View Cutsheet 210430

W x D x H: 5.1 x 5.9 x 2.3 in.

Network: Wireless

Network Notes: WLAN, WLAN/WWAN

Electrical: 120V 60Hz

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Light, Exam/ Treatment — AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation. View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Monitor, Physiological — AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired
Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Monitor, Physiological, Component — AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Pump, I.V.

AE #: PUIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Becton Dickinson	Alaris 8015		Stand	OF/VI	Lease

Alaris PC unit provides power and drives up to (4) detachable infusion and/or monitoring modules; features wireless connectivity using the Guardrails Suite MX software platform. Hardwired communication can be supported via either RJ-45 or RS-232 connectors.

View Cutsheet 107953

Provided by Agility

W x D x H: 6.9 x 9 x 8.8 in.
Network: Wireless
Electrical: 120V 60Hz 1.5A **Weight:** 7.2 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Software: Guardrails Poc - Pc Unit		1	1

Pump, I.V., Component

AE #: PUIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Becton Dickinson	Alaris 8100	8100	Pump	OF/VI	Lease

Pump module.

View Cutsheet 107954

Per 10/17/2024 email from Jennifer Ratner, the pumps are provided by Agility. UKHC lease covers flexing quantities as needed. No project dollars are required to provide.

W x D x H: 3.3 x 5.5 x 8.9 in.
Weight: 2.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Guardrails Point Of Care Software		1	2

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stool, Revolving, Exam

AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

W x D x H: 20 x 20 x 24.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.

Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Patient Support Rails 2ea./Pr.	9A60001	1	1

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Room: Treatment Room **Department:** Multi-Disciplinary Clinic

Room #: B605N

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Off-Stage, Team Work Area

Department: Multi-Disciplinary Clinic

Room #: B607A1, B607D1, B607F1, B607H1

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder Unable to provide larger Tote Bin per UK recycling.

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Workroom **Department:** Multi-Disciplinary Clinic

Room #: B607C

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.*** View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Chemo Waste

AE #: COCW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8938FP		Floor	OF/OI	Project

Sharpscart wire foot pedal cart for 12 and 18 gallon sliding lid large volume and chemosafety containers (container not included). View Cutsheet 162610

For chemo disposal bin requested by Urology.

W x D x H: 12 x 18 x 24 in.

Container, Pharmacy Waste - Black

AE #: COPK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004		Floor	OF/OI	Service Agreement

8-gallon black bin (19.7”h x 13.0”d x 11.3 “w) for hazardous waste with wire step-on dolly. View Cutsheet 164244

W x D x H: 14.3 x 16.5 x 23 in.

Room: Soiled Workroom **Department:** Multi-Disciplinary Clinic

Room #: B607C

Container, Sharps

AE #: COSH-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	DWS-08/C-08-2004LR		Floor	OF/OI	Supply Agreement

8-gallon red bin (19.7”h x 13.0”d x 11.3 “w) for biohazard waste with wire step-on dolly. View Cutsheet 164306

W x D x H: 14.3 x 16.5 x 23 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Workroom **Department:** Multi-Disciplinary Clinic

Room #: B607C

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Truck, Cube

AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Supplies / Linen **Department:** Multi-Disciplinary Clinic

Room #: B607D, B607H

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67 AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Room: Supplies / Linen **Department:** Multi-Disciplinary Clinic

Room #: B607D, B607H

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Light, Speculum

AE #: LISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	80010		Countertop	OF/OI	Project

Complete kleenspec cordless illumination system with charging station with us style ac plug. Associated disposables: kleenspec disposable vaginal specula. View Cutsheet 161569

W x D x H: 3.1 x 9.3 x 6.4 in.
Electrical: 120V 60Hz 0.2A **Weight:** 1.1 lbs.

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.
Weight: 13 lbs.

Room: Supplies / Linen **Department:** Multi-Disciplinary Clinic

Room #: B607D, B607H

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Thermometer, Electronic, Oral

AE #: THEO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	SureTemp Plus 690	01690-400	Wall	OF/CI	Project

Welch Allyn SureTemp Plus 690 Wall-Mount Electronic Thermometer with Interchangeable Oral Probe Well, Oral Probe with 4.0 ft/1.2 m Cord, Last Temperature Recall; 3 Alkaline AA Batteries, provides 4-6 Second Oral, 10-13 Second Pediatric Axillary, and 12-15 Second Adult Axillary Temperature Readings in Fahrenheit or Celsius View Cutsheet 208705

W x D x H: 4.91 x 8.22 x 9.06 in.

Room: Supplies / Linen **Department:** Multi-Disciplinary Clinic

Room #: B607D, B607H

Thermometer, Electronic, Rectal

AE #: THER-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	SURETEMP 692	01692-201	Wall	OF/CI	Project

Rectal temperature reading in approximately 10 seconds. Patient temperature range 80 - 110 degrees fahrenheit. Configuration includes: suretemp plus electronic thermometer model 692, wall mount, security system w/id location field, rectal probe with rectal probe well, 3 year limited warranty. View Cutsheet 159017

W x D x H: 8.8 x 5.5 x 5.5 in.

Weight: 1 lbs.

Elect Notes: Battery powered: with (3) 1.5 vdc "aa" batteries

Accessories:

Description	Catalog	Qty/Item	Ext Qty
9 Foot Cord		1	1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Medication Room **Department:** Multi-Disciplinary Clinic

Room #: B607E

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Medication Room **Department:** Multi-Disciplinary Clinic

Room #: B607E

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

Per Katie Plahn email 9/14/2023

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Medication Room **Department:** Multi-Disciplinary Clinic

Room #: B607E

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Private Phone / Huddle

Department: Multi-Disciplinary Clinic

Room #: B607F

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Toilet (Staff)

Department: Multi-Disciplinary Clinic

Room #: B607G

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult **Department:** Breast Clinic

Room #: A701Y, A701Z

Room Notes: Technically located in Cardio, for Breast use

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight **Department:** Breast Clinic

Room #: B701A1

Room Notes: Vitals to be taken in exam room

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Stand-On

AE #: SCSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Scale-Tronix, Inc.	5002-KX-B		Floor	OF/OI	Project

Mobile stand-on scale, kilograms only. 880 lb. Weighing capacity; low profile with handrails; kg only (k), dataport (x) and battery power (b) with hospital grade plug. View Cutsheet 172814

*** specify integrated height gauge as accessory if needed

W x D x H: 22 x 28 x 60 in.

Network Notes: Rs-232 connectivity available

Electrical: 120V 60Hz

Weight: 61 lbs.

Room: Alcove, Height / Weight **Department:** Breast Clinic

Room #: B701A1

Room Notes: Vitals to be taken in exam room

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Toilet (Patient)

Department: Breast Clinic

Room #: B701A, B702L, B701L1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Breast Clinic

Room #: B701A, B702L, B701L1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department:** Breast Clinic

Room #: B701B, B701C, B701D, B701F, B701G, B701J, B701K, B701M, B702C, B702E

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam Room **Department:** Breast Clinic

Room #: B701B, B701C, B701D, B701F, B701G, B701J, B701K, B701M, B702C, B702E

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Exam Room **Department:** Breast Clinic

Room #: B701B, B701C, B701D, B701F, B701G, B701J, B701K, B701M, B702C, B702E

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room (32")

Department: Breast Clinic

Room #: B701E, B702G

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Exam Room (32")

Department: Breast Clinic

Room #: B701E, B702G

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Exam Room (32")

Department: Breast Clinic

Room #: B701E, B702G

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately.

View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.***

View Cutsheet 209180

Wide table top preferred by department.

W x D x H: 32 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Room: Exam Room (32")

Department: Breast Clinic

Room #: B701E, B702G

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area (6) **Department:** Breast Clinic

Room #: B701H

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder Smaller/Narrow model preferred in this space.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Treatment Room **Department:** Breast Clinic

Room #: B701L

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treatment Room **Department:** Breast Clinic

Room #: B701L

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Treatment Room **Department:** Breast Clinic

Room #: B701L

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation. View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Monitor, Physiological

AE #: MOPH-45

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	MX450		Arm	OF/VI	Project

Portable/bedside patient monitor with 12"-wide touchscreen. EMR compatible with built-in battery and handle. View Cutsheet 146867

W x D x H: 12.9 x 7.2 x 11.3 in.
Network: Wired **Network Notes:** Required two data ports
Electrical: 115V 60Hz 1.8A **Weight:** 12.3 lbs.

Monitor, Physiological, Component

AE #: MOPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3	867030	Monitor	OF/VI	Project

X3 MMS for Philips MX line of monitors. 4 waves, 6.1" display, with dual pressure and temp. View Cutsheet 164119

W x D x H: 9.8 x 3.8 x 4.4 in.
Weight: 3.1 lbs.

Room: Treatment Room **Department:** Breast Clinic

Room #: B701L

Monitor, Physiological, Monitor Arm

AE #: MPMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	PH-0077-04		Wall Channel	OF/VI	Project

Variable height channel-mounted arm with vertical position lock and 8" extension arm for use with Philips MX600/700/800 monitors. Includes 9" downpost for FMS, handle, and channel cover. Load range 20-45 lbs. View Cutsheet 208925

W x D x H: 4 x 39.5 x 10.2 in.

Weight: 15.4 lbs.

Monitor, Wall Channel

AE #: MOWC-19

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GCX Corporation	WC-0002-05		Wall	OF/CI	Project

19" wall channel; seismec; to be secured to metal or wood studs with gypsum board or similar coverings. Mounting hardware to be set anywhere in the channel. Can also be secured to prefabricated headwalls. View Cutsheet 103961

W x D x H: 4 x 1.5 x 19 in.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Room: Treatment Room **Department:** Breast Clinic

Room #: B701L

Sphygmomanometer, Cuff — AE #: SPCU-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-11		Drawer	OF/OI	Project

Reusable flexiport cuff. Size adult. View Cutsheet 160315

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Drawer	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Drawer	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stand, I.V. — AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Room: Treatment Room **Department:** Breast Clinic

Room #: B701L

Stand, Mayo — AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power — AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Container, Biohazard — AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.
Weight: 10.9 lbs.

Room: Treatment Room

Department: Breast Clinic

Room #: B701L

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Height / Weight (WC Scale) **Department:** Breast Clinic

Room #: B702C1

Room Notes: Vitals to be taken in exam room

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Scale, Wheelchair — AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.
Electrical: 120V 60Hz 15W **Weight:** 107 lbs.
Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Stadiometer — AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.
Weight: 3.7 lbs.

Room: Alcove, Height / Weight (WC Scale)

Department: Breast Clinic

Room #: B702C1

Room Notes: Vitals to be taken in exam room

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: On-Stage Team Work Area (12) **Department:** Breast Clinic

Room #: B702J

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case

View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter

View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Mobile Equipment **Department:** Breast Clinic

Room #: B702L1

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Imaging, Ultrasound Scanner

AE #: ULPO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sonosite, Inc.	ST		Floor	OF/VI	Project

With 21" portrait, gray scale, touchscreen display and mobile, adjustable height stand; 2 transducer ports and on-stand storage; In-plane needle visualization. View Cutsheet 209454

** Dimensions noted with Stand

Includes mobile stand To include Breast Transducers, see accessories**

W x D x H: 25.5 x 23 x 68 in.
Network: Networked
Electrical: 120V 60Hz **Weight:** 110 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
L12-3: Art, Breast, Carotid, Lung, MSK, Nerve, Oph		1	1
L15-4: Art, Breast, Carotid, Nerve, MSK, S, V		1	1

Room: Mobile Equipment **Department:** Breast Clinic

Room #: B702L1

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	4

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Mobile Equipment **Department:** Breast Clinic

Room #: B702L1

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Soiled Workroom **Department:** Breast Clinic

Room #: B707E

Room Notes: Shared between Breast Clinic, Cardio/Rehab Onc, and Palliative. Breast gowns to go in Breast Imaging Soiled Linen cart as they are laundered by a different company.

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

For general soiled linen. Soiled breast gowns to go in Breast Imaging Soiled Linen closet.

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Room: Soiled Workroom **Department:** Breast Clinic

Room #: B707E

Room Notes: Shared between Breast Clinic, Cardio/Rehab Onc, and Palliative. Breast gowns to go in Breast Imaging Soiled Linen cart as they are laundered by a different company.

Cart, Supply

AE #: CASU-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	2424FS		Floor	OF/VI	Project

Standard type 304 solid stainless steel shelves with (2) revolving and (2) braking caster wheels. View Cutsheet 167384

W x D x H: 24 x 24 x 68 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Multi-Tier Shelving		1	1

Container, Pharmacy Waste

AE #: COPW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rx Destroyer TM Pharmaceutical Disposal	RX1.0PRO		Countertop	OF/OI	Project

Rx Destroyer™ all purpose is for use with all non-hazardous medications (DEA-controlled & Non-controlled). Includes Pills, Capsules, Tablets, Liquids, Lozenges, Transdermal Patches, Fentanyl Lollipops, and Suppositories. Includes wall mount (RX1.0WALLSEC). View Cutsheet 208805

W x D x H: 7.75 x 6 x 10.5 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Soiled Workroom **Department:** Breast Clinic

Room #: B707E

Room Notes: Shared between Breast Clinic, Cardio/Rehab Onc, and Palliative. Breast gowns to go in Breast Imaging Soiled Linen cart as they are laundered by a different company.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage, Team Work Area

Department: Breast Clinic

Room #: B707F1

Room Notes: Assumes space for 14 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Medication Room

Department: Breast Clinic

Room #: B707F-SHARED1

Room Notes: Shared with Cardio and Palliative room A709E

Room: Clean Supplies / Linen **Department:** Breast Clinic

Room #: B707G

Room Notes: For Breast Clinic

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system — No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Warming — AE #: CAWA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7922TG		Cart	OF/VI	Project

Single compartment warming cabinet with glass door; 9.02 cu. Ft. Capacity; 2 shelves; to be used for heating and storage of fluids or warming blankets; built-in temperature data recorder; keypad for setting internal temperature located above door. View Cutsheet 122436

Will sit on cart/stand.

W x D x H: 30 x 26.6 x 35.5 in.

Electrical: 120V 60Hz 7.5A 750W **Weight:** 325 lbs.

Cabinet, Warming, Component — AE #: CAWC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	3026SSH		Floor	OF/OI	Project

Sawyer h-brace table for table top warming cabinets made of 18 gauge 304 stainless steel. Sawyer table has an h brace in lieu of second shelf. 1/1/4" diameter legs with 3 inch casters. View Cutsheet 166610

W x D x H: 30 x 26 x 34 in.

Weight: 40 lbs.

Room: Clean Supplies / Linen **Department:** Breast Clinic

Room #: B707G

Room Notes: For Breast Clinic

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

(1) for regular linen, (1) for breast gowns

W x D x H: 48 x 24 x 79 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Room: Clean Supplies / Linen **Department:** Breast Clinic

Room #: B707G

Room Notes: For Breast Clinic

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter

View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks

View Cutsheet 163754

For palliative

W x D x H: 24 x 24 x 72 in.

Room: Private Phone / Huddle **Department:** Breast Clinic

Room #: B707H

Room Notes: Can be used as a lactation room PRN, but will not have a sink. Staff can use public lactation room at northern end of waiting room.

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Toilet (Staff)

Department: Breast Clinic

Room #: B709E

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Corridor

Department: Breast Imaging

Room #: B703

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available.

View Cutsheet 208673

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A
Weight: 437 lbs.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703A

Room Notes: 5 female, 1 male

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure — View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes. Plan for (3) L, (2) XL, (1)XXL

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. — View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black — View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703A

Room Notes: 5 female, 1 male

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703A

Room Notes: 5 female, 1 male

Imaging, Digital Mammography — AE #: ISMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	3DIMENSIONS, Genius 3D		Floor	OF/CI/VI	Project

3D digital mammography system. With Genius and Clarity HD High Resolution software for faster mammography with clearer images. Designed to better capture dense breast tissue. Able to detect 20-65% more invasive breast cancers. 2D capabilities come standard as well. View Cutsheet 210444

Include DBT option. Price includes Genius AI Detection, 3D Quorum Training, needle localization kit, and licensing. Quote #Q-393486, dated 8/22/24 Supplemental Info

W x D x H: 66.5 x 51.6 x 87.8 in.
Network: Wired
Electrical: 240V 60Hz 40A **Weight:** 882 lbs.
Elect Notes: **Refer to Hologic site planning information.** 200-240 vac, 50-60hz, single phase, 40 amp
Plumb Notes: **Refer to Hologic site planning information.**
HVAC Notes: **Refer to Hologic site planning information.**
Struct Notes: **Refer to Hologic site planning information.**

Imaging, Mammography Accessory — AE #: IMMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Universal acquisition workstation		Floor	OF/VI	Project

Universal acqusition workstation (with shield) View Cutsheet 165820

Width is 53.4"w with display arm extended. **included with the price of the mammo system.**

W x D x H: 36.9 x 48.4 x 80.3 in.
Network: Wired

Imaging, Mammography Accessory — AE #: IMMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hologic, Inc.	SELENIA DIMENSIONS PADDLE RACK		Wall	OF/CI	Project

Paddle rack. Note** recommended minimum spacing of 12 inches between racks when installing racks over each other. View Cutsheet 165490

Selenia discontinued, but paddle rack is still compatible and the preferred choice for the 3DIMENSIONS

W x D x H: 36.3 x 4 x 7 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703A

Room Notes: 5 female, 1 male

Phantom, Mammography — AE #: PHMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	016A-BR12		Cabinet	OF/OI	Project

Single Exposure High Contrast Resolution Phantom; Incorporates two 17.5 micron thick gold-nickel alloy bar patterns; The bar patterns are positioned at 90 degrees to allow assessment of resolution perpendicular and parallel to anode-cathode axis; Targets have 17 segments from 5 lp to20 lp/mm and are equivalent to 25 microns of lead or 2.6mm of aluminum at 20 keV

View Cutsheet 209569

This model used by physicists. Gaye to send info on other phantoms used in Mammo rooms

W x D x H: 5 x 4 x 2 in.

Weight: 2 lbs.

Rack, Apron — AE #: RAAP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	WR4		Wall	OF/CI	Project

Wall-mounted peg rack designed to hold frontal or wrap around aprons. 4-pegs for two aprons. Each peg is 4" long

View Cutsheet 210231

W x D x H: 12 x 5 x 3 in.

Shield, Thyroid — AE #: SHTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	49995		Rack	OF/OI	Project

Tethered thyroid collar; buckle closure. No top binding makes the collar more comfortable and flexible against the skin. Tether keeps collar with apron at all times. Select fabric and color and protections type (0.5mm cost cruncher, prestige, scatter sentry, star lite or true lite). Fits up to a 20" neck size.

View Cutsheet 165478

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult / Dressing

Department: Breast Imaging

Room #: B703A1

Room Notes: Connected to Mammo 1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Toilet (Patient)

Department: Breast Imaging

Room #: B703B, B705D1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Breast Imaging

Room #: B703B, B705D1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703C

Room Notes: 5 female, 1 male

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure [View Cutsheet 209349]

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes. Plan for (3) L, (2) XL, (1)XXL

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. [View Cutsheet 208674]

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black [View Cutsheet 207790]

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703C

Room Notes: 5 female, 1 male

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703C

Room Notes: 5 female, 1 male

Imaging, Digital Mammography — AE #: ISMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	3DIMENSIONS, Genius 3D		Floor	OF/CI/VI	Project

3D digital mammography system. With Genius and Clarity HD High Resolution software for faster mammography with clearer images. Designed to better capture dense breast tissue. Able to detect 20-65% more invasive breast cancers. 2D capabilities come standard as well. View Cutsheet 210444

Include DBT option. Price includes Genius AI Detection, 3D Quorum Training, needle localization kit, and licensing. Quote #Q-393486, dated 8/22/24 Supplemental Info

W x D x H: 66.5 x 51.6 x 87.8 in.
Network: Wired
Electrical: 240V 60Hz 40A **Weight:** 882 lbs.
Elect Notes: **Refer to Hologic site planning information.** 200-240 vac, 50-60hz, single phase, 40 amp
Plumb Notes: **Refer to Hologic site planning information.**
HVAC Notes: **Refer to Hologic site planning information.**
Struct Notes: **Refer to Hologic site planning information.**

Imaging, Mammography Accessory — AE #: IMMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Universal acquisition workstation		Floor	OF/VI	Project

Universal acqusition workstation (with shield) View Cutsheet 165820

Width is 53.4"w with display arm extended. **included with the price of the mammo system.**

W x D x H: 36.9 x 48.4 x 80.3 in.
Network: Wired

Imaging, Mammography Accessory — AE #: IMMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hologic, Inc.	SELENIA DIMENSIONS PADDLE RACK		Wall	OF/CI	Project

Paddle rack. Note** recommended minimum spacing of 12 inches between racks when installing racks over each other. View Cutsheet 165490

Selenia discontinued, but paddle rack is still compatible and the preferred choice for the 3DIMENSIONS

W x D x H: 36.3 x 4 x 7 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703C

Room Notes: 5 female, 1 male

Phantom, Mammography

AE #: PHMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	016A-BR12		Cabinet	OF/OI	Project

Single Exposure High Contrast Resolution Phantom; Incorporates two 17.5 micron thick gold-nickel alloy bar patterns; The bar patterns are positioned at 90 degrees to allow assessment of resolution perpendicular and parallel to anode-cathode axis; Targets have 17 segments from 5 lp to20 lp/mm and are equivalent to 25 microns of lead or 2.6mm of aluminum at 20 keV

View Cutsheet 209569

This model used by physicists. Gaye to send info on other phantoms used in Mammo rooms

W x D x H: 5 x 4 x 2 in.

Weight: 2 lbs.

Rack, Apron

AE #: RAAP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	WR4		Wall	OF/CI	Project

Wall-mounted peg rack designed to hold frontal or wrap around aprons. 4-pegs for two aprons. Each peg is 4" long

View Cutsheet 210231

W x D x H: 12 x 5 x 3 in.

Shield, Thyroid

AE #: SHTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	49995		Rack	OF/OI	Project

Tethered thyroid collar; buckle closure. No top binding makes the collar more comfortable and flexible against the skin. Tether keeps collar with apron at all times. Select fabric and color and protections type (0.5mm cost cruncher, prestige, scatter sentry, star lite or true lite). Fits up to a 20" neck size.

View Cutsheet 165478

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Nurse Work Area **Department:** Breast Imaging

Room #: B703D

Bin, Shredder — AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless

Network Notes: Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired

Network Notes: Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Container — AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703E

Room Notes: 5 female, 1 male

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure — View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes. Plan for (3) L, (2) XL, (1)XXL

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. — View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black — View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703E

Room Notes: 5 female, 1 male

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703E

Room Notes: 5 female, 1 male

Imaging, Digital Mammography — AE #: ISMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	3DIMENSIONS, Genius 3D		Floor	OF/CI/VI	Project

3D digital mammography system. With Genius and Clarity HD High Resolution software for faster mammography with clearer images. Designed to better capture dense breast tissue. Able to detect 20-65% more invasive breast cancers. 2D capabilities come standard as well. View Cutsheet 210444

Include DBT option. Price includes Genius AI Detection, 3D Quorum Training, needle localization kit, and licensing. Quote #Q-393486, dated 8/22/24 Supplemental Info

W x D x H: 66.5 x 51.6 x 87.8 in.
Network: Wired
Electrical: 240V 60Hz 40A **Weight:** 882 lbs.
Elect Notes: **Refer to Hologic site planning information.** 200-240 vac, 50-60hz, single phase, 40 amp
Plumb Notes: **Refer to Hologic site planning information.**
HVAC Notes: **Refer to Hologic site planning information.**
Struct Notes: **Refer to Hologic site planning information.**

Imaging, Mammography Accessory — AE #: IMMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hologic, Inc.	SELENIA DIMENSIONS PADDLE RACK		Wall	OF/CI	Project

Paddle rack. Note** recommended minimum spacing of 12 inches between racks when installing racks over each other. View Cutsheet 165490

Selenia discontinued, but paddle rack is still compatible and the preferred choice for the 3DIMENSIONS

W x D x H: 36.3 x 4 x 7 in.

Imaging, Mammography Accessory — AE #: IMMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Universal acquisition workstation		Floor	OF/VI	Project

Universal acqusition workstation (with shield) View Cutsheet 165820

Width is 53.4"w with display arm extended. **included with the price of the mammo system.**

W x D x H: 36.9 x 48.4 x 80.3 in.
Network: Wired

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703E

Room Notes: 5 female, 1 male

Phantom, Mammography

AE #: PHMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	016A-BR12		Cabinet	OF/OI	Project

Single Exposure High Contrast Resolution Phantom; Incorporates two 17.5 micron thick gold-nickel alloy bar patterns; The bar patterns are positioned at 90 degrees to allow assessment of resolution perpendicular and parallel to anode-cathode axis; Targets have 17 segments from 5 lp to20 lp/mm and are equivalent to 25 microns of lead or 2.6mm of aluminum at 20 keV

View Cutsheet 209569

This model used by physicists. Gaye to send info on other phantoms used in Mammo rooms

W x D x H: 5 x 4 x 2 in.

Weight: 2 lbs.

Rack, Apron

AE #: RAAP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	WR4		Wall	OF/CI	Project

Wall-mounted peg rack designed to hold frontal or wrap around aprons. 4-pegs for two aprons. Each peg is 4" long

View Cutsheet 210231

W x D x H: 12 x 5 x 3 in.

Shield, Thyroid

AE #: SHTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	49995		Rack	OF/OI	Project

Tethered thyroid collar; buckle closure. No top binding makes the collar more comfortable and flexible against the skin. Tether keeps collar with apron at all times. Select fabric and color and protections type (0.5mm cost cruncher, prestige, scatter sentry, star lite or true lite). Fits up to a 20" neck size.

View Cutsheet 165478

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703F

Room Notes: 5 female, 1 male

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure — View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes. Plan for (3) L, (2) XL, (1)XXL

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. — View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black — View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703F

Room Notes: 5 female, 1 male

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703F

Room Notes: 5 female, 1 male

Imaging, Digital Mammography — AE #: ISMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	3DIMENSIONS, Genius 3D		Floor	OF/CI/VI	Project

3D digital mammography system. With Genius and Clarity HD High Resolution software for faster mammography with clearer images. Designed to better capture dense breast tissue. Able to detect 20-65% more invasive breast cancers. 2D capabilities come standard as well. View Cutsheet 210444

Include DBT option. Price includes Genius AI Detection, 3D Quorum Training, needle localization kit, and licensing. Quote #Q-393486, dated 8/22/24 Supplemental Info

W x D x H: 66.5 x 51.6 x 87.8 in.
Network: Wired
Electrical: 240V 60Hz 40A **Weight:** 882 lbs.
Elect Notes: **Refer to Hologic site planning information.** 200-240 vac, 50-60hz, single phase, 40 amp
Plumb Notes: **Refer to Hologic site planning information.**
HVAC Notes: **Refer to Hologic site planning information.**
Struct Notes: **Refer to Hologic site planning information.**

Imaging, Mammography Accessory — AE #: IMMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hologic, Inc.	SELENIA DIMENSIONS PADDLE RACK		Wall	OF/CI	Project

Paddle rack. Note** recommended minimum spacing of 12 inches between racks when installing racks over each other. View Cutsheet 165490

Selenia discontinued, but paddle rack is still compatible and the preferred choice for the 3DIMENSIONS

W x D x H: 36.3 x 4 x 7 in.

Imaging, Mammography Accessory — AE #: IMMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Universal acquisition workstation		Floor	OF/VI	Project

Universal acqusition workstation (with shield) View Cutsheet 165820

Width is 53.4"w with display arm extended. **included with the price of the mammo system.**

W x D x H: 36.9 x 48.4 x 80.3 in.
Network: Wired

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703F

Room Notes: 5 female, 1 male

Phantom, Mammography

AE #: PHMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	016A-BR12		Cabinet	OF/OI	Project

Single Exposure High Contrast Resolution Phantom; Incorporates two 17.5 micron thick gold-nickel alloy bar patterns; The bar patterns are positioned at 90 degrees to allow assessment of resolution perpendicular and parallel to anode-cathode axis; Targets have 17 segments from 5 lp to20 lp/mm and are equivalent to 25 microns of lead or 2.6mm of aluminum at 20 keV

View Cutsheet 209569

This model used by physicists. Gaye to send info on other phantoms used in Mammo rooms

W x D x H: 5 x 4 x 2 in.

Weight: 2 lbs.

Rack, Apron

AE #: RAAP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	WR4		Wall	OF/CI	Project

Wall-mounted peg rack designed to hold frontal or wrap around aprons. 4-pegs for two aprons. Each peg is 4" long

View Cutsheet 210231

W x D x H: 12 x 5 x 3 in.

Shield, Thyroid

AE #: SHTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	49995		Rack	OF/OI	Project

Tethered thyroid collar; buckle closure. No top binding makes the collar more comfortable and flexible against the skin. Tether keeps collar with apron at all times. Select fabric and color and protections type (0.5mm cost cruncher, prestige, scatter sentry, star lite or true lite). Fits up to a 20" neck size.

View Cutsheet 165478

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Technician Work Area **Department:** Breast Imaging

Room #: B703G

Room Notes: Assumes space for 16 people. Need media disposal bin - dept to send

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult / Consent Room

Department: Breast Imaging

Room #: B703H

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703J

Room Notes: 5 female, 1 male

Apron, Lead — AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure — View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes. Plan for (3) L, (2) XL, (1)XXL

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	1

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. — View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black — View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703J

Room Notes: 5 female, 1 male

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703J

Room Notes: 5 female, 1 male

Imaging, Digital Mammography — AE #: ISMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	3DIMENSIONS, Genius 3D		Floor	OF/CI/VI	Project

3D digital mammography system. With Genius and Clarity HD High Resolution software for faster mammography with clearer images. Designed to better capture dense breast tissue. Able to detect 20-65% more invasive breast cancers. 2D capabilities come standard as well. View Cutsheet 210444

Include DBT option. Price includes Genius AI Detection, 3D Quorum Training, needle localization kit, and licensing. Quote #Q-393486, dated 8/22/24 Supplemental Info

W x D x H: 66.5 x 51.6 x 87.8 in.
Network: Wired
Electrical: 240V 60Hz 40A **Weight:** 882 lbs.
Elect Notes: **Refer to Hologic site planning information.** 200-240 vac, 50-60hz, single phase, 40 amp
Plumb Notes: **Refer to Hologic site planning information.**
HVAC Notes: **Refer to Hologic site planning information.**
Struct Notes: **Refer to Hologic site planning information.**

Imaging, Mammography Accessory — AE #: IMMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hologic, Inc.	SELENIA DIMENSIONS PADDLE RACK		Wall	OF/CI	Project

Paddle rack. Note** recommended minimum spacing of 12 inches between racks when installing racks over each other. View Cutsheet 165490

Selenia discontinued, but paddle rack is still compatible and the preferred choice for the 3DIMENSIONS

W x D x H: 36.3 x 4 x 7 in.

Imaging, Mammography Accessory — AE #: IMMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Universal acquisition workstation		Floor	OF/VI	Project

Universal acqusition workstation (with shield) View Cutsheet 165820

Width is 53.4"w with display arm extended. **included with the price of the mammo system.**

W x D x H: 36.9 x 48.4 x 80.3 in.
Network: Wired

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703J

Room Notes: 5 female, 1 male

Phantom, Mammography

AE #: PHMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	016A-BR12		Cabinet	OF/OI	Project

Single Exposure High Contrast Resolution Phantom; Incorporates two 17.5 micron thick gold-nickel alloy bar patterns; The bar patterns are positioned at 90 degrees to allow assessment of resolution perpendicular and parallel to anode-cathode axis; Targets have 17 segments from 5 lp to20 lp/mm and are equivalent to 25 microns of lead or 2.6mm of aluminum at 20 keV

View Cutsheet 209569

This model used by physicists. Gaye to send info on other phantoms used in Mammo rooms

W x D x H: 5 x 4 x 2 in.

Weight: 2 lbs.

Rack, Apron

AE #: RAAP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	WR4		Wall	OF/CI	Project

Wall-mounted peg rack designed to hold frontal or wrap around aprons. 4-pegs for two aprons. Each peg is 4" long

View Cutsheet 210231

W x D x H: 12 x 5 x 3 in.

Shield, Thyroid

AE #: SHTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	49995		Rack	OF/OI	Project

Tethered thyroid collar; buckle closure. No top binding makes the collar more comfortable and flexible against the skin. Tether keeps collar with apron at all times. Select fabric and color and protections type (0.5mm cost cruncher, prestige, scatter sentry, star lite or true lite). Fits up to a 20" neck size.

View Cutsheet 165478

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Stereotactic Exam **Department:** Breast Imaging

Room #: B703K

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	1

Breast Biopsy Guidance System

AE #: BBGS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	AFFIRM		Imaging System	OF/VI	Project

The Affirm® upright breast biopsy guidance system for a 3Dimensions™ system or Selenia® View Cutsheet 204548

Dimensions® system supports stereotactic 2D biopsy and wire localization. INCLUDES:

• Affirm breast biopsy guidance module

• Biopsy control module with touchscreen display

• One (1) Stereotactic 2D Biopsy software license for one gantry; additional licenses may be purchased

• Biopsy compression paddles (3): Standard biopsy compression paddle (biopsy window: 5.4 x 5.2 cm); axillary biopsy compression paddle (biopsy window: 5.4 x 5.2 cm); wide biopsy compression paddle (biopsy window: 7.4 x 6.2 cm)

• Quality assurance needle and needle guide holder

• Geometry calibration and targeting phantoms

• Affirm tabletop stand

Upright configuration confirmed

Room: Stereotactic Exam **Department:** Breast Imaging

Room #: B703K

Breast Biopsy System

AE #: BRBS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	BREVERA		Floor	OF/VI	Project

Combination biopsy system with real-time imaging; with dual spec imaging and tech displays; integrated, automated core handling; with biopsy device. View Cutsheet 166144

acquisition workstation/specimen imaging display: touchscreen, color, 15" LCD screen

console control display: 7" LED screen

Pricing from Quote #Q-393496-1, dated 8/22/24

W x D x H: 22.8 x 22.8 x 65.3 in.
Clearance: Right 8 in.; Front 8 in.
Network: Wired
Electrical: 120V 60Hz 9A
Weight: 195 lbs.
Elect Notes: 9 amps peak, 4 amps typical
console: 800 watts
cord length: 20 feet
Struct Notes: Max height: 65.25"
min height: 53.25"

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Stereotactic Exam

Department: Breast Imaging

Room #: B703K

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox,

View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Stereotactic Exam **Department:** Breast Imaging

Room #: B703K

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Digital Mammography

AE #: ISMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	3DIMENSIONS, Genius 3D		Floor	OF/CI/VI	Project

3D digital mammography system. With Genius and Clarity HD High Resolution software for faster mammography with clearer images. Designed to better capture dense breast tissue. Able to detect 20-65% more invasive breast cancers. 2D capabilities come standard as well. View Cutsheet 210444

Include DBT option. Price includes Genius AI Detection, 3D Quorum Training, needle localization kit, and licensing. Quote #Q-393486, dated 8/22/24

W x D x H: 66.5 x 51.6 x 87.8 in.
Network: Wired
Electrical: 240V 60Hz 40A **Weight:** 882 lbs.
Elect Notes: **Refer to Hologic site planning information.** 200-240 vac, 50-60hz, single phase, 40 amp
Plumb Notes: **Refer to Hologic site planning information.**
HVAC Notes: **Refer to Hologic site planning information.**
Struct Notes: **Refer to Hologic site planning information.**

Imaging, Mammography Accessory

AE #: IMMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hologic, Inc.	SELENIA DIMENSIONS PADDLE RACK		Wall	OF/CI	Project

Paddle rack. Note** recommended minimum spacing of 12 inches between racks when installing racks over each other. View Cutsheet 165490

Selenia discontinued, but paddle rack is still compatible and the preferred choice for the 3DIMENSIONS

W x D x H: 36.3 x 4 x 7 in.

Room: Stereotactic Exam **Department:** Breast Imaging

Room #: B703K

Imaging, Mammography Accessory

AE #: IMMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Universal acquisition workstation		Floor	OF/VI	Project

Universal acqusition workstation (with shield) View Cutsheet 165820

Width is 53.4"w with display arm extended. Monitor will come from new PACS vendor **included with the price of the mammo system.**

W x D x H: 36.9 x 48.4 x 80.3 in.
Network: Wired

Imaging, Mammography, Chair

AE #: CHIM-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Akrus		Floor	OF/VI	Project

The Akrus chair is designed for screening, diagnostic, and biopsy imaging. Allows a variety of positioning options including upright and decubitus in all mammography projections including magnification views. View Cutsheet 204502

W x D x H: 29.9 x 29.9 x 56.7 in.
Weight: 209.5 lbs.

Imaging, Mammography, Chair, Battery Charger

AE #: IMBC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Akrus Battery Charger		Wall	OF/CI	Project

Battery charger for Akrus chair View Cutsheet 209088

W x D x H: 14 x 6 x 6 in.
Electrical: 115V 60Hz

Rack, Apron

AE #: RAAP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	WR4		Wall	OF/CI	Project

Wall-mounted peg rack designed to hold frontal or wrap around aprons. 4-pegs for two aprons. Each peg is 4" long View Cutsheet 210231

W x D x H: 12 x 5 x 3 in.

Room: Stereotactic Exam **Department:** Breast Imaging

Room #: B703K

Radiography System, Specimen

AE #: RASS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	TRIDENT		Cart	OF/VI	Project

Mammography biopsy specimen radiographic system. Self-contained, fully integrated system with lcd display, auto-sensing magnification, specimen stage storage compartment. View Cutsheet 145970

W x D x H: 37.5 x 26.5 x 68.3 in.
Network: Wired
Electrical: 120V 60Hz 4A **Weight:** 275 lbs.
HVAC Notes: 1535 btu/hr

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Shield, Thyroid

AE #: SHTH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	46997		Shelf	OF/OI	Project

Starlight .5mm Protection. No top binding tether. Minimize X-ray exposure of the thyroid gland and neck with a protective Thyroid Collar. Features hook-and-loop fasteners for a snug fit and better radiation protection. View Cutsheet 146879

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Stereotactic Exam **Department:** Breast Imaging

Room #: B703K

Table, Instrument

AE #: TAIN-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Vevor	24x18x34 SS		Floor	OF/OI	Project

24x18x34 Inch Stainless Steel Work Table 3-Stage Adjustable Shelf with 4 Wheels Heavy Duty Commercial Food Prep Worktable with Brake. View Cutsheet 209466

This model preferred by breast imaging staff.

W x D x H: 24 x 18 x 34 in.

Weight: 22 lbs.

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Alcove, Pathology

Department: Breast Imaging

Room #: B703K1

Bracket, Sharps Container

AE #: BRSC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	0203WMA		Wall	OF/CI	Project

Locking wall mount bracket and key for 2 & 3 gallon containers

View Cutsheet 209292

For 2 gallon sharps container

W x D x H: 13 x 5.75 x 2.75 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Alcove, Pathology **Department:** Breast Imaging

Room #: B703K1

Lab Microscope, Dual Head

AE #: LMDH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX46F3		Countertop	OF/VI	Project

Dual head microscope with side-by-side configuration. With the following objectives: 2, 4, 10, 20, 40. View Cutsheet 209272

Quote No: 2023-JAD-3031 - 11 obtained 8/15/24. Rep Jacob Dunkerson has started with most robust configurations and users can change configuration as needed. **Will need to review configurations with users.

W x D x H: 33.2 x 14.3 x 21.6 in.
Electrical: 115V 60Hz

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Treatment / Ultrasound Room **Department:** Breast Imaging

Room #: B703L

Cabinet, Warming — AE #: CAWA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7922TG		Countertop	OF/VI	Project

Single compartment warming cabinet with glass door; 9.02 cu. Ft. Capacity; 2 shelves; to be used for heating and storage of fluids or warming blankets; built-in temperature data recorder; keypad for setting internal temperature located above door. View Cutsheet 122436

Half-height confirmed

W x D x H: 30 x 26.6 x 35.5 in.
Electrical: 120V 60Hz 7.5A 750W **Weight:** 325 lbs.
HVAC Notes: 1535 btu/hr.

Cabinet, Warming, Component — AE #: CAWC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	3026SSH		Floor	OF/OI	Project

Sawyer h-brace table for table top warming cabinets made of 18 gauge 304 stainless steel. Sawyer table has an h brace in lieu of second shelf. 1/1/4" diameter legs with 3 inch casters. View Cutsheet 166610

W x D x H: 30 x 26 x 34 in.
Weight: 40 lbs.

Cart, Sharps Container — AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Chair, Ultrasound Tech — AE #: CHUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hag Ergonomic Chairs / Izzy Design	H8106		Floor	OF/OI	Project

Hag capisco (the saddle chair) with seat and back. Saddle seat is height adjustable between low and high working positions all the way to standing. View Cutsheet 150834

Standard 200mm gas lift.

W x D x H: 27.6 x 27.6 x 55.1 in.

Room: Treatment / Ultrasound Room

Department: Breast Imaging

Room #: B703L

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8

View Cutsheet 208703

Room: Treatment / Ultrasound Room

Department: Breast Imaging

Room #: B703L

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Breast Ultrasound

AE #: IMBU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	SuperSonic Mach 40		Floor	OF/VI	Project

SuperSonic MACH 40 system provides unprecedented capabilities with unique View Cutsheet 208916

UltraFast™ architecture, innovative transducers and a large FHD viewing screen.

• Smooth images with reduced speckle, regardless of tissue density

• Incredible definition in both fundamental and harmonic imaging modes

• Optimized penetration settings for image clarity regardless of imaging depth

• Acquisition of 3D volumetric data

W x D x H: 23.8 x 47.6 x 72 in.

Network: Wireless

Network Notes: Compliant with 802.11b/g/n standard. WPA/WPA2 Personal security. 2.4GHz band frequency. Wi-Fi device FCC/IC/CE certified. Wireless networking for DICOM modalities and network printer connection.

Electrical: 120V 60Hz

Weight: 246 lbs.

Room: Treatment / Ultrasound Room **Department:** Breast Imaging

Room #: B703L

Regulator, Suction, Continuous & Intermittent

AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, Foot, With Handrail

AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Instrument

AE #: TAIN-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Vevor	24x18x34 SS		Floor	OF/OI	Project

24x18x34 Inch Stainless Steel Work Table 3-Stage Adjustable Shelf with 4 Wheels Heavy Duty Commercial Food Prep Worktable with Brake. View Cutsheet 209466

This model preferred by breast imaging staff.

W x D x H: 24 x 18 x 34 in.

Weight: 22 lbs.

Room: Treatment / Ultrasound Room **Department:** Breast Imaging

Room #: B703L

Table, Ultrasound

AE #: TAUL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Biodex Medical Systems, Inc	Ultra Pro	058-720	Floor	OF/VI	Project

The Biodex Ultra Pro Ultrasound Table 115 VAC is designed for general ultrasound procedures, including OB/GYN. Wt capacity: 500lb. Height adjustable: 23" - 35". Depth has optional side rails included. Enhanced ergonomics reduce sonographer fatigue. Redesigned Fowler back provides utmost patient comfort and require less patient repositioning.

View Cutsheet 209451

See accessories: Include stirrups and side raila

W x D x H: 70 x 35 x 39 in.
Electrical: 115V 60Hz **Weight:** 335 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side Rails	058-633	1	1
Stirrups, Retractable	058-652	1	1

Warmer, Gel

AE #: WAGE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Parker Laboratories, Inc.	83-03		Wall	OF/CI	Project

Multi bottle gel warmer (three bottles) with LED temperature readout

View Cutsheet 147051

W x D x H: 11.5 x 4.3 x 9 in.
Electrical: 120V 60Hz 2.8A

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red

View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.
Weight: 10.9 lbs.

Room: Treatment / Ultrasound Room

Department: Breast Imaging

Room #: B703L

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703M

Room Notes: 5 female, 1 male

Apron, Lead

AE #: APLE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	Sf17-NL		Rack	OF/OI	Project

Standard F17 - Frontal Apron with Stretch Hook & Loop Closure

View Cutsheet 209349

SKU: Sf17-NL. Protective MaterialXenolite 800 NL™ - 0.5mm. See accessories for magnetic, tethered thyroid shield. Price includes shield ($115).

Available in Men's and Women's XS - XL.

Order variety of sizes. Plan for (3) L, (2) XL, (1)XXL

W x D x H: 28 x 44 x N/A in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
TSS - Thyroid Shield Standard		1	1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703M

Room Notes: 5 female, 1 male

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen

AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703M

Room Notes: 5 female, 1 male

Imaging, Digital Mammography — AE #: ISMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	3DIMENSIONS, Genius 3D		Floor	OF/CI/VI	Project

3D digital mammography system. With Genius and Clarity HD High Resolution software for faster mammography with clearer images. Designed to better capture dense breast tissue. Able to detect 20-65% more invasive breast cancers. 2D capabilities come standard as well. View Cutsheet 210444

Include DBT option. Price includes Genius AI Detection, 3D Quorum Training, needle localization kit, and licensing. Quote #Q-393486, dated 8/22/24

W x D x H: 66.5 x 51.6 x 87.8 in.
Network: Wired
Electrical: 240V 60Hz 40A **Weight:** 882 lbs.
Elect Notes: **Refer to Hologic site planning information.** 200-240 vac, 50-60hz, single phase, 40 amp
Plumb Notes: **Refer to Hologic site planning information.**
HVAC Notes: **Refer to Hologic site planning information.**
Struct Notes: **Refer to Hologic site planning information.**

Imaging, Mammography Accessory — AE #: IMMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	Universal acquisition workstation		Floor	OF/VI	Project

Universal acqusition workstation (with shield) View Cutsheet 165820

Width is 53.4"w with display arm extended. **included with the price of the mammo system.**

W x D x H: 36.9 x 48.4 x 80.3 in.
Network: Wired

Imaging, Mammography Accessory — AE #: IMMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Hologic, Inc.	SELENIA DIMENSIONS PADDLE RACK		Wall	OF/CI	Project

Paddle rack. Note** recommended minimum spacing of 12 inches between racks when installing racks over each other. View Cutsheet 165490

Selenia discontinued, but paddle rack is still compatible and the preferred choice for the 3DIMENSIONS

W x D x H: 36.3 x 4 x 7 in.

Room: Mammography Exam **Department:** Breast Imaging

Room #: B703M

Room Notes: 5 female, 1 male

Phantom, Mammography

AE #: PHMA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sun Nuclear Corporation	016A-BR12		Cabinet	OF/OI	Project

Single Exposure High Contrast Resolution Phantom; Incorporates two 17.5 micron thick gold-nickel alloy bar patterns; The bar patterns are positioned at 90 degrees to allow assessment of resolution perpendicular and parallel to anode-cathode axis; Targets have 17 segments from 5 lp to20 lp/mm and are equivalent to 25 microns of lead or 2.6mm of aluminum at 20 keV

View Cutsheet 209569

This model used by physicists. Gaye to send info on other phantoms used in Mammo rooms

W x D x H: 5 x 4 x 2 in.

Weight: 2 lbs.

Rack, Apron

AE #: RAAP-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Burlington Medical, Inc.	WR4		Wall	OF/CI	Project

Wall-mounted peg rack designed to hold frontal or wrap around aprons. 4-pegs for two aprons. Each peg is 4" long

View Cutsheet 210231

W x D x H: 12 x 5 x 3 in.

Shield, Thyroid

AE #: SHTH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bar-Ray Products, Inc	49995		Rack	OF/OI	Project

Tethered thyroid collar; buckle closure. No top binding makes the collar more comfortable and flexible against the skin. Tether keeps collar with apron at all times. Select fabric and color and protections type (0.5mm cost cruncher, prestige, scatter sentry, star lite or true lite). Fits up to a 20" neck size.

View Cutsheet 165478

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Radiologist Work Room (Procedure) **Department:** Breast Imaging

Room #: B703N

Room Notes: Assumes space for 3 people

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Radiologist Work Room (Diagnostic) **Department: Breast Imaging**

Room #: B703P

Room Notes: Assumes space for 5

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Soiled Linen / Tray Closet

Department: Breast Imaging

Room #: B704A

Room Notes: For soiled linen and dirty procedure trays only

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

One cart for breast gowns, one for general linen. Soiled breast gown cart will be shared with breast clinic.

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Room: Clean Supply / Linen / Meds **Department: Breast Imaging**

Room #: B704B

Room Notes: B.I. only. Approx 12' of ParEx space adequate per Breast Imaging staff.

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Linen AE #: CALI-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAXI		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 36" x 24". Two solid (mx2436f) and two grid shelves (mx2436g); on 5" casters - one set swivel (5mdxa) and one set braking (5mdbxa); side and back enclosure panels (mep57e & mep37e); to include blue coated cover with velcro closures (24x36x74vcmb). View Cutsheet 167067

Downsized from a 4' to a 3' cart in order to fit in the clean supply room. For Mammo gowns from Advantage Linens

W x D x H: 36 x 24 x 80.1 in.

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

For regular gowns/linens - Logans

W x D x H: 48 x 24 x 79 in.

Room: Clean Supply / Linen / Meds **Department:** Breast Imaging

Room #: B704B

Room Notes: B.I. only. Approx 12' of ParEx space adequate per Breast Imaging staff.

Drug Dispensing Unit — AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

Per Katie Plahn email 9/14/2023

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Pyxis, Undercounter — AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit. View Cutsheet 170325

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
Elect Notes: 15a dedicated ground circuit; nema 5-15 hospital grade plug 8-10 ft. Battery backup.
HVAC Notes: Variable speed compressor-based forced air refrigeration system; r600a, isobutane, epa snap compliant refrigerant charge

Room: Clean Supply / Linen / Meds

Department: Breast Imaging

Room #: B704B

Room Notes: B.I. only. Approx 12' of ParEx space adequate per Breast Imaging staff.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Consult

Department: Breast Imaging

Room #: B705A

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Passage (Lockers / Linen Hamper) **Department: Breast Imaging**

Room #: B705B

Room Notes: Confirm room number

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal

View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Room: Dressing Room **Department:** Breast Imaging

Room #: B705B1, B705B2, B705B3, B705B4, B705B5, B705B6, B705B7, B705B8

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Ultrasound Room **Department:** Breast Imaging

Room #: B705C, B705E, B705F, B705H

Chair, Ultrasound Tech

AE #: CHUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hag Ergonomic Chairs / Izzy Design	H8106		Floor	OF/OI	Project

Hag capisco (the saddle chair) with seat and back. Saddle seat is height adjustable between low and high working positions all the way to standing. View Cutsheet 150834

Standard 200mm gas lift.

W x D x H: 27.6 x 27.6 x 55.1 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Ultrasound Room **Department: Breast Imaging**

Room #: B705C, B705E, B705F, B705H

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Breast Ultrasound — AE #: IMBU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	SuperSonic Mach 40		Floor	OF/VI	Project

SuperSonic MACH 40 system provides unprecedented capabilities with unique View Cutsheet 208916

UltraFast™ architecture, innovative transducers and a large FHD viewing screen.

• Smooth images with reduced speckle, regardless of tissue density

• Incredible definition in both fundamental and harmonic imaging modes

• Optimized penetration settings for image clarity regardless of imaging depth

• Acquisition of 3D volumetric data

W x D x H: 23.8 x 47.6 x 72 in.

Network: Wireless

Network Notes: Compliant with 802.11b/g/n standard. WPA/WPA2 Personal security. 2.4GHz band frequency. Wi-Fi device FCC/IC/CE certified. Wireless networking for DICOM modalities and network printer connection.

Electrical: 120V 60Hz

Weight: 246 lbs.

Room: Ultrasound Room **Department:** Breast Imaging

Room #: B705C, B705E, B705F, B705H

Table, Ultrasound

AE #: TAUL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Biodex Medical Systems, Inc	Ultra Pro	058-720	Floor	OF/VI	Project

The Biodex Ultra Pro Ultrasound Table 115 VAC is designed for general ultrasound procedures, including OB/GYN. Wt capacity: 500lb. Height adjustable: 23" - 35". Depth has optional side rails included. Enhanced ergonomics reduce sonographer fatigue. Redesigned Fowler back provides utmost patient comfort and require less patient repositioning. View Cutsheet 209451

See accessories: Include stirrups and side raila

W x D x H: 70 x 35 x 39 in.
Electrical: 115V 60Hz **Weight:** 335 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side Rails	058-633	1	1
Stirrups, Retractable	058-652	1	1

Warmer, Gel

AE #: WAGE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Parker Laboratories, Inc.	83-03		Wall	OF/CI	Project

Multi bottle gel warmer (three bottles) with LED temperature readout View Cutsheet 147051

W x D x H: 11.5 x 4.3 x 9 in.
Electrical: 120V 60Hz 2.8A

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Sub-Wait **Department:** Breast Imaging

Room #: B705D

Cabinet, Warming

AE #: CAWA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7921TG	14B792143	Floor	OF/VI	Project

Freestanding single chamber warming cabinet, digital touch screen display with glass door. Heat range from 90-160 degrees. Optional 3" casters available.

View Cutsheet 208673

Place in between Dressing Rooms and Subwait.

W x D x H: 30 x 26.6 x 74.5 in.
Network: Wired
Electrical: 120V 60Hz 7.5A **Weight:** 437 lbs.
HVAC Notes: 1604 BTU/hr

Coffee Brewer

AE #: COBR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Keurig, Inc.	K150P		Countertop	OF/CI	Project

Plumbed version of the k150 model. Ideal for medium volume use. Nsf certified for food service.

View Cutsheet 160824

Place Holder

W x D x H: 10.4 x 14 x 13.9 in.
Electrical: 120V 60Hz 1400W **Weight:** 18 lbs.
Plumb Notes: Water line required.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Kq8 Water Filter Kit		1	1

Dispenser, Cup

AE #: DICU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	San Jamar	C3200PGR	GRAINGER 6ADL7	Wall	OF/CI	Project

Stainless steel cup dispenser for 6-10 oz cups.

View Cutsheet 141423

W x D x H: 4.75 x 4.75 x 34.8 in.

Room: Sub-Wait **Department:** Breast Imaging

Room #: B705D

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in.
Clearance: Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A
Weight: 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in.
Clearance: Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component

AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Room: Sub-Wait

Department: Breast Imaging

Room #: B705D

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Ultrasound Room 5 (Flex Procedure) **Department:** Breast Imaging

Room #: B705G

Room Notes: Back up procedure room

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Chair, Ultrasound Tech

AE #: CHUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hag Ergonomic Chairs / Izzy Design	H8106		Floor	OF/OI	Project

Hag capisco (the saddle chair) with seat and back. Saddle seat is height adjustable between low and high working positions all the way to standing. View Cutsheet 150834

Standard 200mm gas lift.

W x D x H: 27.6 x 27.6 x 55.1 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Ultrasound Room 5 (Flex Procedure) **Department:** Breast Imaging

Room #: B705G

Room Notes: Back up procedure room

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Room: Ultrasound Room 5 (Flex Procedure) **Department:** Breast Imaging

Room #: B705G

Room Notes: Back up procedure room

Imaging, Breast Ultrasound — AE #: IMBU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hologic, Inc.	SuperSonic Mach 40		Floor	OF/VI	Project

SuperSonic MACH 40 system provides unprecedented capabilities with unique UltraFast™ architecture, innovative transducers and a large FHD viewing screen. View Cutsheet 208916

- Smooth images with reduced speckle, regardless of tissue density
- Incredible definition in both fundamental and harmonic imaging modes
- Optimized penetration settings for image clarity regardless of imaging depth
- Acquisition of 3D volumetric data

W x D x H: 23.8 x 47.6 x 72 in.

Network: Wireless

Network Notes: Compliant with 802.11b/g/n standard. WPA/WPA2 Personal security. 2.4GHz band frequency. Wi-Fi device FCC/IC/CE certified. Wireless networking for DICOM modalities and network printer connection.

Electrical: 120V 60Hz

Weight: 246 lbs.

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting. View Cutsheet 85906

W x D x H: 2.8 x 4.8 x 6.5 in.

Weight: 1.25 lbs.

Stool, Foot, With Handrail — AE #: STFH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	1251		Floor	OF/OI	Project

9" footstool with nonslip black rubber mat and rubber tips for added stability. View Cutsheet 43549

W x D x H: 14.3 x 11.4 x 35.8 in.

Room: Ultrasound Room 5 (Flex Procedure) **Department:** Breast Imaging

Room #: B705G

Room Notes: Back up procedure room

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Instrument

AE #: TAIN-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Vevor	24x18x34 SS		Floor	OF/OI	Project

24x18x34 Inch Stainless Steel Work Table 3-Stage Adjustable Shelf with 4 Wheels Heavy Duty Commercial Food Prep Worktable with Brake.

View Cutsheet 209466

This model preferred by breast imaging staff.

W x D x H: 24 x 18 x 34 in.

Weight: 22 lbs.

Table, Ultrasound

AE #: TAUL-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Biodex Medical Systems, Inc	Ultra Pro	058-720	Floor	OF/VI	Project

The Biodex Ultra Pro Ultrasound Table 115 VAC is designed for general ultrasound procedures, including OB/GYN. Wt capacity: 500lb. Height adjustable: 23" - 35". Depth has optional side rails included. Enhanced ergonomics reduce sonographer fatigue. Redesigned Fowler back provides utmost patient comfort and require less patient repositioning.

View Cutsheet 209451

See accessories: Include stirrups and side raila

W x D x H: 70 x 35 x 39 in.

Electrical: 115V 60Hz **Weight:** 335 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side Rails	058-633	1	1
Stirrups, Retractable	058-652	1	1

Room: Ultrasound Room 5 (Flex Procedure) **Department:** Breast Imaging

Room #: B705G

Room Notes: Back up procedure room

Warmer, Gel

AE #: WAGE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Parker Laboratories, Inc.	83-03		Wall	OF/CI	Project

Multi bottle gel warmer (three bottles) with LED temperature readout View Cutsheet 147051

W x D x H: 11.5 x 4.3 x 9 in.
Electrical: 120V 60Hz 2.8A

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.
Weight: 10.9 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Mobile Equipment **Department:** Breast Imaging

Room #: B705H1

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Chair, Mammography

AE #: CHMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MXE, Inc.	700002DERV		Floor	OF/OI	Project

Deluxe hydraulic mammography chair; reclines to a maximum of 170 degrees; seat height adjusts from 23" to 32"; removable arm rests; adjustable removable head rest; removable foot rest; five star chair base with five locking casters; light gray vinyl upholstery; weight capacity: 300 lbs. View Cutsheet 64574

For wc bound patients

W x D x H: 27 x 27 x N/A in.

Lifter, Patient

AE #: LIPA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Guldmann Inc	GL5.2		Floor	OF/VI	Project

Mobile lifter with weight capacity of 205 kg. Features electric lifting and width adjustment to allow access around chairs, baths, and the ability to lift from the floor. View Cutsheet 208837

W x D x H: 27.4 x 52.2 x 53.7 in.
Electrical: 115V 60Hz

Room: Mobile Equipment **Department:** Breast Imaging

Room #: B705H1

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Sphygmomanometer, Aneroid, Mobile

AE #: SPAM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-03		Floor	OF/OI	Project

Mobile aneroid on 5 legged base stand with basket and reusable flexiport adult cuff. View Cutsheet 142718

W x D x H: 22 x 22 x 42 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Room: Mobile Equipment **Department:** Breast Imaging

Room #: B705H1

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Toilet (Staff)

Department: Breast Imaging

Room #: B707B

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Radiologist Work Room (MRI)

Department: Breast Imaging

Room #: B707C

Room Notes: Assumes space for 3

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Office, Shared / Meeting

Department: Breast Imaging

Room #: B707D

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Consult

Department: Cardio and Rehab Oncology

Room #: A701A

Room Notes: Located right next to Palliative Consult room.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Echo

Department: Cardio and Rehab Oncology

Room #: A701P

Room Notes: Echo tech workstation hardware furnished by IT.

Bed, Echo Procedure

AE #: BEEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medical Positioning, Inc	Echo Table	2272	Floor	OF/OI	Project

Echo table, height adjustable from 23" to 34", wt capacity 1000 lbs. Imaging drop section and sonographer drop section, hand controller, patient back support, paper roll holder and cutter. With fowler option.

View Cutsheet 150849

Model confirmed during MEQ signoff meeting 2/5/2024.

W x D x H: 28 x 80 x 34 in.
Electrical: 120V 60Hz 3.2A **Weight:** 240 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W.

View Cutsheet 208699

For holding IV supplies

W x D x H: 27 x 18 x 33 in.

Chair, Ultrasound Tech

AE #: CHUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hag Ergonomic Chairs / Izzy Design	H8106		Floor	OF/OI	Project

Hag capisco (the saddle chair) with seat and back. Saddle seat is height adjustable between low and high working positions all the way to standing.

View Cutsheet 150834

Standard 200mm gas lift.

No footring per department.

W x D x H: 27.6 x 27.6 x 55.1 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Echo

Department: Cardio and Rehab Oncology

Room #: A701P

Room Notes: Echo tech workstation hardware furnished by IT.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Echo **Department: Cardio and Rehab Oncology**

Room #: A701P

Room Notes: Echo tech workstation hardware furnished by IT.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Ultrasound Scanner — AE #: IMUS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Imaging	EPIQ CVX		Floor	OF/VI	Project

Dedicated cardiology ultrasound View Cutsheet 170050

With 3D and strain. Per quote Q-00346148 received from Rick "Opie" Willis on 8/12/2024.

W x D x H: 23.9 x 43 x 67.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 229.9 lbs.

Warmer, Gel — AE #: WAGE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Parker Laboratories, Inc.	83-03		Countertop	OF/OI	Project

Multi bottle gel warmer (three bottles) with LED temperature readout View Cutsheet 147051

W x D x H: 11.5 x 4.3 x 9 in.
Electrical: 120V 60Hz 2.8A

Room: Echo

Department: Cardio and Rehab Oncology

Room #: A701P

Room Notes: Echo tech workstation hardware furnished by IT.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Toilet (Patient)

Department: Cardio and Rehab Oncology

Room #: A701R, A710B, A710M1

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Cardio and Rehab Oncology

Room #: A701R, A710B, A710M1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Staff)

Department: Cardio and Rehab Oncology

Room #: A709A

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Private Phone / Huddle

Department: Cardio and Rehab Oncology

Room #: A709B

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Treatment (Rehab) **Department: Cardio and Rehab Oncology**

Room #: A710D, A710F, A710K

Room Notes: Privacy curtain requested

Allowance, Software

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Prometheus Group	Telesis		Computer	OF/OI	Project

Telesis software interfaces the Pathway MR Series devices with an owner-provided PC. For use with Pathway MR-10, MR-20, MR-15, MR-25. View Cutsheet 209197

Network Notes: System requirements: OS: Windows 10 Professional; 64-bit operating system; Processor type: Intel Core i5 or higher; RAM: 8 GB minimum; 256 GB minimum available hard drive space; available USB ports.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Treatment (Rehab) **Department:** Cardio and Rehab Oncology

Room #: A710D, A710F, A710K

Room Notes: Privacy curtain requested

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Electromyograph

AE #: ELMY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Prometheus Group	Pathway MR-20		Countertop	OF/OI	Project

Pathway MR-20 dual channel EMG system with alpha/numeric LCD displays; monitors 2 muscles at a time. Automatic data storage; hand held portability; functional electrical stimulator interface.

View Cutsheet 90943

this price also includes synergy 3d software to be installed on any pc.

Richard confirmed model via email 9/12/2023

W x D x H: 7 x 3 x 10 in.

Network: Networked

Weight: 2 lbs.

Elect Notes: 9 volt battery

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Synergy 3-D Software		1	1

Room: Treatment (Rehab) **Department: Cardio and Rehab Oncology**

Room #: A710D, A710F, A710K

Room Notes: Privacy curtain requested

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Dept will ask about preference for with/without back.

W x D x H: 20 x 20 x 24.5 in.

Table, Treatment — AE #: TATR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081501626		Floor	OF/VI	Project

Hi-Lo treatment table supports up to 400 lbs. Head section adjusts from -45 to +90 degrees and measures 27" x 15". With (4) 4" locking casters. View Cutsheet 208656

W x D x H: 27 x 76 x 37 in.
Electrical: 115V 60Hz

Room: Treatment (Rehab) **Department: Cardio and Rehab Oncology**

Room #: A710D, A710F, A710K

Room Notes: Privacy curtain requested

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Rehab / Cardio Equipment

Department: Cardio and Rehab Oncology

Room #: A710G

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

With 4-5 shelves

W x D x H: 36 x 24 x 66.8 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

Quantity (1) confirmed in MEQ signoff meeting 2/5/2024.

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Monitor, Transport

AE #: MOTR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	X3		Shelf	OF/VI	Project

MMS module X3; touchscreen user interface View Cutsheet 170125

W x D x H: 7.4 x 3.4 x 6 in.
Electrical: 120V 60Hz 1.3A

Room: Rehab / Cardio Equipment **Department:** Cardio and Rehab Oncology

Room #: A710G

Monitor, Transport, Component — AE #: MOTC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Monitoring	Intellivue Dock	867043	Shelf	OF/VI	Project

Dock provides power to X3, MX100, X2, and MP2 for charging monitors. Additionally intended to provide the connected device with a LAN and flexible sync out interface. Supports variety of measurement extensions. View Cutsheet 209449

W x D x H: 7.5 x 3.9 x 4.4 in.
Electrical: 120V 60Hz **Weight:** 1.61 lbs.
Elect Notes: Power consumption <30 W average

Monitor, Vital Signs — AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	2

Monitor, Vital Signs, Component — AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Rehab / Cardio Equipment

Department: Cardio and Rehab Oncology

Room #: A710G

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Scanner, Bladder

AE #: SCBL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Verathon Inc. - Medical	i10	0270-1014	Stand	OF/VI	Project

Bladder scanner i10 system; on rolling stand.

View Cutsheet 200466

Requested by Rehab

Electrical: 120V 60Hz 1.4A

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Stand	0800-0631	1	1

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult.

View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long.

View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult.

View Cutsheet 160316

Room: Rehab / Cardio Equipment

Department: Cardio and Rehab Oncology

Room #: A710G

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Treatment (Rehab - Bariatric) **Department: Cardio and Rehab Oncology**

Room #: A710H

Room Notes: Privacy curtain requested

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treatment (Rehab - Bariatric) **Department: Cardio and Rehab Oncology**

Room #: A710H

Room Notes: Privacy curtain requested

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Dept will ask about preference for with/without back.

W x D x H: 20 x 20 x 24.5 in.

Room: Treatment (Rehab - Bariatric) **Department:** Cardio and Rehab Oncology

Room #: A710H

Room Notes: Privacy curtain requested

Table, Treatment, Bariatric

AE #: TATB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081502061		Floor	OF/VI	Project

Hi-Low 2-section treatment table with height adjustable from 18" to 37". Weight capacity 500 lbs. Four locking swivel casters. Head section with contoured face/nose opening. View Cutsheet 208659

W x D x H: 34 x 76 x 37 in.
Electrical: 115V 60Hz

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Treatment (Pelvic) **Department:** Cardio and Rehab Oncology

Room #: A710M, A710Q

Room Notes: Privacy curtain requested

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treatment (Pelvic) **Department:** Cardio and Rehab Oncology

Room #: A710M, A710Q

Room Notes: Privacy curtain requested

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Stool, Revolving, Exam — AE #: STRE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	272-001-XXX		Floor	OF/VI	Project

Value series without back Midmark air lift stool; pneumatic adjustment; black composite; 5 caster base with hood; adjustable height from 18" to 24.5" View Cutsheet 122617

Dept will ask about preference for with/without back.

W x D x H: 20 x 20 x 24.5 in.

Room: Treatment (Pelvic) **Department: Cardio and Rehab Oncology**

Room #: A710M, A710Q

Room Notes: Privacy curtain requested

Table, Treatment, Bariatric

AE #: TATB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Performance Health	081502061		Floor	OF/VI	Project

Hi-Low 2-section treatment table with height adjustable from 18" to 37". Weight capacity 500 lbs. Four locking swivel casters. Head section with contoured face/nose opening. View Cutsheet 208659

W x D x H: 34 x 76 x 37 in.
Electrical: 115V 60Hz

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Echo **Department: Cardio and Rehab Oncology**

Room #: B701N

Room Notes: This room has a refrigerator and contrast shaker. Echo tech workstation hardware furnished by IT.

Bed, Echo Procedure

AE #: BEEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medical Positioning, Inc	Echo Table	2272	Floor	OF/OI	Project

Echo table, height adjustable from 23" to 34", wt capacity 1000 lbs. Imaging drop section and sonographer drop section, hand controller, patient back support, paper roll holder and cutter. With fowler option. View Cutsheet 150849

Model confirmed during MEQ signoff meeting 2/5/2024.

W x D x H: 28 x 80 x 34 in.
Electrical: 120V 60Hz 3.2A **Weight:** 240 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

For holding IV supplies

W x D x H: 27 x 18 x 33 in.

Chair, Ultrasound Tech

AE #: CHUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hag Ergonomic Chairs / Izzy Design	H8106		Floor	OF/OI	Project

Hag capisco (the saddle chair) with seat and back. Saddle seat is height adjustable between low and high working positions all the way to standing. View Cutsheet 150834

Standard 200mm gas lift.

No footring per department.

W x D x H: 27.6 x 27.6 x 55.1 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Echo **Department: Cardio and Rehab Oncology**

Room #: B701N

Room Notes: This room has a refrigerator and contrast shaker. Echo tech workstation hardware furnished by IT.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Room: Echo **Department:** Cardio and Rehab Oncology

Room #: B701N

Room Notes: This room has a refrigerator and contrast shaker. Echo tech workstation hardware furnished by IT.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Ultrasound Scanner — AE #: IMUS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Philips Medical Systems - Imaging	EPIQ CVX		Floor	OF/VI	Project

Dedicated cardiology ultrasound View Cutsheet 170050

With 3D and strain. Per quote Q-00346148 received from Rick "Opie" Willis on 8/12/2024.

W x D x H: 23.9 x 43 x 67.5 in.
Network: Wired
Electrical: 115V 60Hz **Weight:** 229.9 lbs.

Mixer, Vortex — AE #: MIVO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lantheus Medical Imaging	VIALMIX		Countertop	OF/OI	Supply Agreement

Countertop vortex mixer for DEFINITY Vial injectable suspension View Cutsheet 207932

W x D x H: 7.68 x 7.68 x 6.5 in.
Electrical: 120V 60Hz 2A

Room: Echo **Department: Cardio and Rehab Oncology**

Room #: B701N

Room Notes: This room has a refrigerator and contrast shaker. Echo tech workstation hardware furnished by IT.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Countertop — AE #: RECO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	REF1-KP		Countertop	OF/VI	Project

Medical grade 1 cu. ft. countertop refrigerator. Programmable operating range 2.2 to 10 degrees C / 36-50 F. Exterior LED displays product temperature in user-selectable F or C (default C). Cylinder lock w/key standard. Include optional keypad lock. One epoxy-coated wire shelf. Self closing right-hinged door is field reversible. View Cutsheet 209191

Keypad lock approved by Katie Plahn in Pharmacy 9/11/2023.

W x D x H: 18.6 x 24 x 17.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 8 in.
Electrical: 120V 60Hz 1.8A **Weight:** 60 lbs.
Elect Notes: NEMA 5-15P 90 degree hospital-grade plug, 8' power cord.
HVAC Notes: Max heat rejection 190 BTU/hr. Refrigerant R134a.
Ventilation clearance with more than 8" top clearance: 2" on both sides. Ventilation clearance with less than 8" top clearance: 6" for one side.

Warmer, Gel — AE #: WAGE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Parker Laboratories, Inc.	83-03		Countertop	OF/OI	Project

Multi bottle gel warmer (three bottles) with LED temperature readout View Cutsheet 147051

W x D x H: 11.5 x 4.3 x 9 in.
Electrical: 120V 60Hz 2.8A

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: On-Stage Team Work Area **Department:** Cardio and Rehab Oncology

Room #: B701Q

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case

View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter

View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department:** Cardio and Rehab Oncology

Room #: B701S, B701T, B701U, B701V, B701W, B701X

Room Notes: Will be used by Cardio only

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room **Department: Cardio and Rehab Oncology**

Room #: B701S, B701T, B701U, B701V, B701W, B701X

Room Notes: Will be used by Cardio only

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Exam Room **Department:** Cardio and Rehab Oncology

Room #: B701S, B701T, B701U, B701V, B701W, B701X

Room Notes: Will be used by Cardio only

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Sphygmomanometer, Aneroid, Wall Mount

AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Exam Room **Department:** Cardio and Rehab Oncology

Room #: B701S, B701T, B701U, B701V, B701W, B701X

Room Notes: Will be used by Cardio only

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs

View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended.

View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Medication Room **Department:** Cardio and Rehab Oncology

Room #: B707F-Shared

Room Notes: Shared with Palliative & Breast Clinic

Cart, Resuscitation, Cardiac

AE #: CARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	LECCRP2		Floor	OF/VI	Project

Blue Lifeline emergency response cart with 5" casters, ergonomic handle, and 5th wheel steering system. Preconfigured cart includes the following: (1) 3" drawer, (3) 6" drawers, waste basket 28 qt. w/holder, lockable sharps container (mounts to handle side), adjustable defibrillator tray, backboard with back assembly kit, oxygen tank holder, IV pole w/cart mount, and 100 pack of security seals. Dimensions include added space needed for side mounted items and IV pole.

View Cutsheet 208817

W x D x H: 45 x 22.6 x 72 in.

Defibrillator

AE #: DEFI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp.	LIFEPAK 15	LP15	Crashcart	OF/OI	Project

LIFEPAK 15 Monitor/Defibrillator; Delivers up to 360 joules; Defibrillation, Synchronized Cardioversion, and AED Shock Advisory System; ECG Monitoring, Heart Rate, and Alarms; SpO2 Monitoring, Pulse Rate, and Alarms; EtCO2 Monitoring and Alarms; NIBP Monitoring and Alarms; Invasive Pressure Monitoring and Alarms; Temperature Monitoring and Alarms; Six main operating modes: AED mode, Manual mode, Archive mode, Setup mode, Service mode, and Demo mode; AC or DC Power Adapters; Rechargeable Lithium-ion batteries; Display: 8.4" diagonal, 6.7 in wide x 5.0 in high; Data management: captures and stores patient data, events (including waveforms and annotations), and continuous waveform and patient impedance records in internal memory, can print reports and transfer data by wired or wireless connection; 12-Lead interpretive algorithm; Printer.

View Cutsheet 203982

W x D x H: 15.8 x 9.1 x 12.5 in.

Network Notes: Serial Port RS232 communication + 12V available; Bluetooth® technology provides short-range wireless communication with other Bluetooth enabled devices.

Electrical: 120V 60Hz 1.8A

Weight: 17.5 lbs.

Elect Notes: Lithium-ion battery

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Medication Room **Department:** Cardio and Rehab Oncology

Room #: B707F-Shared

Room Notes: Shared with Palliative & Breast Clinic

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. hand sanitizers requested outside doors to room

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit

AE #: DRDU-07

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	Single Integrated Main		Floor	OF/VI	Lease

Single column all-door configuration of Pyxis Medstation with 3 doors - available in solid or clear. Stores bulky items. Biometric ID and 2D barcode scanner included. View Cutsheet 171846

Per Katie Plahn email 9/14/2023

W x D x H: 31 x 28 x 80 in.
Network: Wired
Electrical: 120V 60Hz 125W **Weight:** 350 lbs.
HVAC Notes: 362 btu/hr

Room: Medication Room **Department:** Cardio and Rehab Oncology

Room #: B707F-Shared

Room Notes: Shared with Palliative & Breast Clinic

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Refrigerator, Pyxis, Undercounter — AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit. View Cutsheet 170325

Plan to use for Palliative as this is the direction they will be going in the future

W x D x H: 24 x 29 x 32 in. **Clearance:** Rear 3 in.
Electrical: 115V 60Hz 1.4A **Weight:** 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Room: Medication Room

Department: Cardio and Rehab Oncology

Room #: B707F-Shared

Room Notes: Shared with Palliative & Breast Clinic

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage, Team Work Area

Department: Cardio and Rehab Oncology

Room #: B707H1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient)

Department: Gyn Onc Clinic

Room #: A702A, A704B, A704K

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Gyn Onc Clinic

Room #: A702A, A704B, A704K

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Exam Room **Department:** Gyn Onc Clinic

Room #: A702B, A702D, A702F, A702J, A702L, A702N, A704E, A704F, A704G, A704L, A704M, A704N

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Exam Room **Department:** Gyn Onc Clinic

Room #: A702B, A702D, A702F, A702J, A702L, A702N, A704E, A704F, A704G, A704L, A704M, A704N

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes.

View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Exam Room **Department:** Gyn Onc Clinic

Room #: A702B, A702D, A702F, A702J, A702L, A702N, A704E, A704F, A704G, A704L, A704M, A704N

Hamper, Linen

AE #: HALI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80529		Floor	OF/OI	Project

18" with foot pedal View Cutsheet 122368

W x D x H: 19.5 x 18.8 x 37.4 in.

Light, Exam/ Treatment

AE #: LIET-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	GS300	44400	Floor	OF/OI	Project

LED exam light on mobile stand; features 20,000 lux and touchless controls. Ideal for primary care facilities, emergency rooms, outpatient facilities and dermatology; 5-year limited warranty View Cutsheet 122496

W x D x H: 20.9 x 20.9 x 58.7 in.
Electrical: 120V 60Hz 0.35A **Weight:** 12.75 lbs.

Light, Speculum

AE #: LISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	80010		Countertop	OF/OI	Project

Complete kleenspec cordless illumination system with charging station with us style ac plug. Associated disposables: kleenspec disposable vaginal specula. View Cutsheet 161569

W x D x H: 3.1 x 9.3 x 6.4 in.
Electrical: 120V 60Hz 0.2A **Weight:** 1.1 lbs.

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Room: Exam Room **Department:** Gyn Onc Clinic

Room #: A702B, A702D, A702F, A702J, A702L, A702N, A704E, A704F, A704G, A704L, A704M, A704N

Sphygmomanometer, Aneroid, Wall Mount

AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: Exam Room **Department:** Gyn Onc Clinic

Room #: A702B, A702D, A702F, A702J, A702L, A702N, A704E, A704F, A704G, A704L, A704M, A704N

Table, Exam, Power

AE #: TAEP-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626- 32"		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and IQvitals table mount. Length of tabletop is 60"; 76" with footrest extended. ***To include 32" wide top.***

View Cutsheet 209180

Confirm with Dept that 32" is preferred

W x D x H: 32 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.
Weight: 6.1 lbs.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area **Department:** Gyn Onc Clinic

Room #: A703

Room Notes: Assumes space for 6 people

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area **Department:** Gyn Onc Clinic

Room #: A704A

Room Notes: Assumes space for 6 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Workstation, US Infection Control

AE #: WOIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	AuditPro		Countertop	OF/OI	Project

Infection control workflow compliance management in the form of a workstation and mobile unit to be used with the Nanosonic Trophon2. Handheld computer/barcode scanner dimensions: 6.18 x 3.08 x 0.67 in View Cutsheet 210430

W x D x H: 5.1 x 5.9 x 2.3 in.

Network: Wireless **Network Notes:** WLAN, WLAN/WWAN

Electrical: 120V 60Hz

Room: Consult **Department:** Gyn Onc Clinic

Room #: A704C, A704D

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Basket, Sphygmomanometer

AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage

AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Cabinet, Ultrasound Transducer

AE #: CAUT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Civco Medical Solutions	610-1327		Wall / Floor	OF/CI	Project

General purpose & endocavity probe cabinet; holds up to six probes; true HEPA filter provides continuous airflow using positive pressure. Airflow View Cutsheet 165407

specifications: 200 air changes/hour. Filter specifications: 99.97% @ 0.3 µm. Vertical suspension of probes facilitates drying. Includes U.S. power cord.

W x D x H: 24 x 10 x 74 in. **Clearance:** Right 6 in.; Top 10 in.
Electrical: 120V 60Hz 0.5A **Weight:** 100 lbs.
Elect Notes: 15a hospital-grade gfci outlet required

Cart, Electrosurgical

AE #: CAES-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	356		Floor	OF/OI	Project

Stainless steel compact utility stand with drawer. 300 lb capacity. (1) Drawer, (1) shelf. Swivel casters. View Cutsheet 210237

For Finesse+ Electrosurgical Unit to sit on

W x D x H: 18.8 x 16.8 x 30.1 in.

Weight: 36 lbs.

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Colposcope

AE #: COLP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wallach Surgical Devices, Inc.	Zoomscope	906043-40TU-5	Floor	OF/OI	Project

The ZoomScope with Trulight is a multi-purpose microscope for colposcopy. The ZoomScope with Trulight has a continuous Zoom range of magnification from 4.6x to 20x. View Cutsheet 209491

W x D x H: 20 x N/A x 63 in.
Electrical: 120V 60Hz 2A **Weight:** 61.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
4-Leg Base	906043-SP-4	1	1

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula

AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Electrosurgical Unit

AE #: ELUN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Utah Medical Products, Inc.	Finesse+ FIN110		Cart	OF/OI	Project

Gynecologic electrosurgical generator with integrated smoke evacuation View Cutsheet 210234

To sit on top of Lakeside Equipment Stand

W x D x H: 14 x 14.7 x 7.3 in.

Electrical: 115V 60Hz **Weight:** 24 lbs.

Flowmeter, Oxygen

AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, View Cutsheet 208703

CO2, and N2O. All Flowmeters come with a standard 1/8

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Hamper, Linen — AE #: HALI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-120		Cabinet	OF/OI	Project

18 in. Diameter linen hamper without lid; chrome plated steel construction; triangular frame; 3" double ball bearing, swivel casters for easy mobility View Cutsheet 13153

** dimensions with casters swiveled in: 20.07"w x 18.57"d

W x D x H: 23.7 x 21.2 x 32 in.

Imaging, Ultrasound Scanner — AE #: IMUS-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	Voluson P8		Cart	OF/VI	Project

The Voluson P8 delivers excellent image quality, ease of use, and streamlined workflow in a sleek, lightweight package to provide confident, efficient care across a range of applications. View Cutsheet 208830

Price includes printer and probes

W x D x H: 16 x 30 x 53 in.
Network: Wired
Electrical: 120V 60Hz 9A **Weight:** 150 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
BW Printer Kit	H44972LD	1	1
IC9-RS Probe (transducer: obs, gyn, transrectal)	H48691PJ	1	1

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Light, Exam/ Treatment

AE #: LIET-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Skytron	DoVera DE12		Ceiling	OF/CI/VI	Project

Single ceiling-mounted LED exam light with 66" reach, 360 degree arm rotation, 300 degree pitch, and 180 degree roll rotation of the lighthead. *Price includes installation.

View Cutsheet 212153

includes installation

W x D x H: 16 x N/A x N/A in.
Electrical: 120V 60Hz **Weight:** 28.7 lbs.
Elect Notes: see installation guide
Struct Notes: see installation guide

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration.

View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor.

View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.
Weight: 41.01 lbs.

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Ophthalmoscope/ Otoscope

AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Probe Cleaner

AE #: PRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON2		Wall	OF/OI	Project

Ultrasound probe high level disinfection system. Captures user id, instrument id, disinfectant information and chemical indicator. Can download data to usb or to hospital network. View Cutsheet 172692

W x D x H: 14.3 x 12.6 x 21.2 in.
Network: Wired
Electrical: 120V 60Hz 5A **Weight:** 48.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount	E8350NG	1	1

Probe Cleaner Accessory, Printer

AE #: PCAP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON PRINTER		Wall	OF/OI	Project

Printer To Accompany Trophon 2. Connected to Trophon2 Unit via USB Cable. Printer is a Traceability Solution, Printing Trophon Disinfection Labels. View Cutsheet 171574

W x D x H: 4.33 x 6.89 x 9.84 in.
Electrical: 120V 60Hz 1.8A

Probe Cleaner, Component

AE #: PRCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	WALL MOUNT	N05009	Wall	OF/CI	Project

Wall mount for probe cleaner. View Cutsheet 172898

W x D x H: 14.2 x 12.8 x 10.8 in. **Clearance:** Left 10 in.; Right 10 in.

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Probe Cleaner, Component — AE #: PRCC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	PRINTER WALL MOUNT	N00105	Wall	OF/CI	Project

Printer wall mount for trophon printer. View Cutsheet 172899

W x D x H: 4.33 x 6.89 x 9.84 in.

Regulator, Suction, Continuous, High Flow — AE #: RESU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	1247	UROM1500	Wall	OF/OI	Project

High surgical / free-flow suction regulator. Regulates vacuum up to 760 mm/hg. View Cutsheet 209933

W x D x H: 3 x 3.8 x 5.7 in.

Weight: 1.7 lbs.

Sphygmomanometer, Aneroid, Wall Mount — AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

W x D x H: 24 x 24 x 72 in.

Stand, Mayo

AE #: STMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pedigo Products, Inc.	P-1066-SS		Floor	OF/OI	Project

Stainless steel mayo stand with 16-1/4" x 21-1/4" removable tray; foot pedal operated with friction lock to adjust height from 39" to 62"; welded and polished stainless steel construction; 2" conductive double ball bearing swivel casters. View Cutsheet 11322

W x D x H: 21.3 x 16.3 x 39 in.

Stool, With Back

AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Stretcher, Ob/ Gyn

AE #: STOG-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical	GYNNIE	1061	Floor	OF/VI	Project

Ob/gyn stretcher with standard features: 4" ultra comfort mattress w/sealed seams, 8" casters w/wheel covers, 26" wide surface, dual cylinder pneumatic backrest, dual pedestal hydraulics w/constant rate descent, dual side-mounted foot control hydraulics, retractable fifth wheel steering, four-wheel brakes w/dual side and head activators, glideaway siderails, integrated storage tray w/oxygen bottle holder, permanently attached folding foot section and foot supports, pop-up handles, rubber bumpers, 4 iv receptacles, one-handed foot section release lever, trend/reverse trend, 500# weight capacity.

View Cutsheet 69719

W x D x H: 31.5 x 81.5 x 35 in.

Table, Overbed

AE #: TAOV-39

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medviron LLC	Sotto		Floor	OF/VI	Project

Overbed Table designed for Critical Care Beds and Stretchers with 5th Wheel Motorized Drive System. Options: Cupholders (2), Vanity Mirror (1), Tablet Holder (1), Hanging Shelf (1).

View Cutsheet 211777

Model and pricing per UK, change in model across system due to lead times.

W x D x H: 39 x 19 x 45.4 in.

Weight: 25 lbs.

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red

View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.

Weight: 10.9 lbs.

Room: Treatment Room **Department:** Gyn Onc Clinic

Room #: A704H, A704J

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Mobile Equipment **Department:** Gyn Onc Clinic

Room #: A704N1

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Electrocardiograph

AE #: ELCA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare	MAC VU360		Stand	OF/VI	Project

Resting ECG workstation with 15.6" led full HD 1080p display / touch screen. Integrated thermal dot array writer. Dimensions noted are for easy clean trolley with adjustable height (56"-62"h). View Cutsheet 168581

W x D x H: 19 x 28 x 62 in.
Network: Networked
Electrical: 120V 60Hz 0.5A **Weight:** 75.3 lbs.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.
Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.
Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	4

Room: Mobile Equipment **Department:** Gyn Onc Clinic

Room #: A704N1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Mobile Equipment **Department:** Gyn Onc Clinic

Room #: A704N1

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery.

View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.
Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Clean Supplies / Linen **Department:** Gyn Onc Clinic

Room #: A708C

Room Notes: For Gyn Onc

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Warming AE #: CAWA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7922TG		Cart	OF/VI	Project

Single compartment warming cabinet with glass door; 9.02 cu. Ft. Capacity; 2 shelves; to be used for heating and storage of fluids or warming blankets; View Cutsheet 122436

built-in temperature data recorder; keypad for setting internal temperature located above door.

Left hand door swing. Will sit on cart/stand

W x D x H: 30 x 26.6 x 35.5 in.
Electrical: 120V 60Hz 7.5A 750W **Weight:** 325 lbs.
HVAC Notes: 1535 btu/hr.

Cabinet, Warming, Component AE #: CAWC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	3026SSH		Floor	OF/OI	Project

Sawyer h-brace table for table top warming cabinets made of 18 gauge 304 stainless steel. Sawyer table has an h brace in lieu of second shelf. 1/1/4" View Cutsheet 166610

diameter legs with 3 inch casters.

W x D x H: 30 x 26 x 34 in.
Weight: 40 lbs.

Room: Clean Supplies / Linen

Department: Gyn Onc Clinic

Room #: A708C

Room Notes: For Gyn Onc

Cart, Cylinder, Medical Gas

AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position.

View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen

AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures.

View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z)

View Cutsheet 167836

W x D x H: 36 x 24 x 66.8 in.

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders

One for full and one for empty

View Cutsheet 72313

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Room: Soiled Workroom **Department:** Gyn Onc Clinic

Room #: A708D

Room Notes: Shared with Ovarian Screening

Bin, Biohazard Waste

AE #: BIBW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	MWS-30 / 1818V2		Floor	OF/VI	Service Agreement

3.7 cubic f; 30 gal biohazard waste container with dolly and lid; seamless; leakproof; tough, polyethylene construction to eliminate sticks

View Cutsheet 122429

W x D x H: 18.5 x 18 x 25 in.

Cart, Sharps Container

AE #: CASC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Kendall / Covidien	8992H		Floor	OF/OI	Service Agreement

Floor bracket with wheels for 8, 12, & 18 gallon large volume and chemosafety containers; specify container model # to be placed in cart

View Cutsheet 85038

W x D x H: 22.5 x 12.8 x 22 in.

Cart, Soiled Linen

AE #: CASL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Chemtainer	M7090		Floor	OF/OI	Project

Bulk truck for transport of bulk materials. With ergonomic front cut out, chemical-resistant corrosion-free poly base, hand and drain holes, and 6" industrial rubber casters. ***Select color when ordering: Royal Blue, Black Regrind, Forest Green, Silver Grey, Jade Green, Cadet Blue, Red, or Yellow/Bright Lemon.***

View Cutsheet 208909

W x D x H: 28.5 x 47 x 66.5 in.

Weight: 120 lbs.

Container, Sharps

AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key.

View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Soiled Workroom **Department:** Gyn Onc Clinic

Room #: A708D

Room Notes: Shared with Ovarian Screening

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: Soiled Workroom **Department:** Gyn Onc Clinic

Room #: A708D

Room Notes: Shared with Ovarian Screening

Lab Analyzer, Urine

AE #: LAUR-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Siemens Healthcare Diagnostics	CLINITEK STATUS +	BAH1780	Countertop	OF/OI	Project

Point-of-care urinalysis with touch screen user interface. View Cutsheet 103504

W x D x H: 6.7 x 10.7 x 6.2 in.

Network: Wired **Network Notes:** Uni-directional via serial port rs232

Electrical: 120V 60Hz 15W **Weight:** 3.65 lbs.

Elect Notes: 6 aa batteries, non-rechargeable

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Rack, Dunnage

AE #: RADU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	HP2236PDMB		Floor	OF/OI	Project

Polymer dunnage rack with built-in antimicrobial product protection. Weight capacity 3000 pounds. Separate polymer tie provided for joining racks in "end-to-end" and "back-to-back" configurations. NSF listed. View Cutsheet 129036

For UC Refrigerator to sit on

W x D x H: 36 x 22 x 12 in.

Room: Soiled Workroom **Department:** Gyn Onc Clinic

Room #: A708D

Room Notes: Shared with Ovarian Screening

Refrigerator, Undercounter — AE #: REUC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Danby Products Inc	DAR016A1BSLDB	804LG4	Floor	OF/OI	Project

1.6 cu. ft. (45 L) Capacity Compact Refrigerator — View Cutsheet 209114

Under cabinet/counter. Can go directly on floor.

W x D x H: 17.7 x 17.7 x 19.8 in. **Clearance:** Rear 5 in.; Left 2 in.; Right 2 in.; Top 2 in.
Electrical: 120V 60Hz **Weight:** 34.2 lbs.
Elect Notes: This appliance must be grounded. Grounding reduces the risk of electrical shock by providing an escape wire for the electrical current. This appliance has a cord that has a grounding wire with a 3-prong plug. The power cord must be plugged into an outlet that is properly grounded. If the outlet is a 2-prong wall outlet, it must be replaced with a properly grounded 3-prong wall
outlet. The serial rating plate indicates the voltage and frequency the appliance is designed for.

Truck, Cube — AE #: TRCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	4616 / 4615		Floor	OF/OI	Project

Cube truck with 16 cf ft / 500 lb capacity. Order with optional lid. Colors: white, black, dark blue. — View Cutsheet 91514

W x D x H: 31 x 43.8 x 37 in.

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. — View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage, Team Work Area

Department: Gyn Onc Clinic

Room #: A708D1, A708F1

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Medication Room **Department:** Gyn Onc Clinic

Room #: A708E

Room Notes: Shared with Ovarian Screening

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drug Dispensing Unit — AE #: DRDU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	ES 2-Drawer Main		Countertop	OF/VI	Lease

ES platform: 2-drawer main unit View Cutsheet 150403

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 22.8 x 27 x 27.8 in.
Network: Wired
Electrical: 120V 60Hz 3A **Weight:** 300 lbs.
Struct Notes: Counter height recommended 24" max to provide good ergonomics. Countertop depth required 30" to accommodate unit and provide stability. Raised edge countertop recommended.

Monitor, Temperature — AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Medication Room **Department:** Gyn Onc Clinic

Room #: A708E

Room Notes: Shared with Ovarian Screening

Refrigerator, Pyxis, Undercounter

AE #: REPU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Pyxis / Becton Dickinson & Co.	5 CU FT		Undercounter	OF/VI	Lease

Integrated temperature management and refrigeration solution designed to work with the Pyxis Medstation ES system. Features secure locking bins that release when remotely accessed by the Medstation ES system. Medical grade and supports meeting CDC vaccine storage recommendations. Interior shelves 18"x x18", 100 lbs. max capacity per shelf. Two bin sizes to accommodate vials, syringes, iv bags and other dosage forms. Rear access port. Auto defrost. Temperature range 36-50 F / 2-10 C. ADA compatible when used with leveling feet only. Casters also available that add 1.5" to the height of the unit.

View Cutsheet 170325

Pyxis configuration per Katie Plahn per 9/1/2023 call.

W x D x H: 24 x 29 x 32 in.
Clearance: Rear 3 in.
Electrical: 115V 60Hz 1.4A
Weight: 206 lbs.
HVAC Notes: 2185 btu/hr
Struct Notes: Allow 3" behind refrigerator for electrical plug.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Private Phone / Huddle **Department:** Gyn Onc Clinic

Room #: A708F

Room Notes: Assumes no medical equipment required in this area

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Added per Sam O'Bryan email 3/18/2024.

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Toilet (Staff)

Department: Gyn Onc Clinic

Room #: A708G

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Registration **Department:** Ovarian Screening

Room #: A700W5

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Storage Closet **Department: Ovarian Screening**

Room #: A706A

Room Notes: Shelving for misc office / clinic supplies: Office paper, paper sheets & gowns, gel, and trophon solution

Cart, Supply

AE #: CASU-72

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	6 FT METROMAX		Floor	OF/VI	Project

5-tier polymer shevling unit, unit consists of 5 shelves, solid bottom shelf, (2) swivel and (2) swivel brake casters, on 5" casters, with side and back enclosure panels. Casters adds approximately 6". View Cutsheet 127933

Confirm quantity and type of cart/shelving w/department.

W x D x H: 72 x 24 x 80 in.

Room: Clean Supply **Department: Ovarian Screening**

Room #: A706B

Room Notes: For Ovarian Screen only

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system — No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cart, Cylinder, Medical Gas — AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. — View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Supply, 36x24x67 — AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) — View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility — AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. — View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Room: Ultrasound Room **Department:** Ovarian Screening

Room #: A706C, A706D, A706E, A706F, A706H, A706L, A706M, A706N

Cabinet, Probe Rack

AE #: CAPR-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Cone Instruments	CN64988		Wall	OF/CI	Project

Single probe cabinet with clear plexiglass door; With four vents, keyed lock and organization for cords and probes. View Cutsheet 202651

W x D x H: 11.8 x 4.4 x 23 in.

Chair, Ultrasound Tech

AE #: CHUT-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Hag Ergonomic Chairs / Izzy Design	H8106		Floor	OF/OI	Project

Hag capisco (the saddle chair) with seat and back. Saddle seat is height adjustable between low and high working positions all the way to standing. View Cutsheet 150834

Standard 200mm gas lift.

W x D x H: 27.6 x 27.6 x 55.1 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Ultrasound Room **Department:** Ovarian Screening

Room #: A706C, A706D, A706E, A706F, A706H, A706L, A706M, A706N

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Imaging, Ultrasound Scanner

AE #: IMUS-05

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	GE Healthcare - Imaging	Voluson P8		Cart	OF/VI	Grant

The Voluson P8 delivers excellent image quality, ease of use, and streamlined workflow in a sleek, lightweight package to provide confident, efficient care across a range of applications. View Cutsheet 208830

W x D x H: 16 x 30 x 53 in.
Network: Wired
Electrical: 120V 60Hz 9A **Weight:** 150 lbs.

Room: Ultrasound Room **Department:** Ovarian Screening

Room #: A706C, A706D, A706E, A706F, A706H, A706L, A706M, A706N

Probe Cleaner — AE #: PRCL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON2		Wall	OF/OI	Project

Ultrasound probe high level disinfection system. Captures user id, instrument id, disinfectant information and chemical indicator. Can download data to usb or to hospital network. View Cutsheet 172692

W x D x H: 14.3 x 12.6 x 21.2 in.
Network: Wired
Electrical: 120V 60Hz 5A **Weight:** 48.5 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Wall Mount	E8350NG	1	1

Probe Cleaner Accessory, Printer — AE #: PCAP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	TROPHON PRINTER		Countertop	OF/OI	Project

Printer To Accompany Trophon 2. Connected to Trophon2 Unit via USB Cable. Printer is a Traceability Solution, Printing Trophon Disinfection Labels. View Cutsheet 171574

Wall mounted vs countertop? Need confirmation from sonographers

W x D x H: 4.33 x 6.89 x 9.84 in.
Electrical: 120V 60Hz 1.8A

Probe Cleaner, Component — AE #: PRCC-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	PRINTER WALL MOUNT	N00105	Wall	OF/CI	Project

Printer wall mount for trophon printer. View Cutsheet 172899

Wall mounted vs countertop? Need confirmation from sonographers

W x D x H: 4.33 x 6.89 x 9.84 in.

Probe Cleaner, Component — AE #: PRCC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	WALL MOUNT	N05009	Wall	OF/CI	Project

Wall mount for probe cleaner. View Cutsheet 172898

Wall mounted vs countertop? Need confirmation from sonographers

W x D x H: 14.2 x 12.8 x 10.8 in. **Clearance:** Left 10 in.; Right 10 in.

Room: Ultrasound Room **Department:** Ovarian Screening

Room #: A706C, A706D, A706E, A706F, A706H, A706L, A706M, A706N

Table, Exam, Power

AE #: TAEP-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	224-003		Floor	OF/VI	Project

Exam table with power base and gas spring assisted back section; seat height 18"-37"; patient weight capacity 500 lbs; Includes clean assist roller system which is only compatible with the 224-003 model. Dimensions reflect fully extended and raised upright. View Cutsheet 202626

W x D x H: 28 x 76 x 37 in.
Electrical: 120V 60Hz 11.5A **Weight:** 500 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Clean Assist Roller System		1	1

Warmer, Gel

AE #: WAGE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Parker Laboratories, Inc.	83-03		Countertop	OF/OI	Project

Multi bottle gel warmer (three bottles) with LED temperature readout View Cutsheet 147051

W x D x H: 11.5 x 4.3 x 9 in.
Electrical: 120V 60Hz 2.8A

Waste Container, Biohazard

AE #: WACB-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883566		Floor	OF/OI	Project

Slim jim step-on container. 13-gallon capacity. Quiet, controlled lid closure. Internal hinge design to prevent wall damage. Meets OSHA and OBRA standards. Liner retainer band holds bags in place. Color: Red View Cutsheet 150156

W x D x H: 18 x 11.5 x 28.3 in.
Weight: 10.9 lbs.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: On-Stage Team Work Area **Department:** Ovarian Screening

Room #: A706G

Room Notes: Assumes space for 3-5 people

Bin, Shredder — AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Lab Analyzer, Glucose — AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station — AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area **Department: Ovarian Screening**

Room #: A706G

Room Notes: Assumes space for 3-5 people

Workstation, US Infection Control

AE #: WOIC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nanosonics	AuditPro		Countertop	OF/OI	Project

Infection control workflow compliance management in the form of a workstation and mobile unit to be used with the Nanosonic Trophon2. Handheld computer/barcode scanner dimensions: 6.18 x 3.08 x 0.67 in

View Cutsheet 210430

W x D x H: 5.1 x 5.9 x 2.3 in.

Network: Wireless

Network Notes: WLAN, WLAN/WWAN

Electrical: 120V 60Hz

Room: Toilet (Patient)

Department: Ovarian Screening

Room #: A706J, A706K

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard

AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance.

View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient)

Department: Ovarian Screening

Room #: A706J, A706K

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage, Team Work Area

Department: Ovarian Screening

Room #: A708C1

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Off-Stage, Team Work Area **Department:** Palliative Care

Room #: A709B1, A709C1

Room Notes: Assumes space for 3 people. Located within clinic

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons

View Cutsheet 166130

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clean Supply / Linen **Department: Palliative Care**

Room #: A709C

Room Notes: Shared with Cardio, Breast Clinic, and Palliative

Allowance, Supply Dispensing System

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Par Excellence Systems, Inc.	ParEx System		Wall	OF/CI/VI	Project

ParEx supply dispensing system No Cutsheet 208662

Configuration to be determined by Supply Chain. Per quote dated 10/20/2023.

Network: Wired **Network Notes:** One data outlet needed per wall

Electrical: 120V 60Hz

Cabinet, Warming AE #: CAWA-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Blickman Inc	7922TG		Countertop	OF/VI	Project

Single compartment warming cabinet with glass door; 9.02 cu. Ft. Capacity; 2 shelves; to be used for heating and storage of fluids or warming blankets; built-in temperature data recorder; keypad for setting internal temperature located above door. View Cutsheet 122436

W x D x H: 30 x 26.6 x 35.5 in.

Electrical: 120V 60Hz 7.5A 750W **Weight:** 325 lbs.

Cart, Cylinder, Medical Gas AE #: CACM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Anthony Welded Products	6105		Floor	OF/OI	Project

Medical gas cylinder cart, holds one "d" or "e" size cylinder; green enamel finish; wheel diameter is 6" semi pneumatic; hook on cart to allow hanging on bed/stretcher with cylinder in upright position. View Cutsheet 64064

W x D x H: 12 x 10 x 41 in.

Weight: 6 lbs.

Cart, Linen AE #: CALI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	METROMAX W/ COVER		Floor	OF/VI	Project

Clean linen transfer/exchange cart. 48" x 24". One solid and three grid shelves; on casters; wrap around bumper. Side and back enclosures. To include blue cover with velcro closures. View Cutsheet 160213

W x D x H: 48 x 24 x 79 in.

Room: Clean Supply / Linen **Department:** Palliative Care

Room #: A709C

Room Notes: Shared with Cardio, Breast Clinic, and Palliative

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z) View Cutsheet 167836

6 shelves preferred

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility

AE #: CAUT-42

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Lakeside Mfg. Co.	2512		Floor	OF/OI	Project

500-Lb. Capacity, (3) 16.75 x 29.5-in Shelves Plastic Utility Cart w/ Dual Handle (Charcoal). 5 in caster wheels. Plastic. View Cutsheet 207611

W x D x H: 42 x 20 x 37.5 in.

Lab Analyzer, Glucose

AE #: LAAG-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP	54790 / 53425	Countertop	OF/OI	Project

Statstrip Hospital glucose meter 2d kit with Carrying Case View Cutsheet 165841

W x D x H: 5.8 x 3.1 x 1.18 in.

Network: Wireless **Network Notes:** Connectivity: ir port, rj45 or usb

Lab Analyzer, Glucose, Docking Station

AE #: LAGD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nova Biomedical	STATSTRIP DOCKING STATION	53400	Countertop	OF/OI	Project

Docking station for statstrip glucose meter View Cutsheet 148762

W x D x H: 4 x 4 x 2 in.

Network: Wired **Network Notes:** Rj-45 ethernet jack

Electrical: 120V 60Hz 15W

Room: Clean Supply / Linen **Department:** Palliative Care

Room #: A709C

Room Notes: Shared with Cardio, Breast Clinic, and Palliative

Rack, Gas Cylinder Storage

AE #: RGCS-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Anthony Welded Products	6060		Floor	OF/OI	Project

Rack to hold (6) m7, m9, c, d, or e size cylinders View Cutsheet 72313

One for full and one for empty

W x D x H: 15 x 12 x 19.5 in.

Weight: 13 lbs.

Stand, I.V.

AE #: STIV-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS80600		Floor	OF/OI	Project

Heavy duty six-leg iv pole with 3" ball bearing casters and 24" base; height adjustment: 73" to 99.5"; includes (4) ram-horn style hooks View Cutsheet 163754

For palliative

W x D x H: 24 x 24 x 72 in.

Suction Machine

AE #: SUMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Devilbiss Health Care, Inc.	7305P-D		Shelf	OF/OI	Project

Portable suction unit with internal rechargeable battery. Two container options: 800ml disposable and reusable 1200ml container. Vacuum adjustments allow 80-550 mm hg. Adjustable flow regulator. Includes suction unit, 800cc disposable container with internal filter, tubing, elbow, ac & dc power cords, and rechargeable battery. View Cutsheet 159014

During 8/2023 MEQ review, direction given to add to all mobile equipment areas.

W x D x H: 8 x 7 x 9 in.

Electrical: 120V 60Hz 0.75A **Weight:** 6.3 lbs.

Room: Storage

Department: Palliative Care

Room #: A709D

Room Notes: Designated for Palliative. No medical equipment needed per HGA. Will contain filing cabinets only.

Room: TeleHealth

Department: Palliative Care

Room #: A709D1

Room Notes: Space for 3 people

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Consult **Department:** Palliative Care

Room #: A710A

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Tray, Pill Count

AE #: TRPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	McKesson Corp.	ML27741		Countertop	OF/OI	Project

Right- and Left-Handed Pill Counting Trays with Spatulas. Designed for quick, convenient counting. Includes an angled spatula for ease of use. Nonskid tabs on the bottom help keep the tray in place during use. Graduated clear cover allows user to determine the proper bottle size at a glance View Cutsheet 208727

W x D x H: 7 x 5 x N/A in.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Alcove, Height / Weight **Department:** Palliative Care

Room #: A710A1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Monitor, Vital Signs

AE #: MOVS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	CONNEX 6800		Stand	OF/VI	Project

Vital signs monitor with color touchscreen. Suretemp Plus oral and/or Braun ear thermometry. Masimo or Nellcor SpO2. Option for EMR Integration. View Cutsheet 207794

To connect to Epic/EMR Nellcor pulse oximetry. Price includes installation and server application software support agreement.

W x D x H: 11 x 6 x 10 in.

Network: Wireless **Network Notes:** Bluetooth capability to send data to emr.

Electrical: 120V 60Hz

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Configuration: NIBP, Masimo SpO2, SureTemp	MXTX-B	1	1

Room: Alcove, Height / Weight **Department:** Palliative Care

Room #: A710A1

Monitor, Vital Signs, Component

AE #: MOVC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	Mobile Stand w/ Cable Mgmt Storage sts	4800-60	Floor	OF/VI	Project

Mobile stand with accessory cable management storage bin for the Connex Vital Signs monitor. View Cutsheet 208761

W x D x H: 22.7 x 20.2 x 22.6 in.

Weight: 41.01 lbs.

Scale, Wheelchair

AE #: SCWH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	6702SP		Floor	OF/OI	Project

Wheelchair, chair and stand-on scale; accommodates most wheelchairs; weight capacity 400kg / 880 lb in 100 gm / 0.1 lb increments. Platform: 35"w x 30"d x 3.25"h. View Cutsheet 206457

W x D x H: 35 x 30 x N/A in.

Electrical: 120V 60Hz 15W **Weight:** 107 lbs.

Elect Notes: Cordless - uses (6) "d" size disposable batteries (good for 20,000 weighs)

Sphygmomanometer, Cuff

AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff

AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Sphygmomanometer, Cuff

AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Room: Alcove, Height / Weight **Department:** Palliative Care

Room #: A710A1

Stadiometer

AE #: STAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Seca	216		Wall	OF/CI	Project

Measuring range: max 55.3"; variable from 1.4-90" (freely selectable); graduation: 1/16" View Cutsheet 121471

W x D x H: 4.7 x 8.5 x 59.1 in.

Weight: 3.7 lbs.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Exam Room **Department:** Palliative Care

Room #: A710C, A710E, A710N, A7109

Basket, Sphygmomanometer — AE #: BASP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-07		Wall	OF/CI	Project

767 aneroid inflation system basket, white. View Cutsheet 152856

W x D x H: 8 x 4.6 x 7 in.

Weight: 1 lbs.

Cabinet, Storage — AE #: CAST-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	Synthesis M4	M41A.XXX.KCN	Floor	OF/OI	Project

Mobile treatment cabinet, (3) 4" drawers, and (1) 8" drawer. Standard height 33" but is customizable. Top of cart determines width - Kydex top = 27"W. View Cutsheet 208699

To include a keypad lock

W x D x H: 27 x 18 x 33 in.

Container, Pharmacy Waste — AE #: COPW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rx Destroyer TM Pharmaceutical Disposal	RX1.0PRO		Wall	OF/CI	Project

Rx Destroyer™ all purpose is for use with all non-hazardous medications (DEA-controlled & Non-controlled). Includes Pills, Capsules, Tablets, Liquids, View Cutsheet 208805

Lozenges, Transdermal Patches, Fentanyl Lollipops, and Suppositories. Includes wall mount (RX1.0WALLSEC).

W x D x H: 7.75 x 6 x 10.5 in.

Container, Sharps — AE #: COSH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stericycle	C-03RES-0203-OC		Wall	OF/CI	Service Agreement

3-gallon; red container, vertical drop lid, beige case with key. View Cutsheet 164120

W x D x H: 14.5 x 5.6 x 21.5 in.

Room: Exam Room **Department: Palliative Care**

Room #: A710C, A710E, A710N, A7109

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Specula — AE #: DISP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	52400		Wall	OF/CI	Project

KleenSpec dispenser for 524-series disposable ear specula for MacroView and Diagnostic otoscopes. View Cutsheet 208940

W x D x H: 4.8 x 2.05 x 9.65 in.

Weight: 1.1 lbs.

Room: Exam Room **Department: Palliative Care**

Room #: A710C, A710E, A710N, A7109

Flowmeter, Oxygen — AE #: FLOX-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	FM-15UO-CHXX-S		Wall	OF/OI	Project

Amvex Thorpe (Tube) Style Flowmeters are offered in a complete line from Neonatal to Adult. Thorpe style is available in Oxygen, Medical Air, Heliox, CO2, and N2O. All Flowmeters come with a standard 1/8 View Cutsheet 208703

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Cabinet	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Ophthalmoscope/ Otoscope — AE #: OPOT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	77710 / 250-2 / 11720-L		Wall	OF/CI	Project

Ophthalmoscope / otoscope GS777 wall transformer with two handles with coiled cords, diagnostic otoscope 250-2 with integrated LED bulb, and coaxial ophthalmoscope 11720-L with LED bulb and integrated port for pneumatic otoscopy. Specula dispenser noted separately. View Cutsheet 208939

W x D x H: 7.1 x 5.6 x 5.8 in.
Electrical: 115V 60Hz

Regulator, Suction, Continuous & Intermittent — AE #: RESC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ohio Medical Corporation	8705-1251-907		Wall	OF/OI	Project

Push-to-set intermittent suction unit with dual mode operation (continuous or intermittent). Mechanism automatically establishes a vacuum limit with each vacuum level setting in both modes. Flow rate: 0-16 l/min intermittent, and 0-80 l/min continuous. Quick-to-max offers 2 turns to full wall vacuum. View Cutsheet 85906

Analog design with glow-in-the-dark gauge increments and needle. Chemetron rectangle striker adapter with diss male fitting.

W x D x H: 2.8 x 4.8 x 6.5 in.
Weight: 1.25 lbs.

Room: Exam Room **Department:** Palliative Care

Room #: A710C, A710E, A710N, A7109

Sphygmomanometer, Aneroid, Wall Mount — AE #: SPAW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	7670-01CB		Wall	OF/CI	Project

Wall aneroid with traditional two-piece cuff and bladder system. Includes adult size cuff. Recessed dial face and high-contrast red pointer for increased visibility. View Cutsheet 146914

W x D x H: 6.25 x 6.25 x 6.25 in.

Sphygmomanometer, Cuff — AE #: SPCU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12 Large Adult		Basket	OF/OI	Project

Reusable flexiport cuff. Size large adult. View Cutsheet 160316

Sphygmomanometer, Cuff — AE #: SPCU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-12L		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size large adult long. View Cutsheet 150982

Sphygmomanometer, Cuff — AE #: SPCU-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Baxter / Welch Allyn	REUSE-10 Sm Adult		Basket	OF/OI	Project

Reusable flexiport cuff with no tubes or connectors required (attach above fittings directly to current device tubing). Size small adult. View Cutsheet 160321

Stool, With Back — AE #: STWB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Midmark Corporation	273-001-XXX		Floor	OF/VI	Project

Value series stools; ritter air-lift stool with 16.25" diameter molded foam seat; 5-leg 23" diameter black composite base; dual wheel nylon casters; pneumatic height adjustability from 18" to 24.5"; weight capacity is 225 lbs View Cutsheet 46527

W x D x H: 23 x 23 x 25.5 in.

Room: Exam Room **Department: Palliative Care**

Room #: A710C, A710E, A710N, A7109

Table, Exam, Power

AE #: TAEP-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Midmark Corporation	626-001		Floor	OF/VI	Project

Patient weight capacity is 650 lbs. Height of table ranges from 15.5" - 37". Standard features include clean assist roller system, hand and foot control, stirrups and 5 1/5° pelvic tilt, accessory receivers, heated drawer and hospital grade electrical receptacles on left and right sides. Optional features/accessories available include: patient support rail arms, built-in scale, heated upholstery, articulating knee crutches, wireless controls, stainless steel treatment pan, led light, 32"w upholstery top and iqvitals table mount. Length of tabletop is 60"; 76" with footrest extended. View Cutsheet 162444

W x D x H: 28 x 76 x 37 in.
Electrical: 115V 60Hz 12A **Weight:** 435 lbs.

Tray, Pill Count

AE #: TRPC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	McKesson Corp.	ML27741		Countertop	OF/OI	Project

Right- and Left-Handed Pill Counting Trays with Spatulas. Designed for quick, convenient counting. Includes an angled spatula for ease of use. Nonskid tabs on the bottom help keep the tray in place during use. Graduated clear cover allows user to determine the proper bottle size at a glance View Cutsheet 208727

W x D x H: 7 x 5 x N/A in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: On-Stage Team Work Area **Department: Palliative Care**

Room #: A710J

Room Notes: Assumes space for 9-12 people

Bin, Shredder

AE #: BISH-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shred-It	STANDARD CONSOLE		Floor	OF/OI	University

Standard console; beveled plate; flat top surface; hinges on the inside; 32-gallons View Cutsheet 166130

Place Holder

W x D x H: 20.5 x 16 x 36 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet (Patient) **Department:** Palliative Care

Room #: A710L

Room Notes: With drug screen water turn-off

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder — AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included. View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Waste Container, Biohazard — AE #: WACB-04

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1883563		Floor	OF/OI	Project

Slim Jim red step-on resin front step container. 4 gallon/15 liter. Factory mutual certified for fire safety regulatory compliance. View Cutsheet 156758

W x D x H: 9.1 x 14.8 x 15.7 in.

Weight: 6.1 lbs.

Room: Toilet (Patient) **Department: Palliative Care**

Room #: A710L

Room Notes: With drug screen water turn-off

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Soiled Workroom

Department: Palliative Care

Room #: B707E-SHARED

Room Notes: Located in Cardio/Rehab - shared with Breast Clinic, Breast Imaging, and Palliative. See room B707E

Room: Medication Room

Department: Palliative Care

Room #: B707F-SHARED2

Room Notes: Shared with Cardio / Rehab - Onc. See Room B707F for equipment.

Room: Conference Room (small) **Department:** Conference Center

Room #: A000N1, B107F

Room Notes: LL, L1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle, Recycling Combination

AE #: WARC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Max-R	P-RO-STT10D		Floor	OF/OI	Project

10-gallon Top Load Waste & Recycling Bins. View Cutsheet 209397

W x D x H: 28 x 15 x 30 in.

Room: Conference Room (Tumor Board) **Department:** Conference Center

Room #: A607A, A707A

Room Notes: L6, L7

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Lab Microscope — AE #: LAMI-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Olympus America, Inc.	BX46		Countertop	OF/VI	Project

Microscope; BX46 w/ pln4x 4x objective, pln10x 10x objective, pln40x 40x objective, pln50xoi 50x o/i, pln100xo 100x oil objective; with dustcover. View Cutsheet 142868

BX46 with DP23 camera recommended for in-room connectivity per rep Jacob Dunkerson. Pricing from quote #2023-JAD-299-2 (Microscope $19,752. Camera $6,464). 8/15/24 Rep Jacob Dunkerson most recent recommendation is BX 46 with XAPO objectives (versus basic) and DP75 camera(vs DP 23). Quote No: 2023-JAD-2990 - 14 **Need to review configurations with users

W x D x H: 10.8 x 17.9 x 16.1 in.

Electrical: 120V 60Hz 4A **Weight:** 28.7 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Camera	DP23	1	1

Waste Receptacle — AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Conference Room (Tumor Board) **Department:** Conference Center

Room #: A607A, A707A

Room Notes: L6, L7

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Cabinet	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Pre-Function Break-Out **Department:** Conference Center

Room #: C101

Room Notes: 1st floor outside conference room

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Pre-Function Break-Out **Department:** Conference Center

Room #: C101

Room Notes: 1st floor outside conference room

Waste Receptacle, 24 gal

AE #: WARE-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Trashcans Unlimited, LLC	WWXL24		Cabinet	OF/OI	Project

24 Gallon Extra Large Home & Office Trash Can or Recycling Bin. Great for under the counter or as stand alone receptacles. Black and Gray are Blank for trash and Blue and Green have the recycling Mobius Loop. Material: High density polyethylene

View Cutsheet 210487

To go in built-in waste/recycling counter-cabinets

W x D x H: 15.3 x 21.3 x 24 in.

Weight: 7 lbs.

Waste Receptacle, Recycle Bin

AE #: WARB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Global Industrial	35 Gal	T9F641439RBL	Cabinet	OF/OI	Project

35-gallon, square plastic recycle container.

View Cutsheet 210122

To go in built-in waste/recycling counter-cabinets

W x D x H: 19.5 x 19.5 x 27.8 in.

Weight: 9 lbs.

Room: Conference Room **Department:** Conference Center

Room #: C101A, C101B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle, 24 gal

AE #: WARE-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Trashcans Unlimited, LLC	WWXL24		Cabinet	OF/OI	Project

24 Gallon Extra Large Home & Office Trash Can or Recycling Bin. Great for under the counter or as stand alone receptacles. Black and Gray are Blank for trash and Blue and Green have the recycling Mobius Loop. Material: High density polyethylene View Cutsheet 210487

To go in built-in waste/recycling counter-cabinets

W x D x H: 15.3 x 21.3 x 24 in.

Weight: 7 lbs.

Room: Table / Chair Storage

Department: Conference Center

Room #: C101C

Room Notes: Assumes no medical equipment

Room: AV Storage

Department: Conference Center

Room #: C101D

Room Notes: Assumes no MEQ. Will be handled by AV. Confirmed with Rick Rydz.

Room: Housekeeping Level 1 Cafe

Department: Housekeeping

Room #: A107D1

Room Notes: All equipment to be provided by Rippe except for the mop sink. All MEQ items have been removed.

Room: Housekeeping Level 2 (Waiting) **Department:** Housekeeping

Room #: A200W5

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 2 (Waiting) **Department:** Housekeeping

Room #: A200W5

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Level 2 (Surgery) **Department:** Housekeeping

Room #: A207F

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 2 (Surgery) **Department:** Housekeeping

Room #: A207F

Floor Machine, Automatic Scrubber

AE #: FMAS-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tennant	T2		Floor	OF/VI	Project

Walk behind scrubber; 17" pad. View Cutsheet 141154

W x D x H: 45 x 28 x 37 in.
Electrical: 120V 60Hz
Elect Notes: 12 v battery; to be located near electrical outlet to charge

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Level 4 **Department:** Housekeeping

Room #: A406J4

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 4 **Department:** Housekeeping

Room #: A406J4

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Level 5 **Department:** Housekeeping

Room #: A502D, B505C

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 5 **Department:** Housekeeping

Room #: A502D, B505C

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: (Dock) EVS Bulk Stores **Department: Housekeeping**

Room #: B005C

Room Notes: Assumes this area is for bulk items brought in on pallets.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Rack, Dunnage — AE #: RADU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Intermetro Industries	HP2236PDMB		Floor	OF/OI	Project

Polymer dunnage rack with built-in antimicrobial product protection. Weight capacity 3000 pounds. Separate polymer tie provided for joining racks in "end-to-end" and "back-to-back" configurations. NSF listed. View Cutsheet 129036

W x D x H: 36 x 22 x 12 in.

Truck, Tilt — AE #: TRTI-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	FG9T1300BLA		Floor	OF/OI	Project

13.5 cu ft capacity tilt truck View Cutsheet 208657

Place holder pending confirmation of trash compactor specs/size

W x D x H: 26.9 x 57.4 x 33.9 in.

Waste Receptacle, Brute, 32 Gal — AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: (Dock) EVS Stores

Department: Housekeeping

Room #: B005C1

Cart, Supply, 36x24x72

AE #: CASU-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Chrome supply cart; 4-wire shelves; 1-bottom shelf; 4" casters; 2-braking and 2-swivel

View Cutsheet 159101

W x D x H: 36 x 24 x 72 in.

Cart, Supply, 48x24x68

AE #: CASU-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
11	Intermetro Industries	Super Adjustable Super Erecta	5A556BC	Floor	OF/VI	Project

Supply Cart, 5-Shelf Wire Shelving Stem Caster Cart, Chrome, 5" wheel size with 600lb load capacity

View Cutsheet 208682

W x D x H: 50 x 26.2 x 67.9 in.

Weight: 92 lbs.

Room: (Dock) Workstations **Department: Housekeeping**

Room #: B005C2

Room Notes: Plan for (2) workstations

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Housekeeping Tilt Truck

Department: Housekeeping

Room #: B200N1, B300N1, B500N1, B600N1, B700N1

Truck, Tilt

AE #: TRTI-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	FG9T1300BLA		Floor	OF/OI	Project

13.5 cu ft capacity tilt truck

View Cutsheet 208657

PLACE HOLDER pending confirmation of trash compactor specs/size. Trash compactor size requested 34 cubic yards but no specs available as of 2/15/2024.

W x D x H: 26.9 x 57.4 x 33.9 in.

Room: Housekeeping Level 2 (Prep / PACU) **Department:** Housekeeping

Room #: B200N2

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 2 (Prep / PACU) **Department:** Housekeeping

Room #: B200N2

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Level 3 **Department:** Housekeeping

Room #: B307H, A309A

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 3 **Department:** Housekeeping

Room #: B307H, A309A

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Level 6 **Department:** Housekeeping

Room #: B607A, A609A

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 6 **Department:** Housekeeping

Room #: B607A, A609A

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Level 7 **Department:** Housekeeping

Room #: B707A, A708J

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 7 **Department: Housekeeping**

Room #: B707A, A708J

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: (Dock) EVS Equipment

Department: Housekeeping

Room #: C000W1

Cart, Supply, 48x24x68

AE #: CASU-48

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Intermetro Industries	Super Adjustable Super Erecta	5A556BC	Floor	OF/VI	Project

Supply Cart, 5-Shelf Wire Shelving Stem Caster Cart, Chrome, 5" wheel size with 600lb load capacity

View Cutsheet 208682

W x D x H: 50 x 26.2 x 67.9 in.

Weight: 92 lbs.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance.

View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals.

View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: (Dock) EVS Equipment

Department: Housekeeping

Room #: C000W1

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Floor Machine

AE #: FLMA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Nilfisk-Advance, Inc.	PACESETTER 20HD		Floor	OF/OI	Project

20" heavy-duty, multi-purpose floor machine which performs stripping, scrubbing, screening and bonnet cleaning

View Cutsheet 165068

W x D x H: 20 x 20 x 46 in.
Electrical: 120V 60Hz 1.5A **Weight:** 102 lbs.
Elect Notes: *****power cord length 50'

Floor Machine, Automatic Scrubber

AE #: FMAS-66

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Taski	Ultimaxx 1900 Single Disc		Floor	OF/VI	Project

Walk-behind scrubber/dryer

View Cutsheet 210462

Electrical: 115V 60Hz
Elect Notes: Battery powered, plug in to charge battery

Floor Machine, Automatic Scrubber

AE #: FMAS-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tennant	T2		Floor	OF/VI	Project

Walk behind scrubber; 17" pad.

View Cutsheet 141154

W x D x H: 45 x 28 x 37 in.
Electrical: 120V 60Hz
Elect Notes: 12 v battery; to be located near electrical outlet to charge

Room: (Dock) EVS Equipment **Department:** Housekeeping

Room #: C000W1

Floor Machine, Automatic Scrubber — AE #: FMAS-65

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tennant	i-mop XL		Floor	OF/VI	Project

With dual, counter rotating brushes. Clean water tank 1 gallon, recovery water tank 2 gallons. Comes with batteries and charger. View Cutsheet 210461

W x D x H: 19.7 x 15 x 47.3 in.
Electrical: 115V 60Hz
Elect Notes: Outlet required for battery charger. Rechargeable modular battery packs, 1-hour operation time.

Floor Machine, Burnisher — AE #: FLMB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tennant	B5		Floor	OF/VI	Project

Battery powered walk behind burnisher. View Cutsheet 160108

W x D x H: 24.5 x 59 x 43 in.
Electrical: 120V 60Hz 15A
Elect Notes: Electrical Outlet for Battery Charging Required

Floor Machine, Burnisher — AE #: FLMB-06

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tennant	BR-2000-DC		Floor	OF/VI	Project

High speed burnisher with dust control. Pad speed burnishing 2000 rpm @ full load. Pad diameter 20". Direct drive motor, circuit breaker protected. View Cutsheet 210460

Power cord 75 feet.

W x D x H: 22.5 x 31.5 x 47 in.
Electrical: 120V 60Hz 15A **Weight:** 92 lbs.

Floor Machine, Burnisher — AE #: FLMB-27

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tennant	B7		Floor	OF/VI	Project

Battery powered walk-behind burnisher View Cutsheet 210464

W x D x H: 31.5 x 63 x 43 in.
Electrical: 115V 60Hz
Elect Notes: Onboard battery charger, requires outlet to charge

Room: (Dock) EVS Equipment **Department:** Housekeeping

Room #: C000W1

Floor Machine, Extractor

AE #: FLME-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Nilfisk-Advance, Inc.	ES300 XP	56265500	Floor	OF/VI	Project

Self-contained carpet extractor with 16" cleaning path. Height noted above is approximate. View Cutsheet 210471

W x D x H: 19.3 x 28 x 36 in.
Electrical: 115V 60Hz
Elect Notes: 50' power cord.

Floor Scrubber, Stand-On

AE #: FSSO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Taski	swingo XP-R		Floor	OF/VI	Project

Stand-on floor scrubber with squeegee and round disc for heavy duty cleaning. Automatic shut off if operator steps off machine. View Cutsheet 210469

W x D x H: 37.4 x 51.6 x 51.2 in.
Electrical: 120V 60Hz **Weight:** 456.4 lbs.
Elect Notes: Battery powered

Vacuum

AE #: VACU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Windsor Industries, Inc.	SRXP12	SENSOR	Floor	OF/OI	Project

Powerful 1.6 hp vacuum. Optional HEPA filter system available. Available in 12, 15, or 18 inch. View Cutsheet 165065

W x D x H: 12 x 12 x 46 in.
Electrical: 120V 60Hz 1.2A **Weight:** 18 lbs.

Room: (Dock) EVS Equipment **Department:** Housekeeping

Room #: C000W1

Vacuum, Wet/ Dry

AE #: VAWD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tennant	V-WD-24		Floor	OF/VI	Project

Wet-Dry vacuum with 24 gallon tank. View Cutsheet 210465

W x D x H: 18 x 24 x 36 in.
Electrical: 120V 60Hz 1200W **Weight:** 42 lbs.
Elect Notes: 40 ft power cord

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Carpet brush tool		1	2
Front mount squeegee kit		1	2
Package of 10 microfiber fleece bags		1	2
Package of 10 paper bags		1	2
Upstream HEPA filter		1	2

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Housekeeping Lower Level **Department:** Housekeeping

Room #: C000W6, A008B

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Lower Level

Department: Housekeeping

Room #: C000W6, A008B

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side.

View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: (Dock) Pharmaceutical Waste **Department:** Housekeeping

Room #: C003A

Room Notes: Determine users for this space. Pharmacy? EVS?

Container, Pharmacy Waste - Black

AE #: COPK-18

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
100	Stericycle	H18B		Floor	OF/OI	Service Agreement

18-gallon black RCRA container with gasketed black port lid

View Cutsheet 209270

Quantity shown for space planning purposes only. Can stack on floor up to 3 high. Need floor space for up to 34 containers.

W x D x H: 12.5 x 17.3 x 24 in.

Container, Pharmacy Waste - Blue

AE #: COPW-30

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
12	Rubbermaid Commercial Products	Brute 32-Gallon Round Container	FG263200BLUE	Floor	OF/VI	Service Agreement

Round lidded blue container for pharmaceutic waste, 30-gallon capacity. Diameter with handle is 25"(additional 1.54" on each side)

View Cutsheet 209271

W x D x H: 21.9 x 21.9 x 27.8 in. **Clearance:** Left 1.54 in.; Right 1.54 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
32 Gallon Lid	FG263100BLUE	1	12

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Room: (Dock) Regulated Medical Waste

Department: Housekeeping

Room #: C003B

Cart, Biohazard Container

AE #: CABC-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Stericycle			Floor	OF/VI	Project

Custom Shelving Cart to hold Stericycle Biohazard Containers/Boxes

View Cutsheet 209276

W x D x H: 48 x 24 x 69 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Glove Box Holder

AE #: GLBH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	MDS194096B		Wall	OF/CI	Project

Clear PETG plastic dispenser holds 4 boxes of gloves in horizontal or vertical orientation. Fits most glove box sizes. Mounting hardware not included.

View Cutsheet 209178

Available by the each or in case of 4.

W x D x H: 22.3 x 3.75 x 10 in.

Rack, Dunnage

AE #: RADU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Intermetro Industries	HP2236PDMB		Floor	OF/OI	Project

Polymer dunnage rack with built-in antimicrobial product protection. Weight capacity 3000 pounds. Separate polymer tie provided for joining racks in "end-to-end" and "back-to-back" configurations. NSF listed.

View Cutsheet 129036

W x D x H: 36 x 22 x 12 in.

Room: (Dock) Regulated Medical Waste

Department: Housekeeping

Room #: C003B

Waste Receptacle, Brute, 32 Gal

AE #: WARB-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2632/2631/2640		Floor	OF/OI	Project

32 gallon round brute waste receptacle with reinforced handles and base nsf 2, nsf 21, includes lid and dolly; dimensions include dolly height

View Cutsheet 172941

W x D x H: 22 x 22 x 33.8 in.

Room: (Dock) Cart Wash

Department: Housekeeping

Room #: C003 (Cart Wash Alcove)

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.
Plumb Notes: Water Connection Required.
Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Hose

AE #: HOSE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	12F252		Wall	OF/OI	Project

Polypropylene blue water hose with temperature range up to 158 degrees f. Remains flexible at extreme temperatures. Lightweight. Non-kinking. Resists crushing. Brass fittings on both ends. Internal diameter 5/8". 50 feet in length. Max working pressure at 70 degrees f = 100 psi. View Cutsheet 171795

Plumb Notes: Hose fitting size 5/8"

Hose Accessory, Nozzle

AE #: HOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	18D869		Wall	OF/OI	Project

Black rear trigger adjustable spray water nozzle; 100 psi. Brass/stainless steel construction has insulated handle for hot and cold water use. Max temp 200 dg f. View Cutsheet 171796

W x D x H: 1 x 1 x 5.5 in.

Room: (Dock) Cart Wash **Department:** Housekeeping

Room #: C003 (Cart Wash Alcove)

Hose Reel

AE #: HOSE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	2LRK9		Wall	OF/CI	Project

Steel wall mount hose reel. Tri-mount hose reel is crafted from 13-ga. Powder-coated steel. It can be mounted to the wall, floor, or ground. View Cutsheet 166448

W x D x H: 22 x 14.5 x 19 in.
Struct Notes: Wall Backing Required

Washer, Pressure

AE #: WAPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Craftsman	CMEPW2800		Floor	OF/OI	Project

Corded electric cold water mobile pressure washer with 2800 max PSI, 10" wheels, and 5 nozzles including turbo nozzle. Water usage 1.1 GPM. View Cutsheet 209159

Removable soap tank. Onboard storage for nozzles, hose, cord, and wand. Power cord 35' long. No battery.

W x D x H: 20.2 x 20.7 x 22.2 in.
Electrical: 120V 60Hz **Weight:** 59.5 lbs.

Room: Housekeeping Level 1 Specialty Pharmacy **Department:** Housekeeping

Room #: C100C

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 1 Specialty Pharmacy

Department: Housekeeping

Room #: C100C

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side.

View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Level 1 **Department:** Housekeeping

Room #: D103, A108D

Cart, Housekeeping

AE #: CAHO-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	FG9T75		Floor	OF/OI	Project

High security cleaning cart; JCAHO-compliant View Cutsheet 165929

W x D x H: 22 x 48.3 x 53.5 in.

Dispenser, Chemical - Soap

AE #: DICS-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Ecolab Healthcare	OxyCide Dilution Management System		Wall	OF/CI	Supply Agreement

One-button OxyCide dispensing system. Bucket fill hose / spray bottle fill options. Indicates when concentrate bottle is near empty. Overflow tray used to collect any drips. Calibrated quarterly to ensure consistent performance. View Cutsheet 209161

Rep: Stephanie Allen 502-727-8144.

W x D x H: 17 x 8 x 28 in.

Weight: 24 lbs.

Plumb Notes: Water requirements: Temperature: 60 degrees - 120 degrees Fahrenheit; water pressure 20 minimum to 80 maximum PSID; water hardness <10 grains. If connecting to a faucet which as an atmospheric vacuum breaker, a sidekick and backflow preventer assembly must be used. No wye connector with integral shutoffs can be installed to a faucet that has an integral atmospheric vacuum breaker unless it is downstream from the sidekick assembly.

Struct Notes: Mounting height ~48" to button

Dispenser, Chemical - Soap

AE #: DICS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sealed Air	J FILL QUATRO		Wall	OF/CI	Supply Agreement

Four products can be dispensed into bottles, buckets or floor care machines. One hand filling of a bottle or using the hose to fill a bucket. Two doors that are lockable to prevent theft or mis-use of chemicals. View Cutsheet 160106

meets asse 1055-b back-flow prevention requirement

W x D x H: 21 x 10 x 27.5 in.

Plumb Notes: Water Connection Required.

Struct Notes: Unit to be mounted 48 inches from floor. Bottom of unit should be mounted level or above water connection.

Room: Housekeeping Level 1 **Department: Housekeeping**

Room #: D103, A108D

Truck, Cube

AE #: TRBW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	5EME6		Floor	OF/OI	Project

Dual-handle cube truck with 1000 lbs./18.6 cu. ft. capacity. Color: black. With 5" casters: 2 rigid and 2 swivel. One drain hole. Can be steered from either side. View Cutsheet 209162

W x D x H: 31 x 53 x 38 in.

Room: Housekeeping Tilt Truck / Floor Robots **Department:** Housekeeping

Room #: D106

Truck, Tilt — AE #: TRTI-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	FG9T1300BLA		Floor	OF/OI	Project

13.5 cu ft capacity tilt truck View Cutsheet 208657

PLACE HOLDER pending confirmation of trash compactor specs/size. Trash compactor size requested 34 cubic yards but no specs available as of 2/15/2024.

W x D x H: 26.9 x 57.4 x 33.9 in.

Vacuum Sweeper / Scrubber, Robotic — AE #: VASR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Taski	GS Ecobot 40	7525332	Floor	OF/VI	Project

Autonomous sweeping and vacuuming robot. Integrates vacuuming, sweeping, and dust-mopping in one unit. Cleaning width 15", cleans to 1200 square meters/hour. Independent 360-degree view that allows hands-free operation. Automatically returns to charging station to recharge battery. Note charging station separately due to dimensions. View Cutsheet 210463

Per email quote from Curt Courtad 3/1/2024, plan with the charging station, noted separately.

W x D x H: 28 x 27 x 34 in.

Weight: 176 lbs.

Elect Notes: Lithium Ion Phosphate battery, 60 Ah. Charging time 2 hours. Uptime 308 hours.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Installation		1	1

Vacuum Sweeper / Scrubber, Robotic — AE #: VSSR-50

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Taski	GS Ecobot 50	7525455	Floor	OF/VI	Project

Autonomous scrubbing and drying robot. Plan with either charging station only or workstation that serves as hub for charging, water filling, and discharging. View Cutsheet 210501

W x D x H: 27 x 33 x 40 in.

Weight: 343 lbs.

Elect Notes: Onboard battery needs either charging station or workstation to charge battery.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Intallation		1	1

Room: Housekeeping Tilt Truck / Floor Robots **Department:** Housekeeping

Room #: D106

Vacuum Sweeper / Scrubber, Robotic, Charge Station

AE #: WSRC-50

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Taski	GS Workstation 50	7525334	Floor / Wall	OF/CI/VI	Project

Workstation charges, fills, and drains Ecobot 50 robot.

View Cutsheet 210502

W x D x H: 17.7 x 14 x 54.7 in.
Clearance: Left 22 in.; Right 22 in.; Front 60 in.
Electrical: 120V 60Hz 8.3A
Weight: 66 lbs.
Plumb Notes: Water source and drain required.

Vacuum Sweeper / Scrubber, Robotic, Charge Station

AE #: VSRC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Taski	Ecobot 40/50 Charging Station	7525335	Floor / Wall	OF/VI	Project

Charging station for Ecobot 40/50 models

View Cutsheet 210488

W x D x H: 19.7 x 15.7 x 27.2 in.
Clearance: Left 22 in.; Right 22 in.; Front 60 in.
Electrical: 120V 60Hz 900W
Weight: 55 lbs.
Elect Notes: Cord plugs into 120V wall outlet

Room: Facilities Mechanical / Plumbing (Lower Level) **Department:** Maintenance

Room #: B003A

Crane

AE #: CRAN-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Uline	H-8462		Floor	OF/VI	Project

Hydraulic Floor Crane. Retracted Weight Capacity- 2 Tons. Extended Weight Capacity-0.5 Tons. Does not include assembly. View Cutsheet 211845

W x D x H: 63.8 x 33.5 x 59 in.
Weight: 200 lbs.

Crane

AE #: CRAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Uline	H-8464		Floor	OF/VI	Project

Aluminum Gantry Crane - 10 feet. Holds up to a ton. Height adjusts in 6" increments. Will not fit on standard liftgate. Must be removed from shipping carrier with a forklift or other suitable lifting device. View Cutsheet 211846

W x D x H: 116 x 54 x 98 in.
Clearance: Top 24 in.
Weight: 205 lbs.

Drill Press

AE #: DRPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Dayton	54ZW30		Floor	OF/CI	Project

Floor drill press: belt drive type, fixed speed control, spindle speed range 138 RPM - 3476 RPM. 15" swing. View Cutsheet 208615

W x D x H: 11.5 x 30 x 47 in.
Electrical: 115V 60Hz 8.6A 1-Phase

Grinder, Bench

AE #: GRBE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Dayton	49H008		Table	OF/CI	Project

Medium duty bench grinder for construction and maintenance. 1/2 HP. Includes: 2 adjustable tool rests, 2 eye shields, 2 quick adjusting spark guards, grinding wheel, locking rocker switch, and wire wheel. Wheel speed range 2000 - 3450 RPM. View Cutsheet 208616

W x D x H: 19.6 x 12 x 11.3 in.
Electrical: 120V 60Hz 5A
Weight: 43.4 lbs.
Elect Notes: Cord 6' long

Room: Facilities Mechanical / Plumbing (Lower Level) **Department:** Maintenance

Room #: B003A

Hose

AE #: HOSE-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	12F253		Wall	OF/OI	Project

Polypropylene blue water hose with temperature range up to 158 degrees F. 100 feet in length. Remains flexible at extreme temperatures. Lightweight. View Cutsheet 209153

Non-kinking. Resists crushing. Brass fittings 5/8" on both ends. Internal diameter 5/8". Max working pressure at 70 degrees F = 100 psi.

Plumb Notes: Hose fitting size 5/8"

Hose Accessory, Nozzle

AE #: HOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	18D869		Wall	OF/OI	Project

Black rear trigger adjustable spray water nozzle; 100 psi. Brass/stainless steel construction has insulated handle for hot and cold water use. Max temp View Cutsheet 171796

200 dg f.

W x D x H: 1 x 1 x 5.5 in.

Hose Reel

AE #: HOSE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	2LRK9		Wall	OF/CI	Project

Steel wall mount hose reel. Tri-mount hose reel is crafted from 13-ga. Powder-coated steel. It can be mounted to the wall, floor, or ground. View Cutsheet 166448

W x D x H: 22 x 14.5 x 19 in.

Struct Notes: Wall Backing Required

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

One by workbenches, one by sink for paper towel waste.

W x D x H: 11.3 x 20.4 x 30 in.

Room: Facilities Mechanical / Plumbing (Lower Level) **Department:** Maintenance

Room #: B003A

Workbench

AE #: WORK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Tennsco	EB-2-3072C		Floor	OF/OI	Project

Stationary, fixed-height workbench with stringer, and power strip. Powder coated gray 13 gauge steel frame. Includes 16 outlets, 1 shelf, 8 knockouts, 0 drawers, 0 cabinets. Riser runs length of workbench providing elevated storage above work surface. View Cutsheet 208610

W x D x H: 72 x 30 x 33.9 in.
Electrical: 115V 60Hz

Room: Corridor

Department: Maintenance

Room #: B801N

Truck, Tilt

AE #: TRTI-13

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	FG9T1300BLA		Floor	OF/OI	Project

13.5 cu ft capacity tilt truck

View Cutsheet 208657

PLACE HOLDER pending confirmation of trash compactor specs/size. Trash compactor size requested 34 cubic yards but no specs available as of 2/15/2024. For use by 8th floor departments for disposing of cardboard and packaging materials.

W x D x H: 26.9 x 57.4 x 33.9 in.

Room: Corridor - Lift Alcove **Department:** Maintenance

Room #: B807

Scissors Lift

AE #: SCLI-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	MEC Aerial Work Platforms	Micro 26 AC		Floor	OF/VI	Project

AC electric drive. Lift has 2-person platform for indoor use / 1-person platform for outdoor use, with 550 lbs. capacity. Has 36" roll-out decs extension. View Cutsheet 211463

Indoor working height 31 feet, outdoor working height 24 feet. Tires 12" x 5".

Model changed per email exchange w//Matt Mueller. Purchase lift through Glen England at Encon Equipment 859-380-1603. Supplemental Info

W x D x H: 74 x 31.9 x 90.3 in.
Electrical: 120V 60Hz **Weight:** 4190 lbs.
Elect Notes: Power required for charging 240Ah maintenance-free batteries. Has battery charge indicator.

Room: UKHC IT

Department: Maintenance

Room #: B807A

Cart, Supply

AE #: CASU-49

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA		Floor	OF/VI	Project

Super erecta model with chrome finish to include (3) wire shelves, (1) solid bottom shelf, (2) braking casters, (2) swivel casters, and (4) 63" posts

View Cutsheet 160459

W x D x H: 48 x 24 x 68 in.

Cart, Supply, 36x24x67

AE #: CASU-37

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Intermetro Industries	SUPER ERECTA	2436NC / 63UP	Floor	OF/VI	Project

Super erecta chrome wire shelving unit; 5 shelves total - 24"d x 36"w (2436nc); 4 each 61-13/16" high posts (63up); 5" casters 2 each swivel (5mp) and 2 each brake (5mpb); 1 each shelf inlay (2436ci-4); 1 each post clamp (9994z)

View Cutsheet 167836

4 shelves preferred - 3 wire shelves and solid bottom shelf

W x D x H: 36 x 24 x 66.8 in.

Cart, Utility

AE #: CAUT-46

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1066BE		Floor	OF/OI	Project

Tough structural foam won't rust, chip or dent. Two 2-5/8" deep trays are 18 7/8" apart. Non-marking 5" casters: 2 swivel, 2 rigid

View Cutsheet 159705

W x D x H: 26 x 46 x 33 in.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: UKHC IT

Department: Maintenance

Room #: B807A

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: ITS Work

Department: Maintenance

Room #: B807B

Allowance, Bins

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Akro-Mils / Myers Industries			Wall	OF/OI	Project

specify color when ordering

View Cutsheet 76370

Bins for louvered wall panel

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: ITS Work

Department: Maintenance

Room #: B807B

Ladder

AE #: LADD-26

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Little Giant	Velocity	15426-801	Floor	OF/OI	Project

Velocity Little Giant aluminum extra heavy duty ladder with 300 lb. capacity. View Cutsheet 209188

W x D x H: 30 x 8.5 x 80 in.

Weight: 54.5 lbs.

Ladder

AE #: LADD-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Werner	6112		Rack	OF/OI	Project

Fiberglass 12' ladder with slip-resistant steps. HolsterTop with lock-in accessory system. Non-conductive fiberglass rails. Load capacity 300 lbs. Steps 3" wide. Top 13"W x 5.75"D. Approximate spread 79.2". View Cutsheet 208613

Confirm if needed here. In DD2 meeting, group stated that anything over 6' is brought from other location or will use scissor lift.

W x D x H: 31.6 x N/A x 144 in.

Weight: 44 lbs.

Ladder

AE #: LADD-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Werner	6208		Floor	OF/OI	Project

8' fiberglass ladder with a 12' reach; single sided; capacity of 300 lbs. Slip resistant treads; full set of rear horizontal spaced one per foot; all steps and two rear horizontal are knee-spaced. View Cutsheet 126486

Confirm if needed here. In DD2 meeting, group stated that anything over 6' is brought from other location or will use scissor lift.

W x D x H: 20 x 10 x 96 in.

Weight: 30 lbs.

Rack, Ladder

AE #: RALA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	McMaster-Carr	1716A14		Wall	OF/CI	Project

Gray powder-coated steel padded two-pronged wall mounted hanger. Holds items up to 75 lbs. View Cutsheet 209382

W x D x H: 11.3 x 8.75 x 9.75 in.

Room: ITS Work **Department:** Maintenance

Room #: B807B

Vacuum, Electronics

AE #: VAEL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Amazon	B0C7VHZMVS		Desk	OF/OI	Project

Opinta VC016 handheld cordless 3-in-1 compressed air duster/pump and wireless vacuum cleaner with HEPA filter, batteries included. Comes with (3) brushes for dusting, (5) blowing accessories, and (2) vacuuming accessories. Battery life 40 minutes. For use with keyboards and car. View Cutsheet 209976

W x D x H: 4.6 x 6.5 x 2.4 in.
Electrical: 120V 60Hz **Weight:** 1 lbs.
Elect Notes: Plugs in to USB outlet to charge battery.

Wall Board

AE #: WABO-36

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Akro-Mils / Myers Industries	30161		Wall	OF/CI	Project

Louvered wall system. Single sided. View Cutsheet 161260

W x D x H: 36 x 0.5 x 61 in.
Struct Notes: **requires wall backing**

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Workbench

AE #: WORK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tennsco	EB-2-3072C		Floor	OF/OI	Project

Stationary, fixed-height workbench with stringer, and power strip. Powder coated gray 13 gauge steel frame. Includes 16 outlets, 1 shelf, 8 knockouts, 0 drawers, 0 cabinets. Riser runs length of workbench providing elevated storage above work surface. View Cutsheet 208610

W x D x H: 72 x 30 x 33.9 in.
Electrical: 115V 60Hz

Room: Clinical Engineering Workroom **Department:** Maintenance

Room #: B807C

Room Notes: Per HGA, eye wash is plumbed. All tools and testing equipment provided by CE service provider Renovo. No laser connections or specialty outlets needed.

Cabinet, Supply — AE #: CBSU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Grainger	9KA28		Floor	OF/OI	Project

Bin Cabinet with three shelves and a louvered back wall panel. All welded steel cabinet has a keyed handle with a three point locking system. Plastic Storage bins are included. View Cutsheet 200172

Cabinet specs confirmed by Calvin Crum via email 2/1/2024.

W x D x H: 36 x 24 x 78 in.

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Clinical Engineering Workroom **Department:** Maintenance

Room #: B807C

Room Notes: Per HGA, eye wash is plumbed. All tools and testing equipment provided by CE service provider Renovo. No laser connections or specialty outlets needed.

Dispenser, Soap — AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

First Aid Kit — AE #: FIAK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	796J67		Wall	OF/CI	Project

First aid wall-mounted cabinet with 202 components; serves up to 50 people. View Cutsheet 208881

W x D x H: 13.8 x 3.25 x 14.3 in.

Hoist — AE #: HOIS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Harrington	SEQP010SD-12	Grainger 54PM99	Ceiling	OF/CI	Project

Chain hoist with 2000 lb. load capacity. Hoist lift 12 feet(custom). Classification H4. Lift speed 17/3.9 fpm. Motor 1.3 hp. Mounted on push trolley. View Cutsheet 208620

Trolley fits beam flange width 2.25"-5". Fits beam height 3-35/64". Includes chain container and push trolley.

Approved by Matthew Mueller via email 6/23/2023. To run lengthwise down center of room above 2 end-to-end workbenches.

W x D x H: 15.9 x 9.6 x 19.3 in.
Electrical: 115V 60Hz 19A 1-Phase
Elect Notes: 6-ft cord

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Clinical Engineering Workroom **Department:** Maintenance

Room #: B807C

Room Notes: Per HGA, eye wash is plumbed. All tools and testing equipment provided by CE service provider Renovo. No laser connections or specialty outlets needed.

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white View Cutsheet 11329

By sink for paper towel disposal

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Workbench

AE #: WORK-60

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	McMaster-Carr	9054T82		Floor	OF/OI	Project

Fixed, stationary workbench with non-conductive maple top (34" AFF). Overall capacity 1875 lbs. Frame gray powder-coated steel. Knockouts in front and back for duplex electrical outlets. Delivers unassembled. Height noted is estimated to include the upper shelf option. View Cutsheet 209152

Model number provided by CE to be consistent with benches at other sites. Will not place electrical outlets in knockouts. Power outlets requested at 42" AFF behind benches.

W x D x H: 60 x 30 x 52 in.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Backstop and side stops for 60" bench	9054T52	1	2
Lower shelf for 60"W bench	9054T42	1	2
Mounting kit for workbench drawer 30"	9054T185	1	2
Upper shelf for 60"W bench	9054T62	1	2

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Cart, Tool

AE #: CATO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Fastenal	0225938		Floor	OF/OI	Project

Gray steel 4 drawer professional service cart with 5"x2" casters. With key lock. Two drawers 11.6"W x 17.1"D, x 5"H, one drawer 24.6"W x 17.1"D x 3.1"H, and one 24.6"W x 17.1"D x 5"H. View Cutsheet 208611

W x D x H: 30 x 19.3 x 41.3 in.

Weight: 137.5 lbs.

Cart, Utility

AE #: CAUT-88

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	2203280		Floor	OF/OI	Project

Brute black utility cart with flat top shelves and 2 lower lipped shelves. Weight capacity 600 lbs. View Cutsheet 210499

W x D x H: 17.2 x 38.4 x 46.2 in.

Cart, Utility

AE #: CAUT-87

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2196862		Floor	OF/OI	Project

Brute black 3-shelf lipped cart, medium. Load capacity 600 lbs. Space between shelves 12". View Cutsheet 210500

W x D x H: 25.2 x 44 x 47 in.

Coffee Brewer

AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately. View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Room: Facilities Maintenance

Department: Maintenance

Room #: B807D

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Drill Press

AE #: DRPR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Dayton	54ZW30		Floor	OF/CI	Project

Floor drill press: belt drive type, fixed speed control, spindle speed range 138 RPM - 3476 RPM. 15" swing. View Cutsheet 208615

W x D x H: 11.5 x 30 x 47 in.

Electrical: 115V 60Hz 8.6A 1-Phase

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Drum Accessory, Dolly

AE #: DRAD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	6FVJ3		Floor	OF/OI	Project

Steel drum dolly with 3" casters. 1200 lb. load capacity for 5-gal to 55-gal containers. Half round open deck height 6". For maximum container height 34.5". View Cutsheet 208622

W x D x H: 24.1 x 24.1 x 24 in.

Weight: 40.5 lbs.

First Aid Kit

AE #: FIAK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	796J67		Wall	OF/CI	Project

First aid wall-mounted cabinet with 202 components; serves up to 50 people. View Cutsheet 208881

W x D x H: 13.8 x 3.25 x 14.3 in.

Forklift

AE #: FORK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Genie	GL-8		Floor	OF/VI	Project

Mobile material lift with 10'5" maximum lifting height. Up to 400 lb. load capacity. ***INCLUDE COUNTERWEIGHT BASE*** View Cutsheet 208621

W x D x H: 28.8 x 28.5 x 68.5 in.

Weight: 411 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Counterweight base		1	1

Grinder, Bench

AE #: GRBE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Dayton	49H008		Table	OF/CI	Project

Medium duty bench grinder for construction and maintenance. 1/2 HP. Includes: 2 adjustable tool rests, 2 eye shields, 2 quick adjusting spark guards, grinding wheel, locking rocker switch, and wire wheel. Wheel speed range 2000 - 3450 RPM. View Cutsheet 208616

W x D x H: 19.6 x 12 x 11.3 in.

Electrical: 120V 60Hz 5A **Weight:** 43.4 lbs.

Elect Notes: Cord 6' long

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Hoist

AE #: HOIS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Harrington	SEQP010SD-12	Grainger 54PM99	Ceiling	OF/CI	Project

Chain hoist with 2000 lb. load capacity. Hoist lift 12 feet(custom). Classification H4. Lift speed 17/3.9 fpm. Motor 1.3 hp. Mounted on push trolley. View Cutsheet 208620

Trolley fits beam flange width 2.25"-5". Fits beam height 3-35/64". Includes chain container and push trolley.

Approved by Matthew Mueller via email 6/23/2023. To run lengthwise down center of room above 2 end-to-end workbenches.

W x D x H: 15.9 x 9.6 x 19.3 in.
Electrical: 115V 60Hz 19A 1-Phase
Elect Notes: 6-ft cord

Ice Maker / Water Dispenser

AE #: ICMW-11

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	12CI425A-S		Countertop	OF/CI	Project

Integral air-cooled machine with up to 425 lbs of daily production of chewblet ice. 12 lbs storage capacity. Quite night sleep mode turns off ice machine when idle. Automatic self-flushing of ice machine removes impurities; drain cup provides internal air gap for added protection from drain line contaminants; sensorsafe infrared ice and water dispenser. View Cutsheet 141564

W x D x H: 16.1 x 23.5 x 32.5 in.
Clearance: Rear 3 in.; Left 2 in.; Right 6 in.; Top 12 in.
Electrical: 115V 60Hz 11A
Weight: 199 lbs.
Elect Notes: 8.5' cord with nema 5-15 90 degree hospital-grade plug
Plumb Notes: Potable water inlet 3/8"fpt. Drain 3/4"mpt. Water temperature 45-90 degrees f. Water pressure 10-70 psi.
HVAC Notes: Air temperature 50-100 degrees f. Heat rejection 5000 btu/hr
Struct Notes: Utility connection through back or bottom.

Ice Maker / Water Dispenser, Component

AE #: ILEGS-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	AF10LBLEGS		Icemaker	OF/CI	Project

Legs, set of 4, 4" for 12ci series ice makers No Cutsheet 141809

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Inventory Management System, Auxiliary Unit — AE #: IMSA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	KeepStock Vending Auxiliary Cabinet		Floor	OF/VI	Lease

KeepStock Vending locker auxiliary unit View Cutsheet 208886

W x D x H: 34.3 x 35.6 x 83 in. **Clearance:** Left 24 in.; Right 24 in.; Front 12 in.
Electrical: 115V 60Hz **Weight:** 520 lbs.

Inventory Management System, Main Unit — AE #: IMSM-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	KeepStock Vending Locker		Floor	OF/VI	Lease

KeepStock Vending locker system for inventory management. Main cabinet with user interface screen. Tracks who removes items from locker. View Cutsheet 208885

W x D x H: 34.3 x 35.6 x 83 in. **Clearance:** Left 24 in.; Right 24 in.; Front 12 in.
Network: Wired
Electrical: 120V 60Hz **Weight:** 520 lbs.

Ladder — AE #: LADD-26

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Little Giant	Velocity	15426-801	Rack	OF/OI	Project

Velocity Little Giant aluminum extra heavy duty ladder with 300 lb. capacity. View Cutsheet 209188

Model provided by Matt Mueller via email 9/11/2023

W x D x H: 30 x 8.5 x 80 in.
Weight: 54.5 lbs.

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Ladder

AE #: LADD-08

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Werner	6208		Rack	OF/OI	Project

8' fiberglass ladder with a 12' reach; single sided; capacity of 300 lbs. Slip resistant treads; full set of rear horizontal spaced one per foot; all steps and two rear horizontal are knee-spaced. View Cutsheet 126486

Confirm if needed here. In DD2 meeting, group stated that anything over 6' is brought from other location or will use scissor lift.

W x D x H: 20 x 10 x 96 in.

Weight: 30 lbs.

Ladder

AE #: LADD-12

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Werner	6112		Rack	OF/OI	Project

Fiberglass 12' ladder with slip-resistant steps. HolsterTop with lock-in accessory system. Non-conductive fiberglass rails. Load capacity 300 lbs. Steps 3" wide. Top 13"W x 5.75"D. Approximate spread 79.2". View Cutsheet 208613

Confirm if needed here. In DD2 meeting, group stated that anything over 6' is brought from other location or will use scissor lift.

W x D x H: 31.6 x N/A x 144 in.

Weight: 44 lbs.

Microwave Oven, Commercial

AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required View Cutsheet 208710

Added but not requested. Confirm need with department.

W x D x H: 20.5 x 16 x 12.2 in.

Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Pallet Jack

AE #: PAJA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Crown	PTH-50-27-48		Floor	OF/OI	Project

Manual pallet jack with 48" fork length. Maximum lift height up to 7.95". Maximum load capacity up to 5000 lbs. Depth and height estimated based on 48" fork length. 7" articulating wheels. Reinforced handle with ergonomic contoured design. View Cutsheet 208943

Added per email string with Matt Mueller 11/27/2023

W x D x H: 27 x 56 x 48 in.

Weight: 160 lbs.

Press, Hydraulic

AE #: PRHY-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Dake Corporation	972210		Floor	OF/OI	Project

Hydraulic press: manual pump, H-frame frame, 10 ton frame capacity, 8 inch stroke. Includes combination table plates and V-block. Adjustable bed. View Cutsheet 210209

Applications: bending, forming, pressing, punching, straightening, staking and clamping. Distance between uprights 16-3/4". Reservoir capacity 24 fluid ounces.

W x D x H: 28 x 24 x 60 in.

Press, Hydraulic, Accessory

AE #: PRHY-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Shinn Fu Company of America, Inc.	HW93309		Shelf	OF/OI	Project

Hein-Werner press accessory set for use with 25 tons press, 8 pieces. Includes (2) plates, (5) adapters, and medium bearing separator. View Cutsheet 210210

Rack, Ladder

AE #: RALA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	McMaster-Carr	1716A14		Wall	OF/CI	Project

Gray powder-coated steel padded two-pronged wall mounted hanger. Holds items up to 75 lbs. View Cutsheet 209382

W x D x H: 11.3 x 8.75 x 9.75 in.

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Refrigerator Freezer, Upright

AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant. View Cutsheet 208926

W x D x H: 30 x 32 x 66.4 in.
Clearance: Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Tool

AE #: TOOL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	UE Systems	UP-401		Shelf	OF/OI	Project

Digital Grease Caddy Pro translates ultrasound into the audible range enabling users to hear and recognize bearing sounds while simultaneously viewing decibel levels on a display panel. With belt holster. Attaches directly to grease gun, gives visual and audible indication for proper lubrication. View Cutsheet 208618

W x D x H: 7 x 3.2 x 3 in.
Weight: 1.25 lbs.
Elect Notes: Rechargeable lithium polymer battery

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Facilities Maintenance **Department:** Maintenance

Room #: B807D

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white [View Cutsheet 11329]

By sink for paper towel disposal

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Workbench

AE #: WORK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Tennsco	EB-2-3072C		Floor	OF/OI	Project

Stationary, fixed-height workbench with stringer, and power strip. Powder coated gray 13 gauge steel frame. Includes 16 outlets, 1 shelf, 8 knockouts, 0 drawers, 0 cabinets. Riser runs length of workbench providing elevated storage above work surface. [View Cutsheet 208610]

W x D x H: 72 x 30 x 33.9 in.

Electrical: 115V 60Hz

Room: Toilet (Staff)

Department: Maintenance

Room #: B807E, B807F

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Facilities Mechanical / Plumbing (Lower Level) **Department:** Maintenance

Room #: CSA00F

Hose

AE #: HOSE-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	12F253		Wall	OF/OI	Project

Polypropylene blue water hose with temperature range up to 158 degrees F. 100 feet in length. Remains flexible at extreme temperatures. Lightweight. View Cutsheet 209153

Non-kinking. Resists crushing. Brass fittings 5/8" on both ends. Internal diameter 5/8". Max working pressure at 70 degrees F = 100 psi.

Plumb Notes: Hose fitting size 5/8"

Hose Accessory, Nozzle

AE #: HOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	18D869		Wall	OF/OI	Project

Black rear trigger adjustable spray water nozzle; 100 psi. Brass/stainless steel construction has insulated handle for hot and cold water use. Max temp View Cutsheet 171796

200 dg f.

W x D x H: 1 x 1 x 5.5 in.

Hose Reel

AE #: HOSE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Grainger	2LRK9		Wall	OF/CI	Project

Steel wall mount hose reel. Tri-mount hose reel is crafted from 13-ga. Powder-coated steel. It can be mounted to the wall, floor, or ground. View Cutsheet 166448

W x D x H: 22 x 14.5 x 19 in.

Struct Notes: Wall Backing Required

Pallet Jack

AE #: PAJA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Crown	PTH-50-27-48		Floor	OF/OI	Project

Manual pallet jack with 48" fork length. Maximum lift height up to 7.95". Maximum load capacity up to 5000 lbs. Depth and height estimated based on View Cutsheet 208943

48" fork length. 7" articulating wheels. Reinforced handle with ergonomic contoured design.

Added per email string with Matt Mueller 11/27/2023

W x D x H: 27 x 56 x 48 in.

Weight: 160 lbs.

Room: Parking Garage

Department: Maintenance

Room #: MTPG01

Snow Blower

AE #: SNBL-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Toro Company	38701		Floor	OF/OI	Project

Power broom commercial gas powered brush 36". Power steering, variable speed technology with 6 forward and 2 reverse speeds. Pull cord start. View Cutsheet 208624

Independent control levers allow simultaneous engagement of ground drive and broom. Air intake rotates at 180 degrees for multi-season use.

Dimensions approximate.

W x D x H: 40 x 48 x 48 in.

Room: Mechanical (8th Floor) **Department:** Maintenance

Room #: PH800

First Aid Kit

AE #: FIAK-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Grainger	796J67		Wall	OF/CI	Project

First aid wall-mounted cabinet with 202 components; serves up to 50 people. View Cutsheet 208881

W x D x H: 13.8 x 3.25 x 14.3 in.

Hose

AE #: HOSE-10

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Grainger	12F253		Wall	OF/OI	Project

Polypropylene blue water hose with temperature range up to 158 degrees F. 100 feet in length. Remains flexible at extreme temperatures. Lightweight. View Cutsheet 209153

Non-kinking. Resists crushing. Brass fittings 5/8" on both ends. Internal diameter 5/8". Max working pressure at 70 degrees F = 100 psi.

Plumb Notes: Hose fitting size 5/8"

Hose Accessory, Nozzle

AE #: HOAN-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Grainger	18D869		Wall	OF/OI	Project

Black rear trigger adjustable spray water nozzle; 100 psi. Brass/stainless steel construction has insulated handle for hot and cold water use. Max temp View Cutsheet 171796

200 dg f.

W x D x H: 1 x 1 x 5.5 in.

Hose Reel

AE #: HOSE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Grainger	2LRK9		Wall	OF/CI	Project

Steel wall mount hose reel. Tri-mount hose reel is crafted from 13-ga. Powder-coated steel. It can be mounted to the wall, floor, or ground. View Cutsheet 166448

W x D x H: 22 x 14.5 x 19 in.

Struct Notes: Wall Backing Required

Room: Mechanical (8th Floor) **Department:** Maintenance

Room #: PH800

Pallet Jack

AE #: PAJA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Crown	PTH-50-27-48		Floor	OF/OI	Project

Manual pallet jack with 48" fork length. Maximum lift height up to 7.95". Maximum load capacity up to 5000 lbs. Depth and height estimated based on 48" fork length. 7" articulating wheels. Reinforced handle with ergonomic contoured design. View Cutsheet 208943

Added per email string with Matt Mueller 11/27/2023

W x D x H: 27 x 56 x 48 in.

Weight: 160 lbs.

Room: Wheelchair Storage/Vestibule (Cancer Center Entry) **Department: Public**

Room #: A100A

Dispenser, Wipes

AE #: DIWI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Zogics	Z650		Floor	OF/OI	Project

Wipe dispenser has a large 14" base for added stability, a 7 gallon plastic waste receptacle, and easy access door for easier and less frequent servicing. View Cutsheet 209683

Compatible with all of Zogics bulk disinfecting and cleaning wipes, this sleek and stylish disinfecting wipes dispenser has an improved nozzle for hassle free wipe dispensing, and is easier to refill, as it comes with a bucket to hold your rolls of wipes.

W x D x H: 14 x N/A x 36 in.

Wheelchair

AE #: WHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
25	Staxi Corporation	Standard	ST010	Floor	OF/VI	Project

Standard size nesting wheelchair with 600 lb. / 272 kg weight capacity, lifting armrests and footrests, brake, luggage rack, and anti-tip design. Seat width 20". Seat height at front of frame 21.7". View Cutsheet 208910

O2 tank holder needed.

W x D x H: 27 x 38 x 31 in.

Weight: 57 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side mount O2 holder - adds 3" to width		1	25

Wheelchair, Bariatric

AE #: WHBA-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Staxi Corporation	MAX CHAIR		Floor	OF/VI	Project

1000 lb capacity; automatic fail safe ratchet brake; 5" urethane casters and 8" wheels; non-removeable footrests; folding armrests; options include: elevating leg rests, iv pole, and oxygen tank holder View Cutsheet 126514

W x D x H: 42 x 44 x 40.5 in.

Weight: 90 lbs.

Room: Wheelchair Storage/Vestibule (Cancer Center Entry) **Department: Public**

Room #: A100A

Wheelchair, Docking Station

AE #: WHDS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Staxi Corporation	ST120		Floor	OF/VI	Project

Docking station functions as an anchor for nested wheelchairs. Fits all chairs: Standard, Pediatric, Guest Services, Ranger, MRI and Max. View Cutsheet 161550

W x D x H: 32.1 x 21.4 x 77.5 in.

Struct Notes: Recommended access zone: 58" x 32" at rear of unit

Room: Vestibule

Department: Public

Room #: A102

Room Notes: Assumes no medical equipment in this area.

Room: Registration Copy / Work **Department:** Public

Room #: A102C

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

Place Holder

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Safe

AE #: SAFE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gardall Safe Corporation	LCR2014K		Floor	OF/CI	Project

Top loading rotary hopper depository safe with dual key lock. 4 anchoring holes drilled into base. Inside dimensions: 13"w x 11"d 11"h. Door is 10.5" x 11". View Cutsheet 134798

Must be bolted to the floor. To be placed in copy/workroom behind (4) registrars.

W x D x H: 14 x 14 x 20 in.

Weight: 87 lbs.

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Registration Bay, Central

Department: Public

Room #: A102D, A102F, A102G, A102H

Room Notes: UK will be cashless

Waste Container

AE #: WACO-28

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	254300BEIG		Floor	OF/OI	Project

28 qt fire resistant wastebasket, Color Beige, height 15 1/4 inches, width 10 1/2 inches, length 14 1/2 inches, UL listed, rectangular, plastic-fiber filled resin will not rust and resists chips and dents

View Cutsheet 100085

W x D x H: 10.5 x 14.5 x 15.3 in.

Room: Cafe Seating **Department:** Public

Room #: A107

Room Notes: Assumes no medical equipment required in this area

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle, 24 gal — AE #: WARE-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
4	Trashcans Unlimited, LLC	WWXL24		Cabinet	OF/OI	Project

24 Gallon Extra Large Home & Office Trash Can or Recycling Bin. Great for under the counter or as stand alone receptacles. Black and Gray are Blank for trash and Blue and Green have the recycling Mobius Loop. Material: High density polyethylene View Cutsheet 210487

To go in built-in waste/recycling counter-cabinets

W x D x H: 15.3 x 21.3 x 24 in.

Weight: 7 lbs.

Waste Receptacle, Recycle Bin — AE #: WARB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Global Industrial	35 Gal	T9F641439RBL	Cabinet	OF/OI	Project

35-gallon, square plastic recycle container. View Cutsheet 210122

To go in built-in waste/recycling counter-cabinets

W x D x H: 19.5 x 19.5 x 27.8 in.

Weight: 9 lbs.

Room: Cafe Serving Area **Department:** Public

Room #: A107A

Room Notes: Assumes no medical equipment required in this area

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Cafe Mobile Pick-Up **Department: Public**

Room #: A107B

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. Request to be placed outside the door to the room.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Cafe Prep **Department: Public**

Room #: A107B2

Allowance, Kitchen Smallware

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	TBD			Cabinet	OF/OI	Project

Allowance for pots, pans and smallware. No Cutsheet 212150

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Cafe Dishroom **Department:** Public

Room #: A107C

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Toilet, Cafe

Department: Public

Room #: A107E

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Vending **Department:** Public

Room #: A200W1

Room Notes: Vending Machines provided by others

Defibrillator, AED

AE #: DEAE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	LIFEPAK 1000 ADVANCED	99425-000025	Cabinet	OF/OI	Project

Lifepak 1000 advanced with ecg display, manual override - 5 year warranty. Includes ship kit, carrying case with strap, battery, quik combo redi-pak electrodes, 3-wire monitoring cable, accessory pouch, lifepatch ecg electrodes, operating instructions.

View Cutsheet 148405

With Child electrode kit, see accessories

W x D x H: 9.2 x 10.9 x 3.4 in.

Weight: 7.1 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Infant/Child Electrode Starter Kit	11101-000017	1	1

Defibrillator, AED, Cabinet

AE #: DEAC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	11998-000293		Wall	OF/CI	Project

Recessed wall cabinet for aed

View Cutsheet 139806

W x D x H: 14 x 6.75 x 14 in.

Defibrillator, AED, Naloxone, Wall Sign

AE #: AEDW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Illinois Supply Company	EN9599		Wall	OF/CI	Project

Wall-mounted sign clearly indicates the location and contents of your emergency cabinet. This sign designates AED and Naloxone Overdose Emergency Kit only.

View Cutsheet 209497

W x D x H: 7.5 x 3 x 6 in.

Room: Waiting Nourish **Department:** Public

Room #: A300W, A600W2, A600W3, B600W3, B600W6, A700W2, B700W3, A700W4, B700W6

Coffee Brewer

AE #: COBR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wilbur Curtis Company	Airpot Twin D1000GT63A000		Countertop	OF/VI	Project

G3 Coffee Brewing System with the “scroll-through” programming on the oversized LCD display allows programming of the two brewing heads independently of each other. Easily set the brewers to standards, or use the Curtis’ factory settings.

View Cutsheet 209284

W x D x H: 18 x 16.5 x 25.3 in.
Electrical: 220V 60Hz 23A 5050W 1-Phase **Weight:** 54 lbs.
Elect Notes: Voltage to be no less than 208V and no greater than 240V.
Plumb Notes: Water inlet: 1/4" flare. Water filtration device recommended.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ThermoPro™ TLXA 2.2L Airpots		2	2

Dispenser, Cup

AE #: DICU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	San Jamar	C3200PGR	GRAINGER 6ADL7	Wall	OF/CI	Project

Stainless steel cup dispenser for 6-10 oz cups.

View Cutsheet 141423

Need/Use under review, keep for now

W x D x H: 4.75 x 4.75 x 34.8 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Waiting Nourish **Department:** Public

Room #: A300W, A600W2, A600W3, B600W3, B600W6, A700W2, B700W3, A700W4, B700W6

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser. View Cutsheet 142083

W x D x H: 21 x 24 x 36 in.
Clearance: Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase
Weight: 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90º hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in.
Clearance: Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Waiting Nourish **Department:** Public

Room #: A300W, A600W2, A600W3, B600W3, B600W6, A700W2, B700W3, A700W4, B700W6

Ice Maker / Water Dispenser, Component

AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series

No Cutsheet 211856

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity.

View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Waiting Nourish **Department:** Public

Room #: B000W

Coffee Brewer — AE #: COBR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wilbur Curtis Company	Airpot Twin D1000GT63A000		Countertop	OF/VI	Project

G3 Coffee Brewing System with the “scroll-through” programming on the oversized LCD display allows programming of the two brewing heads independently of each other. Easily set the brewers to standards, or use the Curtis’ factory settings. View Cutsheet 209284

W x D x H: 18 x 16.5 x 25.3 in.
Electrical: 220V 60Hz 23A 5050W 1-Phase **Weight:** 54 lbs.
Elect Notes: Voltage to be no less than 208V and no greater than 240V.
Plumb Notes: Water inlet: 1/4" flare. Water filtration device recommended.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ThermoPro™ TLXA 2.2L Airpots		2	2

Defibrillator, AED — AE #: DEAE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	LIFEPAK 1000 ADVANCED	99425-000025	Cabinet	OF/OI	Project

Lifepak 1000 advanced with ecg display, manual override - 5 year warranty. Includes ship kit, carrying case with strap, battery, quik combo redi-pak electrodes, 3-wire monitoring cable, accessory pouch, lifepatch ecg electrodes, operating instructions. View Cutsheet 148405

With Child electrode kit, see accessories

W x D x H: 9.2 x 10.9 x 3.4 in.
Weight: 7.1 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Infant/Child Electrode Starter Kit	11101-000017	1	1

Defibrillator, AED, Cabinet — AE #: DEAC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	11998-000293		Wall	OF/CI	Project

Recessed wall cabinet for aed View Cutsheet 139806

W x D x H: 14 x 6.75 x 14 in.

Room: Waiting Nourish **Department:** Public

Room #: B000W

Defibrillator, AED, Naloxone, Wall Sign

AE #: AEDW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Illinois Supply Company	EN9599		Wall	OF/CI	Project

Wall-mounted sign clearly indicates the location and contents of your emergency cabinet. This sign designates AED and Naloxone Overdose Emergency Kit only. View Cutsheet 209497

W x D x H: 7.5 x 3 x 6 in.

Dispenser, Cup

AE #: DICU-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	San Jamar	C3200PGR	GRAINGER 6ADL7	Wall	OF/CI	Project

Stainless steel cup dispenser for 6-10 oz cups. View Cutsheet 141423

Need/Use under review, keep for now

W x D x H: 4.75 x 4.75 x 34.8 in.

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included. View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Waiting Nourish **Department:** Public

Room #: B000W

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser. View Cutsheet 142083

W x D x H: 21 x 24 x 36 in.
Clearance: Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase
Weight: 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90° hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Ice Maker / Water Dispenser, Component

AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series No Cutsheet 211856

Room: Waiting Nourish **Department:** Public

Room #: B000W

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.

Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Toilet (Single) **Department: Public**

Room #: B000W2, B000W3, B000W4, A102A, A102B, C201C, B300C, B100C3, A100W5, A100W6, A200W3, B200W3, A200W4, B200W5, A300W1, A300W2, A300W3, A300W4, A400W4, A400W5, B500W2, B500W4, B500W5, A600W1, B600W2, A600W4, B600W4, A600W5, B600W5, A700W1, B700W2, B700W4, B700W5, A700W6, A700W7

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. hand sanitizers requested outside doors to room

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Passageway **Department:** Public

Room #: B100C

Defibrillator, AED

AE #: DEAE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	LIFEPAK 1000 ADVANCED	99425-000025	Cabinet	OF/OI	Project

Lifepak 1000 advanced with ecg display, manual override - 5 year warranty. Includes ship kit, carrying case with strap, battery, quik combo redi-pak electrodes, 3-wire monitoring cable, accessory pouch, lifepatch ecg electrodes, operating instructions. View Cutsheet 148405

With Child electrode kit, see accessories

W x D x H: 9.2 x 10.9 x 3.4 in.

Weight: 7.1 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Infant/Child Electrode Starter Kit	11101-000017	1	1

Defibrillator, AED, Cabinet

AE #: DEAC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	11998-000293		Wall	OF/CI	Project

Recessed wall cabinet for aed View Cutsheet 139806

W x D x H: 14 x 6.75 x 14 in.

Defibrillator, AED, Naloxone, Wall Sign

AE #: AEDW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Illinois Supply Company	EN9599		Wall	OF/CI	Project

Wall-mounted sign clearly indicates the location and contents of your emergency cabinet. This sign designates AED and Naloxone Overdose Emergency Kit only. View Cutsheet 209497

W x D x H: 7.5 x 3 x 6 in.

Room: Toilet (Multi)

Department: Public

Room #: B100C1, B100C2

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Waiting / Corridor / Lobby

Department: Public

Room #: B100W, C100, B200W, B500W, B600W, B700W, B100W1

Dispenser, Emesis Bag

AE #: DIEB-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medline Industries, Inc.	3933D		Wall	OF/CI	Project

Emesis bag dispenser. Clear. Holds up to 24 bags. Bags not included.

View Cutsheet 161440

W x D x H: 7 x 7 x 7.5 in.

Room: Wheelchair Alcove **Department:** Public

Room #: B200W1

Room Notes: Do not need a docking station

Wheelchair

AE #: WHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Staxi Corporation	Standard	ST010	Floor	OF/VI	Project

Standard size nesting wheelchair with 600 lb. / 272 kg weight capacity, lifting armrests and footrests, brake, luggage rack, and anti-tip design. Seat width 20". Seat height at front of frame 21.7".

View Cutsheet 208910

O2 tank holder needed.

W x D x H: 27 x 38 x 31 in.

Weight: 57 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side mount O2 holder - adds 3" to width		1	5

Room: Lactation/Respite **Department:** Public

Room #: B200W7, A300W5, B600W8, B700W9

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow. View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Wheelchair Alcove **Department: Public**

Room #: B300W1, A500W2, B600W1, B700W1

Room Notes: Do not need a docking station

Defibrillator, AED

AE #: DEAE-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	LIFEPAK 1000 ADVANCED	99425-000025	Cabinet	OF/OI	Project

Lifepak 1000 advanced with ecg display, manual override - 5 year warranty. Includes ship kit, carrying case with strap, battery, quik combo redi-pak electrodes, 3-wire monitoring cable, accessory pouch, lifepatch ecg electrodes, operating instructions.

View Cutsheet 148405

With Child electrode kit, see accessories

W x D x H: 9.2 x 10.9 x 3.4 in.

Weight: 7.1 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Infant/Child Electrode Starter Kit	11101-000017	1	1

Defibrillator, AED, Cabinet

AE #: DEAC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Stryker Corp. - Medical / Physio-Control Corp.	11998-000293		Wall	OF/CI	Project

Recessed wall cabinet for aed

View Cutsheet 139806

W x D x H: 14 x 6.75 x 14 in.

Defibrillator, AED, Naloxone, Wall Sign

AE #: AEDW-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Illinois Supply Company	EN9599		Wall	OF/CI	Project

Wall-mounted sign clearly indicates the location and contents of your emergency cabinet. This sign designates AED and Naloxone Overdose Emergency Kit only.

View Cutsheet 209497

W x D x H: 7.5 x 3 x 6 in.

Room: Wheelchair Alcove **Department:** Public

Room #: B300W1, A500W2, B600W1, B700W1

Room Notes: Do not need a docking station

Wheelchair

AE #: WHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
5	Staxi Corporation	Standard	ST010	Floor	OF/VI	Project

Standard size nesting wheelchair with 600 lb. / 272 kg weight capacity, lifting armrests and footrests, brake, luggage rack, and anti-tip design. Seat width 20". Seat height at front of frame 21.7".

View Cutsheet 208910

O2 tank holder needed.

W x D x H: 27 x 38 x 31 in.

Weight: 57 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side mount O2 holder - adds 3" to width		1	5

Room: Toilet (Family)

Department: Public

Room #: B600W7, A700W3, B700W8

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Room: Wheelchair Storage (Parking / ACC Entrance) **Department: Public**

Room #: C100A

Dispenser, Wipes

AE #: DIWI-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Zogics	Z650		Floor	OF/OI	Project

Wipe dispenser has a large 14" base for added stability, a 7 gallon plastic waste receptacle, and easy access door for easier and less frequent servicing. View Cutsheet 209683

Compatible with all of Zogics bulk disinfecting and cleaning wipes, this sleek and stylish disinfecting wipes dispenser has an improved nozzle for hassle free wipe dispensing, and is easier to refill, as it comes with a bucket to hold your rolls of wipes.

W x D x H: 14 x N/A x 36 in.

Wheelchair

AE #: WHEE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
10	Staxi Corporation	Standard	ST010	Floor	OF/VI	Project

Standard size nesting wheelchair with 600 lb. / 272 kg weight capacity, lifting armrests and footrests, brake, luggage rack, and anti-tip design. Seat width 20". Seat height at front of frame 21.7". View Cutsheet 208910

O2 tank holder needed.

W x D x H: 27 x 38 x 31 in.

Weight: 57 lbs.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
Side mount O2 holder - adds 3" to width		1	10

Wheelchair, Docking Station

AE #: WHDS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Staxi Corporation	ST120		Floor	OF/VI	Project

Docking station functions as an anchor for nested wheelchairs. Fits all chairs: Standard, Pediatric, Guest Services, Ranger, MRI and Max. View Cutsheet 161550

W x D x H: 32.1 x 21.4 x 77.5 in.

Struct Notes: Recommended access zone: 58" x 32" at rear of unit

Room: Office, Security **Department:** Public

Room #: C201A

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Registration, Private

Department: Public

Room #: C201B

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Nourishment, Staff (Small) **Department:** Universal / Staff Support

Room #: A308A1, A609C2, A708J1

Ice Maker / Water Dispenser

AE #: IMWD-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	7CI112A-IW-CL-ST-00	Champion 7	Countertop	OF/CI	Project

Ice and Water Dispenser. 7 LB Ice Storage Capacity. Integral Air-Cooled Machine with up to 100 Lb. Daily Production of Chewblet Ice. Internal Claris Filter. View Cutsheet 210599

** If unit is to be connected to drain, specify Follett Drip Tray Drain Kit/4" legs part #01535343

W x D x H: 14.6 x 22.4 x 17.6 in.
Clearance: Rear 2 in.; Left 3 in.; Right 3 in.
Electrical: 115V 60Hz 3.8A
Weight: 74 lbs.
Elect Notes: NEMA 5-15
Plumb Notes: See Attached Spec Sheet. Water inlet: 1/4" push-in. Factory equipped external water filter connection: (2) 1/4" push-in (in and out) (hot water models only).
Water temperature: 40 - 90 F (4 - 32 C). Water pressure: 10 - 70 psi (69 - 482 kpa). Water consumption: 12 gal (45.4 L) of potable water per 100 lb (45.4 kg) of ice
** If unit is to be connected to drain, specify Follett Drip Tray Drain Kit/4" legs part #01535343
Struct Notes: ** if using 4" accessory legs, add 4" to height

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Office, Private

Department: Universal / Staff Support

Room #: A607B, A607C, A607D, A607E, A607F, A607G, A607H, A607J, A607K, A608C, A707B, A707C, A707D, A707E, A707F, A707G, A707H

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Nourishment, Staff

Department: Universal / Staff Support

Room #: A608A, A708A

Coffee Brewer

AE #: COBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Bunn-O-Matic	Axiom-DV-3		Countertop	OF/VI	Project

Plumbed coffee brewer with 3 lower burners and hot water faucet. Large 200 ounce tank allows back-to-back brewing capacity. Purchase servers (pots) separately.

View Cutsheet 208424

Place Holder

W x D x H: 16.3 x 22.1 x 16.8 in.
Electrical: 120V 60Hz 15A 1800W
Elect Notes: NEMA 5-15P plug.
Plumb Notes: 20-90 PSI. 1/4" male flare fitting supplied. No specified GPM.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Nourishment, Staff

Department: Universal / Staff Support

Room #: A608A, A708A

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser.

View Cutsheet 142083

W x D x H: 21 x 24 x 36 in.
Clearance: Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase
Weight: 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90º hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Ice Maker / Water Dispenser, Component

AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator.

View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in.
Clearance: Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Room: Nourishment, Staff **Department:** Universal / Staff Support

Room #: A608A, A708A

Ice Maker / Water Dispenser, Component — AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series

No Cutsheet 211856

Refrigerator Freezer, Upright — AE #: REFU-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Frigidaire / Electrolux Home Products	FPHT2097VF		Floor	OF/OI	Project

Stainless steel top freezer refrigerator with 20 cu. ft. capacity. Refrigerator has air filter. Ice maker ready. Freezer auto defrost. Energy star certified. UL listed. ADA compliant.

View Cutsheet 208926

W x D x H: 30 x 32 x 66.4 in. **Clearance:** Rear 1 in.; Left 0.38 in.; Right 0.38 in.; Top 20 in.; Front 26.63 in.
Electrical: 120V 60Hz 2A
Elect Notes: 15 A dedicated circuit required.
HVAC Notes: Energy Star certified. Annual energy 385 kWh. Refrigerant R-600a.
Struct Notes: Right clearance recommendation to allow door to open 140 degrees and complete crisper access and removal. Minimum 3" clearance allows door to open 90 degrees only,

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Waste Receptacle, Recycling w/ Lid/Sign — AE #: WRCB-24

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	3540-07		Floor	OF/OI	University

Wallhugger / Slim Jim model. Blue slim jim recycling with venting channels; 23 gallon. For mixed recycling. With lid and sign.

View Cutsheet 209399

Provided by UK Recycling Services

W x D x H: 22 x 11 x 30 in.

Room: Meeting

Department: Universal / Staff Support

Room #: A608B, A708B

Waste Receptacle

AE #: WARE-40

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	2544		Floor	OF/OI	Project

40 qt. Fire resistant; rectangular shape with rounded corners; color selections: red, gray, brown, lt. Gray, black, lt. Beige, white

View Cutsheet 11329

W x D x H: 11.3 x 15 x 20 in.

Weight: 1 lbs.

Room: Lactation / Respite (Staff)

Department: Universal / Staff Support

Room #: B007A, A503H, B107G, B107H, B207H, A208D, B307J, B607B, A707J

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Monitor, Temperature

AE #: MOTE-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Tridium			Refrigerator	CF/CI	Project

Centralized temperature monitoring system. Use for ref/frz or ambient room. No Cutsheet 209142

Network: Wired

Room: Lactation / Respite (Staff) **Department:** Universal / Staff Support

Room #: B007A, A503H, B107G, B107H, B207H, A208D, B307J, B607B, A707J

Pump, Breast — AE #: PUBR-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medela Inc.	Symphony Plus		Stand	OF/OI	Project

Symphony PLUS® is a hospital-grade (multi-user) breast pump engineered with Initiation Technology™ to help build and maintain your breast milk supply

View Cutsheet 207810

W x D x H: 10.3 x 8.25 x 12.5 in.
Electrical: 120V 60Hz

Pump, Breast, Trolley — AE #: PUBT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Medela Inc.	101029034	6007092	Floor	OF/OI	Project

5 Castor trolley for the Symphony Plus breast pumps.

View Cutsheet 208768

W x D x H: 23 x 23 x 26.5 in.

Refrigerator, Undercounter, ADA Height — AE #: REUA-32

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Accucold	ARS32PVBIADA		Undercounter	OF/VI	Project

Performance series Pharma-Vac 2.83 cu.ft. ADA height solid door commercial all-refrigerator for the display and refrigeration of vaccines; designed for recessed or freestanding installation. Intelligent microprocessor digital temperature controller. Temperature range 2-8 degrees C. Has a separate temperature probe for continuous product readout to simulate stored product temperature. Color white.

View Cutsheet 211261

W x D x H: 19.8 x 22.6 x 32 in.
Electrical: 120V 60Hz 0.75A **Weight:** 102 lbs.
HVAC Notes: Refrigerant R600a

Waste Receptacle — AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Break Room (LL, L1) **Department:** Universal / Staff Support

Room #: B007B, B107K

Room Notes: Slightly smaller than other breakrooms. Services Rad-Onc only on LL and Imaging staff on L1

Coffee Brewer

AE #: COBR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wilbur Curtis Company	Airpot Twin D1000GT63A000		Countertop	OF/VI	Project

G3 Coffee Brewing System with the “scroll-through” programming on the oversized LCD display allows programming of the two brewing heads independently of each other. Easily set the brewers to standards, or use the Curtis’ factory settings.

View Cutsheet 209284

W x D x H: 18 x 16.5 x 25.3 in.
Electrical: 220V 60Hz 23A 5050W 1-Phase **Weight:** 54 lbs.
Elect Notes: Voltage to be no less than 208V and no greater than 240V.
Plumb Notes: Water inlet: 1/4" flare. Water filtration device recommended.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ThermoPro™ TLXA 2.2L Airpots		2	2

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser.

View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Break Room (LL, L1) **Department:** Universal / Staff Support

Room #: B007B, B107K

Room Notes: Slightly smaller than other breakrooms. Services Rad-Onc only on LL and Imaging staff on L1

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Freezer, Commercial

AE #: FRCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Summit Appliance Div / Felix Storch	SCFF237		Floor	OF/VI	Project

The SCFF237 is a 23 cu.ft commercial all-freezer with a complete stainless steel cabinet. View Cutsheet 209340

Alt for Frigidaire Ref/Frzr

W x D x H: 27.5 x 31 x 83.8 in.
Electrical: 115V 60Hz 8A **Weight:** 273 lbs.
Elect Notes: NEMA 15-5P

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser. View Cutsheet 142083

W x D x H: 21 x 24 x 36 in. **Clearance:** Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase **Weight:** 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90° hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Room: Break Room (LL, L1) **Department:** Universal / Staff Support

Room #: B007B, B107K

Room Notes: Slightly smaller than other breakrooms. Services Rad-Onc only on LL and Imaging staff on L1

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator. View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Ice Maker / Water Dispenser, Component — AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series No Cutsheet 211856

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
3	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Refrigerator, Double Door Glass — AE #: REDD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Summit Appliance Div / Felix Storch	SCR49SSG		Floor	OF/VI	Project

49 cu.ft. commercial reach-in refrigerator in complete stainless steel with glass doors. View Cutsheet 210283

Model confirmed with user group

W x D x H: 55.3 x 31 x 83.8 in.
Electrical: 115V 60Hz 7.5A **Weight:** 441 lbs.

Room: Break Room (LL, L1) **Department:** Universal / Staff Support

Room #: B007B, B107K

Room Notes: Slightly smaller than other breakrooms. Services Rad-Onc only on LL and Imaging staff on L1

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Cabinet	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Staff Lockers

Department: Universal / Staff Support

Room #: B007E1, A008B1, B107, B306B, B506B, B606B, B706B

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.

Room: Break Room (L3, L5, L6, L7) **Department:** Universal / Staff Support

Room #: B306D, B506D, B606D, B706D

Coffee Brewer — AE #: COBR-03

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Wilbur Curtis Company	Airpot Twin D1000GT63A000		Countertop	OF/VI	Project

G3 Coffee Brewing System with the “scroll-through” programming on the oversized LCD display allows programming of the two brewing heads independently of each other. Easily set the brewers to standards, or use the Curtis’ factory settings. View Cutsheet 209284

W x D x H: 18 x 16.5 x 25.3 in.
Electrical: 220V 60Hz 23A 5050W 1-Phase **Weight:** 54 lbs.
Elect Notes: Voltage to be no less than 208V and no greater than 240V.
Plumb Notes: Water inlet: 1/4" flare. Water filtration device recommended.

Accessories:

Description	Catalog	Qty/Item	Ext Qty
ThermoPro™ TLXA 2.2L Airpots		2	2

Dispenser, Hand Sanitizer — AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Dispenser, Paper Towel — AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Room: Break Room (L3, L5, L6, L7)

Department: Universal / Staff Support

Room #: B306D, B506D, B606D, B706D

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray. View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Freezer, Commercial

AE #: FRCO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Summit Appliance Div / Felix Storch	SCFF237		Floor	OF/VI	Project

The SCFF237 is a 23 cu.ft commercial all-freezer with a complete stainless steel cabinet. View Cutsheet 209340

Alt for Frigidaire Ref/Frzr

W x D x H: 27.5 x 31 x 83.8 in.
Electrical: 115V 60Hz 8A **Weight:** 273 lbs.
Elect Notes: NEMA 15-5P

Ice Maker / Water Dispenser

AE #: ICMW-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	25CI425A-S		Countertop	OF/CI	Project

Symphony plus ice and water dispenser; 25 lb storage, auto fill, countertop; removable icemaker behind splash panel; 425 lb/day, air cooled; sensor safe dispensing. Optional filter assembly: is 14.25"w x 6"d x 18.5"h. Allow 2.5" clearance at bottom of filter assembly for cartridge removal. Allow 2"-3" additional width for fittings to attach to filter assembly. Optional 4" leg kit adds 4" to height of icemaker. 3" clearance on all sides does not apply to the back or top of ice/water dispenser. View Cutsheet 142083

W x D x H: 21 x 24 x 36 in. **Clearance:** Rear 0 in.; Left 6 in.; Right 3 in.; Top 12 in.
Electrical: 115V 60Hz 11A 1-Phase **Weight:** 226 lbs.
Elect Notes: 115 V/60/1 electrical 11 amps, 0.8 kW
7' (2.1 m) cord, NEMA 5-15 90º hospital-grade plug
Plumb Notes: 3/8" fpt potable water inlet; 3/4" mpt drain; water temperature 45-90 f (7-32 c); water pressure 10-70 psi
HVAC Notes: 5000 btu/hr; air temperature 50-100 f (10-38 c)

Room: Break Room (L3, L5, L6, L7) **Department:** Universal / Staff Support

Room #: B306D, B506D, B606D, B706D

Ice Maker / Water Dispenser, Component — AE #: ILEGS-25

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	00188417, 4" leg kit 25 or 50CI		Icemaker	OF/CI	Project

Item# 00188417 4.00" (10.16 cm) leg kit – for 25CI and 50CI series

No Cutsheet 211856

Ice Maker / Water Dispenser, Component — AE #: ICMW-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Follett Corporation	01233659		Icemaker	OF/CI	Project

Follett bacterial-retentive filter system for the Symphony Plus Series. includes Kleenpak 0.2 micron double layer sterilizing-grade disposable filter capsule, Profile II 1 micron absolute rated pre-filter cartridge and Shurflo pressure regulator.

View Cutsheet 209157

W x D x H: 11.6 x 4.78 x 13.9 in. **Clearance:** Left 2 in.; Right 2 in.; Top 2.5 in.; Front 1 in.
Plumb Notes: Water inlet: 1/2" FNPT; water outlet to dispenser: 1/2" MNPT; water temperature: 45-90 F; water pressure 30-70 psi.

Microwave Oven, Commercial — AE #: MIOC-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
6	Sharp	R-21LTF		Countertop	OF/OI	Project

Medium-Duty Commercial Microwave Oven with 1000 Watts. 1 cu. ft. capacity. AC power required

View Cutsheet 208710

W x D x H: 20.5 x 16 x 12.2 in.
Electrical: 120V 60Hz 14A **Weight:** 37 lbs.

Refrigerator, Double Door Glass — AE #: REDD-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Summit Appliance Div / Felix Storch	SCR49SSG		Floor	OF/VI	Project

49 cu.ft. commercial reach-in refrigerator in complete stainless steel with glass doors.

View Cutsheet 210283

Model confirmed with user group

W x D x H: 55.3 x 31 x 83.8 in.
Electrical: 115V 60Hz 7.5A **Weight:** 441 lbs.

Room: Break Room (L3, L5, L6, L7)

Department: Universal / Staff Support

Room #: B306D, B506D, B606D, B706D

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
2	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Waste Receptacle, Recycle Bin

AE #: WARR-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971257		Cabinet	OF/OI	University

Slim jim container (blue). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 200448

W x D x H: 11 x 22 x 25 in.

Weight: 6.5 lbs.

Room: Work / Copy

Department: Universal / Staff Support

Room #: B307H1, B607A2, A308L1, A608C2, A708B1

Bin, Shredder

AE #: BISH-02

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	HSM	Shredinator 27"	HSM-27SHREDLL-44-720D	Floor	OF/OI	University

The 27" Shredinator efficiently secures confidential documents in a light weight, ergonomic, uniquely designed shred bin that fits in tight spaces. View Cutsheet 209374

W x D x H: 20 x 11 x 27 in.

Weight: 5.8 lbs.

Dispenser, Hand Sanitizer

AE #: DIHS-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	Purell FMX-12	5120-06	Wall	OF/CI	Supply Agreement

Foaming hand sanitizer dispenser. 10" clearance for bottom of dispenser. View Cutsheet 208674

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement. One dispenser needed by each door.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-16

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	1971259		Cabinet	OF/OI	Project

Slim jim container (beige). Includes venting channels, four bag cinches, handles at the base and rim of container. 16 gallon capacity. View Cutsheet 164421

W x D x H: 11 x 22 x 25 in.

Room: Toilet (Staff) **Department: Universal / Staff Support**

Room #: C000W3, C000N2, C000W4, B003D, C000W5, B005H, B007C, B007D, D101, D102, B306A, B306C, B506A, B506C, B606A, B606C, B706A, B706C, B200S1, B200S2

Dispenser, Paper Towel

AE #: DIPT-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Georgia-Pacific	59488A		Wall	OF/CI	Supply Agreement

Enmotion Impulse 10” 1-roll automated touchless paper towel dispenser, black

View Cutsheet 207790

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 14.6 x 9.25 x 14 in.

Dispenser, Soap

AE #: DISO-01

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Gojo Industries	FMX	5160-06	Wall	OF/CI	Supply Agreement

Provon FMX-12 dispenser, dove gray.

View Cutsheet 208694

Confirmed with EVS 9/5/2023 - vendor provides at $0 with supply use agreement.

W x D x H: 6.16 x 5.1 x 9.79 in.

Waste Receptacle

AE #: WARE-23

Qty	Manufacturer	Model	Catalog	Placement	Resp	Funding
1	Rubbermaid Commercial Products	RCP3540		Floor	OF/OI	Project

23 gallon slim jim container. Available in beige, black, gray, brown, blue and yellow.

View Cutsheet 14869

W x D x H: 11.3 x 20.4 x 30 in.